



**SECTION**

- NOTE:**
1. Mix two 50 pound bags of Bentonite with clay removed from hole and retamp the mixture tightly around post. Maximum thickness of a lift of fill before compaction shall be four inches (4").
  2. All holes for crossbar markers must be sealed with water proof sealant, if hollow pipe post is used.
  3. If splices are needed with PVC pipe, use couplers with appropriate adhesive. Couplers should not be located at any of the marker locations on the staff gauge.

**DETAIL 1**  
**STAFF GAUGE**  
**PVC OR WOOD POST**

		Date
Designed	_____	_____
Drawn	M. QUINONES	1/13
Checked	_____	_____
Approved	_____	_____

**STAFF GAUGE FOR LIQUID WASTE IMPOUNDMENT**

