

**EQIP 2008 PASTURE Cost List 90%, PR
FY 2011**

Code	Practice	Component	Units	Unit Cost
314	Brush Management (314)	Hand clearing/Chemical_ woody invasion, equipment, mobilization and labor. Payment is for three (3) consecutive years.	Acre	\$206.70
314	Brush Management (314)	Chemical control: woody invasion, equipment, mobilization and labor. Payment is for three (3) consecutive years.	Acre	\$80.90
315	Herbaceous Weed Control (315)	Chemical Herbaceous weed control with chemicals (glyphosate). Two herbicide application. Payment is for two (2) consecutive years.	Acre	\$100.67
315	Herbaceous Weed Control (315)	Machinery/Oxen Herbaceous weed control with chemicals (glyphosate). Two herbicide application and one harrow pass. Payment is for two (2) consecutive years.	Acre	\$222.17
378	Pond (378)	Pond construction (excavation/hill), materials, (pipe, rock, gravel, concrete, etc.) equipment, mobilization and labor.	CuYd	\$13.00
381	Silvopasture Establishment (381)	Planting trees on existing pastures with tree guard made of goat wire, materials, equipment, mobilization and labor.	No.	\$51.80
382	Fence (382)	Goat or Barbed Wire w/ Treated Wood or Steel Posts, w/Gate, materials, equipment, mobilization and labor.	Ln Ft	\$3.40
382	Fence (382)	Live post (stake), Goat or Barbed Wire w/ Treated Wood or Steel Posts, w/Gate, materials, equipment, mobilization and labor.	Ln Ft	\$4.10
391	Riparian Forest Buffer (391)	Plant Material and Establishment, materials, equipment, mobilization and labor.	No.	\$11.00
391	Riparian Forest Buffer (391)	Natural regeneration, manage of invasive species, materials, equipment, mobilization and labor. Payment for (3) three consecutive years	Acre	\$100.00
472	Access Control (472)	Goat or Barbed Wire w/treated post or Steel Posts, w/Gate, materials, equipment, mobilization and labor.	Lin. Ft.	\$3.40
472	Access Control (472)	Live post (Stake) Goat or Barbed Wire w/treated post or Steel Posts, w/Gate, materials, equipment, mobilization and labor.	Lin Ft	\$4.10
490	Tree/Shrub Site Preparation (490)	Chemical, improves site conditions for establishing/planting trees & shrubs, materials, equipment, mobilization and labor.	No.	\$0.30
490	Tree/Shrub Site Preparation (490)	Hand treating (hoe, machete, other), improves site conditions for establishing/planting trees & shrubs, equipment, mobilization and labor.	No.	\$2.40
490	Tree/Shrub Site Preparation (490)	Chemical and Hand treating , improves site conditions for establishing/planting trees & shrubs, equipment, mobilization and labor.	No.	\$2.70
511	Forage Harvest Management	Taking sample for forage analysis- Labor and material	Acre	\$1.30
512	Forage and Biomass Planting (512)	Seeding & Sprigging, Machinery <20% slope with chemical, Site Preparation/Establishment, materials, equipment, mobilization and labor.	Acre	\$262.80
512	Forage and Biomass Planting (512)	Seeding & Sprigging, No machinery, (oxen) Plant Material, Site Preparation/Establishment, materials, equipment, mobilization and labor.	Acre	\$398.70
516	Pipeline (516)	Plastic (PVC Schedule 40) 1/2 to 3/4 inch diameter pipeline, install from a storage tank to trough, and/or from trough to trough.	Lb.	\$8.50
516	Pipeline (516)	Plastic (PVC Schedule 40) 1 to 2 inch diameter pipeline, install to deliver water from a water source to a storage facility.	Lb.	\$6.10
527	Karst Sinkhole Treatment (527)	Establishment or management vegetation buffer of 25 ft wide around the rim of a sinkhole to reduce contamination. The sinkhole and surrounding buffer will be fenced.	No.	\$677.00
527	Karst Sinkhole Treatment (527)	Obstructions removal and establishment or management vegetation buffer 25 ft wide around the rim to reduce contamination. The sinkhole/surrounding buffer will be fenced. Work includes	No.	\$1,568.00
528	Prescribed Grazing (528)	Establishment and management of appropriate grazing schedule: Proper Stocking Rate-forage height (6 to 10 inches)-resting period (18-25 days) Record Keeping. One payment per acre/contract.	Acre	\$1.20
548	Grazing Land Mechanical Treatment (548)	Chiseling, Machinery or Oxen ≤30% slope, equipment, labor and mobilization.	Acre	\$119.00
561	Heavy Use Area Protection (561)	Concrete pad (6" thick) under high-use area, on wet soils, materials, equipment, mobilization and labor.	Sq. Ft.	\$8.50
561	Heavy Use Area Protection (561)	Gravel pad (1" thick) under high-use area, on wet soils, materials, equipment, mobilization and labor.	Sq. Ft.	\$4.00
561	Heavy Use Area Protection (561)	Gabion pad (9" thick) under high-use area, on wet soils, materials, equipment, mobilization and labor.	Sq. Ft.	\$6.50
578	Stream Crossing (578)	Ford structure in gabion mattresses, materials (baskets, ties, rock, geotextile and foundation material - stone, gravel, sand), equipment, labor and mobilization.	Sq. Ft.	\$16.60
578	Stream Crossing (578)	Ford structure in concrete (6" thick), materials (concrete, reinforcement, geotextile and foundation material - stone, gravel, sand), equipment, labor and mobilization.	Sq. Ft.	\$22.10
590	Nutrient Management (590)	Soil amendments (Lime), materials, equipment, mobilization and labor.	Acre	\$22.00
590	Nutrient Management (590)	NPK application/soil test/record keeping	Acre	\$12.00
595	Integrated Pest Management (595)	IPM. Integrated Pest Management Record keeping, scouting for pest management implementation.	Acre	\$26.20
612	Tree/Shrub Establishment (612)	Tree Establishment (Per Tree), materials, equipment, mobilization and labor.	No.	\$11.00
612	Tree/Shrub Establishment (612)	Establishing tree species by cuttings- live posts (stakes) at recommended distance, materials, equipment, mobilization and labor.	No.	\$3.73
614	Watering Facility (614)	Construction of storage tank and troughs for watering facility, materials, equipment, labor & mobilization.	Cu. Yd.	\$368.00
614	Watering Facility (614)	Installation of plastic tank to store water supply for watering facility, materials (tank and fittings), equipment, labor & mobilization.	Gal.	\$0.68

**EQIP 2008 PASTURE Cost List 75%, PR
FY 2011**

Code	Practice	Component	Units	Unit Cost
314	Brush Management (314)	Hand clearing/Chemical_ woody invasion, equipment, mobilization and labor. Payment is for three (3) consecutive years.	Acre	\$172.30
314	Brush Management (314)	Chemical control: woody invasion, equipment, mobilization and labor. Payment is for three (3) consecutive years.	Acre	\$67.40
315	Herbaceous Weed Control (315)	Chemical Herbaceous weed control with chemicals (glyphosate). Two herbicide application. Payment is for two (2) consecutive years.	Acre	\$83.90
315	Herbaceous Weed Control (315)	Machinery/Oxen Herbaceous weed control with chemicals (glyphosate). Two herbicide application and one harrow pass. Payment is for two (2) consecutive years.	Acre	\$185.10
378	Pond (378)	Pond construction (excavation/hill), materials, (pipe, rock, gravel, concrete, etc.) equipment, mobilization and labor.	CuYd	\$10.90
381	Silvopasture Establishment (381)	Planting trees on existing pastures with tree guard made of goat wire, materials, equipment, mobilization and labor.	No.	\$43.10
382	Fence (382)	Goat or Barbed Wire w/ treated Wood or Steel Posts, w/Gate, materials, equipment, mobilization and labor.	Ln Ft	\$2.84
382	Fence (382)	Live post (stake), Goat or Barbed Wire w/ treated Wood or Steel Posts, w/Gate, materials, equipment, mobilization and labor.	Ln Ft	\$3.40
391	Riparian Forest Buffer (391)	Plant Material and Establishment, materials, equipment, mobilization and labor.	No.	\$9.20
391	Riparian Forest Buffer (391)	Natural regeneration, manage of invasive species, materials, equipment, mobilization and labor. Payment for (3) three consecutive years	Acre	\$83.00
472	Access Control (472)	Goat or Barbed Wire w/treated post or Steel Posts, w/Gate, materials, equipment, mobilization and labor.	Lin. Ft.	\$2.84
472	Access Control (472)	Live post (Stake) Goat or Barbed Wire w/treated post or Steel Posts, w/Gate, materials, equipment, mobilization and labor.	Lin Ft	\$3.40
490	Tree/Shrub Site Preparation (490)	Chemical, improves site conditions for establishing/planting trees & shrubs, materials, equipment, mobilization and labor.	No.	\$0.26
490	Tree/Shrub Site Preparation (490)	Hand treating (hoe, machete, other), improves site conditions for establishing/planting trees & shrubs, equipment, mobilization and labor.	No.	\$2.00
490	Tree/Shrub Site Preparation (490)	Chemical and Hand treating , improves site conditions for establishing/planting trees & shrubs, equipment, mobilization and labor.	No.	\$2.23
511	Forage Harvest Management	Taking sample for forage analysis- Labor and material	Acre	\$1.10
512	Forage and Biomass Planting (512)	Seeding & Sprigging, Machinery <20% slope with chemical, Site Preparation/Establishment, materials, equipment, mobilization and labor.	Acre	\$219.00
512	Forage and Biomass Planting (512)	Seeding & Sprigging, No machinery, (oxen) Plant Material, Site Preparation/Establishment, materials, equipment, mobilization and labor.	Acre	\$332.25
516	Pipeline (516)	Plastic (PVC Schedule 40) 1/2 to 3/4 inch diameter pipeline, install from a storage tank to trough, and/or from trough to trough.	Lb.	\$7.10
516	Pipeline (516)	Plastic (PVC Schedule 40) 1 to 2 inch diameter pipeline, install to deliver water from a water source to a storage facility.	Lb.	\$5.10
527	Karst Sinkhole Treatment (527)	Establishment or management vegetation buffer of 25 ft wide around the rim of a sinkhole to reduce contamination. The sinkhole and surrounding buffer will be fenced.	No.	\$564.00
527	Karst Sinkhole Treatment (527)	Obstructions removal and establishment or management vegetation buffer 25 ft wide around the rim to reduce contamination. The sinkhole/surrounding buffer will be fenced. Work includes	No.	\$1,306.00
528	Prescribed Grazing (528)	Establishment and management of appropriate grazing schedule: Proper Stocking Rate-forage height (6 to 10 inches)-resting period (18-25 days) Record Keeping. One payment per acre/contract.	Acre	\$1.00
548	Grazing Land Mechanical Treatment (548)	Chiseling, Machinery or Oxen <30% slope, equipment, labor and mobilization.	Acre	\$99.00
561	Heavy Use Area Protection (561)	Concrete pad (6" thick) under high-use area, on wet soils, materials, equipment, mobilization and labor.	Sq. Ft.	\$7.00
561	Heavy Use Area Protection (561)	Gravel pad (1" thick) under high-use area, on wet soils, materials, equipment, mobilization and labor.	Sq. Ft.	\$3.30
561	Heavy Use Area Protection (561)	Gabion pad (9" thick) under high-use area, on wet soils, materials, equipment, mobilization and labor.	Sq. Ft.	\$5.40
578	Stream Crossing (578)	Ford structure in gabion mattresses, materials (baskets, ties, rock, geotextile and foundation material - stone, gravel, sand), equipment, labor and mobilization.	Sq. Ft.	\$13.80
578	Stream Crossing (578)	Ford structure in concrete (6" thick), materials (concrete, reinforcement, geotextile and foundation material - stone, gravel, sand), equipment, labor and mobilization.	Sq. Ft.	\$18.40
590	Nutrient Management (590)	Soil amendments (Lime), materials, equipment, mobilization and labor.	Acre	\$18.00
590	Nutrient Management (590)	NPK application/soil test/record keeping	Acre	\$10.00
595	Integrated Pest Management (595)	IPM_ Integrated Pest Management Record keeping, scouting for pest management implementation.	Acre	\$21.80
612	Tree/Shrub Establishment (612)	Tree Establishment (Per Tree), materials, equipment, mobilization and labor.	No.	\$9.20
612	Tree/Shrub Establishment (612)	Establishing tree species by cuttings- live posts (stakes) at recommended distance, materials, equipment, mobilization and labor.	No.	\$3.11
614	Watering Facility (614)	Construction of storage tank and troughs for watering facility, materials, equipment, labor & mobilization.	Cu. Yd.	\$307.00
614	Watering Facility (614)	Installation of plastic tank to store water supply for watering facility, materials (tank and fittings), equipment, labor & mobilization.	Gal.	\$0.57