

**EQIP 2008 ORGANIC Cost List 90%, USVI
FY 2010**

Code	Practice	Component	Units	Unit Cost
328	Conservation Crop Rotation (328)	Crop Rotation; Idle ≥ 6 Months	Acre	\$206.10
345	Residue Management, Mulch Till (345)	Using disking to distribute uniformly crops & other plant residues. Residues shall be distributed over the entire field prior to planting, materials, equipment, mobilization and labor.	Acre	\$275.90
393	Filter Strip (393)	Plant Material, Site Preparation and Establishment, Seeding or Sprigging, materials, equipment, mobilization and labor.	Acre	\$1,793.70
484	Mulching (484)	Straw mulching (bales), 2-4' cover depth erosion & moisture control, materials, equipment, mobilization and labor.	Acre	\$299.50
511	Foraje Harvest Management (511)	Taking forage sample for chemical analysis in 10 acres of hayland	Acre	\$13.80
512	Pasture and Hay Planting (512)	No Machinery, Sprigging & Seeding, Plant Material, Site Preparation & Establishment, materials, equipment, mobilization and labor.	Acre	\$275.00
512	Pasture and Hay Planting (512)	Machinery, Sprigging & Seeding, Plant Material, Site Preparation & Establishment, materials, equipment, mobilization and labor.	Acre	\$292.50
528	Prescribed Grazing (528)	Establishment and management of appropriate grazing schedule, Proper Stocking Rate and Record Keeping.	Acre	\$2.40
590	Nutrient Management (590)	NPK Application/Soil Test & Record Keeping.	Acre	\$15.50
595	Pest Management (595)	IPM_ Integrated Pest Management Record keeping, scouting for pest management implementation.	Acre	\$31.32

**EQIP 2008 ORGANIC Cost List 75%, USVI
FY 2010**

Code	Practice	Component	Units	Unit Cost
328	Conservation Crop Rotation (328)	Crop Rotation; Idle ≥ 6 Months	Acre	\$171.75
345	Residue Management, Mulch Till (345)	Using disking to distribute uniformly crops & other plant residues. Residues shall be distributed over the entire field prior to planting, materials, equipment, mobilization and labor.	Acre	\$229.90
393	Filter Strip (393)	Plant Material, Site Preparation and Establishment, Seeding or Sprigging, materials, equipment, mobilization and labor.	Acre	\$1,494.75
484	Mulching (484)	Straw mulching (bales), 2-4' cover depth erosion & moisture control, materials, equipment, mobilization and labor.	Acre	\$249.60
511	Forage Harvest Management (511)	Taking forage sample for chemical analysis in 10 acres of hayland	Acre	\$11.50
512	Pasture and Hay Planting (512)	No Machinery, Sprigging & Seeding, Plant Material, Site Preparation & Establishment, materials, equipment, mobilization and labor.	Acre	\$229.00
512	Pasture and Hay Planting (512)	Machinery, Sprigging & Seeding, Plant Material, Site Preparation & Establishment, materials, equipment, mobilization and labor.	Acre	\$243.80
528	Prescribed Grazing (528)	Establishment and management of appropriate grazing schedule, Proper Stocking Rate and Record Keeping.	Acre	\$2.00
590	Nutrient Management (590)	NPK Application/Soil Test & Record Keeping.	Acre	\$13.00
595	Pest Management (595)	IPM_ Integrated Pest Management Record keeping, scouting for pest management implementation.	Acre	\$26.10

**EQIP 2008 REGULAR EQIP Cost List 90%, USVI
FY 2010**

Code	Practice	Component	Units	Unit Cost
102	Comprehensive Nutrient Management Plan (No.)	Comprehensive Nutrient Management Plan (CNMP)-Written. Only certified Technical Service Providers (TSPs) qualify for payment.	No.	\$4,176.00
313	Waste Storage Facility (313)	Pond construction (excavation/fill), materials (pipe, rock, gravel, concrete, etc.), equipment, mobilization & labor.	Cu. Yd.	\$10.20
313	Waste Storage Facility (313)	Tank reinforced concrete construction, materials, equipment, mobilization & labor.	Cu. Yd.	\$429.00
313	Waste Storage Facility (313)	Stacking facility Construction, 3 walls concrete structure with roof (metal/galvalum), material, equipment, mobilization & labor.	Sq. Ft.	\$43.00
314	Brush Management (314)	Hand Clearing, woody invasion, equipment, mobilization and labor. Payment for three (3) consecutive yrs.	Acre	\$225.90
314	Brush Management (314)	Chemical Control woody invasion, equipment, mobilization and labor.Payment for three (3) consecutive yrs	Acre	\$93.30
314	Brush Management (314)	Mechanical treatment woody invasion, utilizing wheel tractor with mower, equipment, mobilization and labor. Payment for three (3) consecutive yrs	Acre	\$132.20
328	Conservation Crop Rotation (328)	Crop Rotation; Idle ≥ 6 Months	Acre	\$206.00
329	Residue Management, No-Till/Strip Till (329)	Chemical or manual, materials, equipment, mobilization and labor.	Acre	\$212.80
330	Contour Farming (330)	Furrowing, Machine Plow, Soils slope < 20%, equipment, mobilization and labor.	Acre	\$389.80
330	Contour Farming (330)	Field Layout-Arrangement contour plow or contour farming of selected crop around the hill, labor.	Acre	\$48.80
331	Contour Orchard (331)	Field Layout-Arrangement-Contour plow or contour farming of fruits, orchards and other tropical small fruit across a slope, labor	Acre	\$81.00
342	Critical Area Planting (342)	Sod, to stabilize an area after a structure construction. Includes shaping, earth moving, material, mobilization & installation.	Sq. Ft.	\$0.64
342	Critical Area Planting (342)	Seeding. Includes re-shaping and earth moving, materials, installation, labor & mobilization.	Acre	\$1,265.40
342	Critical Area Planting (342)	Shrub establishment. Includes re-shaping and earth moving, materials, installation, labor & mobilization.	Acre	\$3,115.90
345	Residue Management, Mulch Till (345)	Using disking to distribute uniformly crops & other plant residues. Residues shall be distributed over the entire field prior to planting, materials, equipment, mobilization and labor.	Acre	\$275.90
345	Residue Management, Mulch Till (345)	No-Till Chemical & Furrowing-Plow, equipment, mobilization and labor.	Acre	\$569.70
362	Diversion (362)	Diversion construction (excavation/fill), equipment, labor and mobilization.	Cu. Yd.	\$9.00
378	Pond (378)	Pond construction (excavation/fill), materials, (pipe, rock, gravel, concrete, etc.) equipment, mobilization and labor.	Cu. Yd.	\$8.30
381	Silvopasture Establishment (381)	Site Preparation, establish tree w/animal control barrier, materials, equipment, mobilization and labor.	Ea.	\$104.40
382	Fence (382)	Barbed & Goat Wire w/treated Wood or Steel Posts, w/gate, materials, equipment, mobilization and labor.	Lin. Ft.	\$5.00
382	Fence (382)	Live post perennial tree, Planted at recommended distances, materials, equipment, mobilization and labor.	Ea.	\$4.10
391	Riparian Forest Buffer (391)	Plant Material, establishment, materials, equipment, mobilization and labor.	Ea.	\$13.70
393	Filter Strip (393)	Plant Material, Site Preparation and Establishment, Seeding or Sprigging, materials, equipment, mobilization and labor.	Acre	\$1,793.70
412	Grassed Waterway (412)	Natural channel shaping or channel construction and establishment of suitable vegetation, materials, equipment, mobilization and labor.	Acre	\$18,323.00
430DD	Irrigation Water Conveyance, Pipeline, High-Pressure, Underground, Plastic, (430DD)	PVC pipeline 1/2 to 3/4" dia. for water conveyance, materials and installation. All other pipeline required for irrigation system is included in Practice 441.	Lb.	\$12.70
430DD	Irrigation Water Conveyance, Pipeline, High-Pressure, Underground, Plastic, (430DD)	PVC pipeline 1 to 2" dia. for water/waste conveyance, materials and installation. All other pipeline required for irrigation system is included in Practice 441.	Lb.	\$9.15
430DD	Irrigation Water Conveyance, Pipeline, High-Pressure, Underground, Plastic, (430DD)	PVC pipeline > 2" dia. for water/waste conveyance, materials and installation. All other pipeline required for irrigation system is included in Practice 441.	Lb.	\$5.50
441	Irrigation System, Microirrigation (441)	Installation of Drip-Tape system, materials (tape, PVC pipeline, valves, fittings, filters, etc.), equipment, mobilization & labor. Pump, power, and water source not included.	Acre	\$2,653.00
441	Irrigation System, Microirrigation (441)	Install PE tubing system, materials (PE tubing, emitters, PVC pipeline, valves, fittings, filters, etc.), equipment, mobilization and labor. Pump, power, and water source not included.	Acre	\$3,173.00
449	Irrigation Water Management (449)	Includes record keeping (crop grown, irrigation dates, inches of irrigation, set length & inches of rainfall), soil moisture determined by feel or sensors, control & monitoring of irrigation water.	Acre	\$1.80
460	Land Clearing (460)	Machinery for structural practice, equipment, labor and mobilization.	Acre	\$324.00
472	Access Control (472)	Goat/Barbed Wire w/Steel or Treated Wood Posts, materials, equipment, mobilization and labor.	Lin. Ft.	\$5.00
472	Access Control (472)	Living Stake Posts, planted at recommended distances, materials, equipment, mobilization and labor.	Each	\$4.10
472	Access Control (472)	Posting sign, equipment, mobilization and labor.	Each	\$46.50
484	Mulching (484)	Straw mulching (bales), 2-4" cover depth erosion & moisture control, materials, equipment, mobilization and labor.	Acre	\$299.50

490	Tree/Shrub Site Preparation (490)	Chemical, materials, mobilization and labor.	Each	\$0.83
490	Tree/Shrub Site Preparation (490)	Hand treating (hoe, machete, other), mobilization and labor.	Each	\$2.80
490	Tree/Shrub Site Preparation (490)	Hand/Chemical treating (hoe, machete, other), mobilization and labor.	Each	\$3.20
511	Forage Harvest Management (511)	Taking forage sample for chemical analysis in 10 acres of hayland	Acre	\$7.10
512	Pasture and Hay Planting (512)	No Machinery, Sprigging & Seeding, Plant Material, Site Preparation & Establishment, materials, equipment, mobilization and labor.	Acre	\$275.00
512	Pasture and Hay Planting (512)	Machinery, Sprigging & Seeding, Plant Material, Site Preparation & Establishment, materials, equipment, mobilization and labor.	Acre	\$292.30
516	Pipeline (516)	Plastic (PVC Schedule 40) 1/2 to 3/4 inch diameter pipeline, install from a storage tank to trough, and/or from trough to trough.	Lb.	\$12.70
516	Pipeline (516)	Plastic (PVC Schedule 40) 1 to 2 inch diameter pipeline, install to deliver water from a water source to a storage facility.	Lb.	\$9.15
521A	Pond Sealing or Lining (521A)	Installation of plastic mesh lining for a farm pond, material, equipment, labor and mobilization.	Sq. Ft.	\$1.90
528	Prescribed Grazing (528)	Establishment and management of appropriate grazing schedule, Proper Stocking Rate and Record Keeping.	Acre	\$2.40
533	Pumping Plant (533)	Deep Well, up to 10 HP, equipment (pump, motor and control box). Delivery, wiring and installation included.	Hp	\$589.00
533	Pumping Plant (533)	Deep Well, up to 10 HP/station, equipment (pump/motor/control box). Delivery, wiring and installation included. Pumping station, reinforced concrete floor, masonry wall, galvalum/metal roof.	Hp	\$1,516.00
533	Pumping Plant (533)	Standard centrifugal, up to 30 HP, equipment (pump, motor and control box). Delivery, installation and connection to pipeline included.	Hp	\$511.00
533	Pumping Plant (533)	Standard centrifugal, up to 30 HP/station, equipment (pump/motor/control box). Delivery/installation/connection to pipeline. Pump station, reinforced concrete floor, masonry wall, galvalum/metal roof	Hp	\$806.00
548	Grazing Land Mechanical Treatment (548)	Chiseling, Machinery, ≤20% slope, equipment, labor and mobilization.	Acre	\$297.00
552	Irrigation Regulating Reservoir (552)	Reservoir construction (excavation/fill) to store and regulate a water supply for irrigation, materials (pipe, rock, gravel, concrete, etc.), equipment, mobilization and labor.	Cu. Yd.	\$10.20
552	Irrigation Regulating Reservoir (552)	Plastic tank to store and regulate a water supply for irrigation. Cost includes materials (tank and fittings), installation and mobilization.	Gal.	\$0.80
555	Rock Barrier (555)	Construction of Rock Barrier, materials, equipment, mobilization and labor.	Cu. Yd.	\$98.00
558	Roof Runoff Structure (558)	Gutters and pipes to move rain water away from structures. Cost includes materials and installation.	Lin. Ft.	\$2.00
561	Heavy Use Area Protection (561)	Concrete pad (6" thick) under high-use area, on wet soils, materials, equipment, mobilization and labor.	Sq. Ft.	\$8.80
561	Heavy Use Area Protection (561)	Gravel pad (1" thick) under high-use area, on wet soils, materials, equipment, mobilization and labor.	Sq. Ft.	\$4.00
561	Heavy Use Area Protection (561)	Gabion pad (9" thick) under high-use area, on wet soils, materials, equipment, mobilization and labor.	Sq. Ft.	\$7.00
590	Nutrient Management (590)	NPK Application/Soil Test & Record Keeping.	Acre	\$15.50
595	Pest Management (595)	IPM_ Integrated Pest Management Record keeping, scouting for pest management implementation.	Acre	\$31.30
601	Vegetative Barrier (601)	Cuttings or Seedlings, planting, materials, equipment, mobilization and labor.	Lin. Ft.	\$0.73
612	Tree/Shrub Establishment (612)	Tree Establishment, (Per Tree), materials, equipment, mobilization and labor.	Each	\$13.70
614	Watering Facility (614)	Storage tank or troughs for watering facility, materials, equipment, labor and mobilization.	Cu. Yd.	\$430.00
614	Watering Facility (614)	Installation of plastic tank to store water for watering facility, materials (tank and fittings), equipment, labor and mobilization.	Gal.	\$0.80
632	Solid/Liquid Waste Separation Facility (632)	Concrete/masonry settling tank with roof (metal/galvalum), materials, equipment, labor and mobilization.	Sq. Ft.	\$43.20
633	Waste Utilization (633)	Includes manure application rate, application scheduling and record keeping.	Acre	\$11.00
634	Waste Transfer (634)	Manure irrigation system, materials (PVC pipeline, valves, fittings, guns, etc), equipment (includes slurry pump), labor and mobilization. External power source and water source not included.	Acre	\$4,350.00
634	Waste Transfer (634)	Conduit-Concrete ditch or Plastic Pipe , materials and installation.	LnFt	\$62.10
642	Water Well (642)	Water well, drilling, installation and well pumping test.	Foot	\$50.40
751	Individual Terrace (751)	Construction of small rounded platform for tree and shrub planting on very steep slopes (>15%). Incentive Payment_Single Payment	Ea.	\$0.63

**EQIP 2008 REGULAR EQIP Cost List 75%, USVI
FY 2010**

Code	Practice	Component	Units	Unit Cost
102	Comprehensive Nutrient Management Plan (No.)	Comprehensive Nutrient Management Plan (CNMP)-Written. Only certified Technical Service Providers (TSPs) qualify for payment.	No.	\$3,480.00
313	Waste Storage Facility (313)	Pond construction (excavation/fill), materials (pipe, rock, gravel, concrete, etc.), equipment, mobilization & labor.	Cu. Yd.	\$8.50
313	Waste Storage Facility (313)	Tank reinforced concrete construction, materials, equipment, mobilization & labor.	Cu. Yd.	\$358.00
313	Waste Storage Facility (313)	Stacking facility Construction , 3 walls concrete structure with roof (metal/galvalum) , material, equipment, mobilization & labor.	Sq. Ft.	\$36.00
314	Brush Management (314)	Hand Clearing, woody invasion, equipment, mobilization and labor. Payment for three (3) consecutive yrs.	Acre	\$188.30
314	Brush Management (314)	Chemical Control woody invasion, equipment, mobilization and labor.Payment for three (3) consecutive yrs	Acre	\$77.70
314	Brush Management (314)	Mechanical treatment woody invasion, utilizing wheel tractor with mower, equipment, mobilization and labor. Payment for three (3) consecutive yrs	Acre	\$110.20
328	Conservation Crop Rotation (328)	Crop Rotation; Idle ≥ 6 Months	Acre	\$172.00
329	Residue Management, No-Till/Strip Till (329)	Chemical or manual, materials, equipment, mobilization and labor.	Acre	\$177.30
330	Contour Farming (330)	Furrowing, Machine Plow, Soils slope < 20%, equipment, mobilization and labor.	Acre	\$324.80
330	Contour Farming (330)	field layout arrangement labor	Acre	\$40.70
331	Contour Orchard (331)	Contour Arrangement, labor. field layout arrangement	Acre	\$67.60
342	Critical Area Planting (342)	Sod, to stabilize an area after a structure construction. Includes shaping, earth moving, material, mobilization & installation.	Sq. Ft.	\$0.53
342	Critical Area Planting (342)	Seeding. Includes re-shaping and earth moving, materials, installation, labor & mobilization.	Acre	\$1,054.50
342	Critical Area Planting (342)	Shrub establishment. Includes re-shaping and earth moving, materials, installation, labor & mobilization.	Acre	\$2,596.60
345	Residue Management, Mulch Till (345)	Using disking to distribute uniformly crops & other plant residues. Residues shall be distributed over the entire field prior to planting, materials, equipment, mobilization and labor.	Acre	\$229.90
345	Residue Management, Mulch Till (345)	No-Till Chemical & Furrowing-Plow, equipment, mobilization and labor.	Acre	\$474.80
362	Diversion (362)	Diversion construction (excavation/fill), equipment, labor and mobilization.	Cu. Yd.	\$7.50
378	Pond (378)	Pond construction (excavation/fill), materials, (pipe, rock, gravel, concrete, etc.) equipment, mobilization and labor.	Cu. Yd.	\$6.90
381	Silvopasture Establishment (381)	Site Preparation, establish tree w/animal control barrier, materials, equipment, mobilization and labor.	Ea.	\$87.00
382	Fence (382)	Barbed & Goat Wire w/treated Wood or Steel Posts, w/gate, materials, equipment, mobilization and labor.	Lin. Ft.	\$4.10
382	Fence (382)	Live post perennial tree, Planted at recommended distances, materials, equipment, mobilization and labor.	Ea.	\$3.50
391	Riparian Forest Buffer (391)	Plant Material, establishment, materials, equipment, mobilization and labor.	Ea.	\$11.40
393	Filter Strip (393)	Plant Material, Site Preparation and Establishment, Seeding or Sprigging, materials, equipment, mobilization and labor.	Acre	\$1,494.75
412	Grassed Waterway (412)	Natural channel shaping or channel construction and establishment of suitable vegetation, materials, equipment, mobilization and labor.	Acre	\$15,269.00
430DD	Irrigation Water Conveyance, Pipeline, High-Pressure, Underground, Plastic, (430DD)	PVC pipeline 1/2 to 3/4" dia. for water conveyance, materials and installation. All other pipeline required for irrigation system is included in Practice 441.	Lb.	\$11.00
430DD	Irrigation Water Conveyance, Pipeline, High-Pressure, Underground, Plastic, (430DD)	PVC pipeline 1 to 2" dia. for water/waste conveyance, materials and installation. All other pipeline required for irrigation system is included in Practice 441.	Lb.	\$7.60
430DD	Irrigation Water Conveyance, Pipeline, High-Pressure, Underground, Plastic, (430DD)	PVC pipeline > 2" dia. for water/waste conveyance, materials and installation. All other pipeline required for irrigation system is included in Practice 441.	Lb.	\$4.60
441	Irrigation System, Microirrigation (441)	Installation of Drip-Tape system, materials (tape, PVC pipeline, valves, fittings, filters, etc.), equipment, mobilization & labor. Pump, power, and water source not included.	Acre	\$2,211.00
441	Irrigation System, Microirrigation (441)	Install PE tubing system, materials (PE tubing, emitters, PVC pipeline, valves, fittings, filters, etc.), equipment, mobilization and labor. Pump, power, and water source not included.	Acre	\$2,645.00
449	Irrigation Water Management (449)	Includes record keeping (crop grown, irrigation dates, inches of irrigation, set length & inches of rainfall), soil moisture determined by feel or sensors, control & monitoring of irrigation water.	Acre	\$1.50
460	Land Clearing (460)	Machinery for structural practice, equipment, labor and mobilization.	Acre	\$270.00
472	Access Control (472)	Goat/Barbed Wire w/Steel or Treated Wood Posts, materials, equipment, mobilization and labor.	Lin. Ft.	\$4.10
472	Access Control (472)	Living Stake Posts, planted at recommended distances, materials, equipment, mobilization and labor.	Each	\$3.50
472	Access Control (472)	Posting sign, equipment, mobilization and labor.	Each	\$38.70
484	Mulching (484)	Straw mulching (bales), 2-4" cover depth erosion & moisture control, materials, equipment, mobilization and labor.	Acre	\$249.60
490	Tree/Shrub Site Preparation (490)	Chemical, materials, mobilization and labor.	Each	\$0.70

490	Tree/Shrub Site Preparation (490)	Hand treating (hoe, machete, other), mobilization and labor.	Each	\$2.30
490	Tree/Shrub Site Preparation (490)	Hand/Chemical treating (hoe, machete, other), mobilization and labor.	Each	\$2.60
511	Foraje Harvest Management (511)	Taking forage sample for chemical analysis in 10 acres of hayland	Acre	\$5.90
512	Pasture and Hay Planting (512)	No Machinery, Sprigging & Seeding, Plant Material, Site Preparation & Establishment, materials, equipment, mobilization and labor.	Acre	\$229.00
512	Pasture and Hay Planting (512)	Machinery, Sprigging & Seeding, Plant Material, Site Preparation & Establishment, materials, equipment, mobilization and labor.	Acre	\$243.80
516	Pipeline (516)	Plastic (PVC Schedule 40) 1/2 to 3/4 inch diameter pipeline, install from a storage tank to trough, and/or from trough to trough.	Lb.	\$10.60
516	Pipeline (516)	Plastic (PVC Schedule 40) 1 to 2 inch diameter pipeline, install to deliver water from a water source to a storage facility.	Lb.	\$7.60
521A	Pond Sealing or Lining (521A)	Installation of plastic mesh lining for a farm pond, material, equipment, labor and mobilization.	Sq. Ft.	\$1.64
528	Prescribed Grazing (528)	Establishment and management of appropriate grazing schedule, Proper Stocking Rate and Record Keeping.	Acre	\$2.00
533	Pumping Plant (533)	Deep Well, up to 10 HP, equipment (pump, motor and control box). Delivery, wiring and installation included.	Hp	\$491.00
533	Pumping Plant (533)	Deep Well, up to 10 HP/station, equipment (pump/motor/control box). Delivery, wiring and installation included. Pumping station, reinforced concrete floor, masonry wall, galvalum/metal roof.	Hp	\$1,263.00
533	Pumping Plant (533)	Standard centrifugal, up to 30 HP, equipment (pump, motor and control box). Delivery, installation and connection to pipeline included.	Hp	\$426.00
533	Pumping Plant (533)	Standard centrifugal, up to 30 HP/station, equipment (pump/motor/control box). Delivery/installation/connection to pipeline. Pump station, reinforced concrete floor, masonry wall, galvalum/metal roof	Hp	\$671.00
548	Grazing Land Mechanical Treatment (548)	Chiseling, Machinery, ≤20% slope, equipment, labor and mobilization.	Acre	\$248.00
552	Irrigation Regulating Reservoir (552)	Reservoir construction (excavation/fill) to store and regulate a water supply for irrigation, materials (pipe, rock, gravel, concrete, etc.), equipment, mobilization and labor.	Cu. Yd.	\$8.50
552	Irrigation Regulating Reservoir (552)	Plastic tank to store and regulate a water supply for irrigation. Cost includes materials (tank and fittings), installation and mobilization.	Gal.	\$0.70
555	Rock Barrier (555)	Construction of Rock Barrier, materials, equipment, mobilization and labor.	Cu. Yd.	\$82.00
558	Roof Runoff Structure (558)	Gutters and pipes to move rain water away from structures. Cost includes materials and installation.	Lin. Ft.	\$1.65
561	Heavy Use Area Protection (561)	Concrete pad (6" thick) under high-use area, on wet soils, materials, equipment, mobilization and labor.	Sq. Ft.	\$7.20
561	Heavy Use Area Protection (561)	Gravel pad (1" thick) under high-use area, on wet soils, materials, equipment, mobilization and labor.	Sq. Ft.	\$3.50
561	Heavy Use Area Protection (561)	Gabion pad (9" thick) under high-use area, on wet soils, materials, equipment, mobilization and labor.	Sq. Ft.	\$6.00
590	Nutrient Management (590)	NPK Application/Soil Test & Record Keeping.	Acre	\$13.00
595	Pest Management (595)	IPM Integrated Pest Management Record keeping, scouting for pest management implementation.	Acre	\$26.10
601	Vegetative Barrier (601)	Cuttings or Seedlings, planting, materials, equipment, mobilization and labor.	Lin. Ft.	\$0.60
612	Tree/Shrub Establishment (612)	Tree Establishment, (Per Tree), materials, equipment, mobilization and labor.	Each	\$11.40
614	Watering Facility (614)	Storage tank or troughs for watering facility, materials, equipment, labor and mobilization.	Cu. Yd.	\$359.00
614	Watering Facility (614)	Installation of plastic tank to store water for watering facility, materials (tank and fittings), equipment, labor and mobilization.	Gal.	\$0.70
632	Solid/Liquid Waste Separation Facility (632)	Concrete/masonry settling tank with roof (metal/galvalum), materials, equipment, labor and mobilization.	Sq. Ft.	\$36.00
633	Waste Utilization (633)	Includes manure application rate, application scheduling and record keeping.	Acre	\$8.75
634	Waste Transfer (634)	Manure irrigation system, materials (PVC pipeline, valves, fittings, guns, etc), equipment (includes slurry pump), labor and mobilization. External power source and water source not included.	Acre	\$3,625.00
634	Waste Transfer (634)	Conduit-Concrete ditch or Plastic Pipe, materials and installation.	LnFt	\$51.80
642	Water Well (642)	Water well, drilling, installation and well pumping test.	Foot	\$42.00
751	Individual Terrace (751)	Construction of small rounded platform for tree and shrub planting on very steep slopes (>15%). Incentive Payment_Single Payment	Ea.	\$0.53