
CONSTRUCTION SPECIFICATION
CS-OR-231 VEGETATION OF CONSTRUCTION SITES

231.1 SCOPE

The work shall consist of furnishing seed and fertilizer, seedbed preparation, and seeding of all areas which were disturbed during construction or on specific areas which are shown the drawings or described in Section 231.5 of this specification, Items of Work and Construction Details.

231.2 FERTILIZER

Fertilizer shall be applied at the minimum rates of 30 lbs/ac of actual nitrogen. Other elements may be applied at the rate as determined by soil testing. If the fertilizer is applied to the surface, it shall be mixed with the soil prior to seeding. If fertilizer other than nitrogen at the rate of 30 lbs/ac is to be applied, the fertilizer and application rate will be indicated in Section 231.5 of this specification, Items of Work and Construction Details.

231.3 SEED

The areas shall be seeded to a grass species or mixture of grasses or legumes at the rate of pure live seed per acre as indicated in Section 231.5 of this specification, Items of Work and Construction Details.

231.4 SEEDING

The seeding will be performed when moisture is adequate for germination and establishment. Prepare the seedbed as for pasture and hayland plantings as common for the climatic area. The seeding will be accomplished in the seeding dates as common for the area unless otherwise specified in Section 231.5 of this specification, Items of Work and Construction Details.

When broadcasting, the seeded area will be mulched with 2,000 pounds of grain straw per acre. Grain straw will be used, unless other mulching material and application rate is indicated in Section 231.5 of this specification, Items of Work and Construction Details.

231.5 ITEMS OF WORK AND CONSTRUCTION DETAILS