

DELAWARE CONSTRUCTION SPECIFICATION

STRUCTURE REMOVAL CS 3

1. SCOPE

The work shall consist of the removal, salvage and disposal of structures (including buried structures and fences) from the designated areas.

2. MARKING

The limits of the areas from which structures must be removed will be marked by means of stakes, flags or other suitable methods. Structures to be preserved in place or salvaged will be designated by special markings.

3. REMOVAL

Within the areas so marked all visible structures and attachments and all buried structures located and identified by survey stakes shall be removed to the specified extent and depth or as designated by the technician.

4. SALVAGE

Structures that are designated to be salvaged shall be carefully removed and neatly placed in the specified storage areas. Salvaged structures that are capable of being disassembled shall be dismantled into individual members or sections. Such structures shall be neatly match marked with paint prior to disassembly. All pins, nuts, bolts, washers, plates and other loose parts shall be marked or tagged to indicate their proper locations in the structure and shall be fastened to the appropriate structural member or packed in suitable containers. Materials from fences designated to be salvaged shall be placed outside the work area on the property from which they were removed. Wire shall be rolled into uniform rolls of convenient size. Posts and rails shall be neatly piled.

5. DISPOSAL OF REFUSE MATERIALS

Unless otherwise shown on the plans, all materials resulting from structure removal shall be burned or buried at locations approved by the technician or otherwise removed from the site. Burning operations and burial operations shall be subject to all public laws governing such operations.