

DELAWARE CONSTRUCTION SPECIFICATION

CHANNEL CLEARING AND SHAPING CS 4

1. **SCOPE**

The work shall consist of the clearing of designated areas by the removal and disposal of trees, logs, stumps, snags, shrubs, brush, and rubbish, and the shaping of the channel.

2. **MARKING**

The limits of the areas to be cleared and shaped will be marked by means of stakes, flags, tree markings or other suitable methods, or will be shown on the drawings. Trees to be left standing and uninjured will be designated by special markings.

3. **CLEARING**

Unless otherwise specified, trees not marked for preservation and other woody vegetation shall be cut off as near the ground surface as conventional tools or field conditions will permit. All trees not marked for preservation and all snags, logs, brush, shrubs, stumps, and rubbish shall be cleared from within the limits of the designated areas.

4. **DISPOSAL**

All materials cleared from the designated areas shall be disposed of in the locations and in the manner shown on the drawings.

5. **SHAPING**

The bottom and sides of the channel shall be shaped to be reasonably smooth. Material shall be excavated and removed from the channel as shown on the drawings.