



NOTE: WHEN THE PIPE IS BEING INSTALLED WITHIN 12" OF THE FLOOR, REMOVE THE BOTTOM REBAR. WHEN THE PIPE IS GREATER THAN 3' ABOVE FLOOR, BOTTOM BARS DO NOT NEED TO BE BENT.

**NOTES:**

1. CUT ALL VERTICAL AND RING STEEL 2 INCHES FROM OPENING.
2. FOR EACH RING STEEL BAR INTERRUPTED BY THE OPENING, INSTALL ONE #5 BAR AROUND EACH SIDE OF THE OPENING. A MINIMUM OF 2 - #5 BARS ARE TO BE USED ALONG EACH SIDE.

N.T.S.



CIRCULAR CONCRETE STORAGE FACILITY  
 DETAIL OF PIPE PROTRUDING THROUGH WALL

ISSUE DATE: 12/04  
 DRAWING NO. CT-3D