# Skills Matrix Master

| Conservation Practice | | Lead Discipline | | Controlling Factor | Units | Job Class I | II | III | IV | V | VI |
|---|---|---|---|---|---|---|---|---|---|---|---|
| ALL PRACTICES | | | | | | | | | | | |
| 0 | Hazard Potential-Any Practice | Engineering | CED | Class (Low, Medium or High) | class | Low | Low | Low | Low | Low | Significant |
| GROUPED PRACTICES - AGRICULTURAL WASTE | | | | | | | | | | | |
| 366 | Anaerobic Digester(no) | Engineering | CED-EE | Anaerobic - Volume | cu. ft. x 1000 | 200 | 400 | 750 | 1000 | 2000 | 5000 |
| 316 | Animal Mortality Facility (no) | Engineering | CED-EE | Capacity | cu. ft. x 1000 | none | 100 | 500 | 1000 | 2000 | all |
| 353 | Monitoring Well (ea) | Engineering | CED-EG | Depth | feet | none | all | all | all | all | all |
| 367 | Roofs and Covers (no) | Engineering | CED-EE | Surface Area | acre | 1 | 2 | 4 | 6 | 10 | all |
| 632 | Solid/Liquid Waste Separation Facility | Engineering | CED-EE | Capacity | GPD | 1000 | 5000 | 20000 | 50000 | 100000 | all |
| 635 | Vegetated Treatment Area(ac) | Engineering | CED-EE | Area | acre | 0.5 | 2 | 5 | 10 | 20 | all |
| 360 | Waste Facility Closure | Engineering | CED-EE & ESD-NM | Surface Area | acre | 1 | 2 | 4 | 6 | 10 | all |
| 633 | Waste Reycling (tons) | Engineering | CED-EE | Volume Recycled | Tons/year | 12000 | 24000 | 36000 | 48000 | 60000 | all |
| 313 | Waste Storage Facility (no) | Engineering | CED-EE | Conc. Wall Ht. - Above Ground | feet | 4 | 5 | 6 | 7 | 8 | all |
| | | Engineering | CED-EE | Conc. Wall Ht. - Below Ground | feet | none | none | 4 | 6 | 8 | all |
| | | Engineering | CED-EE | Storage Capacity | cu. ft. x 1000 | none | none | 500 | 1000 | 2000 | 5000 |
| 634 | Waste Transfer (no) | Engineering | CED-EE | Number | each | none | all | all | all | all | all |
| 629 | Waste Treatment | Engineering | CED-EE | Animal Units | each | 100 | 500 | 1000 | 2000 | 4000 | all |
| 359 | Waste Treatment Lagoon (no) | Engineering | CED-EE | Aerobic Surface Area | acre | 1 | 2 | 4 | 6 | 25 | 50 |
| | | Engineering | CED-EE | Anaerobic Volume | cu. ft. x 1000 | 200 | 400 | 750 | 1000 | 2000 | 5000 |
| | | Engineering | CED-EE | Effective Height | feet | 4 | 6 | 8 | 10 | 35 | all |
| GROUPED PRACTICES - DAMS, STRUCTURES, & EARTHEN EMBANKMENTS | | | | | | | | | | | |
| 397 | Aquaculture Ponds (ac) | Engineering | CED-AE & ESD-AqEco | Drainage Area | sq. mi. | 1 | 2 | 10 | 15 | 20 | 40 |
| | | Engineering | CED-AE & ESD-AqEco | Effective Height | feet | 5 | 10 | 15 | 20 | 25 | all |
| | | Engineering | CED-AE & ESD-AqEco | Embankment over Active Fault | each | none | none | none | none | none | none |
| | | Engineering | CED-AE & ESD-AqEco | Depth | feet | 6 | 12 | 15 | 20 | all | all |

| Conservation Practice | | Lead Discipline | | Controlling Factor | Units | Job Class I | II | III | IV | V | VI |
|---|---|---|---|---|---|---|---|---|---|---|---|
| GROUPED PRACTICES - DAMS, STRUCTURES, & EARTHEN EMBANKMENTS | | | | | | | | | | | |
| 402 | Dam (no & ac-ft) | Engineering | CED-DE | Drainage Area | sq. mi. | 1 | 2 | 10 | 15 | 20 | 40 |
| | | Engineering | CED-DE | Effective Height | feet | 5 | 10 | 15 | 20 | 25 | 50 |
| | | Engineering | CED-DE | Embankment over Active Fault | each | none | none | none | none | none | none |
| 348 | Dam, Diversion (no) | Engineering | CED-DE | Streamflow (25 yr. freq.) | cfs | 500 | 750 | 1000 | 1500 | 2000 | 3000 |
| | | Engineering | CED-DE | Flow Diverted | cfs | 10 | 25 | 100 | 150 | 200 | 500 |
| | | Engineering | CED-DE | Height of Drop | feet | 1 | 2 | 4 | 6 | 8 | 15 |
| 356 | Dike (ft) | Engineering | CED-HE | Class III only-Water Height | feet | 2 | 4 | 6 | 8 | 10 | all |
| 410 | Grade Stabilization Structure (no) | Engineering | CED-DE | Full-flow-Drainage Area | acre | 20 | 80 | 300 | 600 | 1200 | 2400 |
| | | Engineering | CED-DE | Detention-Drainage Area | sq. mi. | 1 | 2 | 10 | 15 | 20 | 40 |
| | | Engineering | CED-DE | Detention-Effective Height | feet | 5 | 10 | 15 | 20 | 25 | 50 |
| | | Engineering | CED-DE | Detention-Embankment over Active Fault | each | none | none | none | none | none | none |
| 436 | Irrigation Reservoir (no & ac-ft) | Engineering | CED-WME | Earthen-Drainage Area | sq. mi. | 1 | 2 | 10 | 15 | 20 | 40 |
| | | Engineering | CED-WME | Earthen-Effective Height | feet | 5 | 10 | 15 | 20 | 25 | 50 |
| | | Engineering | CED-WME | Embankment over Active Fault | each | none | none | none | none | none | none |
| | | Engineering | CED-WME | Non-Earthen-Standard Design | gallons | 5000 | 15000 | 25000 | 50000 | 100000 | all |
| | | Engineering | CED-WME | Non-Earthen-Fiberglass | gallons | 2000 | 5000 | 10000 | 15000 | 25000 | all |
| 378 | Pond (no) | Engineering | CED-DE | Drainage Area | sq. mi. | 1 | 2 | 10 | 15 | 20 | 40 |
| | | Engineering | CED-DE | Effective Height | feet | 5 | 10 | 15 | 20 | 25 | all |
| | | Engineering | CED-DE | Embankment over Active Fault | each | none | none | none | none | none | none |
| | | Engineering | CED-DE | Excavated-Depth | feet | 6 | 12 | 15 | 20 | all | all |
| 350 | Sediment Basin (no) | Engineering | CED-DE | Drainage Area | sq. mi. | 1 | 2 | 10 | 15 | 20 | 40 |
| | | Engineering | CED-DE | Effective Height | feet | 5 | 10 | 15 | 20 | 25 | 50 |
| | | Engineering | CED-DE | Embankment over Active Fault | each | none | none | none | none | none | none |
| 638 | Water and Sediment Control Basin (no) | Engineering | CED-AE | Drainage Area | acre | none | 1 | 2 | 5 | 20 | all |
| | | Engineering | CED-AE | Height of Fill | feet | none | 5 | 10 | 15 | all | all |
| GROUPED PRACTICES - IRRIGATION | | | | | | | | | | | |
| 464 | Irrigation Land Leveling (ac) | Engineering | CED-WME | Area Leveled | acre | 20 | 40 | 80 | 320 | 640 | all |
| 441 | Irrigation System, Microirrigation (no & ac) | Engineering | CED-WME | Area Benefited | acre | 5 | 20 | 80 | 160 | 640 | all |

| Conservation Practice | | Lead Discipline | | Controlling Factor | Units | Job Class I | II | III | IV | V | VI |
|---|---|---|---|---|---|---|---|---|---|---|---|
| GROUPED PRACTICES - IRRIGATION | | | | | | | | | | | |
| 442 | Irrigation System, Sprinkler (no & ac) | Engineering | CED-WME | Area Benefited | acre | 10 | 40 | 160 | 320 | 640 | all |
| 443 | Irrigation System, Surface and Subsurface (no & ac) | Engineering | CED-WME | Area Benefited | acre | 10 | 40 | 160 | 320 | 640 | all |
| 447 | Irrigation System, Tailwater Recovery (no) | Engineering | CED-WME | Area Benefited | acre | 10 | 40 | 160 | 320 | 640 | all |
| | | Engineering | CED-WME | Pump Capacity | cfs | 1 | 2 | 3 | 5 | 10 | all |
| 449 | Irrigation Water Management (ac) | Engineering | CED-WME & ESD-Agron | Area Benefited | acre | 40 | 160 | 640 | 1500 | 3000 | all |
| GROUPED PRACTICES - IRRIGATION CONVEYANCE | | | | | | | | | | | |
| 320 | Irrigation Canal or Lateral (ft) | Engineering | CED-WME | Design Capacity | cfs | 5 | 10 | 20 | 50 | 500 | 1000 |
| 428 | Irrigation Ditch Lining | Engineering | CED-WME | Design Capacity | cfs | 5 | 10 | 20 | 50 | 100 | all |
| 388 | Irrigation Field Ditch (ft) | Engineering | CED-WME | Design Capacity | cfs | 2 | 5 | 10 | 20 | 30 | all |
| 430 | Irrigation Pipeline | Engineering | CED-WME | ≥ 50 psi-Design Capacity | gpm | 250 | 500 | 1000 | 2500 | 3500 | all |
| | | Engineering | CED-WME | < 50 psi-Design Capacity | gpm | 450 | 1000 | 2000 | 4000 | 5000 | all |
| | | Engineering | CED-WME | Open Channel Flow within Pipe-Design Capacity | cfs | 5 | 10 | 20 | 50 | 100 | all |
| GROUPED PRACTICES - LIVESTOCK WATER | | | | | | | | | | | |
| 516 | Pipeline (ft) | Engineering | CED-WME | Length | mile | 2 | 5 | 10 | 20 | 25 | all |
| | | Engineering | CED-WME | Diameter | inch | 1.25 | 1.5 | 2 | 4 | 6 | all |
| | | Engineering | CED-WME | Static Pressure | psi | 50 | 100 | 200 | 250 | 300 | all |
| 533 | Pumping Plant (no) | Engineering | CED-WME | Livestock Well Pumps-Static Head | feet | 100 | 200 | 400 | 600 | 1000 | all |
| 642 | Water Well (no) | Engineering | CED-EG | Livestock Well-Depth | feet | 100 | 200 | 400 | 600 | 1000 | all |
| 614 | Watering Facility (no) | Engineering | CED-AE & ESD-WBio | Fiberglass-Capacity | gallons | 2000 | 5000 | 10000 | 15000 | 25000 | all |
| | | Engineering | CED-AE & ESD-WBio | Rubber Tire-Capacity | gallons | 200 | 400 | 800 | 1200 | 2000 | all |
| | | Engineering | CED-AE & ESD-WBio | Standard Design-Capacity | gallons | 5000 | 15000 | 25000 | 50000 | 100000 | all |
| GROUPED PRACTICES - SPILLWAY STRUCTURES | | | | | | | | | | | |
| 587 | Structure for Water Control (no) | Engineering | CED-DE | Reinforced or Formless Concrete Chute-Net Drop | feet | 2 | 6 | 8 | 10 | 12 | all |
| | | Engineering | CED-DE | Reinforced or Formless Concrete Chute-Weir Depth | feet | 1.5 | 3 | 3 | 3 | 3 | all |
| | | Engineering | CED-DE | Reinforced or Formless Concrete Chute-Design Capacity | cfs | 10 | 100 | 200 | 300 | 300 | all |
| | | Engineering | CED-DE | Box Inlet Drop Spillways-Net Drop | feet | none | 3 | 4 | 5 | 6 | all |

| Conservation Practice | | Lead Discipline | | Controlling Factor | Units | Job Class I | II | III | IV | V | VI |
|---|---|---|---|---|---|---|---|---|---|---|---|
| GROUPED PRACTICES - SPILLWAY STRUCTURES | | | | | | | | | | | |
| 587 | Structure for Water Control (no) | Engineering | CED-DE | Box Inlet Drop Spillways-Design Capacity | cfs | none | 100 | 300 | 400 | 500 | all |
| | | Engineering | CED-DE | Prefabricated Conduits (single)-Inside Diameter | inch | 12 | 15 | 24 | 36 | 48 | all |
| | | Engineering | CED-DE | Box Culvert-Area of Opening (Std. Dwg.) | sq. ft. | none | none | none | 9 | 16 | all |
| | | Engineering | CED-DE | Straight Drop Spillway (Std. Type B, C, F)-Net Drop | feet | none | 6 | 6 | 7 | 8 | all |
| | | Engineering | CED-DE | Straight Drop Spillway (Std. Type B, C, F)-Weir Depth | feet | none | 2 | 3 | 4 | 5 | all |
| | | Engineering | CED-DE | Straight Drop Spillway (Std. Type B, C, F)-Design Capacity | cfs | none | 100 | 300 | 400 | 500 | all |
| GROUPED PRACTICES - STRUCTURES FOR WATER CONTROL | | | | | | | | | | | |
| 587 | Structure for Water Control (no) | Engineering | CED-DE | Slide Gate-Head, ≥ 10 feet (Capacity) | cfs | none | 10 | 50 | 100 | 200 | all |
| | | Engineering | CED-DE | Slide Gate-Head, < 10 feet (Capacity) | cfs | 10 | 50 | 200 | 400 | 500 | all |
| | | Engineering | CED-DE | Pipe, Turnout, Check, Division Box-Design Capacity | cfs | 5 | 10 | 25 | 50 | 500 | all |
| | | Engineering | CED-DE | Hi-Flow Turnouts-Design Capacity | cfs | none | none | 10 | 20 | 30 | all |
| | | Engineering | CED-DE | Long Span Supported Pipe-Design Capacity | cfs | none | 3 | 5 | 10 | 25 | all |
| | | Engineering | CED-DE | Long Span Supported Pipe-Total Length | feet | none | 40 | 80 | 120 | 200 | all |
| | | Engineering | CED-DE | Long Span Supported Pipe-Max. Unsupported Length | feet | none | 10 | 20 | 30 | 45 | all |
| | | Engineering | CED-DE | Long Span Supported Pipe-Max. Ht. Above Ground | feet | none | 5 | 8 | 10 | 15 | all |
| | | Engineering | CED-DE | Siphon (Inverted or Sag Pipe)-Head | feet | none | 3 | 6 | 8 | 10 | all |
| | | Engineering | CED-DE | Siphon (Inverted or Sag Pipe)-Design Capacity | cfs | none | 10 | 20 | 50 | 100 | all |
| INDIVIDUAL PRACTICES | | | | | | | | | | | |
| 560 | Access Road (ft) | Engineering | CED-AE | Length | feet x 1000 | 2 | 5 | 10 | 20 | 40 | all |
| | | Engineering | CED-AE | Culvert Pipe, ID | feet | 1.5 | 2 | 3 | 4 | 6 | all |
| | | Engineering | CED-AE | Monolithic Concrete Opening | sq. ft. | none | 4 | 9 | 16 | 25 | all |
| | | Engineering | CED-AE | Bridge Span | feet | none | 12 | 16 | 20 | 24 | all |
| | | Engineering | CED-AE | Surface Treatment | type | soil | soil | gravel | asphalt | concrete | all |
| 371 | Air Filtration and Scrubbing (no) | Engineering | CED-AQS & ESD-ARS | Air Flow | cfm x 1000 | 2 | 5 | 10 | 20 | all | all |

| Conservation Practice | | Lead Discipline | | Controlling Factor | Units | Job Class I | II | III | IV | V | VI |
|---|---|---|---|---|---|---|---|---|---|---|---|
| INDIVIDUAL PRACTICES | | | | | | | | | | | |
| 575 | Animal Trails and Walkways (ft) | Engineering | CED-AE & ESD-Graz Land Sp | Length | mile | 1 | 3 | 5 | 10 | 15 | all |
| 450 | Anionic Polyacrylamide (PAM) Application (ac) | Engineering | CED-WME | Area Benefited | acre | 40 | 160 | 640 | 1500 | 3000 | all |
| 310 | Bedding (ac) | Engineering | CED-WME | Area | acre | 10 | 40 | 160 | 320 | 640 | all |
| 584 | Channel Bed Stabilization (ft) | Engineering | CED-EG | Design Capacity | cfs | 100 | 200 | 300 | 500 | 1000 | 2000 |
| | | Engineering | CED-EG | Design Velocity | fps | 4 | 6 | 6 | 8 | 10 | 12 |
| 326 | Clearing and Snagging (ft) | Engineering | CED-CE | Stream Flow (25 yr. freq.) | cfs | none | 500 | 1000 | 2000 | 3000 | all |
| | | Engineering | CED-CE | Reach Length | feet | none | 1000 | 2500 | 5000 | 20000 | all |
| 372 | Combustion System Improvement (no) | Engineering | CED-AQS & ESD-ARS | Number | each | none | none | none | 1 | all | all |
| 317 | Composting Facility | Engineering | CED-EE & ESD-NM | Treatment Area | sq. yd. | 50 | 100 | 200 | 500 | 1000 | all |
| 656 | Constructed Wetland (no) | Engineering | CED-EE | Surface Area | acre | 0.25 | 0.5 | 2.0 | 4.0 | all | all |
| 362 | Diversion (ft) | Engineering | CED-AE | Design Capacity | cfs | 20 | 100 | 250 | 500 | 700 | all |
| 554 | Drainage Water Management (ac) | Engineering | CED-WME | Area Benefited | acre | 10 | 20 | 80 | 160 | 320 | all |
| 432 | Dry Hydrant (no) | Engineering | CED-HE | Number | each | none | all | all | all | all | all |
| 375 | Dust Control from Animal Activity on Open Lot Surfaces | Engineering | CED-AQS & ESD-ARS | Area of Application | acre | 5 | 10 | 20 | 30 | all | all |
| 373 | Dust Control on Unpaved Roads and Surfaces (sq. ft.) | Engineering | CED-AQS & ESD-ARS | Area of Application | sq. ft. x 1000 | 50 | 100 | 500 | 1000 | all | all |
| 374 | Farmstead Energy Improvement | Engineering | CED-AE | Energy Saved | Kilowatts /yr | 2 | 5 | 10 | 15 | all | all |
| | | Engineering | CED-AE | Reduced Energy Used | % Reductio n/year | 10 | 20 | 30 | 40 | all | all |
| 412 | Grassed Waterway (ac) | Engineering | CED-AE & ESD-Agron | Design Capacity | cfs | 10 | 20 | 40 | 80 | 100 | all |
| 561 | Heavy Use Area Protection (ac) | Engineering | CED-AE | Area | acre | 1 | 2 | 5 | 10 | 20 | all |
| 423 | Hillside Ditch (ft) | Engineering | CED-AE | Area Benefited | acre | 20 | 40 | 80 | 160 | 320 | all |
| 460 | Land Clearing (ac) | Engineering | CED-AE | Area Benefited | acre | 40 | 160 | 640 | 1500 | 3000 | all |
| 466 | Land Smoothing (ac) | Engineering | CED-AE | Area Benefited | acre | 40 | 80 | 320 | 640 | 1500 | all |
| 500 | Obstruction Removal (ac) | Engineering | CED-AE | 3-dimensional features | cu. yd. | 500 | 7000 | 13500 | 20000 | all | all |
| | | Engineering | CED-AE | linear features | feet | 500 | 1500 | 3000 | 4500 | all | all |
| 582 | Open Channel (ft) | Engineering | CED-DE | Design Capacity | cfs | 100 | 200 | 300 | 500 | 1000 | 2000 |

| Conservation Practice | | Lead Discipline | | Controlling Factor | Units | Job Class I | II | III | IV | V | VI |
|---|---|---|---|---|---|---|---|---|---|---|---|
| INDIVIDUAL PRACTICES | | | | | | | | | | | |
| 582 | Open Channel (ft) | Engineering | CED-DE | Design Velocity | fps | 4 | 5 | 6 | 8 | 10 | 12 |
| 521C | Pond Sealing or Lining, Bentonite Treatment (no) | Engineering | CED-SE | Head on Lining | feet | 4 | 8 | 10 | 15 | 20 | all |
| | | Engineering | CED-SE | Area Treated | acre | 1 | 2 | 4 | 6 | 10 | all |
| 521A | Pond Sealing or Lining, Flexible Membrane | Engineering | CED-CE | Area Treated | acre | 1 | 2 | 4 | 6 | 10 | all |
| | | Engineering | CED-CE | Head on Lining | feet | 4 | 8 | 10 | 15 | 20 | all |
| 521B | Pond Sealing or Lining, Soil Dispersersant (no) | Engineering | CED-SE | Head on Lining | feet | 4 | 8 | 10 | 15 | 20 | all |
| | | Engineering | CED-SE | Area Treated | acre | 1 | 2 | 4 | 6 | 10 | all |
| 462 | Precision Land Forming (ac) | Engineering | CED-AE | Area Benefited | acre | 20 | 40 | 80 | 320 | 640 | all |
| 533 | Pumping Plant (no) | Engineering | CED-WME | Centrifugal Pump-Design Capacity | gpm | 500 | 1000 | 2000 | 3000 | 3500 | 5000 |
| | | Engineering | CED-WME | Centrifugal Pump-Static Head | feet | 30 | 50 | 75 | 100 | 350 | 500 |
| | | Engineering | CED-WME | Propeller Pump-Design Capacity | gpm | 500 | 1500 | 2500 | 5000 | 50000 | 100000 |
| | | Engineering | CED-WME | Propeller Pump-Static Head | feet | 15 | 15 | 15 | 15 | 15 | all |
| | | Engineering | CED-WME | Turbine Pump-Design Capacity | gpm | 5 | 10 | 20 | 900 | 3500 | 5000 |
| | | Engineering | CED-WME | Turbine Pump-Static Head | feet | 100 | 150 | 200 | 250 | 500 | 1000 |
| 562 | Recreation Area Improvement (ac) | Engineering | CED-LA& ESD-For | Area | acre | 5 | 10 | 20 | 40 | 80 | all |
| 558 | Roof Runoff Structure (no) | Engineering | CED-EE | Area | sq. ft. | 1500 | 3000 | 5000 | 10000 | 40000 | all |
| 557 | Row Arrangement (ac) | Engineering | CED-AE | Area | acre | 40 | 160 | 640 | 1000 | 2000 | all |
| 610 | Salinity and Sodic Soil Management (ac) | Engineering | CED-WME & ESD-Agron | Area | acre | 40 | 160 | 640 | 1000 | 2000 | all |
| 572 | Spoil Spreading (ac) | Engineering | CED-AE | Cy/Ft. of Ditch | cy. | 2 | 5 | 10 | 20 | 50 | all |
| 574 | Spring Development (no) | Engineering | CED-WME | Yield | gpm | 5 | 10 | 20 | 50 | 100 | all |
| 570 | Stormwater Runoff Control (no & ac) | Engineering | CED-AE | Drainage Area | acre | 1 | 2 | 5 | 10 | 20 | all |
| 578 | Stream Crossing (no) | Engineering | CED-EG | Streamflow (25 yr. freq.) | cfs | 500 | 750 | 1000 | 1500 | 2000 | all |
| 580 | Streambank and Shoreline Protection (ft) | Engineering | CED-DE | Bankfull Capacity | cfs | none | none | 1000 | 1500 | 5000 | 20000 |
| | | Engineering | CED-DE | Drainage Area | sq. mi. | none | none | 50 | 75 | 100 | all |
| | | Engineering | CED-DE | Bankfull Velocity | fps | none | none | 6 | 8 | 10 | 12 |
| | | Engineering | CED-DE | Bankfull Depth | ft | none | none | 2 | 5 | 8 | all |
| | | Engineering | CED-DE | Water Height Above Shoreline | feet | none | none | 1 | 2 | 3 | 5 |

| Conservation Practice | | Lead Discipline | | Controlling Factor | Units | Job Class I | II | III | IV | V | VI |
|---|---|---|---|---|---|---|---|---|---|---|---|
| INDIVIDUAL PRACTICES | | | | | | | | | | | |
| 606 | Subsurface Drain (ft) | Engineering | CED-WME | Area benefited | acre | 20 | 40 | 80 | 160 | 320 | all |
| 607 | Surface Drain, Field Ditch (ft) | Engineering | CED-WME | Design Capacity | cfs | 2 | 5 | 10 | 25 | 50 | all |
| 608 | Surface Drain, Main or Lateral (ft) | Engineering | CED-WME | Design Capacity | cfs | 5 | 10 | 50 | 100 | 1000 | 2000 |
| | | Engineering | CED-WME | Design Velocity | fps | 2 | 4 | 6 | 8 | 10 | 12 |
| 600 | Terrace (ft, m) | Engineering | CED-AE | Area Benefited | acre | 80 | 160 | 1000 | 2000 | 4000 | all |
| 568 | Trails and Walkways (ft) | Engineering | CED-AE | Length | mile | 1 | 2 | 5 | 10 | 20 | all |
| | | Engineering | CED-AE | Surface | type | Earth | Earth | Earth | Gravel | Gravel | all |
| 620 | Underground Outlet (ft) | Engineering | CED-AE | Watershed Area | acre | 2 | 10 | 20 | 40 | 80 | all |
| 636 | Water Harvesting Catchment (no) | Engineering | CED-WME | Constructed-Catchment Area | sq. yd. | 100 | 200 | 300 | 500 | 1000 | all |
| | | Engineering | CED-WME | Natural-Total Contributing Area | sq. yd. | 200 | 400 | 600 | 1000 | 2000 | all |
| 351 | Water Well Decommissioning (no) | Engineering | CED-EG | Well Depth | feet | 100 | 200 | 400 | 600 | 1000 | all |
| 355 | Well Water Testing (no) | Engineering | CED-EG | Well Depth | feet | 100 | 200 | 400 | 600 | 1000 | all |

## Legend

s - Approved std plans only. Foundation conditions and soil loadings must be investigated to verify they are within design assumptions

* - When AFO/CAFO related, the independent implementation of these practices requires training in addition to demonstrated competence. See GM180, Amend OR6 Part 409.10 for a list of required training

** - Inventory and Evaluation (I and E) is defined as whether the person requesting JAA has the demonstrated competence required to incorporate specific practices of specified scope and complexity (job class) into a plan.