



- NOTES:**
1. If supply exceeds 5 GPM install valve on tank inlet or increase overflow pipe size. Pipes and fittings are Sch 40 PVC unless otherwise shown.
 2. Concrete wall and footing to be designed in accordance with RETWALL Program. Details are shown on attached sheet.
 3. For additional details see Missouri Construction Specifications 574 Spring Development, 516 Pipeline and 614 Watering Facility.

DRAFT
NOT FOR
CONSTRUCTION

<p>Date _____</p> <p>Designed _____</p> <p>Drawn _____</p> <p>Checked _____</p> <p>Approved _____</p>	<p>SPRING DEVELOPMENT DETAILS</p> <p>CONCRETE BOX CATCH BASIN</p> <p>TO TANK</p>
<p>United States Department of Agriculture Natural Resources Conservation Service</p> <p>NRCS</p>	
<p>File Name _____</p>	
<p>Drawing Name 29-L-69</p>	
<p>Sheet _____ of _____</p>	