

TECHNICAL NOTE

USDA-Natural Resources Conservation Service
Boise, Idaho – Salt Lake City, Utah

TN PLANT MATERIALS NO. 42

OCTOBER 2010
REVISION

Willow Clump Plantings

J. Chris Hoag, Wetland Plant Ecologist (retired), NRCS, PMC, Aberdeen, Idaho
Daniel G. Ogle, Plant Materials Specialist, NRCS, Boise, Idaho



*Excavator moving a harvested willow clump to planting site on
Mary Jane Creek, Manitou, Manitoba, Canada*

Willow Clump Plantings

J. Chris Hoag, Wetland Plant Ecologist (retired), Plant Materials Center, Aberdeen, Idaho
Daniel G. Ogle, Plant Materials Specialist, Boise, Idaho

INTRODUCTION

Willow clump plantings are a streambank soil bioengineering technique that can be used when large stands of willows are available in the project area. This streambank soil bioengineering technique harvests an entire live willow clump including the above ground stems and roots. This method unlike pole cuttings, already has part of the root system present, so the willow doesn't need to grow as many new roots from scratch. This results in a significant advantage for the plant in terms of shortened establishment period, lower failure rate and faster protection of the problem site.

Another principle that makes this technique desirable is that willows are depositional plants. Willows generally grow in riparian areas and on flood plains that commonly receive sediment from upstream sources. Some of this sediment deposits around the stems when stream flows bring high sediment laden water that flows through the willow stems, slowing flow velocity and thus dropping sediment.

Willow stem collars (where the stem meets the root material); unlike conifers for example, do not need to be at the soil surface or slightly above or below the soils surface for the plant to survive. When sediment is dropped out of the water column, it accumulates around the stem. As the stems are covered with sediment, the root buds in the stem swell and start to sprout roots. This is one way willows increase their root mass. This also results in more stems and leaves. This ability to adapt to sediment deposition makes willow clump plantings a great streambank soil bioengineering technique especially on channel reconstruction projects, for stabilizing outside meanders, areas where cuttings are difficult to plant, and where soil conditions such as saturation or very fine soils make it difficult for willow cuttings to establish new roots.

WILLOW CLUMP HARVESTING AND PLANTING METHODS

- This method should only be used where willows cover extensive areas of the floodplain or meadow areas. In addition, the willow stand should show good regeneration over the area.





- Locate willow clumps that are young and vigorous, about 8-20 feet tall, and about the diameter of the backhoe bucket. Dig straight down and under to the willow clump root mass. Start the hole about 10 inches away from the stems and dig down about the depth of the bucket (approximately 2 feet). Try to get as much of the root mass as possible.
- If the planting site is close to the willow clump source, dig the clump and travel to the planting site with the clump in the bucket. Try to keep as much soil as possible around the root mass.



- If the planting site is a long distance from the harvest site, dig as many willow clumps as you can fit on a flatbed trailer and replant as quickly as possible. Do not allow clumps to dry out

significantly. Transport the clumps to the planting site on the trailer. If it is sunny and hot, consider temporarily tarping the clumps to reduce sun exposure and potential drying during transport. Water the willow clumps when they arrived at the planting site if it will some time before clumps can be planted. Avoid leaving the clumps in the sun for long periods.

- Dig the clumps about 15- 20 feet apart in areas that have lots of willows. Do not harvest willows from critical locations that would be prone to future erosion. The hole that the willow was removed from should be refilled with local, good quality soil materials from off-site locations. Pack the replaced soil firmly in the excavated hole.
- Soil conditions will vary from site to site. In some situations, you will be able to plant the clumps without pre-digging the planting hole by pushing the soil out of the hole with the bottom of the backhoe bucket and then dropping the clump into this hole. Under more difficult soil conditions or where the watertable is deep, you will need to pre-dig the holes to put the willow clumps in. Dig the holes deep enough so you are just above the standing watertable. Do not dig into the watertable. Ideally you want the root mass of the clump to be in the saturated moisture zone and not in the standing water zone. Dig a hole that is about the diameter of the clump. You want to have at least 4-5 feet of the willow stems sticking out of the ground when you are finished planting the clump.



- Pull the clumps off the trailer with a thumb on the backhoe or with the front-end bucket and drop them in the holes. Fill in the hole with soil and water. Mud-in the willow clumps so there are no air pockets around the root mass.
- The last step is to take a set of loppers and cut off about one third to one half of the willow tops straight across. This decreases the amount of stem that the reduced root mass will have to support. It also stimulates a dense regrowth of stems and leaves that will speed up the photosynthesis process to grow additional roots, stems, and leaves and store energy in the root mass.
- Spacing between the willow clumps should be about 6-15 feet. This depends on the critical streamflow energy you are trying to protect against. If your harvest site does not have enough

willows, change to a wider spacing. However, the wider the spacing, the higher the potential that stream energy may impact the bank area you are trying to protect.



- This method is more successful than planting cuttings and more tolerant of droughty conditions.
- You should always obtain permission to harvest clumps from the landowner or public land management agency. In addition, state and federal regulators should be consulted to obtain permits if required and to ensure that they concur with the practice.

CASE STUDIES

Corral Creek, Idaho

Corral Creek in Camas County west of Fairfield, Idaho is a small stream that had major streambank erosion. The landowner wanted to restore the willow community and protect adjacent grazing lands. A large willow community was located near the project site and willow clumps were harvested and brought to the site where the backhoe placed the clump into the bank by pushing the soil out of the hole with the bottom of the backhoe bucket and then dropping the clump straight into the hole. Sod mats from adjacent locations were then placed above the willow clumps to the top of the bank. This was the first willow clump planting project by NRCS in the state of Idaho – installed in 1985.



Figure 1: Willow clump planting with sod mats on a streambank of Corral Creek



Figure 2: Corral Creek willow clump planting after 25 years of growth. Note grass growth between willows and stream and the deeper stream channel. Willows reduced the stream energy-flow rate on the outside meander resulting in sediment deposition in front of the willow clumps. This was quickly followed by natural revegetation and permanent relocation of the low flow stream channel.

Irving Creek, Idaho

Irving Creek, a tributary of Medicine Lodge Creek about 25 miles west of Dubois, Idaho near the Montana border, had major erosion problems because of an improperly installed road culvert. The streambed below the culvert had down cut and the existing willow community was dying because the water table was well below the root mass. The steep banks were reshaped and willow clumps were placed at the toe of the bank. Large rocks were placed as toe rock in front of the clumps. The willow clumps were trimmed so that about 1/3 of the stems remained. New growth was extensive and lush.



Figure 3: Steep cut bank on Irving Creek was eroding during high flow periods. The landowner signed up for the FSA/NRCS program “Continuous CRP” to restore the stream. As part of the project, cattle were fenced out of the stream area.



Figure 4: Willow clumps installed on Irving Creek

Medicine Lodge Creek, Idaho

A serious bank erosion problem existed on the lower end of Medicine Lodge Creek about 15 miles west of Dubois, Idaho. The treatment included rock rip-rap, willow clumps, stream barbs, fascines, and a brush mattress. This area is extremely dry and the riparian vegetation is limited to the wetted areas of the stream. The willow clump plantings established very well and helped to add aesthetics to the rock rip-rap and other functions such as wildlife habitat, water quality improvement and fish habitat.



Figure 5: Willow clumps installed in rip-rap along the lower end of Medicine Lodge Creek



Figure 6: Willow clump planting on Medicine Lodge Creek after one growing season

The United States Department of Agriculture (USDA) prohibits discrimination in all its programs on the basis of race, color, national origin, gender, religion, age, disability, political beliefs, sexual orientation, and marital or familial status. (Not all prohibited bases apply to all programs.) Persons with disabilities who require alternative means for communication of program information (Braille, large print, audiotape) should contact USDA's TARGET center at 202-720-2600 (voice and TDD).

To file a complaint, write the USDA, Director, Office of Civil Rights, Room 326W, Whitten Building, 14th and Independence Avenues, SW, Washington, D.C. 20250-9410 or call (202) 720-5964 (voice and TDD). USDA is an equal opportunity provider and employer.