

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #50 - Non-Dairy Operation Less Than 300 AU with Land Application

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on a small non-dairy Animal Feeding Operation (AFO) of less than 300 animal units (AU)--primarily swine, poultry, and beef AFOs. The producer may export (material transferred to another owner with written documentation of the transfer) modest amounts of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The producer has an animal production area, farms cropland and applies most nutrients. The CNMP is a conservation plan that addresses resource concerns on the AFO production area and land application areas. Production area components of the plan must include animal confinement facilities, feeding and lounging lots, animal mortality facilities, and manure containment and storage facilities. Land application components of the plan must include all lands under the control of the AFO owner or operator where waste materials are being applied. Planned practices on the production area and land application areas must result in meeting NRCS quality criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner/operator's production objectives.

Before Situation:

The owner/operator of a small sized non-dairy AFO has not received a written Comprehensive Nutrient Management Plan (CNMP) that addresses all resource concerns present on the facility production area and land waste application areas. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. The producer may or may not have a conservation plan or a nutrient management plan. Partial implementation of CNMP-related practices for the AFO has potentially occurred. Resource concerns on the AFO production area and land waste application areas remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, treatment of land application areas to reduce soil erosion to sustainable levels, and application of waste nutrients at an agronomic rate that meets application crop needs and does not exceed site risk analysis assessment condition. Negative air quality impacts and farmstead safety and security issues may remain on the AFO, and recordkeeping methods for crop yields, inspection and monitoring of the existing CNMP-related practices, and manure application and imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive nutrient management plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS with the CNMP Case File data that describes management and conservation practice solutions to all identified resource concerns on the small-sized non-dairy AFO production area and land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories-evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria by a Professional Engineer. Management and conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; implement conservation practices to reduce soil erosion on land application areas to sustainable levels; land apply waste material nutrients in a manner than meets NRCS 590 Nutrient Management standard technical criteria. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts and improve farmland safety and security. Practices selected in the Record of Decision will provide estimated quantities for conservation practices to be installed in units of measure that align with the practice standards. Accurate recordkeeping documents for crop yields, operation and maintenance of existing and new CNMP-related practices, manure application, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP. If the CNMP is not implemented all identified resource concerns will still exist.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$8,068.46

Scenario Cost/Unit: \$8,068.46

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	55	\$4,883.45
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to prod	Hour	\$74.07	43	\$3,185.01

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #51 - Dairy Operation Less Than 300 AU with Land Application

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) and CNMP Case File will be developed to address resource concerns on a small Dairy Animal Feeding Operation (AFO) of less than 300 animal units (AU). The producer may export (material transferred to another owner with written documentation of the transfer) modest amounts of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The producer has an animal production area, farms cropland and applies most nutrients. The CNMP is a conservation plan that addresses resource concerns on the AFO production area and land application areas. Production area components of the plan must include animal confinement facilities, feeding and lounging lots, animal mortality facilities, and manure containment and storage facilities. Land application components of the plan must include all lands under the control of the AFO owner or operator where waste materials are being applied. Planned practices on the production area and land application areas must result in meeting NRCS quality criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner/operator's production objectives.

Before Situation:

The owner/operator of a small sized dairy AFO has not received a written Comprehensive Nutrient Management Plan (CNMP) that addresses all resource concerns present on the facility production area and land waste application areas. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. The producer may or may not have a conservation plan or a nutrient management plan. Partial implementation of CNMP-related practices for the AFO has potentially occurred. Resource concerns on the AFO production area and land waste application areas remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, treatment of land application areas to reduce soil erosion to sustainable levels, and application of waste nutrients at an agronomic rate that meets application crop needs and does not exceed site risk analysis assessment condition. Negative air quality impacts and farmstead safety and security issues may remain on the AFO, and recordkeeping methods for crop yields, inspection and monitoring of the existing CNMP-related practices, and manure application and imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive nutrient management plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS the CNMP with Case File data that describes management and conservation practice solutions to all identified resource concerns on the small-sized dairy AFO production area and land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories-evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria by a Professional Engineer. Management and conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; implement conservation practices to reduce soil erosion on land application areas to sustainable levels; land apply waste material nutrients in a manner than meets NRCS 590 Nutrient Management standard technical criteria. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts and improve farmland safety and security. Practices selected in the Record of Decision will provide estimated quantities for conservation practices to be installed in units of measure that align with the practice standards. Accurate recordkeeping documents for crop yields, operation and maintenance of existing and new CNMP-related practices, manure application, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP. If the CNMP is not implemented all identified resource concerns will still exist.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$10,066.47

Scenario Cost/Unit: \$10,066.47

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	75	\$6,659.25
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to prod	Hour	\$74.07	46	\$3,407.22

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #52 - Non-Dairy Operation Greater Than or Equal to 300 AU and Less Than 700 AU with Land Application

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on a medium non-dairy Animal Feeding Operation (AFO) of greater than or equal to 300 and less than 700 animal units (AU).--primarily swine, poultry, and beef AFOs. The producer may export (material transferred to another owner with written documentation of the transfer) modest amounts of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The producer has an animal production area, farms cropland and applies most nutrients. The CNMP is a conservation plan that addresses resource concerns on the AFO production area and land application areas. Production area components of the plan must include animal confinement facilities, feeding and lounging lots, animal mortality facilities, and manure containment and storage facilities. Land application components of the plan must include all lands under the control of the AFO owner or operator where waste materials are being applied. Planned practices on the production area and land application areas must result in meeting NRCS quality criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner/operator's production objectives.

Before Situation:

The owner/operator of a medium sized non-dairy AFO has not received a written Comprehensive Nutrient Management Plan (CNMP) that addresses all resource concerns present on the facility production area and land waste application areas. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. The producer may or may not have a conservation plan or a nutrient management plan. Partial implementation of CNMP-related practices for the AFO has potentially occurred. Resource concerns on the AFO production area and land waste application areas remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, treatment of land application areas to reduce soil erosion to sustainable levels, and application of waste nutrients at an agronomic rate that meets application crop needs and does not exceed site risk analysis assessment condition. Negative air quality impacts and farmstead safety and security issues may remain on the AFO, and recordkeeping methods for crop yields, inspection and monitoring of the existing CNMP-related practices, and manure application and imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive nutrient management plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS with the CNMP Case File data that describes management and conservation practice solutions to all identified resource concerns on the non-dairy AFO production area and land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories-evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria by a Professional Engineer. Management and conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; implement conservation practices to reduce soil erosion on land application areas to sustainable levels; land apply waste material nutrients in a manner than meets NRCS 590 Nutrient Management standard technical criteria. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts and improve farmland safety and security. Practices selected in the Record of Decision will provide estimated quantities for conservation practices to be installed in units of measure that align with the practice standards. Accurate recordkeeping documents for crop yields, operation and maintenance of existing and new CNMP-related practices, manure application, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP. If the CNMP is not implemented all identified resource concerns will still exist.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$10,392.66

Scenario Cost/Unit: \$10,392.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	72	\$6,392.88
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to prod	Hour	\$74.07	54	\$3,999.78

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #53 - Dairy Operation Greater Than or Equal to 300 AU and Less Than 700 AU with Land Application

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on a medium Dairy Animal Feeding Operation (AFO) of greater than or equal to 300 and less than 700 animal units (AU). The producer may export (material transferred to another owner with written documentation of the transfer) modest amounts of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The producer has an animal production area, farms cropland and applies most nutrients. The CNMP is a conservation plan that addresses resource concerns on the AFO production area and land application areas. Production area components of the plan must include animal confinement facilities, feeding and lounging lots, animal mortality facilities, and manure containment and storage facilities. Land application components of the plan must include all lands under the control of the AFO owner or operator where waste materials are being applied. Planned practices on the production area and land application areas must result in meeting NRCS quality criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner/operator's production objectives.

Before Situation:

The owner/operator of a medium sized Dairy AFO has not received a written Comprehensive Nutrient Management Plan (CNMP) that addresses all resource concerns present on the facility production area and land waste application areas. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. The producer may or may not have a conservation plan or a nutrient management plan. Partial implementation of CNMP-related practices for the AFO has potentially occurred. Resource concerns on the AFO production area and land waste application areas remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, treatment of land application areas to reduce soil erosion to sustainable levels, and application of waste nutrients at an agronomic rate that meets application crop needs and does not exceed site risk analysis assessment condition. Negative air quality impacts and farmstead safety and security issues may remain on the AFO, and recordkeeping methods for crop yields, inspection and monitoring of the existing CNMP-related practices, and manure application and imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive nutrient management plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS the CNMP with Case File data that describes management and conservation practice solutions to all identified resource concerns on the dairy AFO production area and land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories-evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria by a Professional Engineer. Management and conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; implement conservation practices to reduce soil erosion on land application areas to sustainable levels; land apply waste material nutrients in a manner than meets NRCS 590 Nutrient Management standard technical criteria. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts and improve farmland safety and security. Practices selected in the Record of Decision will provide estimated quantities for conservation practices to be installed in units of measure that align with the practice standards. Accurate recordkeeping documents for crop yields, operation and maintenance of existing and new CNMP-related practices, manure application, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP. If the CNMP is not implemented all identified resource concerns will still exist.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$11,502.77

Scenario Cost/Unit: \$11,502.77

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	82	\$7,280.78
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to prod	Hour	\$74.07	57	\$4,221.99

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #54 - Non-Dairy Operation Greater Than or Equal to 700 AU with Land Application

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on a large non-dairy Animal Feeding Operation ((AFO) of greater than or equal to 700 animal units (AU)--primarily swine, poultry, and beef AFOs. The producer may export (material transferred to another owner with written documentation of the transfer) modest amounts of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The producer has an animal production area, farms cropland and applies most nutrients. The CNMP is a conservation plan that addresses resource concerns on the AFO production area and land application areas. Production area components of the plan must include animal confinement facilities, feeding and lounging lots, animal mortality facilities, and manure containment and storage facilities. Land application components of the plan must include all lands under the control of the AFO owner or operator where waste materials are being applied. Planned practices on the production area and land application areas must result in meeting NRCS quality criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner/operator's production objectives.

Before Situation:

The owner/operator of a large sized non-dairy AFO has not received a written Comprehensive Nutrient Management Plan (CNMP) that addresses all resource concerns present on the facility production area and land waste application areas. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. The producer may or may not have a conservation plan or a nutrient management plan. Partial implementation of CNMP-related practices for the AFO has potentially occurred. Resource concerns on the AFO production area and land waste application areas remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, treatment of land application areas to reduce soil erosion to sustainable levels, and application of waste nutrients at an agronomic rate that meets application crop needs and does not exceed site risk analysis assessment condition. Negative air quality impacts and farmstead safety and security issues may remain on the AFO, and recordkeeping methods for crop yields, inspection and monitoring of the existing CNMP-related practices, and manure application and imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive nutrient management plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS with the CNMP Case File data that describes management and conservation practice solutions to all identified resource concerns on the non-dairy AFO production area and land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories-evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria by a Professional Engineer. Management and conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; implement conservation practices to reduce soil erosion on land application areas to sustainable levels; land apply waste material nutrients in a manner than meets NRCS 590 Nutrient Management standard technical criteria. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts and improve farmland safety and security. Practices selected in the Record of Decision will provide estimated quantities for conservation practices to be installed in units of measure that align with the practice standards. Accurate recordkeeping documents for crop yields, operation and maintenance of existing and new CNMP-related practices, manure application, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP. If the CNMP is not implemented all identified resource concerns will still exist.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$12,554.00

Scenario Cost/Unit: \$12,554.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	88	\$7,813.52
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to prod	Hour	\$74.07	64	\$4,740.48

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #55 - Dairy Operation Greater Than or Equal to 700 AU with Land Application

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on a large Dairy Animal Feeding Operation (AFO) of greater than or equal to 700 animal units (AU). The producer may export (material transferred to another owner with written documentation of the transfer) modest amounts of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The producer has an animal production area, farms cropland and applies most nutrients. The CNMP is a conservation plan that addresses resource concerns on the AFO production area and land application areas. Production area components of the plan must include animal confinement facilities, feeding and lounging lots, animal mortality facilities, and manure containment and storage facilities. Land application components of the plan must include all lands under the control of the AFO owner or operator where waste materials are being applied. Planned practices on the production area and land application areas must result in meeting NRCS quality criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner/operator's production objectives.

Before Situation:

The owner/operator of a large sized Dairy AFO has not received a written Comprehensive Nutrient Management Plan (CNMP) that addresses all resource concerns present on the facility production area and land waste application areas. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. The producer may or may not have a conservation plan or a nutrient management plan. Partial implementation of CNMP-related practices for the AFO has potentially occurred. Resource concerns on the AFO production area and land waste application areas remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, treatment of land application areas to reduce soil erosion to sustainable levels, and application of waste nutrients at an agronomic rate that meets application crop needs and does not exceed site risk analysis assessment condition. Negative air quality impacts and farmstead safety and security issues may remain on the AFO, and recordkeeping methods for crop yields, inspection and monitoring of the existing CNMP-related practices, and manure application and imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive nutrient management plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS the CNMP with Case File data that describes management and conservation practice solutions to all identified resource concerns on the dairy AFO production area and land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories-evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria by a Professional Engineer. Management and conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; implement conservation practices to reduce soil erosion on land application areas to sustainable levels; land apply waste material nutrients in a manner than meets NRCS 590 Nutrient Management standard technical criteria. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts and improve farmland safety and security. Practices selected in the Record of Decision will provide estimated quantities for conservation practices to be installed in units of measure that align with the practice standards. Accurate recordkeeping documents for crop yields, operation and maintenance of existing and new CNMP-related practices, manure application, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP. If the CNMP is not implemented all identified resource concerns will still exist.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$12,790.93

Scenario Cost/Unit: \$12,790.93

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	89	\$7,902.31
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to prod	Hour	\$74.07	66	\$4,888.62



Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #56 - Livestock Operation Less Than 300 AU without Land Application

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on a small Animal Feeding Operation (AFO) of less than 300 animal units (AU). The producer exports (material transferred to another owner with written documentation of the transfer) nearly all of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The CNMP is a conservation plan that addresses resource concerns on the AFO production area and land application areas owned or controlled by the AFO owner/operator. In this scenario, the primary focus will be addressing resource concerns present on the production area, including manure/wastewater handling and storage, and documentation of manure generation by the AFO, and its export. Production area components of the plan must include animal confinement facilities, feeding and lounging areas, animal mortality facilities, and manure containment and storage facilities. Planned practices on the production area must result in meeting NRCS quality criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner's/operator's production objectives.

Before Situation:

The owner/operator of a small AFO has not received a written comprehensive nutrient management plan (CNMP) that addresses all resource concerns present on the facility production areas and any applicable land application areas. Partial implementation of CNMP- related practices for the AFO has potentially occurred. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. The producer may or may not have a conservation plan or a nutrient management plan. Resource concerns on the AFO production area remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, erosion and runoff issues from feeding and lounging areas, and recordkeeping documentation of manure generation and exports. Negative air quality impacts and farmstead safety and security issues may remain on the AFO, and recordkeeping methods for inspection and monitoring of the existing CNMP-related practices, manure imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive conservation plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS a the CNMP Case File that describes management and conservation practice solutions to all identified resource concerns on the small sized AFO production area and any applicable land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories/evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria by a Professional Engineer. Conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; minimize erosion and runoff from feeding and lounging areas, keep accurate AFO animal inventory information, and document AFO manure generation and exports. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts and improve farmland safety and security. Decisions selected in the Record of Decision will provide estimated quantities for conservation practices to be installed in units of measure that align with those in the conservation practice. Accurate recordkeeping documents for operation and maintenance of existing and new CNMP-related practices, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP. If the CNMP is not implemented all identified resource concerns will still exist..

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$7,267.47

Scenario Cost/Unit: \$7,267.47

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	66	\$5,860.14
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to prod	Hour	\$74.07	19	\$1,407.33

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #57 - Livestock Operation Greater Than 300 AU without Land Application

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on a medium-large Animal Feeding Operation (AFO) of greater than or equal to 300 animal units (AU). The producer exports (material transferred to another owner with written documentation of the transfer) nearly all of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The CNMP is a conservation plan that addresses resource concerns on the AFO production area and land application areas owned or controlled by the AFO owner/operator. In this scenario, the primary focus will be addressing resource concerns present on the production area, including manure/wastewater handling and storage, and documentation of manure generation by the AFO, and its export. Production area components of the plan must include animal confinement facilities, feeding and lounging lots, animal mortality facilities, and manure containment and storage facilities. Planned practices on the production area must result in meeting NRCS quality criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner's/operator's production objectives.

Before Situation:

The owner/operator of a medium-large sized AFO has not received a written comprehensive nutrient management plan (CNMP) that addresses all resource concerns present on the facility production areas and any applicable land application areas. Partial implementation of CNMP-related practices for the AFO has potentially occurred. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. The producer may or may not have a conservation plan or a nutrient management plan. Resource concerns on the AFO production area remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, erosion and runoff issues from feeding and lounging areas, and recordkeeping documentation of manure generation and exports. Negative air quality impacts and farmstead safety and security issues may remain on the AFO, and recordkeeping methods for inspection and monitoring of the existing CNMP-related practices, manure imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive conservation plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS a the CNMP Case File that describes management and conservation practice solutions to all identified resource concerns on the small sized AFO production area and any applicable land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories/evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria by a Professional Engineer. Conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; minimize erosion and runoff from feeding and lounging areas, keep accurate AFO animal inventory information, and document AFO manure generation and exports. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts and improve farmland safety and security. Decisions selected in the Record of Decision will provide estimated quantities for conservation practices to be installed in units of measure that align with those in the conservation practice. Accurate recordkeeping documents for operation and maintenance of existing and new CNMP-related practices, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP. If the CNMP is not implemented all identified resource concerns will still exist.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$9,028.55

Scenario Cost/Unit: \$9,028.55

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	85	\$7,547.15
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to prod	Hour	\$74.07	20	\$1,481.40



Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #135 - CNMP Less Than or Equal to 300 AU with Land Application (Minimal Engineer Assistance)

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on a small non-dairy Animal Feeding Operation (AFO) of less than 300 animal units (AU)--primarily swine, poultry, and beef AFOs. This scenario is for sites or states where the services of a professional engineer are minimal. The producer may export modest amounts of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The producer has an animal production area, farms cropland and applies most nutrients. The CNMP is a conservation plan that addresses resource concerns on the AFO production area and land application areas. Production area components of the plan must include animal confinement facilities, feeding and lounging lots, animal mortality facilities, and manure containment and storage facilities. Land application components of the plan includes all lands under the control of the AFO owner or operator where waste materials are being applied. Planned practices on the production area and land application areas result in meeting NRCS planning criteria for water quality, soil erosion, and air quality concerns. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner/operator's production objectives.

Before Situation:

The owner/operator of an AFO has not received a written Comprehensive Nutrient Management Plan (CNMP) that addresses all resource concerns present on the facility production area and land waste application areas. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. Partial implementation of conservation practices for the AFO has potentially occurred. Resource concerns on the AFO production area and land waste application areas remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, treatment of land application areas to reduce soil erosion to sustainable levels, and application of waste nutrients at an agronomic rate that meets application crop needs and does not exceed site risk analysis assessment condition. Negative air quality impacts issues may remain on the AFO, and recordkeeping methods for crop yields, inspection and monitoring of the existing CNMP-related practices, and manure application and imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive nutrient management plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS with the CNMP Case File data that describes management and conservation practice systems to address all identified resource concerns on the AFO production area and land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories-evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria. Management and conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; implement conservation practices to address soil erosion, water quality, and air quality within the NRCS planning criteria. Accurate record keeping documents for crop yields, operation and maintenance of existing and new CNMP-related practices, manure application, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP.

Feature Measure: Each

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$4,679.90

Scenario Cost/Unit: \$4,679.90

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	50	\$3,792.00
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	10	\$887.90

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #136 - CNMP Less Than or Equal to 300 AU without Land Application (Minimal Engineer Assistance)

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on the Animal Feeding Operation (AFO) of less than 300 or equal animal units (AU). This scenario is for sites or states where the services of a professional engineer are minimal. The producer exports nearly all of the manure or organic products from the farm. The CNMP is a conservation plan that addresses soil erosion, water quality, and air quality resource concerns on the AFO production area and land application areas owned or controlled by the AFO owner/operator. In this scenario, the primary focus will be addressing soil erosion, water quality, and air quality resource concerns present on the production area, including manure/wastewater handling and storage, and documentation of manure generation by the AFO, and its export. Production area components of the plan must include animal confinement facilities, feeding and lounging areas, animal mortality facilities, and manure containment and storage facilities. Planned practices on the production area must result in meeting NRCS planning criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner's/operator's production objectives.

Before Situation:

The owner/operator of the AFO has not received a written comprehensive nutrient management plan (CNMP) that addresses all resource concerns present on the facility production areas and any applicable land application areas. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. The producer may or may not have a conservation plan or a nutrient management plan. Resource concerns on the AFO production area remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, erosion and runoff issues from feeding and lounging areas, and record keeping documentation of manure generation and exports. Negative air quality impacts and farmstead safety and security issues may remain on the AFO, and record keeping methods for inspection and monitoring of the existing CNMP-related practices, manure imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive conservation plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS a the CNMP Case File that describes management and conservation practice practices to address all identified soil erosion, water quality, and air quality resource concerns on the AFO production area and any applicable land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories/evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria. Conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; minimize erosion and runoff from feeding and lounging areas, keep accurate AFO animal inventory information, and document AFO manure generation and exports. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts and improve farmland safety and security. Decisions selected in the Record of Decision will provide estimated quantities for conservation practices to be installed in units of measure that align with those in the conservation practice. Accurate record keeping documents for operation and maintenance of existing and new CNMP-related practices, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP.

Feature Measure: Each

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$2,739.65

Scenario Cost/Unit: \$2,739.65

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	10	\$887.90
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to prod	Hour	\$74.07	25	\$1,851.75

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #137 - CNMP Greater Than 300 AU with Land Application (Minimal Engineer Assistance)

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on an Animal Feeding Operation (AFO) of greater than or equal to 300 animal units (AU). This scenario is for sites or states where the services of a professional engineer are minimal. The producer may export modest amounts of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The producer has an animal production area, farms cropland and applies most manure nutrients. The CNMP is a conservation plan that addresses resource concerns on the AFO production area and land application areas. Production area components of the plan must include animal confinement facilities, feeding and lounging lots, animal mortality facilities, and manure containment and storage facilities. Land application components of the plan must include all lands under the control of the AFO owner or operator where waste materials are being applied. Planned practices on the production area and land application areas must result in meeting NRCS planning criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owner/operator's production objectives.

Before Situation:

The owner/operator of an AFO has not received a written Comprehensive Nutrient Management Plan (CNMP) that addresses all resource concerns present on the facility production area and land waste application areas. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. Partial implementation of CNMP-related practices for the AFO has potentially occurred. Resource concerns on the AFO production area and land waste application areas remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, treatment of land application areas to reduce soil erosion to sustainable levels, and application of waste nutrients at an agronomic rate that meets application crop needs and does not exceed site risk analysis assessment condition. Negative air quality impacts and farmstead safety and security issues may remain on the AFO, and record keeping methods for crop yields, inspection and monitoring of the existing CNMP-related practices, and manure application and imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered, to the AFO owner/operator, a comprehensive nutrient management plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS with the CNMP Case File data that describes management and conservation practices to address all identified soil erosion, water quality, and air quality resource concerns on the AFO production area and land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems will be inventories-evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria. Management and conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; implement conservation practices to reduce soil erosion on land application areas to sustainable levels; land apply waste material nutrients in a manner than meets NRCS 590 Nutrient Management standard technical criteria. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts. Practices selected in the Record of Decision will provide estimated quantities for conservation practices to be installed in units of measure that align with the practice standards. Accurate record keeping documents for crop yields, operation and maintenance of existing and new CNMP-related practices, manure application, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP.

Feature Measure: Each

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$6,146.40

Scenario Cost/Unit: \$6,146.40

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	15	\$1,331.85
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to prod	Hour	\$74.07	65	\$4,814.55

Practice: 102 - Comprehensive Nutrient Management Plan - Written

Scenario #138 - CNMP Greater Than 300 AU without Land Application (Minimal Engineer Assistance)

Scenario Description:

A Comprehensive Nutrient Management Plan (CNMP) will be developed to address resource concerns on an Animal Feeding Operation (AFO) of greater than 300 animal units (AU). This scenario is for sites or states where the services of a professional engineer are minimal. The producer exports nearly all of the manure or organic products from the farm. For operations where manure is both applied to land the AFO owner/operator controls and exported offsite, guidance to determine appropriate CNMP CAP scenario selection shall be provided by NRCS at the state level. The CNMP is a conservation plan that addresses the soil erosion, water quality, and air quality resource concerns on the AFO production area and land application areas owned or controlled by the AFO owner/operator. In this scenario, the primary focus will be addressing resource concerns present on the production area, including manure/wastewater handling and storage, and documentation of manure generation by the AFO, and its export. Production area components of the plan must include animal confinement facilities, feeding and lounging lots, animal mortality facilities, and manure containment and storage facilities. Planned practices on the production area must result in meeting NRCS planning criteria for water quality and soil erosion. Any applicable air emission and negative air quality impacts occurring as a result of planned CNMP activities, or existing on-farm activities must be mitigated in the CNMP if feasible. The CNMP meets the AFO owners/operator's production objectives.

Before Situation:

The owner/operator of an AFO has not received a written comprehensive nutrient management plan (CNMP) that addresses the soil erosion, water quality, and air quality resource concerns present on the facility production areas and any applicable land application areas. Various levels of management and conservation implementation has occurred on the farm. Little documentation of the systems used and practices installed exists. The producer may or may not have a conservation plan or a nutrient management plan. Resource concerns on the AFO production area remain to be addressed through the development of a complete CNMP including management and conservation practices for proper manure/wastewater storage and handling, proper disposal of animal mortality, soil erosion, water quality, and air quality concerns from feeding and lounging areas, and record keeping documentation of manure generation and exports. Negative air quality impacts issues may remain on the AFO, and record keeping methods for inspection and monitoring of the existing CNMP-related practices, manure imports/exports may need further improvement.

After Situation:

A certified Technical Services Provider (TSP) has delivered to the AFO owner/operator, a comprehensive conservation plan meeting CNMP CAP criteria (GM - Part 405 - Comprehensive Nutrient Management Plans) and to NRCS a the CNMP Case File that describes management and conservation practice solutions to all identified resource concerns on the small sized AFO production area and any applicable land application areas. Collection, transfer, and storage of manure and wastewater systems, mortality management facilities, as well as any rainfall or runoff diversion systems are inventoried/evaluated and planned for adequacy according to applicable NRCS conservation practice standard technical criteria. Conservation practices in the CNMP document delivered to the client ensure that, if implemented, the AFO will properly, within applicable NRCS standards and specifications, store, handle, and contain manure and wastewater materials generated by the AFO; dispose of AFO mortality; minimize soil erosion, water quality, and air quality concerns from feeding and lounging areas, keep accurate AFO animal inventory information, and document AFO manure generation and exports. Decisions presented within the CNMP have been made to mitigate, if feasible, negative air quality impacts. Decisions selected in the Record of Decisions will provide estimated quantities for conservation practices to be installed in units of measure that align with those in the conservation practice. Accurate record keeping documents for operation and maintenance of existing and new CNMP-related practices, AFO manure imports and exports, and other information relevant to the management and compliance of the AFO with state and/or local rules and regulations are included in the CNMP.

Feature Measure: Each

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$3,110.00

Scenario Cost/Unit: \$3,110.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	10	\$887.90
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to prod	Hour	\$74.07	30	\$2,222.10

Practice: 104 - Nutrient Management Plan - Written

Scenario #32 - Nutrient Management CAP Less Than or Equal to 100 Acres (Not part of a CNMP)

Scenario Description:

Various on-farm land uses where natural or artificial amendments are applied. Natural Resource Concern: Water Quality, Soil Erosion, Water Quantity, and other associated resource concerns.

Before Situation:

Agricultural producer has no plan or minimal knowledge for application and management of nutrients. The producer currently manages nutrient application based upon personal knowledge, or other local criteria. Producer is interested in management of nutrients to maximize yields, profits margin, reduce costs, and for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Nutrient Management" conservation activity plan consistent with the criteria in CAP 104 and 590 Nutrient Management. The CAP criteria requires the plan to meet quality criteria for the primary Water Quality resource concern and other applicable resource concerns and provides for opportunities to manage nutrients for plant production and address offsite movement of nutrients. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 104 plan as cited in the NRCS Field Office Technical Guide and CPS 590 Nutrient Management.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$2,275.20

Scenario Cost/Unit: \$2,275.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Labor

CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	30	\$2,275.20
-----------------------	------	---	------	---------	----	------------

Practice: 104 - Nutrient Management Plan - Written

Scenario #33 - Nutrient Management CAP 104- 101-300 Acres (Not part of a CNMP)

Scenario Description:

Various on-farm land uses where organic or inorganic amendments are applied. Natural Resource Concern: Water Quality, Soil Erosion, Water Quantity, and other associated resource concerns.

Before Situation:

Agricultural producer has no plan or minimal knowledge for applicant and management of land applied nutrients. The producer currently manages nutrient application based upon label instructions, personal knowledge, or other local criteria. Producer is interested in management of nutrients to maximize yields, profits margin, reduce costs, nutrient use efficiency and for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Nutrient Management" conservation activity plan. The CAP criteria requires the plan to meet Nutrient Management criteria for the primary Water Quality resource concern and other applicable resource concerns and provides for opportunities to manage nutrients for plant production and address offsite movement of nutrients. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic criteria for the 104 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$3,033.60

Scenario Cost/Unit: \$3,033.60

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	40	\$3,033.60



Practice: 104 - Nutrient Management Plan - Written

Scenario #34 - Nutrient Management CAP 104 Greater Than 300 Acres (Not part of a CNMP)

Scenario Description:

Various on-farm land uses where organic or inorganic amendments are applied. Natural Resource Concern: Water Quality, Soil Erosion, Water Quantity, and other associated resource concerns.

Before Situation:

Agricultural producer has no plan or minimal knowledge for applicant and management of land applied nutrients. The producer currently manages nutrient application based upon label instructions, personal knowledge, or other local criteria. Producer is interested in management of nutrients to maximize yields, profits margin, reduce costs, nutrient use efficiency, and for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Nutrient Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for the primary Water Quality resource concern and other applicable resource concerns and provides for opportunities to manage nutrients for plant production and address offsite movement of nutrients. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic criteria for the 104 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$3,792.00

Scenario Cost/Unit: \$3,792.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	50	\$3,792.00

Practice: 104 - Nutrient Management Plan - Written

Scenario #35 - Nutrient Management CAP 104 Less Than or Equal to 100 Acres (Element of a CNMP)

**Scenario Description:**

Various on-farm land uses where natural or artificial nutrient amendments are applied. Natural Resource Concern: Water Quality, Soil Erosion, Water Quantity, and other associated resource concerns.

**Before Situation:**

Agricultural producer has no plan or minimal knowledge for applicant and management of nutrient applied to the land. The producer currently manages nutrient application based upon label instructions, personal knowledge, or other local criteria. Producer is interested in management of nutrients to maximize yields, profits margin, reduce costs, and for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan.

**After Situation:**

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Nutrient Management" conservation activity plan. The CAP criteria requires the plan to meet nutrient criteria for the primary Water Quality resource concern in 590 and other applicable resource concerns and provides for opportunities to manage nutrients for plant production and address offsite movement of nutrients. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic criteria for the 104 plan as cited in the NRCS Field Office Technical Guide.

**Feature Measure:** Number

**Scenario Unit::** Number

**Scenario Typical Size:** 1.0

**Scenario Total Cost:** \$3,792.00

**Scenario Cost/Unit:** \$3,792.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	50	\$3,792.00

Practice: 104 - Nutrient Management Plan - Written

Scenario #36 - Nutrient Management CAP 104 - 101-300 Acres (Element of a CNMP)

Scenario Description:

Various on-farm land uses where organic or inorganic amendments are applied. Natural Resource Concern: Water Quality, Soil Erosion, Water Quantity, and other associated resource concerns.

Before Situation:

Agricultural producer has no plan or minimal knowledge for applicant and management of applied nutrients to the land. The producer currently manages nutrient application based upon label instructions, personal knowledge, or other local criteria. Producer is interested in management of nutrients to maximize yields, profits margin, reduce costs, and for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Nutrient Management" conservation activity plan. The CAP criteria requires the plan to meet 590 criteria for the primary Water Quality resource concern and other applicable resource concerns and provides for opportunities to manage nutrients for plant production and address offsite movement of nutrients. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 104 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$5,308.80

Scenario Cost/Unit: \$5,308.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	70	\$5,308.80

**Practice:** 104 - Nutrient Management Plan - Written

**Scenario #37 - Nutrient Management CAP 104 Greater Than 300 Acres (Element of a CNMP)**

**Scenario Description:**  
Various on-farm land uses where organic or inorganic amendments are applied. Natural Resource Concern: Water Quality, Soil Erosion, Water Quantity, and other associated resource concerns.

**Before Situation:**  
Agricultural producer has no plan or minimal knowledge for applicant and management of nutrient s applied to the land. The producer currently manages nutrient application based upon label instructions, personal knowledge, or other local criteria. Producer is interested in management of nutrients to maximize yields, profits margin, reduce costs, and for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan.

**After Situation:**  
After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Nutrient Management" conservation activity plan. The CAP criteria requires the plan to meet 590 criteria for the primary Water Quality resource concern and other applicable resource concerns and provides for opportunities to manage nutrients for plant production and address offsite movement of nutrients. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic criteria for the 104 plan as cited in the NRCS Field Office Technical Guide.

**Feature Measure:** Number

**Scenario Unit::** Number

**Scenario Typical Size:** 1.0

**Scenario Total Cost:** \$6,446.40

**Scenario Cost/Unit:** \$6,446.40

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	85	\$6,446.40

Practice: 106 - Forest Management Plan - Written

Scenario #38 - FMP Less Than or Equal to 20 acres

Scenario Description:

Non Industrial Private Forest Land typically unmanaged or limited management activities. Typical site is approximately 1 to 20 acres in size and consists of existing uneven-aged mixed species stands of harvestable trees. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition; on Forest Land.

Before Situation:

The producer currently manages forested lands without an existing forest management plan, or with an outdated plan. Resource concern(s) exist which are not addressed by a management plan. A Forest Management Plan or Conservation Activity Plan, as defined by EQIP regulation is needed to allow the producer to apply for financial assistance through EQIP or other programs to help implement needed conservation practices. Associated Practices: 472, 666, 654, 655,384, 394, 383, 379, 338, 391, 791, 490, 612, 660, 311, 380.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Forest Management Plan" Conservation Activity Plan (CAP). The CAP criteria requires the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Forest Management CAP is not considered a Forest Harvest Plan, but should complement the needs for harvest if desired by the land user. Additional CAP plan criteria is detailed in the Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,365.91

Scenario Cost/Unit: \$1,365.91

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Labor

CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	19	\$1,365.91
---------------------	------	---	------	---------	----	------------

Practice: 106 - Forest Management Plan - Written

Scenario #39 - FMP 21 to 100 acres

Scenario Description:

Non Industrial Private Forest Land typically unmanaged or limited management activities. Typical site is approximately 21 to 100 acres in size and consists of existing uneven-aged mixed species stands of harvestable trees. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition; on Forest Land.

Before Situation:

The producer currently manages forested lands without an existing forest management plan, or with an outdated plan. Resource concern(s) exist which are not addressed by a management plan. A Forest Management Plan or Conservation Activity Plan, as defined by EQIP regulation is needed to allow the producer to apply for financial assistance through EQIP or other programs to help implement needed conservation practices. Associated Practices: 472, 666, 654, 655,384, 394, 383, 379, 338, 391, 791, 490, 612, 660, 311, 380.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Forest Management Plan" Conservation Activity Plan (CAP). The CAP criteria requires the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Forest Management CAP is not considered a Forest Harvest Plan, but should complement the needs for harvest if desired by the land user. Additional CAP plan criteria is detailed in the Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,725.36

Scenario Cost/Unit: \$1,725.36

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	24	\$1,725.36



Practice: 106 - Forest Management Plan - Written

Scenario #40 - FMP 101 to 250 acres

Scenario Description:

Non Industrial Private Forest Land typically unmanaged or limited management activities. Typical site is approximately 101 to 250 acres in size and consists of existing uneven-aged mixed species stands of harvestable trees. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition; on Forest Land.

Before Situation:

The producer currently manages forested lands without an existing forest management plan, or with an outdated plan. Resource concern(s) exist which are not addressed by a management plan. A Forest Management Plan or Conservation Activity Plan, as defined by EQIP regulation is needed to allow the producer to apply for financial assistance through EQIP or other programs to help implement needed conservation practices. Associated Practices: 472, 666, 654, 655,384, 394, 383, 379, 338, 391, 791, 490, 612, 660, 311, 380.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Forest Management Plan" Conservation Activity Plan (CAP). The CAP criteria requires the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Forest Management CAP is not considered a Forest Harvest Plan, but should complement the needs for harvest if desired by the land user. Additional CAP plan criteria is detailed in the Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$3,091.27

Scenario Cost/Unit: \$3,091.27

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	43	\$3,091.27

Practice: 106 - Forest Management Plan - Written

Scenario #41 - FMP Greater Than 1000 acres

Scenario Description:

Non Industrial Private Forest Land typically unmanaged or limited management activities. Typical site is approximately 1001 acres or greater in size and consists of existing uneven-aged mixed species stands of harvestable trees. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition; on Forest Land.

Before Situation:

The producer currently manages forested lands without an existing forest management plan, or with an outdated plan. Resource concern(s) exist which are not addressed by a management plan. A Forest Management Plan or Conservation Activity Plan, as defined by EQIP regulation is needed to allow the producer to apply for financial assistance through EQIP or other programs to help implement needed conservation practices. Associated Practices: 472, 666, 654, 655,384, 394, 383, 379, 338, 391, 791, 490, 612, 660, 311, 380.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Forest Management Plan" Conservation Activity Plan (CAP). The CAP criteria requires the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Forest Management CAP is not considered a Forest Harvest Plan, but should complement the needs for harvest if desired by the land user. Additional CAP plan criteria is detailed in the Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$6,470.10

Scenario Cost/Unit: \$6,470.10

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	90	\$6,470.10

Practice: 106 - Forest Management Plan - Written

Scenario #42 - FMP 251 to 500 acres

Scenario Description:

Non Industrial Private Forest Land typically unmanaged or limited management activities. Typical site is approximately 251 to 500 acres in size and consists of existing uneven-aged mixed species stands of harvestable trees. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition; on Forest Land.

Before Situation:

The producer currently manages forested lands without an existing forest management plan, or with an outdated plan. Resource concern(s) exist which are not addressed by a management plan. A Forest Management Plan or Conservation Activity Plan, as defined by EQIP regulation is needed to allow the producer to apply for financial assistance through EQIP or other programs to help implement needed conservation practices. Associated Practices: 472, 666, 654, 655,384, 394, 383, 379, 338, 391, 791, 490, 612, 660, 311, 380.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Forest Management Plan" Conservation Activity Plan (CAP). The CAP criteria requires the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Forest Management CAP is not considered a Forest Harvest Plan, but should complement the needs for harvest if desired by the land user. Additional CAP plan criteria is detailed in the Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$4,457.18

Scenario Cost/Unit: \$4,457.18

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	62	\$4,457.18

Practice: 106 - Forest Management Plan - Written

Scenario #43 - FMP 501 to 1000 acres

Scenario Description:

Non Industrial Private Forest Land typically unmanaged or limited management activities. Typical site is approximately 501 to 1000 acres in size and consists of existing uneven-aged mixed species stands of harvestable trees. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition; on Forest Land.

Before Situation:

The producer currently manages forested lands without an existing forest management plan, or with an outdated plan. Resource concern(s) exist which are not addressed by a management plan. A Forest Management Plan or Conservation Activity Plan, as defined by EQIP regulation is needed to allow the producer to apply for financial assistance through EQIP or other programs to help implement needed conservation practices. Associated Practices: 472, 666, 654, 655,384, 394, 383, 379, 338, 391, 791, 490, 612, 660, 311, 380.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Forest Management Plan" Conservation Activity Plan (CAP). The CAP criteria requires the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Forest Management CAP is not considered a Forest Harvest Plan, but should complement the needs for harvest if desired by the land user. Additional CAP plan criteria is detailed in the Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$5,176.08

Scenario Cost/Unit: \$5,176.08

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	72	\$5,176.08

Practice: 108 - Feed Management Plan - Written

Scenario #37 - Feed Management Plan

Scenario Description:

The owner/operator of an Animal Feeding Operation (AFO) has not received a written Feed Management Plan (FeedMP) that addresses all resource concerns present on the facility. Various levels of management and conservation implementation has occurred in the operation. Little documentation of the methods of feed management used and practices installed exists, and the producer is not likely to developed a complete forage inventory or nutrient analysis. The producer may or may not have a conservation plan or a nutrient management plan. Nutrient management related resource concerns on the operation remain to be addressed through the development of a complete FeedMP including management and conservation practices for proper quantity and quality of available nutrients, feedstuffs, and/or additives fed to livestock or poultry that may be present on the operation. Present operation and feed methodology poses risk of feeding excessive amounts of nutrients in animal manure which result in negative impacts to water quality and odor resource concerns. Negative water and air quality impacts as well as farmstead safety and security issues may remain on the AFO, and inadequate recordkeeping nutrient, inspection and monitoring of the existing operation may need further improvement.

Before Situation:

Producer has no plan or limited knowledge of management of feed, nutrients, feedstuffs, or nutritional additives provided to domestic livestock and poultry. The producer currently manages feed without a plan which would address livestock production limitations and water and air quality resource concern impacts. Producer currently lacks plan to provide proper balance of forage, grains or other feeds and supplements to assure domestic animal nutritional needs are met without negatively impacting water and air quality. Producer is interested in management of feed for domestic animals to maximize profit margin, reduce costs, improve or address livestock production opportunities, and for other environmental benefits. Producer is willing to collaborate with a certified Technical Service Provider (TSP) to develop a plan, and to collect/coordinate data and records to determine current nutritional needs. Associated Practice(s): 590-Nutrient Management

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the “Feed Management” (FM) conservation activity plan (CAP). The CAP criteria requires the plan to meet quality criteria for applicable natural resource concerns and provides for opportunities to identify and implement conservation practices related to management of feed, forages, or delivery of supplements to maximize efficient feeding operations and livestock growth. The CAP plan may serve as the basis for implementation of the primary conservation practice 592-Feed Management. If applicable, the FM CAP may also be developed to complement Comprehensive Nutrient Management Plans (CNMP) or to help meet requirements of NRCS practice standard 590 - Nutrient Management. As addressed in the CAP planning criteria, the plan may include recommendations for addressing associated natural resource concerns with other conservation practices. The FM CAP meets the basic quality criteria for the 108 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$2,402.72

Scenario Cost/Unit: \$2,402.72

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	16	\$1,213.44
CAP Labor, range conservation	1299	Conservation Activity Plan labor to study, plan the use and management of rangelands to maximize their use in a sustainable manner. Range managers may inventory soils, plants, and animals; develop resource management plans; identify monitoring methods an	Hour	\$74.33	16	\$1,189.28

Practice: 110 - Grazing Management Plan - Written

Scenario #1 - Grazing Management Plan Less Than or Equal to 100 acres

**Scenario Description:**

Small agricultural operation with less than 100 acres grazed land. Natural Resource Concern: Soil erosion, water quality, fish and wildlife, plant condition, and all other appropriate resource concerns.

**Before Situation:**

Producer has no plan or limited knowledge of management of livestock or other animals on grazed land resources. The producer currently manages animals without plan to address identified natural resource concerns. Producer is interested in management of animals to maximize profit margin, reduce costs, improve or address wildlife opportunities, and for other environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: In addition to the essential practices listed previously, addition practices to consider include: Channel Bank Vegetation, Prescribed Burning, Critical Area Planting, Pond, Windbreak/Shelterbelt Establishment, Silvopasture Establishment, Riparian Herbaceous Cover, Stream Habitat Improvement and Management, Pipeline, Heavy Use Area Protection, Spring Development, and Animal Trails and Walkways.

**After Situation:**

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Grazing Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to implement essential conservation practices: Brush Management, Fencing, Firebreak, Forage Harvest Management, Grazing Land Mechanical Treatment, Herbaceous Weed Control, Nutrient Management, Forage and Biomass Planting, Prescribed Grazing, Range Planting, Access Control, and Watering Facilities. As addressed in the CAP criteria, the plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 110 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$2,229.90

Scenario Cost/Unit: \$2,229.90

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, range conservation	1299	Conservation Activity Plan labor to study, plan the use and management of rangelands to maximize their use in a sustainable manner. Range managers may inventory soils, plants, and animals; develop resource management plans; identify monitoring methods an	Hour	\$74.33	30	\$2,229.90



Practice: 110 - Grazing Management Plan - Written

Scenario #2 - Grazing Management Plan 101 to 500 acres

Scenario Description:

Small agricultural operation with 101 to 500 acres grazed land. Natural Resource Concern: Soil erosion, water quality, fish and wildlife, plant condition, and all other appropriate resource concerns.

Before Situation:

Producer has no plan or limited knowledge of management of livestock or other animals on grazed land resources. The producer currently manages animals without plan to address identified natural resource concerns. Producer is interested in management of animals to maximize profit margin, reduce costs, improve or address wildlife opportunities, and for other environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: In addition to the essential practices listed previously, addition practices to consider include: Channel Bank Vegetation, Prescribed Burning, Critical Area Planting, Pond, Windbreak/Shelterbelt Establishment, Silvopasture Establishment, Riparian Herbaceous Cover, Stream Habitat Improvement and Management, Pipeline, Heavy Use Area Protection, Spring Development, and Animal Trails and Walkways.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Grazing Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to implement essential conservation practices: Brush Management, Fencing, Firebreak, Forage Harvest Management, Grazing Land Mechanical Treatment, Herbaceous Weed Control, Nutrient Management, Forage and Biomass Planting, Prescribed Grazing, Range Planting, Access Control, and Watering Facilities. As addressed in the CAP criteria, the plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 110 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$2,973.20

Scenario Cost/Unit: \$2,973.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, range conservation	1299	Conservation Activity Plan labor to study, plan the use and management of rangelands to maximize their use in a sustainable manner. Range managers may inventory soils, plants, and animals; develop resource management plans; identify monitoring methods an	Hour	\$74.33	40	\$2,973.20

Practice: 110 - Grazing Management Plan - Written

Scenario #3 - Grazing Management Plan 1501 to 5000 acres

Scenario Description:

Small agricultural operation with 1501 to 5000 acres grazed land. Natural Resource Concern: Soil erosion, water quality, fish and wildlife, plant condition, and all other appropriate resource concerns.

Before Situation:

Producer has no plan or limited knowledge of management of livestock or other animals on grazed land resources. The producer currently manages animals without plan to address identified natural resource concerns. Producer is interested in management of animals to maximize profit margin, reduce costs, improve or address wildlife opportunities, and for other environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: In addition to the essential practices listed previously, addition practices to consider include: Channel Bank Vegetation, Prescribed Burning, Critical Area Planting, Pond, Windbreak/Shelterbelt Establishment, Silvopasture Establishment, Riparian Herbaceous Cover, Stream Habitat Improvement and Management, Pipeline, Heavy Use Area Protection, Spring Development, and Animal Trails and Walkways.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Grazing Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to implement essential conservation practices: Brush Management, Fencing, Firebreak, Forage Harvest Management, Grazing Land Mechanical Treatment, Herbaceous Weed Control, Nutrient Management, Forage and Biomass Planting, Prescribed Grazing, Range Planting, Access Control, and Watering Facilities. As addressed in the CAP criteria, the plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 110 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$4,459.80

Scenario Cost/Unit: \$4,459.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, range conservation	1299	Conservation Activity Plan labor to study, plan the use and management of rangelands to maximize their use in a sustainable manner. Range managers may inventory soils, plants, and animals; develop resource management plans; identify monitoring methods an	Hour	\$74.33	60	\$4,459.80

Practice: 110 - Grazing Management Plan - Written

Scenario #5 - Grazing Management Plan Greater Than 5000 acres

Scenario Description:

Small agricultural operation with more than 5000 acres grazed land. Natural Resource Concern: Soil erosion, water quality, fish and wildlife, plant condition, and all other appropriate resource concerns.

Before Situation:

Producer has no plan or limited knowledge of management of livestock or other animals on grazed land resources. The producer currently manages animals without plan to address identified natural resource concerns. Producer is interested in management of animals to maximize profit margin, reduce costs, improve or address wildlife opportunities, and for other environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: In addition to the essential practices listed previously, addition practices to consider include: Channel Bank Vegetation, Prescribed Burning, Critical Area Planting, Pond, Windbreak/Shelterbelt Establishment, Silvopasture Establishment, Riparian Herbaceous Cover, Stream Habitat Improvement and Management, Pipeline, Heavy Use Area Protection, Spring Development, and Animal Trails and Walkways.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Grazing Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to implement essential conservation practices: Brush Management, Fencing, Firebreak, Forage Harvest Management, Grazing Land Mechanical Treatment, Herbaceous Weed Control, Nutrient Management, Forage and Biomass Planting, Prescribed Grazing, Range Planting, Access Control, and Watering Facilities. As addressed in the CAP criteria, the plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 110 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$5,203.10

Scenario Cost/Unit: \$5,203.10

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, range conservation	1299	Conservation Activity Plan labor to study, plan the use and management of rangelands to maximize their use in a sustainable manner. Range managers may inventory soils, plants, and animals; develop resource management plans; identify monitoring methods an	Hour	\$74.33	70	\$5,203.10

Practice: 110 - Grazing Management Plan - Written

Scenario #66 - Grazing Management Plan 501 to 1500 acres

Scenario Description:

Small agricultural operation with 501 to 1500 acres grazed land. Natural Resource Concern: Soil erosion, water quality, fish and wildlife, plant condition, and all other appropriate resource concerns.

Before Situation:

Producer has no plan or limited knowledge of management of livestock or other animals on grazed land resources. The producer currently manages animals without plan to address identified natural resource concerns. Producer is interested in management of animals to maximize profit margin, reduce costs, improve or address wildlife opportunities, and for other environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: In addition to the essential practices listed previously, addition practices to consider include: Channel Bank Vegetation, Prescribed Burning, Critical Area Planting, Pond, Windbreak/Shelterbelt Establishment, Silvopasture Establishment, Riparian Herbaceous Cover, Stream Habitat Improvement and Management, Pipeline, Heavy Use Area Protection, Spring Development, and Animal Trails and Walkways.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Grazing Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to implement essential conservation practices: Brush Management, Fencing, Firebreak, Forage Harvest Management, Grazing Land Mechanical Treatment, Herbaceous Weed Control, Nutrient Management, Forage and Biomass Planting, Prescribed Grazing, Range Planting, Access Control, and Watering Facilities. As addressed in the CAP criteria, the plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 110 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number of plans

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$3,716.50

Scenario Cost/Unit: \$3,716.50

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, range conservation	1299	Conservation Activity Plan labor to study, plan the use and management of rangelands to maximize their use in a sustainable manner. Range managers may inventory soils, plants, and animals; develop resource management plans; identify monitoring methods an	Hour	\$74.33	50	\$3,716.50

Practice: 112 - Prescribed Burning Plan - Written

Scenario #38 - Prescribed Burning Plan Less Than or Equal to 20 Acres

Scenario Description:

Non Industrial Private Forest Land, Pasture or Range Land typically less than or equal to 20 acres in size and is dominated by fire tolerant species that are competing with undesirable vegetation and accumulating fuel load. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition.

Before Situation:

Producer has no existing plan or an obsolete plan that is insufficient for current stand condition. Due to the size, landscape position, low to moderate fuel loads and presence of both natural firebreaks (i.e. – streams, lakes, etc.) and man-made firebreaks (i.e. – roads, farm paths, agricultural fields, etc.), few newly constructed firebreaks are needed to implement the prescribed burn. A Prescribed Burning Plan or Conservation Activity Plan is needed to enable the producer to apply for financial assistance through EQIP or other financial assistance programs in order to implement needed conservation practices. Associated Practices: 394, 383, 384, 528, 314, 315, 550, 644, 645, 659, 342, 647, 460, 643, 666, 595

After Situation:

After EQIP contract approval, participant has obtained services from a certified Technical Service Provider (TSP) for development of the “Prescribed Burning Plan” Conservation Activity Plan (CAP). The CAP criteria require the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Prescribed Burning Plan CAP is not considered a Forest Management Plan, a Reforestation Plan, a Forest Harvest Plan, or a Prescribed Grazing Plan, but should complement the needs of those plans if they exist and if desired by the decision maker. The CAP plan will fully describe all aspects of the prescribed burn including, but not limited to objectives of the burn (i.e. - site preparation, wildlife habitat, etc.), site conditions (i.e. - fuel load, fuel type, etc.), implementation strategies (i.e. - method of ignition, number of persons required, equipment needs, etc.), tolerable weather parameters (i.e. - wind direction, relative humidity, mixing height, etc.) and identification of Smoke Sensitive Areas. Additional CAP plan criteria are detailed in the Field Office Technical Guide and potentially state developed technical criteria.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$359.45

Scenario Cost/Unit: \$359.45

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	5	\$359.45

Practice: 112 - Prescribed Burning Plan - Written

Scenario #39 - Prescribed Burning Plan 21-100 Acres

Scenario Description:

Non Industrial Private Forest Land, Pasture or Range Land typically 21 to 100 acres in size and is dominated by fire tolerant species that are competing with undesirable vegetation and accumulating fuel load. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition.

Before Situation:

Producer has no existing plan or an obsolete plan that is insufficient for current stand condition. Due to the size, landscape position, low to moderate fuel loads and presence of both natural firebreaks (i.e. – streams, lakes, etc.) and man-made firebreaks (i.e. – roads, farm paths, agricultural fields, etc.), few newly constructed firebreaks are needed to implement the prescribed burn. A Prescribed Burning Plan or Conservation Activity Plan is needed to enable the producer to apply for financial assistance through EQIP or other financial assistance programs in order to implement needed conservation practices. Associated Practices: 394, 383, 384, 528, 314, 315, 550, 644, 645, 659, 342, 647, 460, 643, 666, 595

After Situation:

After EQIP contract approval, participant has obtained services from a certified Technical Service Provider (TSP) for development of the “Prescribed Burning Plan” Conservation Activity Plan (CAP). The CAP criteria require the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Prescribed Burning Plan CAP is not considered a Forest Management Plan, a Reforestation Plan, a Forest Harvest Plan, or a Prescribed Grazing Plan, but should complement the needs of those plans if they exist and if desired by the decision maker. The CAP plan will fully describe all aspects of the prescribed burn including, but not limited to objectives of the burn (i.e. - site preparation, wildlife habitat, etc.), site conditions (i.e. - fuel load, fuel type, etc.), implementation strategies (i.e. - method of ignition, number of persons required, equipment needs, etc.), tolerable weather parameters (i.e. - wind direction, relative humidity, mixing height, etc.) and identification of Smoke Sensitive Areas. Additional CAP plan criteria are detailed in the Field Office Technical Guide and potentially state developed technical criteria.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$575.12

Scenario Cost/Unit: \$575.12

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	8	\$575.12

Practice: 112 - Prescribed Burning Plan - Written

Scenario #40 - Prescribed Burning Plan 101-250 Acres

Scenario Description:

Non Industrial Private Forest Land, Pasture or Range Land typically 101 to 250 acres in size and is dominated by fire tolerant species that are competing with undesirable vegetation and accumulating fuel load. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition.

Before Situation:

Producer has no existing plan or an obsolete plan that is insufficient for current stand condition. Due to the size, landscape position, low to moderate fuel loads and presence of both natural firebreaks (i.e. – streams, lakes, etc.) and man-made firebreaks (i.e. – roads, farm paths, agricultural fields, etc.), few newly constructed firebreaks are needed to implement the prescribed burn. A Prescribed Burning Plan or Conservation Activity Plan is needed to enable the producer to apply for financial assistance through EQIP or other financial assistance programs in order to implement needed conservation practices. Associated Practices: 394, 383, 384, 528, 314, 315, 550, 644, 645, 659, 342, 647, 460, 643, 666, 595

After Situation:

After EQIP contract approval, participant has obtained services from a certified Technical Service Provider (TSP) for development of the “Prescribed Burning Plan” Conservation Activity Plan (CAP). The CAP criteria require the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Prescribed Burning Plan CAP is not considered a Forest Management Plan, a Reforestation Plan, a Forest Harvest Plan, or a Prescribed Grazing Plan, but should complement the needs of those plans if they exist and if desired by the decision maker. The CAP plan will fully describe all aspects of the prescribed burn including, but not limited to objectives of the burn (i.e. - site preparation, wildlife habitat, etc.), site conditions (i.e. - fuel load, fuel type, etc.), implementation strategies (i.e. - method of ignition, number of persons required, equipment needs, etc.), tolerable weather parameters (i.e. - wind direction, relative humidity, mixing height, etc.) and identification of Smoke Sensitive Areas. Additional CAP plan criteria are detailed in the Field Office Technical Guide and potentially state developed technical criteria.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$862.68

Scenario Cost/Unit: \$862.68

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	12	\$862.68

Practice: 112 - Prescribed Burning Plan - Written

Scenario #41 - Prescribed Burning Plan 251-500 Acres

Scenario Description:

Non Industrial Private Forest Land, Pasture or Range Land typically 251 to 500 acres in size and is dominated by fire tolerant species that are competing with undesirable vegetation and accumulating fuel load. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition.

Before Situation:

Producer has no existing plan or an obsolete plan that is insufficient for current stand condition. Due to the size, landscape position, low to moderate fuel loads and presence of both natural firebreaks (i.e. – streams, lakes, etc.) and man-made firebreaks (i.e. – roads, farm paths, agricultural fields, etc.), few newly constructed firebreaks are needed to implement the prescribed burn. A Prescribed Burning Plan or Conservation Activity Plan is needed to enable the producer to apply for financial assistance through EQIP or other financial assistance programs in order to implement needed conservation practices. Associated Practices: 394, 383, 384, 528, 314, 315, 550, 644, 645, 659, 342, 647, 460, 643, 666, 595

After Situation:

After EQIP contract approval, participant has obtained services from a certified Technical Service Provider (TSP) for development of the “Prescribed Burning Plan” Conservation Activity Plan (CAP). The CAP criteria require the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Prescribed Burning Plan CAP is not considered a Forest Management Plan, a Reforestation Plan, a Forest Harvest Plan, or a Prescribed Grazing Plan, but should complement the needs of those plans if they exist and if desired by the decision maker. The CAP plan will fully describe all aspects of the prescribed burn including, but not limited to objectives of the burn (i.e. - site preparation, wildlife habitat, etc.), site conditions (i.e. - fuel load, fuel type, etc.), implementation strategies (i.e. - method of ignition, number of persons required, equipment needs, etc.), tolerable weather parameters (i.e. - wind direction, relative humidity, mixing height, etc.) and identification of Smoke Sensitive Areas. Additional CAP plan criteria are detailed in the Field Office Technical Guide and potentially state developed technical criteria.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,150.24

Scenario Cost/Unit: \$1,150.24

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	16	\$1,150.24



Practice: 112 - Prescribed Burning Plan - Written

Scenario #42 - Prescribed Burning Plan 501-1000 Acres

Scenario Description:

Non Industrial Private Forest Land, Pasture or Range Land typically 501 to 1000 acres in size and is dominated by fire tolerant species that are competing with undesirable vegetation and accumulating fuel load. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition.

Before Situation:

Producer has no existing plan or an obsolete plan that is insufficient for current stand condition. Due to the size, landscape position, low to moderate fuel loads and presence of both natural firebreaks (i.e. – streams, lakes, etc.) and man-made firebreaks (i.e. – roads, farm paths, agricultural fields, etc.), few newly constructed firebreaks are needed to implement the prescribed burn. A Prescribed Burning Plan or Conservation Activity Plan is needed to enable the producer to apply for financial assistance through EQIP or other financial assistance programs in order to implement needed conservation practices. Associated Practices: 394, 383, 384, 528, 314, 315, 550, 644, 645, 659, 342, 647, 460, 643, 666, 595

After Situation:

After EQIP contract approval, participant has obtained services from a certified Technical Service Provider (TSP) for development of the “Prescribed Burning Plan” Conservation Activity Plan (CAP). The CAP criteria require the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Prescribed Burning Plan CAP is not considered a Forest Management Plan, a Reforestation Plan, a Forest Harvest Plan, or a Prescribed Grazing Plan, but should complement the needs of those plans if they exist and if desired by the decision maker. The CAP plan will fully describe all aspects of the prescribed burn including, but not limited to objectives of the burn (i.e. - site preparation, wildlife habitat, etc.), site conditions (i.e. - fuel load, fuel type, etc.), implementation strategies (i.e. - method of ignition, number of persons required, equipment needs, etc.), tolerable weather parameters (i.e. - wind direction, relative humidity, mixing height, etc.) and identification of Smoke Sensitive Areas. Additional CAP plan criteria are detailed in the Field Office Technical Guide and potentially state developed technical criteria.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,437.80

Scenario Cost/Unit: \$1,437.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	20	\$1,437.80

Practice: 112 - Prescribed Burning Plan - Written

Scenario #43 - Prescribed Burning Plan Greater Than 1000 Acres

Scenario Description:

Non Industrial Private Forest Land, Pasture or Range Land typically greater than 1000 acres in size and is dominated by fire tolerant species that are competing with undesirable vegetation and accumulating fuel load. Natural Resource Concern: Fish and Wildlife; Soil Erosion; Soil Condition; Water Quality; Plant Condition.

Before Situation:

Producer has no existing plan or an obsolete plan that is insufficient for current stand condition. Due to the size, landscape position, low to moderate fuel loads and presence of both natural firebreaks (i.e. – streams, lakes, etc.) and man-made firebreaks (i.e. – roads, farm paths, agricultural fields, etc.), few newly constructed firebreaks are needed to implement the prescribed burn. A Prescribed Burning Plan or Conservation Activity Plan is needed to enable the producer to apply for financial assistance through EQIP or other financial assistance programs in order to implement needed conservation practices. Associated Practices: 394, 383, 384, 528, 314, 315, 550, 644, 645, 659, 342, 647, 460, 643, 666, 595

After Situation:

After EQIP contract approval, participant has obtained services from a certified Technical Service Provider (TSP) for development of the “Prescribed Burning Plan” Conservation Activity Plan (CAP). The CAP criteria require the plan to identify approved Field Office Technical Guide conservation practices where needed to address identified resource concerns. The Prescribed Burning Plan CAP is not considered a Forest Management Plan, a Reforestation Plan, a Forest Harvest Plan, or a Prescribed Grazing Plan, but should complement the needs of those plans if they exist and if desired by the decision maker. The CAP plan will fully describe all aspects of the prescribed burn including, but not limited to objectives of the burn (i.e. - site preparation, wildlife habitat, etc.), site conditions (i.e. - fuel load, fuel type, etc.), implementation strategies (i.e. - method of ignition, number of persons required, equipment needs, etc.), tolerable weather parameters (i.e. - wind direction, relative humidity, mixing height, etc.) and identification of Smoke Sensitive Areas. Additional CAP plan criteria are detailed in the Field Office Technical Guide and potentially state developed technical criteria.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,725.36

Scenario Cost/Unit: \$1,725.36

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	24	\$1,725.36

Practice: 114 - Integrated Pest Management Plan - Written

Scenario #14 - IPM Management CAP Small-Specialty Less Than 50 Acres

**Scenario Description:**

Various on-farm land uses where pests are managed on smaller operations, including organic and specialty crop operations where more complicated pest management evaluations and solutions may be necessary. Current pest control activities cause environmental concerns with water quality and/or erosion. Natural Resource Concern: Water quality and all other appropriate resource concerns.

**Before Situation:**

Agricultural currently producer has no plan or limited knowledge of development or management of agricultural pests. The producer currently manages pests based upon pesticide label instructions, personal knowledge, or other local criteria. Producer is interested in management of pests and reduce the environmental impacts for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: Integrated Pest Management, Crop Rotation, Cover Crop, Field Boarder, Filter Strip, Stripcropping, and Residue and Tillage management practices, or other application conservation practices cited tin the NRCS Field Office Technical Guide.

**After Situation:**

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Integrated Pest Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to utilize the following strategies: Prevention, Avoidance, Monitoring, and Suppression, which will be implemented through use of "Integrated Pest Management and may use one or more conservation practices and/or risk reduction strategies. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 114 plan as cited in the NRCS Field Office Technical Guide.

**Feature Measure:** Number

**Scenario Unit::** Number

**Scenario Typical Size:** 1.0

**Scenario Total Cost:** \$1,896.00

**Scenario Cost/Unit:** \$1,896.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	25	\$1,896.00

Practice: 114 - Integrated Pest Management Plan - Written

Scenario #15 - IPM Management CAP Medium 51 - 250 Acres

Scenario Description:

Various on-farm land uses where pests are managed on a moderately-sized farm where IPM is to be applied. Current pest control activities cause environmental concerns with water quality and/or erosion. Natural Resource Concern: Water quality and all other appropriate resource concerns.

Before Situation:

Agricultural currently producer has no plan or limited knowledge of development or management of agricultural pests. The producer currently manages pests based upon pesticide label instructions, personal knowledge, or other local criteria. Producer is interested in management of pests and reduce the environmental impacts for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: Integrated Pest Management, Crop Rotation, Cover Crop, Field Boarder, Filter Strip, Stripcropping, and Residue and Tillage management practices, or other application conservation practices cited tin the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Integrated Pest Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to utilize the following strategies: Prevention, Avoidance, Monitoring, and Suppression, which will be implemented through use of "Integrated Pest Management and may use one or more conservation practices and/or risk reduction strategies. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 114 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$2,426.88

Scenario Cost/Unit: \$2,426.88

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	32	\$2,426.88

Practice: 114 - Integrated Pest Management Plan - Written

Scenario #16 - IPM Management CAP Large - Greater Than 250 Acres

**Scenario Description:**

Various on-farm land uses where pests are managed on a larger farm where IPM strategies are to be applied. Current pest control activities cause environmental concerns with water quality and/or erosion. Natural Resource Concern: Water quality and all other appropriate resource concerns.

**Before Situation:**

Agricultural currently producer has no plan or limited knowledge of development or management of agricultural pests. The producer currently manages pests based upon pesticide label instructions, personal knowledge, or other local criteria. Producer is interested in management of pests and reduce the environmental impacts for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: Integrated Pest Management, Crop Rotation, Cover Crop, Field Boarder, Filter Strip, Stripcropping, and Residue and Tillage management practices, or other application conservation practices cited tin the NRCS Field Office Technical Guide.

**After Situation:**

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Integrated Pest Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to utilize the following strategies: Prevention, Avoidance, Monitoring, and Suppression, which will be implemented through use of "Integrated Pest Management and may use one or more conservation practices and/or risk reduction strategies. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 114 plan as cited in the NRCS Field Office Technical Guide.

**Feature Measure:** Number

**Scenario Unit::** Number

**Scenario Typical Size:** 1.0

**Scenario Total Cost:** \$3,792.00

**Scenario Cost/Unit:** \$3,792.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	50	\$3,792.00

Practice: 118 - Irrigation Water Management Plan - Written

Scenario #6 - Irrigation Water Management Conservation Activity Plan CAP

Scenario Description:

Agricultural operations supported with existing irrigation systems. Natural Resource Concern: Water quantity and all other appropriate resource concerns.

Before Situation:

Currently producer has no plan or limited knowledge for management of water application to meet crop needs and address identified resource concerns. The producer currently manages water application based upon personal knowledge, or other local criteria. Producer is interested in management of irrigation water to maximize yields, profit margin, reduce costs, and for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: Irrigation Water Management (449); Irrigation System (442); Irrigation System, Surface & Subsurface (443); Irrigation Pipeline (430); Irrigation Ditch Lining (428); Irrigation Field Ditch (388); Irrigation Canal or Lateral (320); Structure for Water Control (587); Irrigation Reservoir (436); Irrigation System, Tailwater Recovery (447); Pumping Plant (533); Irrigation Land Leveling (464); Anionic Polyacrylamide (PM) Application (450); Salinity and Sodic Soil Management (590); Nutrient Management (590); Waste Utilization (633); or other applicable conservation practices in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Irrigation Water Management" conservation activity plan to control the volume, frequency, and rate of water for efficient irrigation and to address other resource concerns. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 118 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$3,107.65

Scenario Cost/Unit: \$3,107.65

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	35	\$3,107.65

Practice: 118 - Irrigation Water Management Plan - Written

Scenario #17 - Irrigation Water Management CAP with pump test

Scenario Description:

Agricultural operations supported with existing irrigation systems. Natural Resource Concern: Water quantity and all other appropriate resource concerns.

Before Situation:

Currently producer has no plan or limited knowledge for management of water application to meet crop needs and address identified resource concerns. The producer currently manages water application based upon personal knowledge, or other local criteria. The pump for the irrigation system is of unknown performance. Producer is interested in management of irrigation water to maximize yields, profit margin, reduce costs, and for environmental benefit. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: Irrigation Water Management (449); Irrigation System (442); Irrigation System, Surface & Subsurface (443); Irrigation Pipeline (430); Irrigation Ditch Lining (428); Irrigation Field Ditch (388); Irrigation Canal or Lateral (320); Structure for Water Control (587); Irrigation Reservoir (436); Irrigation System, Tailwater Recovery (447); Pumping Plant (533); Irrigation Land Leveling (464); Anionic Polyacrylamide (PM) Application (450); Salinity and Sodic Soil Management (590); Nutrient Management (590); Waste Utilization (633); or other applicable conservation practices in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Irrigation Water Management" conservation activity plan to control the volume, frequency, and rate of water for efficient irrigation and to address other resource concerns. Because a pump test was performed, a new pump that operates more efficiently and matches the irrigation system has been analyzed and could possibly be installed such that less water and energy are consumed. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 118 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Acre

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$4,883.45

Scenario Cost/Unit: \$4,883.45

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	55	\$4,883.45

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #39 - AgEMP Small, One Enterprise

Scenario Description:

Typical operation has either < 300 Acres < 300 AU Up to 2 irrigation pumps <20,000 sq ft of heater greenhouse, or A maple syrup enterprise One enterprise as defined in the ASABE S612 Standard on-farm energy audit standard. A small operation is as described above. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource: Energy Conservation

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer currently manages a small operation as described above. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement, or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$2,034.95

Scenario Cost/Unit: \$2,034.95

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	9	\$799.11
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$39.94	17	\$678.98
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	\$27.32	1.5	\$40.98
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	\$42.99	12	\$515.88



Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #41 - AgEMP Medium, One Enterprise

Scenario Description:

Typical operation has either 301 to 2500 Ac 301 to 1000 AU 3 to 6 Irrigation Pumps, or 20,001 to 40,000 sq ft heated greenhouse One enterprise as defined in the ASABE S612 Standard on-farm energy audit standard. A medium operation as described above. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource: Energy Conservation

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer currently manages a medium small operation with enterprise described above. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$2,526.88

Scenario Cost/Unit: \$2,526.88

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	12	\$1,065.48
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$39.94	18	\$718.92
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	\$27.32	2	\$54.64
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	\$42.99	16	\$687.84

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #43 - AgEMP Large, One Enterprise

Scenario Description:

Typical operation has either > 2,500 Ac > 1000 AU More than 7 irrigation pumps or > 40,001 sq ft of heater greenhouse One enterprise as defined in the ASABE S612 Standard on-farm energy audit standard in combination with a large operation with one enterprise, one of which is described above. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource: Energy Conservation.

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer currently manages a large operation with enterprise described above. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$3,327.93

Scenario Cost/Unit: \$3,327.93

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	19	\$1,687.01
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$39.94	20	\$798.80
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	\$27.32	2.5	\$68.30
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	\$42.99	18	\$773.82

**Practice:** 128 - Agricultural Energy Management Plan - Written

**Scenario #44 - AgEMP Small, Two Enterprise**

**Scenario Description:**

Typical operation has either <300 Ac <300 AU Up to 2 irrigation pumps, or <20,000 sq ft heated greenhouse Two enterprises as defined in the ASABE S612 Standard on-farm energy audit standard. A small operation as described above. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource: Energy Conservation

**Before Situation:**

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. An Agricultural Energy Mgmt CAP for any type small sized operation with two enterprises will be planned according to the ASABE S612 Standard (e.g., broiler and greenhouse). Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement, or other applicable practices approved in the NRCS Field Office Technical Guide.

**After Situation:**

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

**Feature Measure:** Number

**Scenario Unit::** Number

**Scenario Typical Size:** 1.0

**Scenario Total Cost:** \$3,141.68

**Scenario Cost/Unit:** \$3,141.68

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Labor</b>						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	15	\$1,331.85
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$39.94	21	\$838.74
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	\$27.32	2.5	\$68.30
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	\$42.99	21	\$902.79

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #45 - AgEMP Medium Two Enterprises

Scenario Description:

Typical operation has either 301 to 2500 Ac 301 to 1000 AU 3 to 6 Irrigation Pumps, or 20,001 to 40,000 sq ft heated greenhouse Two enterprises as defined in the ASABE S612 Standard on-farm energy audit standard in combination with a medium operation, one of which is described above. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource: Energy Conservation

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. An Agricultural Energy Mgmt CAP for any operation with two enterprises will be planned according to the ASABE S612 Standard (e.g., broiler and greenhouse). Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement, or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$4,248.41

Scenario Cost/Unit: \$4,248.41

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	21	\$1,864.59
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$39.94	25	\$998.50
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	\$27.32	3.5	\$95.62
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	\$42.99	30	\$1,289.70

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #46 - AgEMP Large, Two Enterprises

Scenario Description:

Typical operation has either > 2,500 Ac > 1000 AU More than 7 irrigation pumps or > 40,001 sq ft of heater greenhouse Two enterprises as defined in the ASABE S612 Standard on-farm energy audit standard in combination with a large operation, one of which is described above . Multiple irrigation systems or a mixture of irrigation types may be counted as one of extra enterprises. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource: Energy Conservation

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. An Agricultural Energy Mgmt CAP for any operation with two enterprises (complex or multiple irrigation systems can count as one of the extra enterprises) will be planned according to the ASABE S612 Standard (e.g., broiler and greenhouse). Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. An EMP is developed to assist an owner/operator in meeting all applicable local, tribal, State, and Federal water quality goals or regulations. Associated Practices: 449 Irrigation Water Management, 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement, or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$5,799.09

Scenario Cost/Unit: \$5,799.09

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	32	\$2,841.28
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$39.94	29	\$1,158.26
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	\$27.32	4.5	\$122.94
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	\$42.99	39	\$1,676.61

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #47 - AgEMP Small, Three Enterprise

Scenario Description:

Typical operation has either < 300 Acres < 300 AU Up to 2 irrigation pumps <20,000 sq ft of heater greenhouse, or Three enterprises as defined in the ASABE S612 Standard on-farm energy audit standard in combination with a small operation, one of which is described above. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource Concern: Energy

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. An Agricultural Energy Mgmt CAP for any type of operation with three enterprises will be planned according to the ASABE S612 Standard (e.g., broiler and greenhouse). Producer is willing to collaborate with a certified TSP to develop an AgEMP 122 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement, or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$3,633.61

Scenario Cost/Unit: \$3,633.61

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	18	\$1,598.22
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$39.94	22	\$878.68
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	\$27.32	3	\$81.96
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	\$42.99	25	\$1,074.75

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #48 - AgEMP Medium, Three Enterprise

Scenario Description:

Typical operation has either 301 to 2500 Ac 301 to 1000 AU 3 to 6 Irrigation Pumps, or 20,001 to 40,000 sq ft heated greenhouse Three enterprises as defined in the ASABE S612 Standard on-farm energy audit standard in combination with a medium operation, one of which is described above. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource Concern: Energy Conservation.

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. An Agricultural Energy Mgmt CAP for any type of operation with three enterprises will be planned according to the ASABE S612 Standard (e.g., broiler and greenhouse). Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement, or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$4,740.34

Scenario Cost/Unit: \$4,740.34

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	24	\$2,130.96
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$39.94	26	\$1,038.44
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	\$27.32	4	\$109.28
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	\$42.99	34	\$1,461.66

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #49 - AgEMP Large, Three Enterprise

Scenario Description:

Typical operation has either > 2,500 Ac > 1000 AU More than 7 irrigation pumps or > 40,001 sq ft of heater greenhouse Three enterprise as defined in the ASABE S612 Standard on-farm energy audit standard in combination with a large operation, one of which is described above. Multiple irrigation systems or a mixture of irrigation types may be counted as one of extra enterprises. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource Concern: Energy Conservation.

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. An Agricultural Energy Mgmt CAP for any type operation with three enterprises (complex or multiple irrigation systems can count as one of the extra enterprises) will be planned according to the ASABE S612 Standard (e.g., broiler and greenhouse). Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 449 Irrigation Water Management, 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement, or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$6,379.81

Scenario Cost/Unit: \$6,379.81

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	36	\$3,196.44
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$39.94	30	\$1,198.20
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	\$27.32	5	\$136.60
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	\$42.99	43	\$1,848.57



Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #50 - AgEMP Small, Four Enterprises

Scenario Description:

Typical operation has either < 300 Acres < 300 AU Up to 2 irrigation pumps, or <20,000 sq ft of heater greenhouse Four enterprises as defined in the ASABE S612 Standard on-farm energy audit standard in combination with an small operation, one of which is described above. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource Concern: Energy Conservation.

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. An Agricultural Energy Mgmt CAP for any operation with four enterprises will be planned according to the ASABE S612 Standard (e.g., broiler and greenhouse). Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 374 Farmstead Energy Improvement, 670Lighting System Improvement, 672 Building Envelope Improvement, or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$4,434.66

Scenario Cost/Unit: \$4,434.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	25	\$2,219.75
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$39.94	24	\$958.56
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	\$27.32	3.5	\$95.62
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	\$42.99	27	\$1,160.73

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #51 - AgEMP 128 Medium, Four Enterprise

Scenario Description:

Typical operation has either 301 to 2500 Ac 301 to 1000 AU 3 to 6 Irrigation Pumps, or 20,001 to 40,000 sq ft heated greenhouse Four enterprise as defined in the ASABE S612 Standard on-farm energy audit standard in combination with an medium operation, one of which is described above. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource Concern: Energy Conservation.

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. An Agricultural Energy Mgmt CAP for any type of operation with four or more enterprises will be planned according to the ASABE S612 Standard (e.g., broiler and greenhouse). Producer is willing to collaborate with a certified TSP to develop an AgEMP 122 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement, or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$5,541.39

Scenario Cost/Unit: \$5,541.39

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	31	\$2,752.49
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$39.94	28	\$1,118.32
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	\$27.32	4.5	\$122.94
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	\$42.99	36	\$1,547.64

Practice: 128 - Agricultural Energy Management Plan - Written

Scenario #52 - AgEMP 128 Large, Four Enterprise

Scenario Description:

Typical operation has either > 2,500 Ac > 1000 AU More than 7 irrigation pumps or > 40,001 sq ft of heater greenhouse Four enterprises as defined in the ASABE S612 Standard on-farm energy audit standard in combination with an large livestock operation, one of which is described above. . Multiple irrigation systems or a mixture of irrigation types may be counted as one of extra enterprises. Agricultural producer currently has minimal knowledge of and no plan for energy conservation. Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Natural Resource Concern: Energy Conservation.

Before Situation:

Agricultural producer currently has minimal knowledge of and no plan for energy conservation. An Agricultural Energy Mgmt CAP for any type of livestock operation with two non-livestock enterprises (complex or multiple irrigation systems can count as one of the extra enterprises) will be planned according to the ASABE S612 Standard (e.g., broiler and greenhouse). Producer is willing to collaborate with a certified TSP to develop an AgEMP 128 CAP. The AgEMP is a grouping of conservation measures and management activities which, when implemented as part of a conservation system, will help to ensure that both production and natural resource protection goals are achieved. An AgEMP incorporates recommended measures to maximize energy conservation and efficiency. Associated Practices: 449 Irrigation Water Management, 374 Farmstead Energy Improvement, 670 Lighting System Improvement, 672 Building Envelope Improvement, or other applicable practices approved in the NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for development of the "Agricultural Energy Management Plan". The CAP criteria requires the plan to meet quality criteria for energy conservation and efficiency. The CAP plan may include recommendations for associated conservation practices which address energy conservation. The CAP meets the basic quality criteria for the 128 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$7,269.65

Scenario Cost/Unit: \$7,269.65

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	44	\$3,906.76
CAP Labor, Manager	1603	Conservation Activity Plan labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$39.94	32	\$1,278.08
CAP Labor, Administrative Assistant	1739	Conservation Activity Plan labor involving routine clerical and administrative functions such as drafting correspondence, scheduling appointments, organizing and maintaining paper and electronic files, or providing information to callers.	Hour	\$27.32	5.5	\$150.26
CAP Labor, Energy Auditor	1740	Conservation Activity Plan labor involving analyzing energy efficient measures and conducting energy audits of industrial areas and facilities.	Hour	\$42.99	45	\$1,934.55

Practice: 130 - Drainage Water Management Plan - Written

Scenario #9 - DWMP - Tile Map Available

Scenario Description:

A Drainage Water Management Plan (DWMP) will be developed on a relatively flat crop field with a patterned drainage system, where a map of the tile system is available. The DWMP will document soil, topographic, and drainage system maps of the site, and identify the number and location of water control structures that are needed to implement drainage water management according to Field Office Technical Guide standards. The DWMP will also provide guidelines for management of the water control structures to achieve desired resource outcomes.

Before Situation:

Producer has no plan for or knowledge of managing drainage water. The producer does not manage the field for the purpose of controlling water retention during the crop season and therefore crop yields are reduced. Existing ditches and/or tile drains on the cropland field currently conduct flow off field to waterways resulting in potential water quality resource concerns related to excessive nitrogen.

After Situation:

A certified Technical Service Provider (TSP) develops the "Drainage Water Management" conservation activity plan (CAP). The DWMP documents soil, topographic, and drainage system maps of the site, and identifies the number and location of water control structures that are needed to implement drainage water management according to Field Office Technical Guide standards. The DWMP also provides guidelines for management of the water control structures to achieve desired resource outcomes. The plan is ready for implementation with structural measures and management once the structures are installed. No actual benefits to resource concerns are achieved until the practices in the DWMP are implemented.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$2,639.87

Scenario Cost/Unit: \$2,639.87

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, small surveying crew	1296	Conservation Activity Plan labor to perform surveying and mapping duties, usually under the direction of an engineer, surveyor, cartographer, or photogrammetrist to obtain data used for construction, mapmaking, boundary location, mining, or other purposes	Hour	\$104.52	8	\$836.16
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to prod	Hour	\$74.07	13	\$962.91
Cap Labor, Survey and Mapping Technician	1591	Conservation Activity Plan labor to perform surveying and mapping duties, usually under the direction of an engineer, surveyor, cartographer, or photogrammetrist to obtain data used for construction, mapmaking, boundary location, mining, or other purposes	Hour	\$52.55	16	\$840.80

Practice: 130 - Drainage Water Management Plan - Written

Scenario #10 - DWMP - No Tile Map Available

Scenario Description:

A Drainage Water Management Plan (DWMP) will be developed on a relatively flat crop field with a patterned drainage system, where no map of the tile system is available. The DWMP will document soil, topographic, and drainage system maps of the site, and identify the number and location of water control structures that are needed to implement drainage water management according to Field Office Technical Guide standards. The DWMP will also provide guidelines for management of the water control structures to achieve desired resource outcomes.

Before Situation:

Producer has no plan for or knowledge of managing drainage water. The producer does not manage the field for the purpose of controlling water retention during the crop season and therefore crop yields are reduced. Existing ditches and/or tile drains on the cropland field currently conduct flow off field to waterways resulting in potential water quality resource concerns related to excessive nitrogen.

After Situation:

A certified Technical Service Provider (TSP) develops the "Drainage Water Management" conservation activity plan (CAP). The DWMP documents soil, topographic, and drainage system maps of the site, and identifies the number and location of water control structures that are needed to implement drainage water management according to Field Office Technical Guide standards. The DWMP also provides guidelines for management of the water control structures to achieve desired resource outcomes. The plan is ready for implementation with structural measures and management once the structures are installed. No actual benefits to resource concerns are achieved until the practices in the DWMP are implemented.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$3,149.31

Scenario Cost/Unit: \$3,149.31

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, small surveying crew	1296	Conservation Activity Plan labor to perform surveying and mapping duties, usually under the direction of an engineer, surveyor, cartographer, or photogrammetrist to obtain data used for construction, mapmaking, boundary location, mining, or other purposes	Hour	\$104.52	8	\$836.16
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to prod	Hour	\$74.07	13	\$962.91
Cap Labor, Survey and Mapping Technician	1591	Conservation Activity Plan labor to perform surveying and mapping duties, usually under the direction of an engineer, surveyor, cartographer, or photogrammetrist to obtain data used for construction, mapmaking, boundary location, mining, or other purposes	Hour	\$52.55	16	\$840.80
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	16	\$509.44

Practice: 138 - Conservation Plan Supporting Organic Transition - Written

Scenario #10 - Conservation Plan Supporting Organic Transition CAP

Scenario Description:

Agricultural operation where producer will transition from conventional to organic to meet USDA National Organic Program (NOP) requirements. Natural Resource Concern: Soil Erosion, Water Quality, Plant Condition, and other identified natural resource concerns.

Before Situation:

Agricultural operation currently managed using traditional and conventional methods for farming and/or ranching. The producer currently manages operation based upon personal knowledge, or other local criteria. Producer is interested in transitioning part or all of the management unit to meet national USDA requirements for certified operation. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: Refer to the NRCS Plan Criteria for conservation practices associated with operations transitioning to organic certification and typically needed to address identified natural resource concerns.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP to develop the "Conservation Plan Supporting Organic Transition" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to implement a system of conservation practices which assist the producer to transition from conventional farming or ranching to an organic production system. The CAP plan will include conservation practices which address related resource concerns. CAP meets the basic quality criteria for the 138 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$3,036.87

Scenario Cost/Unit: \$3,036.87

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to prod	Hour	\$74.07	41	\$3,036.87

Practice: 138 - Conservation Plan Supporting Organic Transition - Written

Scenario #11 - Conservation Plan Supporting Organic Transition CAP No Local TSP

Scenario Description:

Agricultural operation where producer will transition from conventional to organic to meet USDA National Organic Program (NOP) requirements. No qualified TSP within 300 miles. Natural Resource Concern: Soil Erosion, Water Quality, Plant Condition, and other identified natural resource concerns.

Before Situation:

Agricultural operation currently managed using traditional and conventional methods for farming and/or ranching. The producer currently manages operation based upon personal knowledge, or other local criteria. Producer is interested in transitioning part or all of the management unit to meet national USDA requirements for certified operation. Producer is willing to collaborate with a certified TSP to develop a plan and collect/coordinate data recording to monitor per requirements of plan. Associated Practices: Refer to the NRCS Plan Criteria for conservation practices associated with operations transitioning to organic certification and typically needed to address identified natural resource concerns.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP to develop the "Conservation Plan Supporting Organic Transition" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to implement a system of conservation practices which assist the producer to transition from conventional farming or ranching to an organic production system. The CAP plan will include conservation practices which address related resource concerns. CAP meets the basic quality criteria for the 138 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$4,740.48

Scenario Cost/Unit: \$4,740.48

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Cap Labor, conservation scientist	1300	Conservation Activity Plan labor to manage, improve, and protect natural resources to maximize their use without damaging the environment. Interprets resource information and assess resource conditions to provide conservation practice alternatives to prod	Hour	\$74.07	64	\$4,740.48

Practice: 142 - Fish and Wildlife Habitat Plan - Written

Scenario #6 - Fish and Wildlife Habitat Management CAP

Scenario Description:

Various on-farm land uses. Natural Resource Concern: Fish and Wildlife, and other applicable resource concerns on an agricultural operation.

Before Situation:

Agricultural currently producer has no plan or knowledge of development or management of fish and/or wildlife habitat. The producer does not currently manage or enhance habitat to promote opportunities for fish and/or habitat. Within existing land uses, producer is interested in management of land or for establishment of new habitat for benefit of appropriate fish or wildlife species. Associated Practices: Applicable conservation practices cited in the CAP criteria and NRCS Field Office Technical Guide.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Fish and Wildlife Management" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for the primary fish/wildlife habitat resource concern and other applicable resource concerns and provides for opportunities to improve, restore, or enhance habitat that supports native and/or managed species. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 142 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$3,225.18

Scenario Cost/Unit: \$3,225.18

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Labor

CAP Labor, biologist	1298	Conservation Activity Plan labor to study the origins, behavior, diseases, genetics, and life processes of animals and wildlife. May specialize in wildlife research and management. May collect and analyze biological data to determine the environmental eff	Hour	\$76.79	42	\$3,225.18
----------------------	------	---	------	---------	----	------------



Practice: 146 - Pollinator Habitat Plan - Written

Scenario #10 - Pollinator Habitat Enhancement Plan CAP

Scenario Description:

Various on-farm land uses. Natural Resource Concern: Fish and Wildlife, Plant Condition, Soil Erosion, Water Quality on an agricultural operation.

Before Situation:

Agricultural producer currently has no plan or knowledge of development or management of pollinator habitat. The producer does not currently manage or enhance habitat to promote opportunities for pollinator habitat. Within existing land uses, producer may be interested in management of land or for establishment of new habitat for benefit of appropriate pollinator species. Associated Practices: 311, 322, 327, 328, 656, 332, 340, 342, 647, 386, 393, 412, 422, 603, 379, 512, 595, 338, 528, 550, 329, 643, 391, 390, 381, 395, 580, 585, 612, 645, 601, 659, 657, 644, 380, 650.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Pollinator Habitat Enhancement" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to improve, restore, or enhance flower-rich habitat that supports native and/or managed pollinator species. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 146 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$3,225.18

Scenario Cost/Unit: \$3,225.18

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, biologist	1298	Conservation Activity Plan labor to study the origins, behavior, diseases, genetics, and life processes of animals and wildlife. May specialize in wildlife research and management. May collect and analyze biological data to determine the environmental eff	Hour	\$76.79	42	\$3,225.18

Practice: 146 - Pollinator Habitat Plan - Written

Scenario #11 - Pollinator Habitat Enhancement Plan CAP - No Local TSP

Scenario Description:

Various on-farm land uses, No qualified TSP within 300 miles. Natural Resource Concern: Fish and Wildlife, Plant Condition, Soil Erosion, Water Quality on an agricultural operation.

Before Situation:

Agricultural producer currently has no plan or knowledge of development or management of pollinator habitat. The producer does not currently manage or enhance habitat to promote opportunities for pollinator habitat. Within existing land uses, producer may be interested in management of land or for establishment of new habitat for benefit of appropriate pollinator species. Associated Practices: 311, 322, 327, 328, 656, 332, 340, 342, 647, 386, 393, 412, 422, 603, 379, 512, 595, 338, 528, 550, 329, 643, 391, 390, 381, 395, 580, 585, 612, 645, 601, 659, 657, 644, 380, 650.

After Situation:

After EQIP contract approval, participant has obtained services from a certified TSP for develop of the "Pollinator Habitat Enhancement" conservation activity plan. The CAP criteria requires the plan to meet quality criteria for applicable resource concerns and provides for opportunities to improve, restore, or enhance flower-rich habitat that supports native and/or managed pollinator species. The CAP plan may include recommendations for associated conservation practices which address other related resource concerns. CAP meets the basic quality criteria for the 146 plan as cited in the NRCS Field Office Technical Guide.

Feature Measure: Number

Scenario Unit:: Number

Scenario Typical Size: 1.0

Scenario Total Cost: \$4,684.19

Scenario Cost/Unit: \$4,684.19

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Labor

CAP Labor, biologist	1298	Conservation Activity Plan labor to study the origins, behavior, diseases, genetics, and life processes of animals and wildlife. May specialize in wildlife research and management. May collect and analyze biological data to determine the environmental eff	Hour	\$76.79	61	\$4,684.19
----------------------	------	---	------	---------	----	------------

Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #56 - Data Collect Surface Year 1-QAPP

Scenario Description:

This practice scenario provides for the design and use of an edge-of-field WQ monitoring station(s) for surface run-off for one control and one treatment site with an average of 20 samples per year per station. The scenario requires the creation of a survey to site a monitoring station, preparation of monitoring plan and a quality assurance project plan to detail how data will be collected, handled and analyzed, provides for the data collection, analysis, semiannual report, and annual report. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP need to be prepared prior to installation under Edge-of-Field Water Quality Monitoring - System Installation (202). THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will not have a plan or quality assurance project plan prepared for installing equipment nor collecting data for sediment and nutrients leaving the edge of field.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual report, and annual report for one control and one treatment site. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP have been prepared prior to installation under Edge-of-Field Water Quality Monitoring - System Installation (202). The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201.

Feature Measure: Measuring Sites

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$21,773.96

Scenario Cost/Unit: \$21,773.96

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	100	\$7,584.00
CAP Labor, small surveying crew	1296	Conservation Activity Plan labor to perform surveying and mapping duties, usually under the direction of an engineer, surveyor, cartographer, or photogrammetrist to obtain data used for construction, mapmaking, boundary location, mining, or other purposes	Hour	\$104.52	16	\$1,672.32
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	20	\$1,775.80
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	130	\$4,139.20
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	\$27.06	4	\$108.24
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	40	\$1,082.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	40	\$1,082.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	40	\$1,082.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	20	\$541.20

Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	20	\$541.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	40	\$1,082.40

Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #57 - Data Collect Surface Year 1 - NO QAPP

Scenario Description:

This practice scenario provides for the use of an edge-of-field WQ monitoring station(s) for surface run-off for one control and one treatment site. The scenario requires the collection and analysis of edge-of-field water quality data with an average sample collection of 20 per year for surface systems. The data will be transferred through semi-annual submittal and annual report which include some preliminary annual analysis. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP will be not prepared as this is for an existing monitoring system that has been accepted as meeting both Activity 201 and 202. THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will have an existing system for collecting water quality data but not have been operating with a long enough time frame to measure practice effectiveness.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual submittal, and annual report for one control and one treatment site. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP have been prepared as part of an existing monitoring system installation where the QAPP and monitoring plan meets Activity 201 requirements and no major changes are needed to meet Activity 202 requirements. The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201.

Feature Measure: Measuring Site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$15,292.24

Scenario Cost/Unit: \$15,292.24

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	60	\$4,550.40
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	130	\$4,139.20
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	\$27.06	4	\$108.24
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	20	\$541.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	40	\$1,082.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	20	\$541.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	40	\$1,082.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	40	\$1,082.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	40	\$1,082.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	40	\$1,082.40

Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #58 - Data Collect Surface Year 2+

Scenario Description:

This practice scenario provides for the use of an edge-of-field WQ monitoring station(s) for surface run-off for one control and one treatment site. The scenario requires the collection and analysis of edge-of-field water quality data with an average sample collection of 20 per year for surface systems. The data will be transferred through semi-annual submittal and annual report which include some preliminary annual analysis. This scenario will normally be used in year 2 to next to the last year of monitoring. THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will have an existing system for collecting water quality data but not have been operating with a long enough time frame to measure practice effectiveness.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual submittal, and annual report for one control and one treatment site. The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201.

Feature Measure: Measuring Site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$15,292.24

Scenario Cost/Unit: \$15,292.24

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	60	\$4,550.40
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	130	\$4,139.20
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	\$27.06	4	\$108.24
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	20	\$541.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	40	\$1,082.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	40	\$1,082.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	40	\$1,082.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	20	\$541.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	40	\$1,082.40

Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #59 - Data Collect Surface Last Year

Scenario Description:

This practice scenario provides for the use of an edge-of-field WQ monitoring station(s) for surface run-off for one control and one treatment site with an average of 20 samples per year per station. The scenario requires the collection and analysis of edge-of-field water quality data along with a comprehensive report to statistically prove relationship between select conservation practices and water quality. The data will be transferred through semi-annual submittal and annual report and a comprehensive report of practice effectiveness. This scenario will be used in the last year of monitoring. THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will have an existing system for collecting water quality data but not have been operating with a long enough time frame to measure practice effectiveness.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual submittal, and annual report for one control and one treatment site. The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201 to provide a comprehensive report of statistical testing of data collected to complete monitoring period.

Feature Measure: Measuring Site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$18,325.84

Scenario Cost/Unit: \$18,325.84

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	100	\$7,584.00
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	130	\$4,139.20
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	\$27.06	4	\$108.24
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	20	\$541.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	20	\$541.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	40	\$1,082.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	40	\$1,082.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	40	\$1,082.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	40	\$1,082.40

**Practice:** 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

**Scenario #60 - Data Collect Tile Year 1-QAPP**

**Scenario Description:**

This practice scenario provides for the design and use of an edge-of-field WQ monitoring station(s) for tile and subsurface drainage run-off for one control and one treatment site with an average of 40 samples per year per station. A subsurface system also requires the addition of a surface sampling system at the same outlet to capture overland flow with 20 samples per year. Without the surface system then not all runoff is captured for calculating a true event mean concentration as per the 201 Standard. The scenario requires the creation of a survey to site a monitoring station, preparation of monitoring plan and a quality assurance project plan to detail how data will be collected, handled and analyzed, provides for the data collection, analysis, semiannual report, and annual report. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP need to be prepared prior to installation under Edge-of-Field Water Quality Monitoring - System Installation (202). THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

**Before Situation:**

The agricultural operation prior to installing this practice will not have a plan or quality assurance project plan prepared for installing equipment nor collecting data for sediment and nutrients leaving the edge of field.

**After Situation:**

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual report, and annual report for one control and one treatment site. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP have been prepared prior to installation under Edge-of-Field Water Quality Monitoring - System Installation (202). The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201.

**Feature Measure:** Measuring Site

**Scenario Unit::** Each

**Scenario Typical Size:** 1.0

**Scenario Total Cost:** \$43,049.32

**Scenario Cost/Unit:** \$43,049.32

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Labor</b>						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	130	\$9,859.20
CAP Labor, small surveying crew	1296	Conservation Activity Plan labor to perform surveying and mapping duties, usually under the direction of an engineer, surveyor, cartographer, or photogrammetrist to obtain data used for construction, mapmaking, boundary location, mining, or other purposes	Hour	\$104.52	16	\$1,672.32
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	20	\$1,775.80
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	312	\$9,934.08
<b>Materials</b>						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	\$27.06	12	\$324.72
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	120	\$3,247.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	120	\$3,247.20



Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	120	\$3,247.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	120	\$3,247.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	120	\$3,247.20

Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #61 - Data Collect Tile Year 1 - NO QAPP

Scenario Description:

This practice scenario provides for the design and use of an edge-of-field WQ monitoring station(s) for tile and subsurface drainage run-off for one control and one treatment site with an average of 40 samples per year per station. A subsurface system also requires the addition of a surface sampling system at the same outlet to capture overland flow with 20 samples per year. Without the surface system then not all runoff is captured for calculating a true event mean concentration as per the 201 Standard. The data will be transferred through semi-annual submittal and annual reports, which include some preliminary annual analysis. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP will be not prepared as this is for an existing monitoring system be accepted as meeting both Activity 201 and 202. THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will have an existing system for collecting water quality data but not have been operating with a long enough time frame to measure practice effectiveness.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual submittal, and annual report for one control and one treatment site. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP have been prepared as part of an existing monitoring system installation where the QAPP and monitoring plan meets Activity 201 requirements and no major changes are needed to meet Activity 202 requirements. The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201.

Feature Measure: Measuring Site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$36,567.60

Scenario Cost/Unit: \$36,567.60

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	90	\$6,825.60
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	312	\$9,934.08
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	\$27.06	12	\$324.72
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	120	\$3,247.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	120	\$3,247.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	120	\$3,247.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	120	\$3,247.20

Testing, Water Quality

2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	120	\$3,247.20
------	---	------	---------	-----	------------

Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #62 - Data Collect Tile Year 2+

Scenario Description:

This practice scenario provides for the design and use of an edge-of-field WQ monitoring station(s) for tile and subsurface drainage run-off for one control and one treatment site with an average of 40 samples per year per station. A subsurface system also requires the addition of a surface sampling system at the same outlet to capture overland flow with 20 samples per year. Without the surface system then not all runoff is captured for calculating a true event mean concentration as per the 201 Standard. The data will be transferred through semi-annual submittal and annual report, which include some preliminary annual analysis. This scenario will normally be used in year 2 to next to the last year of monitoring. THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will not have a plan or quality assurance project plan prepared for installing equipment nor collecting data for sediment and nutrients leaving the edge of field.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual report, and annual report for one control and one treatment site. The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201.

Feature Measure: Measuring site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$36,567.60

Scenario Cost/Unit: \$36,567.60

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	90	\$6,825.60
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	312	\$9,934.08
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	\$27.06	12	\$324.72
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	120	\$3,247.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	120	\$3,247.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	120	\$3,247.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	120	\$3,247.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	120	\$3,247.20

Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #63 - Data Collect Tile Last Year

Scenario Description:

This practice scenario provides for the design and use of an edge-of-field WQ monitoring station(s) for tile and subsurface drainage run-off for one control and one treatment site with an average of 40 samples per year per station. A subsurface system also requires the addition of a surface sampling system at the same outlet to capture overland flow with 20 samples per year. Without the surface system then not all runoff is captured for calculating a true event mean concentration as per the 201 Standard. The scenario requires the collection and analysis of edge-of-field water quality data along with a comprehensive report to statistically prove relationship between select conservation practices and water quality. The data will be transferred through semi-annual submittal and annual report and a comprehensive report of practice effectiveness. This scenario will be used in the last year of monitoring. THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will have an existing system for collecting water quality data but not have been operating with a long enough time frame to measure practice effectiveness.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual submittal, and annual report for one control and one treatment site. The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201 to provide a comprehensive report of statistical testing of data collected during to complete monitoring period.

Feature Measure: Measuring site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$39,601.20

Scenario Cost/Unit: \$39,601.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	130	\$9,859.20
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	312	\$9,934.08
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	\$27.06	12	\$324.72
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	120	\$3,247.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	120	\$3,247.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	120	\$3,247.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	120	\$3,247.20
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60



Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #64 - Data Collect Surface Year 1-QAPP with two treatment Sites

Scenario Description:

This practice scenario provides for the design and use of an edge-of-field WQ monitoring station(s) for surface run-off for one control and two treatment sites with an average of 20 samples per year per station. The scenario requires the creation of a survey to site a monitoring station, preparation of monitoring plan and a quality assurance project plan to detail how data will be collected, handled and analyzed, provides for the data collection, analysis, semiannual report, and annual report. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP need to be prepared prior to installation under Edge-of-Field Water Quality Monitoring - System Installation (202). THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will not have a plan or quality assurance project plan prepared for installing equipment nor collecting data for sediment and nutrients leaving the edge of field.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual report, and annual report for one control and one treatment site. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP have been prepared prior to installation under Edge-of-Field Water Quality Monitoring - System Installation (202). The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201.

Feature Measure: Measuring Sites

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$29,902.38

Scenario Cost/Unit: \$29,902.38

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	130	\$9,859.20
CAP Labor, small surveying crew	1296	Conservation Activity Plan labor to perform surveying and mapping duties, usually under the direction of an engineer, surveyor, cartographer, or photogrammetrist to obtain data used for construction, mapmaking, boundary location, mining, or other purposes	Hour	\$104.52	24	\$2,508.48
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	30	\$2,663.70
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	156	\$4,967.04
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	\$27.06	6	\$162.36
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60

Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	30	\$811.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	30	\$811.80



Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #65 - Data Collect Surface Year 1 less QAPP (pre-install information) with two treatment sites

Scenario Description:

This practice scenario provides for the use of an edge-of-field WQ monitoring station(s) for surface run-off for one control and two treatment sites. The scenario requires the collection and analysis of edge-of-field water quality data with an average sample collection of 20 per year for each surface system. The data will be transferred through semi-annual submittal and annual report, which include some preliminary annual analysis. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP will not be prepared as this is for an existing monitoring system be accepted as meeting both Activity 201 and 202. THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will have an existing system for collecting water quality data but not have been operating with a long enough time frame to measure practice effectiveness.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual submittal, and annual report for one control and two treatment sites. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP have been prepared as part of an existing monitoring system installation where the QAPP and monitoring plan meets Activity 201 requirements and no major changes are needed to meet Activity 202 requirements. The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201.

Feature Measure: Measuring site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$21,696.60

Scenario Cost/Unit: \$21,696.60

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	90	\$6,825.60
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	156	\$4,967.04
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	\$27.06	6	\$162.36
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	30	\$811.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	30	\$811.80

Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #66 - Data Collect Surface Year 2+ with two treatment sites

Scenario Description:

This practice scenario provides for the use of an edge-of-field WQ monitoring station(s) for surface run-off for one control and two treatment sites. The scenario requires the collection and analysis of edge-of-field water quality data with an average sample collection of 20 per year for each surface system. The data will be transferred through semi-annual submittal and annual report, which include some preliminary annual analysis. This scenario will normally be used in year 2 to next to the last year of monitoring. THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will have an existing system for collecting water quality data but not have been operating with a long enough time frame to measure practice effectiveness.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual submittal, and annual report for one control and two treatment sites. The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201.

Feature Measure: Measuring site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$21,696.60

Scenario Cost/Unit: \$21,696.60

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	90	\$6,825.60
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	156	\$4,967.04
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	\$27.06	6	\$162.36
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	30	\$811.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	30	\$811.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60

Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #67 - Data Collect Surface Last Year with two treatment sites

Scenario Description:

This practice scenario provides for the use of an edge-of-field WQ monitoring station(s) for surface run-off for one control and two treatment sites with an average of 20 samples per year per station. The scenario requires the collection and analysis of edge-of-field water quality data along with a comprehensive report to statistically prove relationship between select conservation practices and water quality. The data will be transferred through semi-annual submittal and annual report and a comprehensive report of practice effectiveness. This scenario will be used in the last year of monitoring. THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will have an existing system for collecting water quality data but not have been operating with a long enough time frame to measure practice effectiveness.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual submittal, and annual report for one control and two treatment sites. The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201 to provide a comprehensive report of statistical testing of data collected during to complete monitoring period.

Feature Measure: Measuring site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$26,247.00

Scenario Cost/Unit: \$26,247.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	150	\$11,376.00
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	156	\$4,967.04
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	\$27.06	6	\$162.36
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	30	\$811.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	30	\$811.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	60	\$1,623.60

**Practice:** 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

**Scenario #68** - Data Collect Tile Year 1 with two treatment sites and QAPP

#### Scenario Description:

This practice scenario provides for the design and use of an edge-of-field WQ monitoring station(s) for tile and subsurface drainage run-off for one control and two treatment sites with an average of 40 samples per year per station. A subsurface system also requires the addition of a surface sampling system at the same outlet to capture overland flow with 20 samples per year. Without the surface system then not all runoff is captured for calculating a true event mean concentration as per the 201 Standard. The scenario requires the creation of a survey to site monitoring stations, preparation of monitoring plan and a quality assurance project plan (QAPP) to detail how data will be collected, handled and analyzed, provides for the data collection, analysis, semiannual report, and annual report. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP need to be prepared prior to installation under Edge-of-Field Water Quality Monitoring - System Installation (202). THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

#### Before Situation:

The agricultural operation prior to installing this practice will not have a plan or quality assurance project plan prepared for installing equipment nor collecting data for sediment and nutrients leaving the edge of field.

#### After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual report, and annual report for one control and two treatment sites. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP have not been prepared prior to installation under Edge-of-Field Water Quality Monitoring - System Installation (202). The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201.

**Feature Measure:** Measuring site

**Scenario Unit::** Each

**Scenario Typical Size:** 1.0

**Scenario Total Cost:** \$59,745.82

**Scenario Cost/Unit:** \$59,745.82

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Labor</b>						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	175	\$13,272.00
CAP Labor, small surveying crew	1296	Conservation Activity Plan labor to perform surveying and mapping duties, usually under the direction of an engineer, surveyor, cartographer, or photogrammetrist to obtain data used for construction, mapmaking, boundary location, mining, or other purposes	Hour	\$104.52	24	\$2,508.48
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	30	\$2,663.70
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	364	\$11,589.76
<b>Materials</b>						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	\$27.06	18	\$487.08
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	90	\$2,435.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	90	\$2,435.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	180	\$4,870.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	180	\$4,870.80

Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	180	\$4,870.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	180	\$4,870.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	180	\$4,870.80

Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #69 - Data Collect Tile Year 1 less QAPP (pre-install information) with two treatment sites

Scenario Description:

This practice scenario provides for the design and use of an edge-of-field WQ monitoring station(s) for tile and subsurface drainage run-off for one control and two treatment sites with an average of 40 samples per year per station. A subsurface system also requires the addition of a surface sampling system at the same outlet to capture overland flow with 20 samples per year. Without the surface system then not all runoff is captured for calculating a true event mean concentration as per the 201 Standard. The data will be transferred through semi-annual submittal and annual reports, which include some preliminary annual analysis. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP will not be prepared as this is for an existing monitoring system be accepted as meeting both Activity 201 and 202. THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will have an existing system for collecting water quality data but not have been operating with a long enough time frame to measure practice effectiveness.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual submittal, and annual report for one control and two treatment sites. This scenario will normally be used in year 1 of the contract when a monitoring plan and QAPP have been prepared as part of an existing monitoring system installation where the QAPP and monitoring plan meets Activity 201 requirements and no major changes are needed to meet Activity 202 requirements. The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201.

Feature Measure: Measuring site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$51,540.04

Scenario Cost/Unit: \$51,540.04

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	135	\$10,238.40
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	364	\$11,589.76
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	\$27.06	18	\$487.08
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	180	\$4,870.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	180	\$4,870.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	180	\$4,870.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	90	\$2,435.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	90	\$2,435.40

Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	180	\$4,870.80
------------------------	------	---	------	---------	-----	------------

Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #70 - Data Collect Tile Year 2+ with two treatment sites

Scenario Description:

This practice scenario provides for the design and use of an edge-of-field WQ monitoring station(s) for tile and subsurface drainage run-off for one control and two treatment sites with an average of 40 samples per year per station. A subsurface system also requires the addition of a surface sampling system at the same outlet to capture overland flow with 20 samples per year. Without the surface system then not all runoff is captured for calculating a true event mean concentration as per the 201 Standard. The data will be transferred through semi-annual submittal and annual report, which include some preliminary annual analysis. This scenario will normally be used in year 2 to next to the last year of monitoring. THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will have an existing system for collecting water quality data but not have been operating with a long enough time frame to measure practice effectiveness.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual report, and annual report for one control and two treatment sites. The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201.

Feature Measure: Measuring site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$51,540.04

Scenario Cost/Unit: \$51,540.04

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	135	\$10,238.40
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	364	\$11,589.76
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	\$27.06	18	\$487.08
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	90	\$2,435.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	90	\$2,435.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	180	\$4,870.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	180	\$4,870.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	180	\$4,870.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	180	\$4,870.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	180	\$4,870.80



Practice: 201 - Edge-of-Field Water Quality Monitoring-Data Collection and Evaluation

Scenario #71 - Data Collect Tile Last Year with two treatment sites

Scenario Description:

This practice scenario provides for the design and use of an edge-of-field WQ monitoring station(s) for tile and subsurface drainage run-off for one control and two treatment sites with an average of 40 samples per year per station. A subsurface system also requires the addition of a surface sampling system at the same outlet to capture overland flow with 20 samples per year. Without the surface system then not all runoff is captured for calculating a true event mean concentration as per the 201 Standard. The scenario requires the collection and analysis of edge-of-field water quality data along with a comprehensive report to statistically prove relationship between select conservation practices and water quality. The data will be transferred through semi-annual submittal and annual report and a comprehensive report of practice effectiveness. This scenario will be used in the last year of monitoring. THIS IS PLACED IN A PAIRED SITUATION IF THE CONTROL AND TREATMENT ARE ON DIFFERENT LANDOWNERS FIELDS THEN A JOINT CONTRACT WILL BE NECESSARY.

Before Situation:

The agricultural operation prior to installing this practice will have an existing system for collecting water quality data but not have been operating with a long enough time frame to measure practice effectiveness.

After Situation:

This practice scenario after installation of the WQ monitoring stations, provides for the data collection, analysis, semiannual submittal, and annual report for one control and two treatment sites. The operator will be able to collect field level water quality data of sufficient quality to measure loss of nutrients as listed in 201 to provide a comprehensive report of statistical testing of data collected during to complete monitoring period.

Feature Measure: Measuring site

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$56,090.44

Scenario Cost/Unit: \$56,090.44

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	195	\$14,788.80
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	364	\$11,589.76
Materials						
Testing, Blanks Samples	2612	Blanks or Duplicate Samples; Includes materials only.	Each	\$27.06	18	\$487.08
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	180	\$4,870.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	180	\$4,870.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	90	\$2,435.40
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	180	\$4,870.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	180	\$4,870.80
Testing, Water Quality	2613	Ammonium, Nitrite plus Nitrate, Total Kjeldahl Nitrogen, Soluble Reactive P (Orthophosphate), Total Phosphorus, Suspended Sediment Concentration ??? Preferred, or Total Suspended Solids. Includes materials only.	Each	\$27.06	90	\$2,435.40



Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #38 - System Installation-Surface

Scenario Description:

This edge-of-field water quality monitoring system is applicable to a single control or treatment site that has a field defined with surface runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The component monitoring equipment are associated with a typical system for southern latitudes where winter time heating is not required for sampling. It will allow for installation of automated sampling data collection system with protective housing to reduce potential for vandalism, battery backup for operation during periods when electricity is down or solar panels are not creating an electrical current, and a berm or other directional flow structure to guide the runoff to a sampling flume.

Before Situation:

The agricultural operation prior to installing the monitoring equipment is guessing about the effects of the conservation system with regards to meeting practice intent of avoid, controlling, or trapping sediment and nutrients.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$19,241.82

Scenario Cost/Unit: \$19,241.82

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	5	\$379.20
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	60	\$1,910.40
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will incl	Each	\$460.51	1	\$460.51
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all ma	Kilowatt	\$8,258.60	0.12	\$991.03
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance	Each	\$1,070.10	1	\$1,070.10
Automated sampler with bottles and tubing	2606	Equipment used to collect the water samples on a flow weighted interval of 1.27 mm of runoff (volumetric depth) during a storm event.	Each	\$2,372.99	1	\$2,372.99
Connectors, cables, platform materials	2607	Miscellaneous (connectors, cables, berm, platform materials); Includes materials only.	Each	\$2,165.14	1	\$2,165.14
Depth (stage) sensor	2608	Device used to relay information to the Data logger about incremental increases in runoff. ISCO 730 Module with 1/8-in x 25-ft vinyl bubble line. Includes equipment only. Used for A202 water quality monitoring	Each	\$3,016.58	1	\$3,016.58
Equipment shelter	2609	Building designed to house and reduce the risk of equipment damage from weather, animals, and vandalism.	Each	\$760.15	1	\$760.15
Pre-calibrated flow control structure-surface	2610	Pre-calibrated flow control structure-surface. Used for A202 water quality monitoring	Each	\$3,559.13	1	\$3,559.13
Device, communications	2616	Piece of equipment or hardware designed to transmit real time data or information collected prior to site visits. Includes equipment only.	Each	\$2,556.59	1	\$2,556.59

Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #39 - System Installation-Surface Cold Climate

Scenario Description:

This edge-of-field water quality monitoring system is applicable to a single control or treatment site that has a field defined with surface runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The component monitoring equipment are associated with a typical system for northern latitudes where winter time heating is required for sampling. It will allow for installation of automated sampling data collection system with protective housing to reduce potential for vandalism, battery backup for operation during periods when electricity is down or solar panels are not creating an electrical current, a calf hut or other structure with heat is required over the flume to allow sampling under northern latitude winter conditions, and a berm or other directional flow structure to guide the runoff to a sampling flume.

Before Situation:

The agricultural operation prior to installing the monitoring equipment is guessing about the effects of the conservation system with regards to meeting practice intent of avoid, controlling, or trapping sediment and nutrients. Nothing is known about the volume or mass of sediment and nutrients leaving the edge of field through the tile or other subsurface drainage system.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$20,644.49

Scenario Cost/Unit: \$20,644.49

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	5	\$379.20
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	60	\$1,910.40
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will incl	Each	\$460.51	1	\$460.51
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all ma	Kilowatt	\$8,258.60	0.12	\$991.03
Heater, high efficiency	1165	Natural gas, propane, or fuel oil unit heater or boiler and venting materials. Based on input kBTU/hour. Includes materials and shipping only.	1,000 BTU/Hour	\$12.24	1	\$12.24
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance	Each	\$1,070.10	1	\$1,070.10
Automated sampler with bottles and tubing	2606	Equipment used to collect the water samples on a flow weighted interval of 1.27 mm of runoff (volumetric depth) during a storm event.	Each	\$2,372.99	1	\$2,372.99
Connectors, cables, platform materials	2607	Miscellaneous (connectors, cables, berm, platform materials); Includes materials only.	Each	\$2,165.14	1	\$2,165.14
Depth (stage) sensor	2608	Device used to relay information to the Data logger about incremental increases in runoff. ISCO 730 Module with 1/8-in x 25-ft vinyl bubble line. Includes equipment only. Used for A202 water quality monitering	Each	\$3,016.58	1	\$3,016.58
Equipment shelter	2609	Building designed to house and reduce the risk of equipment damage from weather, animals, and vandalism.	Each	\$760.15	1	\$760.15
Pre-calibrated flow control structure-surface	2610	Pre-calibrated flow control structure-surface. Used for A202 water quality monitoring	Each	\$3,559.13	1	\$3,559.13
Device, communications	2616	Piece of equipment or hardware designed to transmit real time data or information collected prior to site visits. Includes equipment only.	Each	\$2,556.59	1	\$2,556.59

Equipment Shed	2617	Equipment Shed (10' x 10') made of steel applied over the sampling flume to allow collection of water samples during the winter in colder climates.	Each	\$1,390.43	1	\$1,390.43
----------------	------	---	------	------------	---	------------

Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #40 - System Installation-Tile

Scenario Description:

This edge-of-field water quality monitoring system is applicable to a single control or treatment site that has a field defined with tile or other subsurface drainage runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The component monitoring equipment are associated with a typical system for southern latitudes where winter time heating is not required for sampling. It will allow for installation of automated sampling data collection system for a subsurface collection and separate surface automated sample collection system with protective housing to reduce potential for vandalism, battery backup for operation during periods when electricity is down or solar panels are not creating an electrical current, an area velocity sensor for pipe flow and estimation of submerged flow, and a berm or other directional flow structure to guide the runoff to a sampling flume.

Before Situation:

The agricultural operation prior to installing the monitoring equipment is guessing about the effects of the conservation system with regards to meeting practice intent of avoid, controlling, or trapping sediment and nutrients. Nothing is known about the volume or mass of sediment and nutrients leaving the edge of field through the tile or other subsurface drainage system.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$29,767.50

Scenario Cost/Unit: \$29,767.50

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	6	\$455.04
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	100	\$3,184.00
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will incl	Each	\$460.51	1	\$460.51
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all ma	Kilowatt	\$8,258.60	0.12	\$991.03
Heater, high efficiency	1165	Natural gas, propane, or fuel oil unit heater or boiler and venting materials. Based on input kBTU/hour. Includes materials and shipping only.	1,000 BTU/Hour	\$12.24	1	\$12.24
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance	Each	\$1,070.10	1	\$1,070.10
Automated sampler with bottles and tubing	2606	Equipment used to collect the water samples on a flow weighted interval of 1.27 mm of runoff (volumetric depth) during a storm event.	Each	\$2,372.99	2	\$4,745.98
Connectors, cables, platform materials	2607	Miscellaneous (connectors, cables, berm, platform materials); Includes materials only.	Each	\$2,165.14	1	\$2,165.14
Depth (stage) sensor	2608	Device used to relay information to the Data logger about incremental increases in runoff. ISCO 730 Module with 1/8-in x 25-ft vinyl bubble line. Includes equipment only. Used for A202 water quality monitering	Each	\$3,016.58	2	\$6,033.16
Equipment shelter	2609	Building designed to house and reduce the risk of equipment damage from weather, animals, and vandalism.	Each	\$760.15	2	\$1,520.30
Pre-calibrated flow control structure-surface	2610	Pre-calibrated flow control structure-surface. Used for A202 water quality monitoring	Each	\$3,559.13	1	\$3,559.13
Pre-calibrated flow control structure-subsurface (pipe flow)	2615	Equipment used to collect runoff for ease in measure of flow, sample collection and to reduce time in constructing and calibrating of a flow structure.	Each	\$1,623.85	1	\$1,623.85

Device, communications	2616	Piece of equipment or hardware designed to transmit real time data or information collected prior to site visits. Includes equipment only.	Each	\$2,556.59	1	\$2,556.59
Equipment Shed	2617	Equipment Shed (10' x 10') made of steel applied over the sampling flume to allow collection of water samples during the winter in colder climates.	Each	\$1,390.43	1	\$1,390.43

Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #41 - System Installation-Tile Cold Climate

Scenario Description:

This edge-of-field water quality monitoring system is applicable to a single control or treatment site that has a field defined with tile or other subsurface drainage runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The component monitoring equipment are associated with a typical system for northern latitudes where winter time heating is required for sampling. It will allow for installation of automated sampling data collection system for a subsurface collection and separate surface automated sample collection system with protective housing to reduce potential for vandalism, battery backup for operation during periods when electricity is down or solar panels are not creating an electrical current, an area velocity sensor for pipe flow and estimation of submerged flow, a calf hut or other structure with heat is required over the flume to allow sampling under northern latitude winter conditions and a berm or other directional flow structure to guide the runoff to a sampling flume.

Before Situation:

The agricultural operation prior to installing the monitoring equipment is guessing about the effects of the conservation system with regards to meeting practice intent of avoid, controlling, or trapping sediment and nutrients. Nothing is known about the volume or mass of sediment and nutrients leaving the edge of field through the tile or other subsurface drainage system.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$29,767.50

Scenario Cost/Unit: \$29,767.50

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	6	\$455.04
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	100	\$3,184.00
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will incl	Each	\$460.51	1	\$460.51
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all ma	Kilowatt	\$8,258.60	0.12	\$991.03
Heater, high efficiency	1165	Natural gas, propane, or fuel oil unit heater or boiler and venting materials. Based on input kBTU/hour. Includes materials and shipping only.	1,000 BTU/Hour	\$12.24	1	\$12.24
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance	Each	\$1,070.10	1	\$1,070.10
Automated sampler with bottles and tubing	2606	Equipment used to collect the water samples on a flow weighted interval of 1.27 mm of runoff (volumetric depth) during a storm event.	Each	\$2,372.99	2	\$4,745.98
Connectors, cables, platform materials	2607	Miscellaneous (connectors, cables, berm, platform materials); Includes materials only.	Each	\$2,165.14	1	\$2,165.14
Depth (stage) sensor	2608	Device used to relay information to the Data logger about incremental increases in runoff. ISCO 730 Module with 1/8-in x 25-ft vinyl bubble line. Includes equipment only. Used for A202 water quality monitoring	Each	\$3,016.58	2	\$6,033.16
Equipment shelter	2609	Building designed to house and reduce the risk of equipment damage from weather, animals, and vandalism.	Each	\$760.15	2	\$1,520.30
Pre-calibrated flow control structure-surface	2610	Pre-calibrated flow control structure-surface. Used for A202 water quality monitoring	Each	\$3,559.13	1	\$3,559.13
Pre-calibrated flow control structure-subsurface (pipe flow)	2615	Equipment used to collect runoff for ease in measure of flow, sample collection and to reduce time in constructing and calibrating of a flow structure.	Each	\$1,623.85	1	\$1,623.85



Device, communications	2616	Piece of equipment or hardware designed to transmit real time data or information collected prior to site visits. Includes equipment only.	Each	\$2,556.59	1	\$2,556.59
Equipment Shed	2617	Equipment Shed (10' x 10') made of steel applied over the sampling flume to allow collection of water samples during the winter in colder climates.	Each	\$1,390.43	1	\$1,390.43

Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #42 - System Installation-Above&Below

Scenario Description:

This edge-of-field water quality monitoring system is applicable where a conservation practice has a pre- and post treatment area in the same field drainage with surface or subsurface drainage runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The component monitoring equipment are associated with a typical system for southern latitudes where winter time heating is not required for sampling. It will allow for installation of automated sampling data collection system with protective housing to reduce potential for vandalism, battery backup for operation during periods when electricity is down or solar panels are not creating an electrical current, and a berm or other directional flow structure to guide the runoff to a sampling flume. The actual installation will differ on the subsurface flow by allowing a smaller precalibrated flume with the addition of a velocity sensor meter as in the tile alternative.

Before Situation:

The agricultural operation prior to installing the monitoring equipment is guessing about the effects of the conservation system with regards to meeting practice intent of avoid, controlling, or trapping sediment and nutrients.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$29,026.51

Scenario Cost/Unit: \$29,026.51

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	6	\$455.04
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	60	\$1,910.40
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will incl	Each	\$460.51	1	\$460.51
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all ma	Kilowatt	\$8,258.60	0.12	\$991.03
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance	Each	\$1,070.10	1	\$1,070.10
Automated sampler with bottles and tubing	2606	Equipment used to collect the water samples on a flow weighted interval of 1.27 mm of runoff (volumetric depth) during a storm event.	Each	\$2,372.99	2	\$4,745.98
Connectors, cables, platform materials	2607	Miscellaneous (connectors, cables, berm, platform materials); Includes materials only.	Each	\$2,165.14	1	\$2,165.14
Depth (stage) sensor	2608	Device used to relay information to the Data logger about incremental increases in runoff. ISCO 730 Module with 1/8-in x 25-ft vinyl bubble line. Includes equipment only. Used for A202 water quality monitoring	Each	\$3,016.58	2	\$6,033.16
Equipment shelter	2609	Building designed to house and reduce the risk of equipment damage from weather, animals, and vandalism.	Each	\$760.15	2	\$1,520.30
Pre-calibrated flow control structure-surface	2610	Pre-calibrated flow control structure-surface. Used for A202 water quality monitoring	Each	\$3,559.13	2	\$7,118.26
Device, communications	2616	Piece of equipment or hardware designed to transmit real time data or information collected prior to site visits. Includes equipment only.	Each	\$2,556.59	1	\$2,556.59

Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #43 - System Installation-Above&Below cold climate

Scenario Description:

This edge-of-field water quality monitoring system is applicable where a conservation practice has a pre- and post treatment area in the same field drainage with surface or subsurface drainage runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The component monitoring equipment are associated with a typical system for northern latitudes where winter time heating is required for sampling. It will allow for installation of automated sampling data collection system with protective housing to reduce potential for vandalism, battery backup for operation during periods when electricity is down or solar panels are not creating an electrical current, a calf hut or other structure with heat is required over the flume to allow sampling under northern latitude winter conditions, and a berm or other directional flow structure to guide the runoff to a sampling flume. The actual installation will different on the subsurface flow by allowing a smaller pre-calibrated flume with the addition of a velocity sensor meter as in the tile alternative.

Before Situation:

The agricultural operation prior to installing the monitoring equipment is guessing about the effects of the conservation system with regards to meeting practice intent of avoid, controlling, or trapping sediment and nutrients. Nothing is known about the volume or mass of sediment and nutrients leaving the edge of field through the tile or other subsurface drainage system.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$34,388.44

Scenario Cost/Unit: \$34,388.44

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	6	\$455.04
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	60	\$1,910.40
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will incl	Each	\$460.51	1	\$460.51
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all ma	Kilowatt	\$8,258.60	0.12	\$991.03
Heater, high efficiency	1165	Natural gas, propane, or fuel oil unit heater or boiler and venting materials. Based on input kBTU/hour. Includes materials and shipping only.	1,000 BTU/Hour	\$12.24	2	\$24.48
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance	Each	\$1,070.10	1	\$1,070.10
Automated sampler with bottles and tubing	2606	Equipment used to collect the water samples on a flow weighted interval of 1.27 mm of runoff (volumetric depth) during a storm event.	Each	\$2,372.99	2	\$4,745.98
Connectors, cables, platform materials	2607	Miscellaneous (connectors, cables, berm, platform materials); Includes materials only.	Each	\$2,165.14	1	\$2,165.14
Depth (stage) sensor	2608	Device used to relay information to the Data logger about incremental increases in runoff. ISCO 730 Module with 1/8-in x 25-ft vinyl bubble line. Includes equipment only. Used for A202 water quality monitoring	Each	\$3,016.58	2	\$6,033.16
Equipment shelter	2609	Building designed to house and reduce the risk of equipment damage from weather, animals, and vandalism.	Each	\$760.15	2	\$1,520.30
Pre-calibrated flow control structure-surface	2610	Pre-calibrated flow control structure-surface. Used for A202 water quality monitoring	Each	\$3,559.13	2	\$7,118.26
Device, communications	2616	Piece of equipment or hardware designed to transmit real time data or information collected prior to site visits. Includes equipment only.	Each	\$2,556.59	2	\$5,113.18

Equipment Shed	2617	Equipment Shed (10' x 10') made of steel applied over the sampling flume to allow collection of water samples during the winter in colder climates.	Each	\$1,390.43	2	\$2,780.86
----------------	------	---	------	------------	---	------------

Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #44 - System Installation-Retrofit 1

Scenario Description:

This edge-of-field water quality monitoring system is to retrofit an existing system that is being used in associated with the 799 interim practice or comparable system. The retrofit is applicable to a single control or treatment site that has a field defined with surface or subsurface drainage runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The data represents the installation of an automated and manual backup rain gauge and back-up/solar power supply be added to existing system. It is actually to represent a cost for any system updates that has component costs of \$2,400 or less as per the component costs in various scenarios.

Before Situation:

The agricultural operation prior to retrofit has an edge-of-field data collection system but it does not meet the present standards for accuracy or reliability as detailed in either or both of Activity 201 and Activity 202.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$3,410.28

Scenario Cost/Unit: \$3,410.28

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	5	\$379.20
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	16	\$509.44
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will incl	Each	\$460.51	1	\$460.51
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all ma	Kilowatt	\$8,258.60	0.12	\$991.03
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance	Each	\$1,070.10	1	\$1,070.10

Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #45 - System Installation-Retrofit 2

Scenario Description:

This edge-of-field water quality monitoring system is to retrofit an existing system that is being used in associated with the 799 interim practice or comparable system. The retrofit is applicable to a single control or treatment site that has a field defined with surface or subsurface drainage runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The data represents the installation of an automated and manual backup rain gauge, back-up/solar power supply, communications device, and depth (stage) sensor to be added to existing system. It is actually to represent a cost for any system updates that has component costs greater than \$2,400 but less than or equal to \$7,300 as per the component costs in various scenarios.

Before Situation:

The agricultural operation prior to retrofit has an edge-of-field data collection system but it does not meet the present standards for accuracy or reliability as detailed in either or both of Activity 201 and Activity 202.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$9,110.81

Scenario Cost/Unit: \$9,110.81

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	5	\$379.20
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	20	\$636.80
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will incl	Each	\$460.51	1	\$460.51
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all ma	Kilowatt	\$8,258.60	0.12	\$991.03
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance	Each	\$1,070.10	1	\$1,070.10
Depth (stage) sensor	2608	Device used to relay information to the Data logger about incremental increases in runoff. ISCO 730 Module with 1/8-in x 25-ft vinyl bubble line. Includes equipment only. Used for A202 water quality monitoring	Each	\$3,016.58	1	\$3,016.58
Device, communications	2616	Piece of equipment or hardware designed to transmit real time data or information collected prior to site visits. Includes equipment only.	Each	\$2,556.59	1	\$2,556.59

Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #46 - System Installation-Retrofit 3

Scenario Description:

This edge-of-field water quality monitoring system is to retrofit an existing system that is being used in associated with the 799 interim practice or comparable system. The retrofit is applicable to a single control or treatment site that has a field defined with surface or subsurface drainage runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The data represents the installation of an automated and manual backup rain gauge, back-up/solar power supply, communications device, pre-calibrated flow control structure, and depth (stage) sensor to be added to existing system. It is actually to represent a cost for any system updates that has component costs greater than \$7,300 but less than or equal to \$10,500 as per the component costs in various scenarios. Anything above \$10,500 will evaluated as a full system replacement as per scenarios for surface or tile (subsurface) drainage.

Before Situation:

The agricultural operation prior to retrofit has an edge-of-field data collection system but it does not meet the present standards for accuracy or reliability as detailed in either or both of Activity 201 and Activity 202.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$13,052.02

Scenario Cost/Unit: \$13,052.02

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	5	\$379.20
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	32	\$1,018.88
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will incl	Each	\$460.51	1	\$460.51
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all ma	Kilowatt	\$8,258.60	0.12	\$991.03
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance	Each	\$1,070.10	1	\$1,070.10
Depth (stage) sensor	2608	Device used to relay information to the Data logger about incremental increases in runoff. ISCO 730 Module with 1/8-in x 25-ft vinyl bubble line. Includes equipment only. Used for A202 water quality monitoring	Each	\$3,016.58	1	\$3,016.58
Pre-calibrated flow control structure-surface	2610	Pre-calibrated flow control structure-surface. Used for A202 water quality monitoring	Each	\$3,559.13	1	\$3,559.13
Device, communications	2616	Piece of equipment or hardware designed to transmit real time data or information collected prior to site visits. Includes equipment only.	Each	\$2,556.59	1	\$2,556.59

Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #47 - System Installation-Retrofit Above and Below 1

Scenario Description:

This edge-of-field water quality monitoring system is to retrofit an existing above and below monitoring designed system that is being used in associated with the 799 interim practice or comparable system. The retrofit is applicable to an above and below system that has a field defined with surface or subsurface drainage runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The data represents the installation of an automated and manual backup rain gauge and two back-up/solar power supply be added to existing paired system. It is actually to represent a cost for any system updates that has component costs of \$3,300 or less as per the component costs in various scenarios.

Before Situation:

The agricultural operation prior to retrofit has an edge-of-field data collection system but it does not meet the present standards for accuracy or reliability as detailed in either or both of Activity 201 and Activity 202.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$4,910.75

Scenario Cost/Unit: \$4,910.75

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	5	\$379.20
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	32	\$1,018.88
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will incl	Each	\$460.51	1	\$460.51
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all ma	Kilowatt	\$8,258.60	0.24	\$1,982.06
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance	Each	\$1,070.10	1	\$1,070.10



Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #48 - System Installation-Retrofit Above 2

Scenario Description:

This edge-of-field water quality monitoring system is to retrofit an existing above and below monitoring designed system that is being used in associated with the 799 interim practice or comparable system. The retrofit is applicable to an above and below system that has a field defined with surface or subsurface drainage runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The data represents the installation of an automated and manual backup rain gauge, two back-up/solar power supplies, two communications devices, and two depth (stage) sensors to be added to existing paired system. It is actually to represent a cost for any system updates that has component costs greater than \$3,300 but less than or equal to \$13,200 as per the component costs in various scenarios.

Before Situation:

The agricultural operation prior to retrofit has an edge-of-field data collection system but it does not meet the present standards for accuracy or reliability as detailed in either or both of Activity 201 and Activity 202.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$16,132.93

Scenario Cost/Unit: \$16,132.93

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	6	\$455.04
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	32	\$1,018.88
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will incl	Each	\$460.51	1	\$460.51
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all ma	Kilowatt	\$8,258.60	0.24	\$1,982.06
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance	Each	\$1,070.10	1	\$1,070.10
Depth (stage) sensor	2608	Device used to relay information to the Data logger about incremental increases in runoff. ISCO 730 Module with 1/8-in x 25-ft vinyl bubble line. Includes equipment only. Used for A202 water quality monitoring	Each	\$3,016.58	2	\$6,033.16
Device, communications	2616	Piece of equipment or hardware designed to transmit real time data or information collected prior to site visits. Includes equipment only.	Each	\$2,556.59	2	\$5,113.18

Practice: 202 - Edge-of-Field Water Quality Monitoring-System Installation

Scenario #49 - System Installation-Retrofit Above 3

Scenario Description:

This edge-of-field water quality monitoring system is to retrofit an existing above and below monitoring designed system that is being used in associated with the 799 interim practice or comparable system. The retrofit is applicable to an above and below system that has a field defined with surface or subsurface drainage runoff that can be captured and sampled at the edge of a field before entering a ditch or receiving water body or water course. The data represents the installation of an automated and manual backup rain gauge, two back-up/solar power supplies, two communications devices, two pre-calibrated flumes, and two depth (stage) sensors to be added to existing paired system. It is actually to represent a cost for any system updates that has component costs greater than \$13,500 but less than or equal to \$20,500 as per the component costs in various scenarios. Anything above a \$20,500 will evaluated as a full system replacement as per scenarios for surface or tile (subsurface) drainage.

Before Situation:

The agricultural operation prior to retrofit has an edge-of-field data collection system but it does not meet the present standards for accuracy or reliability as detailed in either or both of Activity 201 and Activity 202.

After Situation:

The agricultural operation after installing the monitoring equipment will be receiving feedback in the form of edge-of-field runoff water quality samples. The samples will allow the operator to understand the relationship between rain/irrigation, practice choice, and nutrient inputs effecting nutrient and sediment loss for the field. Thus, providing an opportunity to make adaptive management changes to the agricultural operation to reduce sediment and nutrient loss and/or profitability.

Feature Measure: System installed

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$23,505.91

Scenario Cost/Unit: \$23,505.91

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, agronomist	1295	Conservation Activity Plan labor to conduct research in breeding, physiology, production, yield, and management of crops and agricultural plants or trees, shrubs, and nursery stock, their growth in soils, and control of pests; or study the chemical, physi	Hour	\$75.84	6	\$455.04
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	40	\$1,273.60
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will incl	Each	\$460.51	1	\$460.51
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all ma	Kilowatt	\$8,258.60	0.24	\$1,982.06
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance	Each	\$1,070.10	1	\$1,070.10
Depth (stage) sensor	2608	Device used to relay information to the Data logger about incremental increases in runoff. ISCO 730 Module with 1/8-in x 25-ft vinyl bubble line. Includes equipment only. Used for A202 water quality monitoring	Each	\$3,016.58	2	\$6,033.16
Pre-calibrated flow control structure-surface	2610	Pre-calibrated flow control structure-surface. Used for A202 water quality monitoring	Each	\$3,559.13	2	\$7,118.26
Device, communications	2616	Piece of equipment or hardware designed to transmit real time data or information collected prior to site visits. Includes equipment only.	Each	\$2,556.59	2	\$5,113.18

Practice: 311 - Alley Cropping

Scenario #1 - Single row container planting stock

Scenario Description:

The crop or grass land is planted with rows of container stock trees to increase crop diversity. Final row width, and spacing of trees within the row is based on farm equipment size, growth form of trees, light needs of annual crop or grass, and intent of the landowner. Payment includes the trees, tree planting costs and foregone income for the area of land being removed from crop production and put into trees. The resource concerns are plant condition - inadequate structure and composition. Site preparation is not included and must be implemented through associated practice 490 Tree/Shrub Site Preparation.

Before Situation:

The landscape has been cropped or in perennial grass for many years. It is void of any perennial tree vegetation. On cropland site preparation needs may need deep ripping to eliminate any plow pan and on grass land competing vegetation control is accomplished prior to tree planting.

After Situation:

Trees have been established to diversify the crop production of the field. Typically the area planted is 10 acres on approximately 12 x 40 foot spacing. Associated practices may include: 490 Tree/Shrub Site Preparation, 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, and 484 Mulching

Feature Measure: planted seedling

Scenario Unit:: Each

Scenario Typical Size: 900.0

Scenario Total Cost: \$23,572.07

Scenario Cost/Unit: \$26.19

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	\$7.46	80	\$596.80
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	4	\$88.88
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	\$58.85	90	\$5,296.50
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	1.25	\$519.01
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	1.25	\$518.75
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	180	\$3,956.40
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	80	\$1,767.20
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	20	\$775.60
Materials						
Tree, hardwood, seedling or transplant, potted or B&B, 2-3 gal.	1532	Potted or balled and burlapped hardwood tree, 2-3 gal. Includes materials and shipping only.	Each	\$7.15	900	\$6,435.00
Tree shelter, solid tube type, 5" x 48"	1571	5" x 48" tree tube for protection from animal damage. Materials only.	Each	\$2.11	900	\$1,899.00
Cable ties, plastic	1575	Plastic cable ties (typ. 8-12") to assist in securing items. Materials only.	Each	\$0.05	900	\$45.00
Stakes, wood, 3/4" x 3/4" x 60"	1583	3/4" x 3/4" x 60" wood stakes to fasten items in place. Includes materials only.	Each	\$1.57	900	\$1,413.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 311 - Alley Cropping

Scenario #2 - Single row bareroot planting stock

Scenario Description:

The crop or grass land is planted with rows of bareroot trees to increase crop diversity. Final row width, and spacing of trees within the row is based on farm equipment size, growth form of trees, light needs of annual crop or grass, and intent of the landowner. Payment includes the trees, tree planting costs and foregone income for the area of land being removed from crop production and put into trees. The resource concerns are plant condition - inadequate structure and composition. Site preparation is not included and must be implemented through associated practice 490 Tree/Shrub Site Preparation.

Before Situation:

The landscape has been cropped or in perennial grass for many years. It is void of any perennial tree vegetation. On cropland site preparation needs may need deep ripping to eliminate any plow pan and on grass land competing vegetation control is accomplished prior to tree planting.

After Situation:

Trees have been established to diversify the crop production of the field. Typically the area planted is 10 acres on approximately 12 x 40 foot spacing. Associated practices may include: 490 Tree/Shrub Site Preparation, 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, and 484 Mulching

Feature Measure: planted seedling

Scenario Unit:: Each

Scenario Typical Size: 900.0

Scenario Total Cost: \$1,803.17

Scenario Cost/Unit: \$2.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	1.25	\$27.78
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	1.25	\$31.59
Mechanical tree planter	1600	Mechanical tree planter. Requires a pulling unit of either tractor or small dozer depending upon site conditions. Does not include labor.	Hour	\$6.84	1.25	\$8.55
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	1.25	\$519.01
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	1.25	\$518.75
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	1.25	\$27.48
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	1.25	\$27.61
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1.25	\$48.48
Materials						
Tree, hardwood, seedling or transplant, bare root, 6-18"	1509	Bare root hardwood trees 6-18" tall. Includes materials and shipping only.	Each	\$0.37	900	\$333.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 311 - Alley Cropping

Scenario #3 - Single row bareroot planting stock with tree shelters

Scenario Description:

The crop or grass land is planted with rows of bareroot trees to increase crop diversity. Final row width, and spacing of trees within the row is based on farm equipment size, growth form of trees, light needs of annual crop or grass, and intent of the landowner. Payment includes the trees, tree planting costs. tree shelters, and foregone income for the area of land being removed from crop production and put into trees. The resource concerns are plant condition - inadequate structure and composition. Site preparation is not included and must be implemented through associated practice 490 Tree/Shrub Site Preparation.

Before Situation:

The landscape has been cropped or in perennial grass for many years. It is void of any perennial tree vegetation. On cropland site preparation needs may need deep ripping to eliminate any plow pan and on grass land competing vegetation control is accomplished prior to tree planting.

After Situation:

Trees have been established to diversify the crop production of the field. Typically the area planted is 10 acres on approximately 12 x 40 foot spacing. Associated practices may include: 490 Tree/Shrub Site Preparation, 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Feature Measure: planted seedling

Scenario Unit:: Each

Scenario Typical Size: 900.0

Scenario Total Cost: \$5,489.87

Scenario Cost/Unit: \$6.10

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	1.25	\$27.78
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	1.25	\$31.59
Mechanical tree planter	1600	Mechanical tree planter. Requires a pulling unit of either tractor or small dozer depending upon site conditions. Does not include labor.	Hour	\$6.84	1.25	\$8.55
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	1.25	\$519.01
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	1.25	\$518.75
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16.25	\$357.18
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	1.25	\$27.61
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1.25	\$48.48
Materials						
Tree, hardwood, seedling or transplant, bare root, 6-18"	1509	Bare root hardwood trees 6-18" tall. Includes materials and shipping only.	Each	\$0.37	900	\$333.00
Tree shelter, solid tube type, 5" x 48"	1571	5" x 48" tree tube for protection from animal damage. Materials only.	Each	\$2.11	900	\$1,899.00
Cable ties, plastic	1575	Plastic cable ties (typ. 8-12") to assist in securing items. Materials only.	Each	\$0.05	900	\$45.00
Stakes, wood, 3/4" x 3/4" x 60"	1583	3/4" x 3/4" x 60" wood stakes to fasten items in place. Includes materials only.	Each	\$1.57	900	\$1,413.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 313 - Waste Storage Facility

Scenario #1 - Earthen Storage Facility

Scenario Description:

An earthen waste impoundment constructed with cuts and fills balanced such that one half of the impoundment depth is excavated and the remainder of the storage is created with the embankment. The structure is constructed to store wastes such as manure, wastewater, and contaminated runoff as part of an agricultural waste management system. This practice will address soil and water quality by reducing the pollution potential for surface water and groundwater quality degradation. Payment includes materials and equipment necessary for construction of the storage structure. If a roof is to be included in the installation, refer to Practice Standard 367 - Roofs and Covers. If an earthen storage liner is to be included in the installation, refer to associated Practice Standards 521A, 521B, 521C, or 521D. Vehicular and equipment access is addressed in Heavy Use Area Protection (561). Adequately protect liner at agitation and access points.

Before Situation:

Operator presently has a confined animal feeding operation without a waste management system adequate to handle the waste stream leaving the animal production facilities. Manure and other agricultural waste by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or are being transported but not properly utilized or disposed of. This situation poses an environmentally threat of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources.

After Situation:

An earthen storage structure constructed from on-site material provides an environmentally safe facility for storing manure and other agricultural waste by-products. This facility provides the landowner a means of storing waste until it can be utilized in a proper manner in accordance with a nutrient management plan. Typical design size: total storage volume 147,000 ft3; 150'X150' (top); 3:1 inside and outside side slopes; embankment topwidth = 10'; compaction ratio = 1.1; total depth = 10'; embankment volume = 10,430 cu yd Potential Associated Practices: Pond Sealing or Lining, Bentonite Sealant (521C), Pond Sealing or Lining, Compacted Clay Treatment (521D), Pond Sealing or Lining, Flexible Membrane (521A), Pond Sealing or Lining, Soil Dispersant (521B), Fence (382), Critical Area Planting (342), Nutrient Management (590), Waste Transfer (634), Heavy Use Area Protection (561), Roofs and Covers (367), and Solid/Liquid Waste Separation Facility (632), Waste Treatment (629) .

Feature Measure: Total Storage Volume

Scenario Unit:: Cubic Foot

Scenario Typical Size: 147,000.0

Scenario Total Cost: \$30,178.84

Scenario Cost/Unit: \$0.21

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	4110	\$16,686.60
Stripping and stockpiling, topsoil	1199	Stripping and stockpiling of topsoil adjacent to stripping area. Includes equipment and labor.	Cubic Yard	\$0.91	980	\$891.80
Excavation, common earth, large equipment, 150 ft	1223	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 150 feet. Includes equipment and labor.	Cubic Yard	\$3.85	3130	\$12,050.50
Materials						
Structural steel tubing, 2" diameter	1120	Structural steel tubing, 2" diameter, 1/8" wall thickness, materials only	Foot	\$3.51	8	\$28.08
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: 313 - Waste Storage Facility

Scenario #3 - Glass Lined Steel Tank, <25,000 Cu Ft Storage

Scenario Description:

An above ground circular glass lined steel structure constructed to store wastes such as manure, wastewater, and contaminated runoff as part of an agricultural waste management system. This scenario has a total storage volume of less than 25,000 Cu Ft. Payment includes materials and equipment necessary for construction of the storage structure and support. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Vehicular and equipment access is addressed in Heavy Use Area Protection (561). This practice will address soil and water quality by reducing the pollution potential for surface water and groundwater quality degradation.

Before Situation:

Operator presently has a confined animal feeding operation without a waste management system adequate to handle the waste stream leaving the animal production facilities. Manure and other agricultural waste by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or are being transported but not properly utilized or disposed of. This situation poses an environmental threat of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources.

After Situation:

An above ground storage structure provides an environmentally safe facility for storing manure and other agricultural waste by-products. This facility provides the landowner a means of storing waste until it can be utilized in a proper manner in accordance with a nutrient management plan. Typical design size : total storage volume 14,340 ft3; based on 31' X 19' glass lined steel tank Potential Associated Practices: Fence (382), Critical Area Planting (342), Nutrient Management (590), Waste Transfer (634), Roof and Covers (367), Heavy Use Area Protection (561), Solid/Liquid Waste Separation Facility (632), Waste Treatment (629), and Pumping Plant (533).

Feature Measure: Total Storage Volume

Scenario Unit:: Cubic Foot

Scenario Typical Size: 14,340.0

Scenario Total Cost: \$81,707.31

Scenario Cost/Unit: \$5.70

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	12	\$3,295.44
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	16	\$6,833.76
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	80	\$324.80
Excavation, common earth, large equipment, 150 ft	1223	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 150 feet. Includes equipment and labor.	Cubic Yard	\$3.85	80	\$308.00
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	20	\$511.40
Waste Storage, Glass lined steel structure (<25,000 ft3)	1616	Includes materials, equipment and labor to install 31' (diameter) X19' (height) steel lined structure. Includes materials, equipment and labor.	Cubic Foot	\$5.82	12000	\$69,840.00
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

**Practice:** 313 - Waste Storage Facility

**Scenario #4** - Glass Lined Steel Tank, 25,000 - 99,999 Cu Ft Storage

#### Scenario Description:

An above ground circular glass lined steel structure constructed to store wastes such as manure, wastewater, and contaminated runoff as part of an agricultural waste management system. This scenario has a total storage volume 25,000 Cu Ft to 99,999 Cu Ft. Payment includes materials and equipment necessary for construction of the storage structure and support. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Vehicular and equipment access is addressed in Heavy Use Area Protection (561). This practice will address soil and water quality by reducing the pollution potential for surface water and groundwater quality degradation.

#### Before Situation:

Operator presently has a confined animal feeding operation without a waste management system adequate to handle the waste stream leaving the animal production facilities. Manure and other agricultural waste by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or are being transported but not properly utilized or disposed of. This situation poses an environmental threat of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources.

#### After Situation:

An above ground storage structure provides an environmentally safe facility for storing manure and other agricultural waste by-products. This facility provides the landowner a means of storing waste until it can be utilized in a proper manner in accordance with a nutrient management plan. Typical design size : total storage volume 79,520 ft<sup>3</sup>; based on 73' X 19' glass lined steel tank Potential Associated Practices: Fence (382), Critical Area Planting (342), Nutrient Management (590), Waste Transfer (634), Roof and Covers (367), Heavy Use Area Protection (561), Solid/Liquid Waste Separation Facility (632), Waste Treatment (629), and Pumping Plant (533).

**Feature Measure:** Total Storage Volume

**Scenario Unit::** Cubic Foot

**Scenario Typical Size:** 79,520.0

**Scenario Total Cost:** \$175,138.50

**Scenario Cost/Unit:** \$2.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	65	\$17,850.30
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	38	\$16,230.18
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	250	\$1,015.00
Excavation, common earth, large equipment, 150 ft	1223	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 150 feet. Includes equipment and labor.	Cubic Yard	\$3.85	250	\$962.50
<b>Materials</b>						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	73	\$1,866.61
Waste Storage, glass lined steel structure, 25,000 - 100,000 cubic foot	1620	Includes materials, equipment and labor to install a steel glass lined structure (based on typical 73' diameter X 19' height) . Includes materials, equipment and labor.	Cubic Foot	\$2.07	66000	\$136,620.00
<b>Mobilization</b>						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86



Practice: 313 - Waste Storage Facility

Scenario #5 - Glass Lined Steel Tank, >=100,000 Cu Ft Storage

Scenario Description:

An above ground circular glass lined steel structure constructed to store wastes such as manure, wastewater, and contaminated runoff as part of an agricultural waste management system. This scenario has a total storage volume >=100,000 Cu Ft. Payment includes materials and equipment necessary for construction of the storage structure and support. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Vehicular and equipment access is addressed in Heavy Use Area Protection (561). This practice will address soil and water quality by reducing the pollution potential for surface water and groundwater quality degradation.

Before Situation:

Operator presently has a confined animal feeding operation without a waste management system adequate to handle the waste stream leaving the animal production facilities. Manure and other agricultural waste by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or are being transported but not properly utilized or disposed of. This situation poses an environmental threat of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources.

After Situation:

An above ground storage structure provides an environmentally safe facility for storing manure and other agricultural waste by-products. This facility provides the landowner a means of storing waste until it can be utilized in a proper manner in accordance with a nutrient management plan. Typical design size : Total storage volume 187,190 ft3; based on 112' X 19' glass lined steel tank. Volume includes the total volume of the structure which includes operating volume, emergency volume and freeboard volume. Potential Associated Practices: Fence (382), Critical Area Planting (342), Nutrient Management (590), Waste Transfer (634), Roof and Covers (367), Heavy Use Area Protection (561), Solid/Liquid Waste Separation Facility (632), Waste Treatment (629), and Pumping Plant (533).

Feature Measure: Total Storage Volume

Scenario Unit:: Cubic Foot

Scenario Typical Size: 187,190.0

Scenario Total Cost: \$327,316.93

Scenario Cost/Unit: \$1.75

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	152	\$41,742.24
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	52	\$22,209.72
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	456	\$1,851.36
Excavation, common earth, large equipment, 150 ft	1223	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 150 feet. Includes equipment and labor.	Cubic Yard	\$3.85	456	\$1,755.60
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	130	\$3,324.10
Waste Storage, glass lined steel structure, 100,000-200,000 cubic foot	1621	Includes materials, equipment and labor to install a steel glass lined structure (based on typical 112' diameter X 19' height) . Includes materials, equipment and labor.	Cubic Foot	\$1.64	156000	\$255,840.00
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: 313 - Waste Storage Facility

Scenario #6 - Dry Stack Facility, Earthen Floor with Concrete Side Walls

Scenario Description:

This scenario consists of a dry stack facility with compacted earthen floor with concrete side walls. This scenario is intended for poultry litter or similar dry product. Payment includes materials and equipment necessary for construction of the floor and walls. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Vehicular and equipment access is addressed in Heavy Use Area Protection (561). The purpose of this practice is to properly store manure and other agricultural by-products until they can be hauled away from the site for proper disposal or utilization on land at agronomical rates. This practice will address soil and water quality by reducing the pollution potential to soil, surface water and ground water.

Before Situation:

Manure and other agricultural by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or other location, or are being transported but not properly utilized or disposed of. This situation poses an environmentally threat of excessive nutrients, organics, and pathogens being transported into surface and ground waters, in addition to the use of excessive amounts of fertilizers.

After Situation:

The typical is 40' x 56' slab with walls. The earthen floor will be prepared by stripping the top 1' of soil and roller compacting it back into floor. Walls are 5' reinforced concrete. Walls consist of three perimeter walls (40' + 56' + 40') for a total wall length of 136 linear feet. Walls allow for greater storage volume. Manure and other agricultural by-products are being controlled, by the collection at the source, and stored temporarily, at an environmentally suitable location, until such time that they are disposed of or utilized in a proper manner, typically in accordance with a nutrient management plan. Potential Associated practices: 342-Critical Area Planting, 362-Diversion, 561-Heavy Use Area Protection, 367-Roofs and Covers, 558-Roof Runoff Structure, 317-Composting Facility, 633-Waste Recycling, 634-Waste Transfer, 635-Vegetated Treatment Area

Feature Measure: Cubic Foot Storage

Scenario Unit:: Cubic Foot

Scenario Typical Size: 11,200.0

Scenario Total Cost: \$13,940.66

Scenario Cost/Unit: \$1.24

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	30	\$12,813.30
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	83	\$178.45
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	83	\$336.98
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 313 - Waste Storage Facility

Scenario #7 - Dry Stack Facility, Concrete Floor without Side Walls

Scenario Description:

This scenario consists of a dry stack facility with reinforced concrete floor without side walls. This scenario is intended for situations where consistency of manure or geographical conditions prohibit earthen floors. Payment includes materials and equipment necessary for construction of the floor. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Vehicular and equipment access is addressed in Heavy Use Area Protection (561). The purpose of this practice is to properly store manure and other agricultural by-products that are stackable until they can be hauled away from the site for proper disposal or utilization on land at agronomical rates. This practice will address soil and water quality by reducing the pollution potential to soil, surface water and ground water.

Before Situation:

Manure and other agricultural by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or other location, or are being transported but not properly utilized or disposed of. This situation poses an environmentally threat of excessive nutrients, organics, and pathogens being transported into surface and ground waters, in addition to the use of excessive amounts of fertilizers.

After Situation:

The typical is 75'x226'. The facility floor is 5" reinforced concrete without side walls. Manure and other agricultural by-products are being controlled, by the collection at the source, and stored temporarily, at an environmentally suitable location, until such time that they are disposed of or utilized in a proper manner, typically in accordance with a nutrient management plan. Potential Associated practices: 342-Critical Area Planting, 362-Diversion, 561-Heavy Use Area Protection, 367-Roofs and Covers, 558-Roof Runoff Structure, 317-Composting Facility, 633-Waste Recycling, 634-Waste Transfer, 635-Vegetated Treatment Area

Feature Measure: Square Foot Floor Area

Scenario Unit:: Square Foot

Scenario Typical Size: 16,950.0

Scenario Total Cost: \$79,823.88

Scenario Cost/Unit: \$4.71

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	260	\$71,401.20
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	630	\$1,354.50
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	315	\$1,278.90
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	206	\$5,267.42
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: 313 - Waste Storage Facility

Scenario #9 - Dry Stack Facility, Concrete Floor with Concrete Side Walls

Scenario Description:

This scenario consists of a dry stack facility with reinforced concrete floor and concrete side walls. This scenario is intended for situations where consistency of manure or geographical conditions prohibit earthen floors. Payment includes materials and equipment necessary for construction of the floor and walls. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Vehicular and equipment access is addressed in Heavy Use Area Protection (561). The purpose of this practice is to properly store manure and other agricultural by-products that are stackable until they can be hauled away from the site for proper disposal or utilization on land at agronomical rates. This practice will address soil and water quality by reducing the pollution potential to soil, surface water and ground water.

Before Situation:

Manure and other agricultural by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or other location, or are being transported but not properly utilized or disposed of. This situation poses an environmentally threat of excessive nutrients, organics, and pathogens being transported into surface and ground waters, in addition to the use of excessive amounts of fertilizers.

After Situation:

The typical is 40' x 56' concrete slab with 5' high walls. The facility floor is 5" reinforced concrete with 5' reinforced concrete walls. Walls allow for greater storage volume. Walls consist of three perimeter walls (40' + 56' + 40') for a total wall length of 136 linear feet. Manure and other agricultural by-products are being controlled, by the collection at the source, and stored temporarily, at an environmentally suitable location, until such time that they are disposed of or utilized in a proper manner, typically in accordance with a nutrient management plan. Note on use of concrete walls versus wood walls: different states utilize different options depending on many specific conditions which may change what is considered least cost. Each state will decide individually based on the suite of scenarios developed which meets their program policy and resource goals and needs Potential Associated practices: 342-Critical Area Planting, 362-Diversion, 561-Heavy Use Area Protection, 367-Roofs and Covers, 558-Roof Runoff Structure, 317-Composting Facility, 633-Waste Recycling, 634-Waste Transfer, 635-Vegetated Treatment Area

Feature Measure: Cubic Foot Storage

Scenario Unit:: Cubic Foot

Scenario Typical Size: 11,200.0

Scenario Total Cost: \$24,178.25

Scenario Cost/Unit: \$2.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	35	\$9,611.70
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	30	\$12,813.30
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	83	\$178.45
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	83	\$336.98
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	28	\$715.96
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: 313 - Waste Storage Facility

Scenario #10 - ConcreteLid Tank, <1,000 Cu Ft Storage

Scenario Description:

This scenario consists of installing a small concrete tank with a solid lid and a total storage volume of less than 1,000 Cu Ft. Design volume does not include freeboard. This practice will address soil and water quality by reducing the pollution potential to soil, surface water and ground water. Payment includes all materials, equipment and labor to install a concrete lid tank and gravel for drainfill around the tank.

Before Situation:

Manure and other agricultural by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or other location, or are being transported but not properly utilized or disposed of. This situation poses an environmentally threat of excessive nutrients, organics, and pathogens being transported into surface and ground waters, in addition to the use of excessive amounts of fertilizers.

After Situation:

Manure and other agricultural by-products are being controlled, by the collection at the source, and stored temporarily, at an environmentally suitable location, until such time that they are disposed of or utilized in a proper manner, typically in accordance with a nutrient management plan. Tank typically 5' deep x 8' wide x 9' long, with a total storage volume of 360 cubic feet. Sizing based on manure, other wastes, rainfall, lot runoff, etc. Tanks associated with open lots sized to handle design storm in tank or in combination with lot as per state regulations. Potential Associated Practices: Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Waste Transfer (634), Heavy Use Area Protection (561), Roof and Covers (367), Solid/Liquid Waste Separation Facility (632), Diversion (362), Subsurface Drain (606), Pumping Plant (533),and Underground Outlet (620).

Feature Measure: Total Storage Volume

Scenario Unit:: Cubic Foot

Scenario Typical Size: 360.0

Scenario Total Cost: \$5,152.70

Scenario Cost/Unit: \$14.31

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	6	\$2,562.66
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	60	\$321.60
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	10	\$1,160.10
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	10	\$283.00
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	4	\$102.28
Waterstop, PVC, ribbed, 3/16" x 6"	1614	Waterstop, PVC, ribbed, 3/16" thick by 6"wide. Includes materials, equipment and labor.	Foot	\$5.03	40	\$201.20
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: 313 - Waste Storage Facility

Scenario #11 - Concrete Lid Tank, >=1,000 Cu Ft Storage

Scenario Description:

This scenario consists of installing a small concrete tank with a solid lid and a total storage volume of greater than or equal to 1,000 Cu Ft. Design volume does not include freeboard. This practice will address soil and water quality by reducing the pollution potential to soil, surface water and ground water. Payment includes all materials, equipment and labor to install a concrete lid tank and gravel for drain fill around the tank.

Before Situation:

Manure and other agricultural by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or other location, or are being transported but not properly utilized or disposed of. This situation poses an environmentally threat of excessive nutrients, organics, and pathogens being transported into surface and groundwater, in addition to the use of excessive amounts of fertilizers.

After Situation:

Manure and other agricultural by-products are being controlled, by the collection at the source, and stored temporarily, at an environmentally suitable location, until such time that they are disposed of or utilized in a proper manner, typically in accordance with a nutrient management plan. Tank typically 8' deep x 12' wide x 40' long, with a total storage volume of 3,840 cubic feet. Sizing based on manure, other wastes, rainfall, lot runoff, etc. Tanks associated with open lots sized to handle design storm in tank or in combination with lot as per state regulations. Potential Associated Practices: Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Waste Transfer (634), Heavy Use Area Protection (561), Roof and Covers (367), Solid/Liquid Waste Separation Facility (632), Diversion (362), Subsurface Drain (606), Pumping Plant (533),and Underground Outlet (620).

Feature Measure: Total Storage Volume

Scenario Unit:: Cubic Foot

Scenario Typical Size: 3,840.0

Scenario Total Cost: \$22,600.69

Scenario Cost/Unit: \$5.89

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	10	\$2,746.20
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	35	\$14,948.85
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	100	\$536.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	20	\$2,320.20
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	20	\$566.00
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	14	\$357.98
Waterstop, PVC, ribbed, 3/16" x 6"	1614	Waterstop, PVC, ribbed, 3/16" thick by 6"wide. Includes materials, equipment and labor.	Foot	\$5.03	120	\$603.60
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: 313 - Waste Storage Facility

Scenario #12 - Concrete Tank Open Top, &lt;5,000 Cu Ft Storage

**Scenario Description:**

This scenario consists of installing an open top concrete tank with or without a full width ramp that has a total storage volume less than 5,000 Cu Ft. Payment includes materials and equipment necessary for construction of the concrete tank. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Vehicular and equipment access is addressed in Heavy Use Area Protection (561). Tank can also be installed under an animal facility using slats. Design volume does not include freeboard. This practice will address soil and water quality by reducing the pollution potential to soil, surface water and ground water. Payment includes all materials, equipment and labor to install a concrete tank and gravel for drainfill around the tank.

**Before Situation:**

Manure and other agricultural by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or other location, or are being transported but not properly utilized or disposed of. This situation poses an environmentally threat of excessive nutrients, organics, and pathogens being transported into surface and ground waters, in addition to the use of excessive amounts of fertilizers.

**After Situation:**

Manure and other agricultural by-products are being controlled, by the collection at the source, and stored temporarily, at an environmentally suitable location, until such time that they are disposed of or utilized in a proper manner, typically in accordance with a nutrient management plan. Tank typically 5' deep, with a bottom area of 880 sq ft, and a total storage volume of 4,400 cu ft. Sizing based on volume of manure, other wastes, rainfall, lot runoff, etc. as appropriate. Potential Associated Practices: Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Waste Transfer (634), Heavy Use Area Protection (561), Roof and Covers (367), Solid/Liquid Waste Separation Facility (632), Diversion (362), Subsurface Drain (606), and Underground Outlet (620).

Feature Measure: Total Storage Volume

Scenario Unit:: Cubic Foot

Scenario Typical Size: 4,400.0

Scenario Total Cost: \$21,766.27

Scenario Cost/Unit: \$4.95

## Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	25.7	\$7,057.73
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	15.2	\$6,492.07
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	200	\$1,072.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	30	\$3,480.30
<b>Labor</b>						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	30	\$849.00
<b>Materials</b>						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	53	\$1,355.21
Waterstop, PVC, ribbed, 3/16" x 6"	1614	Waterstop, PVC, ribbed, 3/16" thick by 6"wide. Includes materials, equipment and labor.	Foot	\$5.03	186.5	\$938.10
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: 313 - Waste Storage Facility

Scenario #13 - Concrete Tank Open Top, 7,500 - 14,999 Cu Ft Storage

Scenario Description:

This scenario consists of installing an open top concrete tank that has a total storage volume from 7,500 to 14,999 Cu Ft. Payment includes materials and equipment necessary for construction of the concrete tank. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Vehicular and equipment access is addressed in Heavy Use Area Protection (561). Tank can also be installed under an animal facility using slats. This practice will address soil and water quality by reducing the pollution potential to soil, surface water and ground water. Payment includes all materials, equipment and labor to install a concrete tank and gravel for drain fill around the tank.

Before Situation:

Manure and other agricultural by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or other location, or are being transported but not properly utilized or disposed of. This situation poses an environmentally threat of excessive nutrients, organics, and pathogens being transported into surface and groundwater, in addition to the use of excessive amounts of fertilizers.

After Situation:

Manure and other agricultural by-products are being controlled, by the collection at the source, and stored temporarily, at an environmentally suitable location, until such time that they are disposed of or utilized in a proper manner, typically in accordance with a nutrient management plan. Tank typically 8' deep, with a bottom area of 1256 SF, and a total storage volume of 10,048 cubic feet. Sizing based on volume of manure, other wastes, rainfall, lot runoff, etc. as appropriate. Potential Associated Practices: Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Waste Transfer (634), Heavy Use Area Protection (561), Roof and Covers (367), Solid/Liquid Waste Separation Facility (632), Diversion (362), Subsurface Drain (606), and Underground Outlet (620).

Feature Measure: Total Storage Volume

Scenario Unit:: Cubic Foot

Scenario Typical Size: 10,048.0

Scenario Total Cost: \$34,803.22

Scenario Cost/Unit: \$3.46

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	20	\$5,492.40
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	50	\$21,355.50
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	200	\$1,072.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	30	\$3,480.30
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	30	\$849.00
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	48	\$1,227.36
Waterstop, PVC, ribbed, 3/16" x 6"	1614	Waterstop, PVC, ribbed, 3/16" thick by 6"wide. Includes materials, equipment and labor.	Foot	\$5.03	160	\$804.80
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86



**Practice:** 313 - Waste Storage Facility

**Scenario #14 - Concrete Tank Open Top, 15,000 - 24,999 Cu Ft Storage**

**Scenario Description:**

This scenario consists of installing an open top concrete tank that has a total storage volume from 15,000 to 24,999 Cu Ft. Payment includes materials and equipment necessary for construction of the concrete tank. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Vehicular and equipment access is addressed in Heavy Use Area Protection (561). Tank can also be installed under an animal facility using slats. The design volume does not include freeboard. This practice will address soil and water quality by reducing the pollution potential to soil, surface water and ground water. Payment includes all materials, equipment and labor to install a concrete tank and gravel for drainfill around the tank.

**Before Situation:**

Manure and other agricultural by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or other location, or are being transported but not properly utilized or disposed of. This situation poses an environmentally threat of excessive nutrients, organics, and pathogens being transported into surface and ground waters, in addition to the use of excessive amounts of fertilizers.

**After Situation:**

Manure and other agricultural by-products are being controlled, by the collection at the source, and stored temporarily, at an environmentally suitable location, until such time that they are disposed of or utilized in a proper manner, typically in accordance with a nutrient management plan. Tank is typically 8 ft deep, with a bottom area of 2,670 sq.ft., and a total storage volume of 21,360 cubic feet. Size based on volume of manure, other wastes, rainfall, lot runoff, etc. as appropriate. Potential Associated Practices: Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Waste Transfer (634), Heavy Use Area Protection (561), Roof and Covers (367), Solid/Liquid Waste Separation Facility (632), Diversion (362), Subsurface Drain (606), Pumping Plant (533) and Underground Outlet (620).

**Feature Measure:** Total Storage Volume

**Scenario Unit::** Cubic Foot

**Scenario Typical Size:** 21,360.0

**Scenario Total Cost:** \$39,573.58

**Scenario Cost/Unit:** \$1.85

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	45	\$12,357.90
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	37	\$15,803.07
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	240	\$1,286.40
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	46	\$5,336.46
<b>Labor</b>						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	46	\$1,301.80
<b>Materials</b>						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	80	\$2,045.60
Waterstop, PVC, ribbed, 3/16" x 6"	1614	Waterstop, PVC, ribbed, 3/16" thick by 6"wide. Includes materials, equipment and labor.	Foot	\$5.03	183	\$920.49
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: 313 - Waste Storage Facility

Scenario #15 - Concrete Tank Open Top, 25,000 - 49,999 Cu Ft Storage

Scenario Description:

This scenario consists of installing an open top concrete tank that has a total storage volume from 25,000 to 49,999 Cu Ft. Payment includes materials and equipment necessary for construction of the concrete tank. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Vehicular and equipment access is addressed in Heavy Use Area Protection (561). Tank can also be installed under an animal facility using slats. The design volume does not include freeboard. This practice will address soil and water quality by reducing the pollution potential to soil, surface water and ground water. Payment includes all materials, equipment and labor to install a concrete tank and gravel for drainfill around the tank.

Before Situation:

Manure and other agricultural by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or other location, or are being transported but not properly utilized or disposed of. This situation poses an environmentally threat of excessive nutrients, organics, and pathogens being transported into surface and ground waters, in addition to the use of excessive amounts of fertilizers.

After Situation:

Manure and other agricultural by-products are being controlled, by the collection at the source, and stored temporarily, at an environmentally suitable location, until such time that they are disposed of or utilized in a proper manner, typically in accordance with a nutrient management plan. Tank installed is 8' deep, with an interior bottom area of 3,786 SF, and a total storage volume of 30,288 cubic feet. Outside dimensions, 4,225 sq ft (includes 3' footing and 8" wall). Size based on manure, other wastes, rainfall, lot runoff, etc. as appropriate. Potential Associated Practices: Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Waste Transfer (634), Heavy Use Area Protection (561), Roof and Covers (367), Solid/Liquid Waste Separation Facility (632), Diversion (362), Subsurface Drain (606), and Underground Outlet (620).

Feature Measure: Total Storage Volume

Scenario Unit:: Cubic Foot

Scenario Typical Size: 30,288.0

Scenario Total Cost: \$56,042.72

Scenario Cost/Unit: \$1.85

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	80	\$21,969.60
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	50	\$21,355.50
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	400	\$2,144.00
Excavation, common earth, large equipment, 150 ft	1223	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 150 feet. Includes equipment and labor.	Cubic Yard	\$3.85	1450	\$5,582.50
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	126	\$3,221.82
Waterstop, PVC, ribbed, 3/16" x 6"	1614	Waterstop, PVC, ribbed, 3/16" thick by 6"wide. Includes materials, equipment and labor.	Foot	\$5.03	248	\$1,247.44
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: 313 - Waste Storage Facility

Scenario #16 - Concrete Tank Open Top, 50,000 - 74,999 Cu Ft Storage

Scenario Description:

This scenario consists of installing an open top concrete tank that has a total storage volume from 50,000 to 74,999 Cu Ft. Payment includes materials and equipment necessary for construction of the concrete tank. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Vehicular and equipment access is addressed in Heavy Use Area Protection (561). Tank can also be installed under an animal facility using slats. The design volume does not include freeboard. This practice will address soil and water quality by reducing the pollution potential to soil, surface water and ground water. Payment includes all materials, equipment and labor to install a concrete tank and gravel for drainfill around the tank.

Before Situation:

Manure and other agricultural by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or other location, or are being transported but not properly utilized or disposed of. This situation poses an environmentally threat of excessive nutrients, organics, and pathogens being transported into surface and ground waters, in addition to the use of excessive amounts of fertilizers.

After Situation:

Manure and other agricultural by-products are being controlled, by the collection at the source, and stored temporarily, at an environmentally suitable location, until such time that they are disposed of or utilized in a proper manner, typically in accordance with a nutrient management plan. Tank typically 8' deep, with a bottom area of 8470 SF, and a total storage volume of 67,760 cubic feet. Outside dimensions 9,216 sq ft (includes 3' footing and 8" wall). Sizing based on manure, other wastes, rainfall, lot runoff, etc. as appropriate. Potential Associated Practices: Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Waste Transfer (634), Heavy Use Area Protection (561), Roof and Covers (367), Solid/Liquid Waste Separation Facility (632), Diversion (362), Subsurface Drain (606), and Underground Outlet (620).

Feature Measure: total Storage Volume

Scenario Unit:: Cubic Foot

Scenario Typical Size: 67,760.0

Scenario Total Cost: \$99,350.43

Scenario Cost/Unit: \$1.47

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	160	\$43,939.20
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	75	\$32,033.25
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	600	\$3,216.00
Excavation, common earth, large equipment, 150 ft	1223	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 150 feet. Includes equipment and labor.	Cubic Yard	\$3.85	3000	\$11,550.00
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	244	\$6,239.08
Waterstop, PVC, ribbed, 3/16" x 6"	1614	Waterstop, PVC, ribbed, 3/16" thick by 6"wide. Includes materials, equipment and labor.	Foot	\$5.03	368	\$1,851.04
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: 313 - Waste Storage Facility

Scenario #17 - Concrete Tank Open Top, 75,000 - 109,999 Cu Ft Storage

Scenario Description:

This scenario consists of installing an open top concrete tank that has a total storage volume from 75,000 to 109,999 Cu Ft. Payment includes materials and equipment necessary for construction of the concrete tank. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Vehicular and equipment access is addressed in Heavy Use Area Protection (561). Tank can also be installed under an animal facility using slats. The design volume does not include freeboard. This practice will address soil and water quality by reducing the pollution potential to soil, surface water and ground water. Payment includes all materials, equipment and labor to install a concrete tank and gravel for drainfill around the tank.

Before Situation:

Manure and other agricultural by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or other location, or are being transported but not properly utilized or disposed of. This situation poses an environmentally threat of excessive nutrients, organics, and pathogens being transported into surface and ground waters, in addition to the use of excessive amounts of fertilizers.

After Situation:

Manure and other agricultural by-products are being controlled, by the collection at the source, and stored temporarily, at an environmentally suitable location, until such time that they are disposed of or utilized in a proper manner, typically in accordance with a nutrient management plan. This practice will address soil and water quality by reducing the pollution potential to soil, surface water and ground water. Tank typically 8' deep, with a bottom area of 12,642 SF, and a storage capacity of 101,136 cubic feet. Outside dimensions 13,456 sq ft (includes 3' footing and 8" wall).Sizing based on manure, other wastes, rainfall, lot runoff, etc. as appropriate. Potential Associated Practices: Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Waste Transfer (634), Heavy Use Area Protection (561), Roof and Covers (367), Solid/Liquid Waste Separation Facility (632), Diversion (362), Pipeline (516), Subsurface Drain (606), and Underground Outlet (620).

Feature Measure: Total Storage Volume

Scenario Unit:: Cubic Foot

Scenario Typical Size: 101,136.0

Scenario Total Cost: \$134,051.54

Scenario Cost/Unit: \$1.33

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	230	\$63,162.60
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	90	\$38,439.90
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	900	\$4,824.00
Excavation, common earth, large equipment, 150 ft	1223	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 150 feet. Includes equipment and labor.	Cubic Yard	\$3.85	4300	\$16,555.00
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	324	\$8,284.68
Waterstop, PVC, ribbed, 3/16" x 6"	1614	Waterstop, PVC, ribbed, 3/16" thick by 6"wide. Includes materials, equipment and labor.	Foot	\$5.03	450	\$2,263.50
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: 313 - Waste Storage Facility

Scenario #18 - Concrete Tank Open Top, >=110,000 Cu Ft Storage

Scenario Description:

This scenario consists of installing an open top concrete tank that has a total storage volume of 110,000 Cu Ft or greater. Payment includes materials and equipment necessary for construction of the concrete tank. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Vehicular and equipment access is addressed in Heavy Use Area Protection (561). Tank can also be installed under an animal facility using slats. The design volume does not include freeboard. This practice will address soil and water quality by reducing the pollution potential to soil, surface water and ground water. Payment includes all materials, equipment and labor to install a concrete tank and gravel for drain fill around the tank.

Before Situation:

Manure and other agricultural by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or other location, or are being transported but not properly utilized or disposed of. This situation poses an environmentally threat of excessive nutrients, organics, and pathogens being transported into surface and groundwater, in addition to the use of excessive amounts of fertilizers.

After Situation:

Manure and other agricultural by-products are being controlled, by the collection at the source, and stored temporarily, at an environmentally suitable location, until such time that they are disposed of or utilized in a proper manner, typically in accordance with a nutrient management plan. Tank typically 8' deep with a bottom area of 21,000 SF and a total storage volume of 168,000 CF. Outside dimensions 22,200 sq ft (includes 3' footing and 8" wall).Sizing based on manure, other wastes, rainfall, lot runoff, etc. as appropriate. Sizing based on manure, other wastes, rainfall, lot runoff, etc. as appropriate. Potential Associated Practices: Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Waste Transfer (634), Heavy Use Area Protection (561), Roof and Covers (367), Solid/Liquid Waste Separation Facility (632), Diversion (362), Pipeline (516), Subsurface Drain (606), and Underground Outlet (620).

Feature Measure: Total Storage Volume

Scenario Unit:: Cubic Foot

Scenario Typical Size: 168,000.0

Scenario Total Cost: \$196,603.53

Scenario Cost/Unit: \$1.17

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	346	\$95,018.52
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	115	\$49,117.65
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	1667	\$8,935.12
Excavation, common earth, large equipment, 150 ft	1223	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 150 feet. Includes equipment and labor.	Cubic Yard	\$3.85	7000	\$26,950.00
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	514	\$13,142.98
Waterstop, PVC, ribbed, 3/16" x 6"	1614	Waterstop, PVC, ribbed, 3/16" thick by 6"wide. Includes materials, equipment and labor.	Foot	\$5.03	580	\$2,917.40
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: 313 - Waste Storage Facility

Scenario #30 - Concrete Tank Open Top, 5,000 - 7,499 Cu Ft Storage

Scenario Description:

This scenario consists of installing an open top concrete tank that has a total storage volume from 5,000 to 7,499 Cu Ft. Payment includes materials and equipment necessary for construction of the concrete tank. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Vehicular and equipment access is addressed in Heavy Use Area Protection (561). Tank can also be installed under an animal facility using slats. This practice will address soil and water quality by reducing the pollution potential to soil, surface water and ground water. Payment includes all materials, equipment and labor to install a concrete tank and gravel for drain fill around the tank.

Before Situation:

Manure and other agricultural by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or other location, or are being transported but not properly utilized or disposed of. This situation poses an environmentally threat of excessive nutrients, organics, and pathogens being transported into surface and groundwater, in addition to the use of excessive amounts of fertilizers.

After Situation:

Manure and other agricultural by-products are being controlled, by the collection at the source, and stored temporarily, at an environmentally suitable location, until such time that they are disposed of or utilized in a proper manner, typically in accordance with a nutrient management plan. Tank typically 5' deep, with a bottom area of 1200 SF, and a total storage volume of 6,000 cubic feet. Sizing based on volume of manure, other wastes, rainfall, lot runoff, etc. as appropriate. Potential Associated Practices: Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Waste Transfer (634), Heavy Use Area Protection (561), Roof and Covers (367), Solid/Liquid Waste Separation Facility (632), Diversion (362), Subsurface Drain (606), and Underground Outlet (620).

Feature Measure: Total Storage Volume

Scenario Unit:: Cubic Foot

Scenario Typical Size: 6,000.0

Scenario Total Cost: \$27,710.50

Scenario Cost/Unit: \$4.62

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	19	\$5,217.78
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	34	\$14,521.74
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	203	\$1,088.08
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	30	\$3,480.30
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	30	\$849.00
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	47	\$1,201.79
Waterstop, PVC, ribbed, 3/16" x 6"	1614	Waterstop, PVC, ribbed, 3/16" thick by 6"wide. Includes materials, equipment and labor.	Foot	\$5.03	165	\$829.95
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: 314 - Brush Management

Scenario #2 - Medium Brush Management

Scenario Description:

Medium brush management is used on non-cropland acres (including forestland, pasture, and wildlife areas) where 10% - 39% canopy cover across the treatment area is in undesirable non-herbaceous cover, and the treatment area is less than 18% slope on average. Payment is based on impacted acres only. Treatment may consist of chemical, mechanical, manual, or a combination of methods. Cost represents typical situations for conventional, organic, and transitioning to organic producers. For organic land, chemical applications must be OMRI approved chemicals.

Before Situation:

Non-cropland acres consisting of a percentage of undesirable species such as (but not limited to) Amur cork tree, Siberian elm, callery pear, autumn olive, multiflora rose, barberry, burning bush, honeysuckle, or periwinkle that must be controlled. Undesirable species can contribute to degraded plant condition, inadequate feed & forage, and potential animal health issues.

After Situation:

Undesirable non-herbaceous species are controlled with a pass with a brush hog over the treatment area followed by spot chemical treatment. The treatment area is mechanically treated early in the growing season to reduce above ground biomass. The treated plants will readily resprout, and after adequate re-sprouting occurs herbicide will be applied to the new growth. This combined treatment will allow better access for the herbicide application equipment, better coverage on target plants, and less overall herbicide applied.

Feature Measure: Acres planned

Scenario Unit:: Acre

Scenario Typical Size: 25.0

Scenario Total Cost: \$2,039.17

Scenario Cost/Unit: \$81.57

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	12	\$635.28
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	10	\$661.90
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	14	\$307.72
Materials						
Herbicide, Triclopyor	338	Refer to WIN-PST for product names and active ingredients. Materials and shipping	Acre	\$42.37	7.5	\$317.78
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: 314 - Brush Management

Scenario #3 - High Brush Management

Scenario Description:

High brush management is used on non-cropland acres (including forestland, pasture, and wildlife areas) where 40%-60% canopy cover across the treatment area is in undesirable non-herbaceous cover, or the treatment area is on land with 18% - 25% slopes on average regardless of percent cover of undesirable species. Payment is based on impacted acres only. Treatment may consist of chemical, mechanical, manual, or a combination of methods. Cost represents typical situations for conventional, organic, and transitioning to organic producers. For organic land, chemical applications must be OMRI approved chemicals.

Before Situation:

Non-cropland acres consisting of a percentage of undesirable species such as (but not limited to) Tree of heaven, Paulownia (princess tree), honeysuckle, Japanese knotweed, privet, or wintercreeper, that must be controlled. Undesirable species can contribute to degraded plant condition, inadequate feed & forage, and potential animal health issues.

After Situation:

Undesirable non-herbaceous species are controlled with a combination of manual chain sawing, pass with a brush hog over the treatment area, and spot chemical treatment. The treatment area is mechanically treated early in the growing season to reduce above ground biomass. The treated plants will readily resprout, and after adequate re-sprouting occurs herbicide will be applied to the new growth. This combined treatment will allow better access for the herbicide application equipment, better coverage on target plants, and less overall herbicide applied.

Feature Measure: Acres planned

Scenario Unit:: Acre

Scenario Typical Size: 25.0

Scenario Total Cost: \$4,863.70

Scenario Cost/Unit: \$194.55

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	8	\$35.60
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	20	\$1,058.80
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	24	\$1,588.56
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	65	\$1,428.70
Materials						
Herbicide, Triclopyor	338	Refer to WIN-PST for product names and active ingredients. Materials and shipping	Acre	\$42.37	15	\$635.55
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05



Practice: 314 - Brush Management

Scenario #4 - Very High Brush Management

Scenario Description:

High brush management is used on non-cropland acres (including forestland, pasture, and wildlife areas) where greater than 60% canopy cover across the treatment area is in undesirable non-herbaceous cover, or the treatment area is on land with greater than 25% slopes on average regardless of percent cover of undesirable species. Payment is based on impacted acres only. Treatment may consist of chemical, mechanical, manual, or a combination of methods. Cost represents typical situations for conventional, organic, and transitioning to organic producers. For organic land, chemical applications must be OMRI approved chemicals.

Before Situation:

Non-cropland acres consisting of a percentage of undesirable species such as (but not limited to) Tree of heaven, Paulownia (princess tree), honeysuckle, Japanese knotweed, privet, or wintercreeper, that must be controlled. Undesirable species can contribute to degraded plant condition, inadequate feed & forage, and potential animal health issues.

After Situation:

Undesirable non-herbaceous species are controlled with a combination of manual chain sawing, pass with a brush hog over the treatment area, and spot chemical treatment. The treatment area is mechanically treated early in the growing season to reduce above ground biomass. The treated plants will readily resprout, and after adequate re-sprouting occurs herbicide will be applied to the new growth. This combined treatment will allow better access for the herbicide application equipment, better coverage on target plants, and less overall herbicide applied.

Feature Measure: Acres planned

Scenario Unit:: Acre

Scenario Typical Size: 25.0

Scenario Total Cost: \$7,964.18

Scenario Cost/Unit: \$318.57

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	20	\$89.00
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	40	\$2,117.60
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	40	\$2,647.60
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	88	\$1,934.24
Materials						
Herbicide, Triclopyor	338	Refer to WIN-PST for product names and active ingredients. Materials and shipping	Acre	\$42.37	25	\$1,059.25
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: 314 - Brush Management

Scenario #284 - Linear Tree Removal for Grassland Bird Habitat

Scenario Description:

Scenario is to open the vista and visual ranges for Prairie Chickens and other grassland dependent birds and reduce grassland habitat fragmentation by removing undesirable trees. Establishment of herbaceous vegetative cover on the cleared site is accomplished through associated practices such as 327 Conservation Cover.

Before Situation:

Grassland habitat for Prairie Chickens and other grassland dependent birds is fragmented by fencerows and other linear areas grown up in mature trees and brush.

After Situation:

Habitat is improved by removal of mature trees and brush. Typical size of area cleared is 1,800 ft long by 30 ft wide. Due to the mature trees in the area to be cleared a dozer is typically required. Removed debris is piles and burned and the cleared area is seeded to wildlife friendly vegetation through associated practice 327 Conservation Cover. If needed, associated practice 382 Fence is utilized to protect the area from livestock.

Feature Measure: size of area cleared

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,499.33

Scenario Cost/Unit: \$1,499.33

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	\$126.50	8	\$1,012.00
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	8	\$226.40
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 315 - Herbaceous Weed Control

Scenario #1 - Light Spot Treatment

Scenario Description:

Light spot treatment herbaceous weed control is used on non-cropland acres (including forestland, pasture, and idle areas) where less than 10% canopy coverage across the treatment area is in undesirable herbaceous cover, or a specific area spot treatment is needed such as creating open ground under a wildlife habitat structure . Payment is based on impacted acres only. The practice entails the treatment of weeds using small equipment (such as an ATV with sprayer) to apply chemicals, or using hand tools (such as axes, shovels, hoes, nippers) to remove or cut off herbaceous plants at or below the root collar. Cost represents typical situations for conventional, organic, and transitioning to organic producers. For organic land, chemical applications must be OMRI approved chemicals.

Before Situation:

Area consists of herbaceous weed species such as sericia lespedeza, japanese stilt grass, periwinkle, ironweed, ragweed, etc. that exceed the desirable ecological site condition degrading forage quality, promoting noxious and invasive species, increasing risk of soil erosion and degrading wildlife habitat.

After Situation:

Herbaceous weeds are removed to achieve the desirable plant community based on species composition, structure, density, and canopy cover or height. Ecological site condition is progressing in an upward trend, hydrology and plant health and vigor is returning to near normal levels, and wildlife habitat is improved.

Feature Measure: Acres Treated

Scenario Unit:: Acre

Scenario Typical Size: 25.0

Scenario Total Cost: \$795.90

Scenario Cost/Unit: \$31.84

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	8	\$529.52
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Materials						
Herbicide, Triclopyor	338	Refer to WIN-PST for product names and active ingredients. Materials and shipping	Acre	\$42.37	2.5	\$105.93
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: 315 - Herbaceous Weed Control

Scenario #2 - Medium Spot Treatments

Scenario Description:

Medium spot treatment herbaceous species management is used on non-cropland acres (including forestland, pasture, and idle areas) where greater than 10% canopy coverage across the treatment area is in undesirable herbaceous cover, and spot treatment is preferred over blanket treatment to maintain the persistence of desirable broadleaf and legumes within the treatment area. Payment is based on impacted acres only. The practice entails the treatment of weeds using small equipment (such as an ATV with sprayer) to apply chemicals, or using applicable mechanical methods such as hand tools (such as axes, shovels, hoes, nippers) to remove or cut off herbaceous plants at or below the root collar, and/or spot mowing. Cost represents typical situations for conventional, organic, and transitioning to organic producers. For organic land, chemical applications must be OMRI approved chemicals.

Before Situation:

Area consists of herbaceous weed species such as sericia lespedeza, japanese stilt grass, periwinkle, ironweed, ragweed, etc. that exceed the desirable ecological site condition degrading forage quality, promoting noxious and invasive species, increasing risk of soil erosion and degrading wildlife habitat.

After Situation:

Herbaceous weeds are removed to achieve the desirable plant community based on species composition, structure, density, and canopy cover or height. Ecological site condition is progressing in an upward trend, hydrology and plant health and vigor is returning to near normal levels, and wildlife habitat is improved.

Feature Measure: Acres Treated

Scenario Unit:: Acre

Scenario Typical Size: 25.0

Scenario Total Cost: \$2,299.82

Scenario Cost/Unit: \$91.99

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	24	\$1,588.56
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Materials						
Herbicide, Triclopyr	338	Refer to WIN-PST for product names and active ingredients. Materials and shipping	Acre	\$42.37	13	\$550.81
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: 315 - Herbaceous Weed Control

Scenario #3 - Blanket Treatment One Pass

Scenario Description:

Blanket treatment one pass herbaceous weed control is used on non-cropland acres (including forestland, pasture, and idle areas) where a blanket treatment approach is acceptable and the non-desirable weeds can be controlled with one treatment. Payment is based on impacted acres only. The practice entails the treatment of weeds using a blanket chemical application or mechanical brush hog operation. Cost represents typical situations for conventional, organic, and transitioning to organic producers. For organic land, chemical applications must be OMRI approved chemicals.

Before Situation:

Area consists of herbaceous weed species such as sericia lespedeza, japanese stilt grass, periwinkle, ironweed, ragweed, etc. that exceed the desirable ecological site condition degrading forage quality, promoting noxious and invasive species, increasing risk of soil erosion and degrading wildlife habitat.

After Situation:

Herbaceous weeds are removed to achieve the desirable plant community based on species composition, structure, density, and canopy cover or height. Ecological site condition is progressing in an upward trend, hydrology and plant health and vigor is returning to near normal levels, and wildlife habitat is improved.

Feature Measure: Acres Treated

Scenario Unit:: Acre

Scenario Typical Size: 25.0

Scenario Total Cost: \$1,568.23

Scenario Cost/Unit: \$62.73

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	25	\$156.50
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	6	\$132.54
Materials						
Herbicide, Triclopyr	338	Refer to WIN-PST for product names and active ingredients. Materials and shipping	Acre	\$42.37	25	\$1,059.25
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: 315 - Herbaceous Weed Control

Scenario #4 - Blanket Treatment Multi Pass

Scenario Description:

Blanket treatment multi pass herbaceous weed control is used on non-cropland acres (including forestland, pasture, and idle areas) where a blanket treatment approach is acceptable and multiple passes or approaches are needed to control the non-desirable weeds. Payment is based on impacted acres only. The practice entails the treatment of weeds using multiple blanket chemical applications or multiple mechanical brush hog operations, or a combination of chemical and mechanical. Cost represents typical situations for conventional, organic, and transitioning to organic producers. For organic land, chemical applications must be OMRI approved chemicals.

Before Situation:

Area consists of herbaceous weed species such as sericia lespedeza, japanese stilt grass, periwinkle, ironweed, ragweed, etc. that exceed the desirable ecological site condition degrading forage quality, promoting noxious and invasive species, increasing risk of soil erosion and degrading wildlife habitat.

After Situation:

Herbaceous weeds are removed to achieve the desirable plant community based on species composition, structure, density, and canopy cover or height. Ecological site condition is progressing in an upward trend, hydrology and plant health and vigor is returning to near normal levels, and wildlife habitat is improved.

Feature Measure: Acres Treated

Scenario Unit:: Acre

Scenario Typical Size: 25.0

Scenario Total Cost: \$3,409.92

Scenario Cost/Unit: \$136.40

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	4	\$88.88
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	6	\$317.64
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	50	\$313.00
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12" , Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	10	\$220.90
Materials						
Herbicide, Triclopyor	338	Refer to WIN-PST for product names and active ingredients. Materials and shipping	Acre	\$42.37	50	\$2,118.50
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00

Practice: 315 - Herbaceous Weed Control

Scenario #5 - Tree & Shrub Post-planting Weed Control

Scenario Description:

Treatment takes place in areas where newly planted trees and/or shrubs are experiencing encroachment by grass and weed competition. Chemical treatment is needed to ensure the successful establishment of desirable woody species through the application of appropriate herbicides via directional spray to reduce residual effects on planted trees and/or shrubs. Mowing between rows during the growing season is needed to control residual weed growth. Areas to be treated tend to be small and isolated, resulting in high mobilization costs. Due to desirable species mixed with undesirable, caution is needed during treatment.

Before Situation:

Planted trees or shrubs are experiencing excessive grass and weed competition resulting in poor plant health, reduced growth, and some mortality.

After Situation:

Desirable vegetation is released from competing vegetation. All undesirable vegetation is removed within 2 feet of desired plants.

Feature Measure: Acres treated

Scenario Unit:: Acre

Scenario Typical Size: 5.0

Scenario Total Cost: \$700.20

Scenario Cost/Unit: \$140.04

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	1	\$52.94
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	2	\$132.38
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	2	\$57.68
Materials						
Herbicide, Sulfometuron-methyl	340	Used for the control of annual and perennial grasses and broad leaved weeds in non-crop land. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$40.65	5	\$203.25
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shi	Acre	\$1.28	5	\$6.40
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: 316 - Animal Mortality Facility

Scenario #1 - Incinerator

Scenario Description:

This scenario consists of installing a manufactured Type IV incinerator. Payment includes the incinerator, fuel tank and concrete slab to support the incinerator and fuel tank. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. The purpose of the practice is to address resource concerns related to water quality degradation due to excessive nutrients, organics, and pathogens being transported into surface and groundwater resources.

Before Situation:

Animal mortality is done in a manner that results in non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Improper operation results in odors and spread of pathogens from incomplete composting, incineration, or interaction with predators. No plan was formulated for both normal and catastrophic mortality events.

After Situation:

Animal mortality is being done in a manner that prevents non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Proper operation results in little to no odors, complete incineration, and protection from predators to minimize pathogen survival or spreading. Included is a concrete slab to set the incinerator on and a fuel tank. Ash materials to be stored in suitable containers until land disposal as per the nutrient management plan or landfilled. Potential Associated Practices: Heavy Use Area Protection (561), Fence (382), Critical Area Planting (342), Access Road (560), Waste Storage Facility (313), Nutrient Management (590), Roofs and Covers (367), Critical Area Planting (342).

Feature Measure: Pounds capacity of incinerator

Scenario Unit:: Pounds per Day

Scenario Typical Size: 400.0

Scenario Total Cost: \$14,106.38

Scenario Cost/Unit: \$35.27

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	4	\$1,098.48
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	8	\$17.20
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	1	\$116.01
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	1	\$21.98
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	1	\$22.09
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	4	\$102.28
Fuel Tank, Anchored	1033	Fuel tank for operating incinerators and/or gasifiers. Materials only.	Gallon	\$3.57	285	\$1,017.45
Incinerator, 400 lbs/day	1625	Poultry and livestock incinerator with an approximate chamber capacity of 400 pounds per day. Includes equipment and after burner only.	Each	\$11,449.96	1	\$11,449.96
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93



Practice: 316 - Animal Mortality Facility

Scenario #20 - Medium- High Animal Composter

Scenario Description:

This scenario applies to composting of medium-sized animals, regardless of technology; each state is responsible for determining the size range of the animals to which this scenario applies. The typical scenario is a series of concrete bins, open on one end, on top of a concrete pad, to compost mortality in static piles with sufficient bulking material to allow natural aeration. The producer will be managing the composting with heavy equipment, requiring durable, concrete walls. Facility sizing parameters include primary and secondary composting area requirements, to allow piles to be turned at least once to go into another heat cycle prior to final disposal, typically land application. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Where needed, use Practice Standard 561 - Heavy Use Area Protection adjacent to the composting facility for protected access, and Practice Standard 362 - Diversion to divert surface flow away from the facility. Typical scenario design uses the process outlined in the Illinois supplement to Chapter 10 of the Ag Waste Field Handbook (IL651.1007(f)), using a volume factor of 20 cubic feet. Animals being composted are grow-finish swine at an average weight of 165 lb, and the average mortality rate (death loss) for the operation is 4%, or 87 lbs/day for a 2400-head operation with 2 turns per year. The resulting typical design has twelve bins, each 10' x 9.8' by 5'7" high (reference standard drawing IL-ENG-149). Site preparation includes topsoil removal, minimal re-grading and compaction, installing gravel or sand sub base and then concrete.

Before Situation:

Animal mortality is done in a manner that results in non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Improper operation results in odors and spread of pathogens from incomplete composting, incineration, or interaction with predators. No plan was formulated for both normal and catastrophic mortality events.

After Situation:

Animal mortality is being done in a manner that prevents non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Proper operation results in little to no odors, complete composting, and protection from predators to minimize pathogen survival or spreading. An overall plan covers normal and catastrophic mortality events. Potential Associated Practices: Roofs and Covers (367), Roof Runoff Structure (558), Heavy Use Area Protection (561), Underground Outlet (620), Diversion (362), Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Structure for Water Control (587), Subsurface Drain (606).

Feature Measure: pounds of dead animals per day

Scenario Unit:: Pounds per Day

Scenario Typical Size: 87.0

Scenario Total Cost: \$22,263.60

Scenario Cost/Unit: \$255.90

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	20	\$5,492.40
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	37	\$15,803.07
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	48	\$103.20
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	48	\$194.88
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	16	\$409.12
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 316 - Animal Mortality Facility

Scenario #21 - Large Animal Composter

Scenario Description:

This scenario applies to composting of larger animals, regardless of technology; each state is responsible for determining the size range of the animals to which this scenario applies. The typical scenario is a concrete pad sized for composting animal mortality in windrow(s), including equipment access to the material. Facility sizing parameters include primary and secondary composting area requirements to allow piles to be turned at least once to go into another heat cycle prior to final disposal, typically land application. Site to be located out of drainage areas, off-site water diverted and any runoff to spread out into a grassed area or vegetated treatment area as per regulations. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Where needed, use Practice Standard 561 - Heavy Use Area Protection adjacent to the composting facility for protected access, and Practice Standard 362 - Diversion to divert surface flow away from the facility. Typical scenario design is Example 4 from the Ohio Livestock and Poultry Mortality Composting Manual. Animals being composted are cattle at an average weight of 1,400 lb, and the average mortality rate (death loss) for the operation is 20 lbs/day. The windrow system includes a primary and a secondary composting operation, with 30 days' worth of storage. The resulting typical design is a 25' x 60' concrete pad, 5" thick, with light reinforcement. Site preparation includes topsoil removal, minimal regrading and compaction, installing gravel or sand sub base and then concrete. An earthen berm (2' tall, 4' topwidth with 2:1 side slopes) around three sides of the facility captures any leachate.

Before Situation:

Animal mortality is done in a manner that results in non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Improper operation results in odors and spread of pathogens from incomplete composting, incineration, or interaction with predators. No plan is formulated for either normal or catastrophic mortality events.

After Situation:

Animal mortality is being done in a manner that prevents non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Proper operation results in little to no odors, complete composting, and protection from predators to minimize pathogen survival or spreading. An overall plan covers normal and catastrophic mortality events. Potential Associated Practices: Roofs and Covers (367), Roof Runoff Structure (558), Heavy Use Area Protection (561), Underground Outlet (620), Diversion (362), Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Structure for Water Control (587), Subsurface Drain (606).

Feature Measure: pounds of dead animals per day

Scenario Unit:: Pounds per Day

Scenario Typical Size: 20.0

Scenario Total Cost: \$7,356.91

Scenario Cost/Unit: \$367.85

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	23	\$6,316.26
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	56	\$120.40
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	107	\$434.42
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	19	\$485.83

Practice: 316 - Animal Mortality Facility

Scenario #22 - Small Animal Composter

Scenario Description:

This scenario applies to composting of small animals, regardless of technology; each state is responsible for determining the size range of the animals to which this scenario applies. The typical scenario is a series of concrete bins, open on one end, on top of a concrete pad, to compost mortality in static piles with sufficient bulking material to allow natural aeration. The producer will be managing the composting with heavy equipment, requiring durable, concrete walls. Facility sizing parameters include primary and secondary composting area requirements, to allow piles to be turned at least once to go into another heat cycle prior to final disposal, typically land application. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Where needed, use Practice Standard 561 - Heavy Use Area Protection adjacent to the composting facility for protected access, and Practice Standard 362 - Diversion to divert surface flow away from the facility. Typical scenario design uses the Indiana NRCS composter design spreadsheet process. Animals being composted are poultry at an average weight of 3 lb, and the average mortality rate (death loss) for the operation is 4%, or 267 lbs/day for a 100,000-chicken operation with a 45 day cycle time. The resulting typical design has four bins, each 10' x 9.8' by 5'7" high (reference standard drawing IL-ENG-161. Site preparation includes topsoil removal, minimal regrading and compaction, installing gravel or sand sub base and then concrete.

Before Situation:

Animal mortality is done in a manner that results in non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Improper operation results in odors and spread of pathogens from incomplete composting, incineration, or interaction with predators. No plan was formulated for both normal and catastrophic mortality events.

After Situation:

Animal mortality is being done in a manner that prevents non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Proper operation results in little to no odors, complete composting, and protection from predators to minimize pathogen survival or spreading. An overall plan covers normal and catastrophic mortality events. Potential Associated Practices: Roofs and Covers (367), Roof Runoff Structure (558), Heavy Use Area Protection (561), Underground Outlet (620), Diversion (362), Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Structure for Water Control (587), Subsurface Drain (606).

Feature Measure: pounds of dead animals per day

Scenario Unit:: Pounds per Day

Scenario Typical Size: 267.0

Scenario Total Cost: \$7,146.68

Scenario Cost/Unit: \$26.77

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	7	\$1,922.34
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	11	\$4,698.21
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	18	\$38.70
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	18	\$73.08
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	6	\$153.42
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 316 - Animal Mortality Facility

Scenario #23 - Medium - Low Animal Composter

Scenario Description:

This scenario applies to composting of medium-sized animals, regardless of technology; each state is responsible for determining the size range of the animals to which this scenario applies. The typical scenario is a series of concrete bins, open on one end, on top of a concrete pad, to compost mortality in static piles with sufficient bulking material to allow natural aeration. The producer will be managing the composting with heavy equipment, requiring durable, concrete walls. Facility sizing parameters include primary and secondary composting area requirements, to allow piles to be turned at least once to go into another heat cycle prior to final disposal, typically land application. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Where needed, use Practice Standard 561 - Heavy Use Area Protection adjacent to the composting facility for protected access, and Practice Standard 362 - Diversion to divert surface flow away from the facility. Typical scenario design uses the process outlined in the Illinois supplement to Chapter 10 of the Ag Waste Field Handbook (IL651.1007(f)), using a volume factor of 10 cubic feet. Animals being composted are large poultry at an average weight of 12 lbs, and the average mortality rate (death loss) for the operation is 7%, or 108 lbs/day for a 14,500 - head operation with 3 turns per year. The resulting typical design has four bins, each 14' x 9.33' by 5' high. Site preparation includes topsoil removal, minimal re-grading and compaction, installing gravel or sand sub base and then concrete.

Before Situation:

Animal mortality is done in a manner that results in non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Improper operation results in odors and spread of pathogens from incomplete composting, incineration, or interaction with predators. No plan was formulated for both normal and catastrophic mortality events.

After Situation:

Animal mortality is being done in a manner that prevents non-point source pollution of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources. Proper operation results in little to no odors, complete composting, and protection from predators to minimize pathogen survival or spreading. An overall plan covers normal and catastrophic mortality events. Potential Associated Practices: Roofs and Covers (367), Roof Runoff Structure (558), Heavy Use Area Protection (561), Underground Outlet (620), Diversion (362), Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Structure for Water Control (587), Subsurface Drain (606).

Feature Measure: pounds of dead animals per day

Scenario Unit:: Pounds per Day

Scenario Typical Size: 108.0

Scenario Total Cost: \$11,581.43

Scenario Cost/Unit: \$107.24

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	18	\$4,943.16
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	14	\$5,979.54
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	27	\$58.05
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	27	\$109.62
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	9	\$230.13
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 317 - Composting Facility

Scenario #2 - Concrete Slab Under Concrete Bin Dividers

Scenario Description:

A composting facility for manure and other agricultural organic by-products designed with a concrete slab under concrete bin dividers. Composter is installed to address water quality concerns and results in a composted product that can be used in multiple ways. Payment includes materials and equipment necessary for pad and bin construction. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Not to be used for animal mortality composting. All animal mortality composting shall be done using Practice Standard 316 - Animal Mortality Facility.

Before Situation:

Manure and other agricultural by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or other location, or are being transported but not properly utilized or disposed of. This situation poses an environmentally threat of excessive nutrients, organics, and pathogens being transported into surface and ground waters, in addition to the use of excessive amounts of fertilizers.

After Situation:

Manure, litter and other agricultural by-products are being controlled, by the collection at the source, and stored properly, at an environmentally suitable location, until such time that they are disposed of or utilized in a proper manner. This scenario is based upon a 40' x 56' concrete slab with 5' high bin dividers, and 5 bins (configured 2 at 20'x28' and 3 at 20'x18.5'). Preparation includes stripping the top 1' of soil and roll compact same back into sub-floor. The bins are constructed on a 5" concrete slab used to store and stabilize manure, litter and other agricultural by-products. Note regarding scenario for concrete walls versus wood walls: the more sturdy concrete walls are necessary in situations where a producer is managing the composting with heavy equipment that would easily damage and compromise the integrity of wooden walls. Potential Associated Practices: Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Structure for water control (587), Diversion (362), Pipeline (516), Subsurface Drain (606), Heavy Use Area Protection (561), Roofs and Covers (367), Roof Runoff Structure (558), Waste Storage Facility (313), Waste Recycling (633), Waste Transfer (634), Underground Outlet (620) and Vegetative Treatment Area (635).

Feature Measure: Cubic Foot of Storage

Scenario Unit:: Cubic Foot

Scenario Typical Size: 11,200.0

Scenario Total Cost: \$26,052.87

Scenario Cost/Unit: \$2.33

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	35	\$9,611.70
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	35	\$14,948.85
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	83	\$178.45
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	83	\$336.98
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	28	\$715.96
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 317 - Composting Facility

Scenario #3 - Compacted Earth Pad

Scenario Description:

A composting facility for manure and other agricultural organic by-products designed with a compacted earth pad. Composter is installed to address water quality concerns and results in a composted product that can be used in multiple ways. Payment includes materials and equipment necessary for pad construction. This scenario is applicable when geological, soil, and climate conditions are appropriate for earth floors and are allowed by state and local regulations. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Not to be used for animal mortality composting. All animal mortality composting shall be done using Practice Standard 316 - Animal Mortality Facility.

Before Situation:

Manure and other agricultural by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or other location, or are being transported but not properly utilized or disposed of. This situation poses an environmentally threat of excessive nutrients, organics, and pathogens being transported into surface and ground waters, in addition to the use of excessive amounts of fertilizers.

After Situation:

Manure and other agricultural by-products are being controlled, by the collection at the source, and stored temporarily, at an environmentally suitable location, until such time that they are disposed of or utilized in a proper manner. This scenario consists of removing and compacting back into place the top 1' of soil to create a compacted, impervious earthen floor to act as a working area to compost organic material in a static pile, windrow, that has sufficient carbon based bulking material to allow natural aeration. Piles typically turned at least once to go into another heat cycle prior to final disposal, typically land application. Construct a 75'x226' earthen surface on an improved compacted earthen surface. Include sufficient area for processing equipment access. Single piles or windrows to minimize runoff. Site to be located out of drainage areas, off-site water diverted and any runoff to spread out into a grassed area or vegetated treatment area as per regulations. Site preparation includes topsoil removal, compaction of subsoil, and reinstalling topsoil, compacted. Potential Associated Practices: Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Structure for water control (587), Diversion (362), Pipeline (516), Subsurface Drain (606), Heavy Use Area Protection (561), Roofs and Covers (367), Roof Runoff Structure (558), Waste Storage Facility (313), Waste Recycling (633), Waste Transfer (634), Underground Outlet (620) and Vegetative Treatment Area (635).

Feature Measure: Square Foot Floor Area

Scenario Unit:: Square Foot

Scenario Typical Size: 16,950.0

Scenario Total Cost: \$4,173.23

Scenario Cost/Unit: \$0.25

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	630	\$1,354.50
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	630	\$2,557.80
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 317 - Composting Facility

Scenario #4 - Concrete Pad

Scenario Description:

A composting facility for manure and other agricultural organic by-products designed with a concrete pad. Composter is installed to address water quality concerns and results in a composted product that can be used in multiple ways. Payment includes materials and equipment necessary for pad construction. This scenario is applicable when geological, soil, climate conditions or state and local regulations prohibit the use of an earthen surface. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Not to be used for animal mortality composting. All animal mortality composting shall be done using Practice Standard 316 - Animal Mortality Facility.

Before Situation:

Manure and other agricultural by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or other location, or are being transported but not properly utilized or disposed of. This situation poses an environmentally threat of excessive nutrients, organics, and pathogens being transported into surface and ground waters, in addition to the use of excessive amounts of fertilizers.

After Situation:

Manure and other agricultural by-products are being controlled, by the collection at the source, and stored temporarily, at an environmentally suitable location, until such time that they are disposed of or utilized in a proper manner. This scenario consists of removing and compacting back into place the top 1' of soil to create a compacted, impervious earthen floor to act as a working area to compost organic material in a static pile, windrow, that has sufficient carbon based bulking material to allow natural aeration. Piles typically turned at least once to go into another heat cycle prior to final disposal, typically land application. Construct a 75'x226' concrete surface 5" thick on an improved compacted earthen surface. Include sufficient area for processing equipment access. Single piles or windrows to minimize runoff. Site to be located out of drainage areas, off-site water diverted and any runoff to spread out into a grassed area or vegetated treatment area as per regulations. Site preparation includes topsoil removal, compaction of subsoil, and reinstalling topsoil, compacted. Note regarding scenario for concrete versus just earthen pad: concrete pads are necessary in situations such as, but not limited to, a site with soils that are permeable, karst, frequently accessed or have regulatory requirements that do not allow for an earthen surface. Potential Associated Practices: Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Structure for water control (587), Diversion (362), Pipeline (516), Subsurface Drain (606), Heavy Use Area Protection (561), Roofs and Covers (367), Roof Runoff Structure (558), Waste Storage Facility (313), Waste Recycling (633), Waste Transfer (634), Underground Outlet (620) and Vegetative Treatment Area (635).

Feature Measure: Square Foot Floor Area

Scenario Unit:: Square Foot

Scenario Typical Size: 16,950.0

Scenario Total Cost: \$79,562.95

Scenario Cost/Unit: \$4.69

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	260	\$71,401.20
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	630	\$1,354.50
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	315	\$1,278.90
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	206	\$5,267.42
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 317 - Composting Facility

Scenario #5 - Compacted Gravel Pad, 6 inch compacted gravel

Scenario Description:

A composting facility for manure and other agricultural organic by-products designed with a 6" compacted gravel pad. Composter is installed to address water quality concerns and results in a composted product that can be used in multiple ways. Payment includes materials and equipment necessary for pad construction. This scenario is applicable when geological, soil, climate conditions or state and local regulations prohibit the use of an earthen surface, but does not require a hard working surface such as concrete. If a roof is to be included in the installation refer to Practice Standard 367 - Roofs and Covers. Not to be used for animal mortality composting. All animal mortality composting shall be done using Practice Standard 316 - Animal Mortality Facility.

Before Situation:

Manure and other agricultural by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or other location, or are being transported but not properly utilized or disposed of. This situation poses an environmentally threat of excessive nutrients, organics, and pathogens being transported into surface and ground waters, in addition to the use of excessive amounts of fertilizers.

After Situation:

Manure and other agricultural by-products are being controlled, by the collection at the source, and stored properly, at an environmentally suitable location, until such time that they are disposed of or utilized in a proper manner. This scenario consists of installing a gravel pad over impervious soil to act as a working area to compost organic material in a static pile, windrow, that has sufficient carbon based bulking material to allow natural aeration. Piles typically turned at least once to go into another heat cycle prior to final disposal, typically land application. Construct a 75'x226' area on an improved gravel surface. Sub base material sufficiently compacted or improved. Include sufficient area for processing equipment access. Single piles or windrows to minimize runoff. Site to be located out of drainage areas, off-site water diverted and any runoff to spread out into a grassed area or vegetated treatment area as per regulations. Site preparation includes topsoil removal, compaction of subsoil, and installing 6" of compacted gravel. Potential Associated Practices: Fence (382), Critical Area Planting (342), Nutrient Management (590), Access Road (560), Structure for water control (587), Diversion (362), Pipeline (516), Subsurface Drain (606), Heavy Use Area Protection (561), Roofs and Covers (367), Roof Runoff Structure (558), Waste Storage Facility (313), Waste Recycling (633), Waste Transfer (634), Underground Outlet (620) and Vegetative Treatment Area (635).

Feature Measure: Square Foot Floor Area

Scenario Unit:: Square Foot

Scenario Typical Size: 16,950.0

Scenario Total Cost: \$15,449.25

Scenario Cost/Unit: \$0.91

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.39	1883	\$4,500.37
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	630	\$1,354.50
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	315	\$1,278.90
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	315	\$8,054.55
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93



Practice: 325 - High Tunnel System

Scenario #3 - High Tunnel System, Gothic Style

Scenario Description:

A manufactured frame of tubular steel covered with 4-year 6mil plastic. Costs are based on purchase of manufactured kit and landowner installing the structure. Structure must be installed to manufacturer's specifications.

Before Situation:

Cropland where extension of the growing season is needed. Additional resource concerns that may need to be addressed include; soil erosion, soil condition, water quality, water quantity, plant condition, and energy use.

After Situation:

A gothic style seasonal high tunnel (30 x 72 ft.) has been installed and the growing season has been extended for 1-4 months on average. The gothic style is encouraged to hedge against possible failure under snow loads. Plant health and vigor is improved and there is decreased energy use by producing food locally.

Feature Measure: Area of tunnel

Scenario Unit:: Square Foot

Scenario Typical Size: 2,160.0

Scenario Total Cost: \$11,089.60

Scenario Cost/Unit: \$5.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	80	\$1,758.40
Materials						
Hoop House, gothic style, base package	1278	Includes heavy-duty, gothic framework complete with all predrilled steel, hardware and instructions. Includes 6 mil 4-year polyethylene film to cover tunnel, roll-up sides, lumber, and polylock for sides and ends for a gothic style (peaked top) hoop house	Square Foot	\$4.32	2160	\$9,331.20

Practice: 327 - Conservation Cover

Scenario #22 - Monarch Species Mix

Scenario Description:

Establish permanent vegetative cover for pollinator habitat according to state specifications. Typically used for high quality nectar and pollen species. Assumes seed/plugs, equipment and labor for seed bed prep/planting, and weed management during establishment. Used for conventional or organic land on small, intensive areas that are central to specialty crop production. Not typically used for large-scale plantings. This is applicable to both organic and non-organic conditions.

Before Situation:

Old hayfields that are mowed typically in the fall lack milkweed needed for monarchs. Other crops such as corn, soybeans, or cotton are conventionally grown and harvested. The system provides little to no wildlife or pollinator habitat.

After Situation:

The 327 Implementation Requirements have been developed and applied for the site. Land covered with permanent monarch habitat including a mix of milkweed species, native grasses, legumes, and forbs. Plants sown for monarch habitat may also provide cover for beneficial insects and wildlife.

Feature Measure: area planted

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$897.83

Scenario Cost/Unit: \$897.83

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	3	\$34.11
Mechanical weed control, Vegetation termination	957	Mechanical operations, Includes: Roller/crimper, mower, shredder, etc. Includes equipment, power unit and labor costs.	Acre	\$20.95	2	\$41.90
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Materials						
Three Species Mix, Native Forb	2333	Native forb mix. Includes material and shipping only.	Acre	\$571.46	1.4	\$800.04

Practice: 327 - Conservation Cover

Scenario #55 - Monarch Species Mix - Interseeding

Scenario Description:

Enhance existing perennial vegetative cover with the interseeding of milkweeds and/or other high quality nectar and pollen species to enhance beneficial organism habitat. Scenario is appropriate for conventional or organic production. Payment includes seed, seeding and fertility for interseeding establishment.

Before Situation:

Existing grass/legume stand that lacks the species diversity needed to attract targeted species such as the Monarch Butterfly.

After Situation:

A more diverse mix of milkweed species, native grasses, legumes, and/or forbs provides improved habitat for beneficial organisms such as the Monarch Butterfly. Payment scenario is based on running a no till drill through ½ of the area to enhance the current perennial vegetation.

Feature Measure: area interseeded

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: \$6,046.10

Scenario Cost/Unit: \$302.31

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	10	\$113.70
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	10	\$217.80
Materials						
Three Species Mix, Native Forb	2333	Native forb mix. Includes material and shipping only.	Acre	\$571.46	10	\$5,714.60

Practice: 327 - Conservation Cover

Scenario #72 - Introduced with Forgone Income

Scenario Description:

This practice applies on organically managed land needing permanent protective cover. This practice typically involves conversion from an intensive organic cropping system to permanent non-native vegetation (scenario includes non-native grass/legume mix). The typical size of the practice is 20 acres. This practice scenario is typically used to reduce soil erosion, reduce soil quality degradation, improve water quality, develop wildlife habitat, and reduce air quality impacts.

Before Situation:

Crops such as vegetables and small fruit crops are organically grown and harvested. Full width tillage is utilized, weeds controlled mainly by cultivation. Soil surface residue amounts average 10% or less. Erosion exceeds tolerable rates and sediment may be moving offsite into surface water degrading water quality. Soil quality (soil organic matter) declines over time as a result of tillage practices, low residue, and long periods of bare soil. Air quality may be impacted during field operations by the creation of particulates. The system provides little to no wildlife habitat.

After Situation:

The 327 Implementation Requirements have been developed for the site and has been applied. Organically managed land covered with permanent non- native grass/legume mix vegetation has reduced soil erosion, reduced water/sediment runoff, and improved air quality due to the elimination of dust emissions. . Plants sown for conservation cover may provide cover for beneficial insects and wildlife. This scenario does not apply to plantings for forage production or to critical area plantings.

Feature Measure: Area planted

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$27,427.75

Scenario Cost/Unit: \$548.56

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	150	\$1,705.50
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.75	50	\$337.50
Mechanical weed control, Vegetation termination	957	Mechanical operations, Includes: Roller/crimper, mower, shredder, etc. Includes equipment, power unit and labor costs.	Acre	\$20.95	50	\$1,047.50
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	50	\$1,089.00

Foregone Income

Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	25	\$10,380.25
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	25	\$10,375.00

Materials

Nitrogen, Organic	266	ORGANIC Nitrogen	Pound	\$0.20	2500	\$500.00
Phosphorus, Organic	267	ORGANIC Phosphorus	Pound	\$0.20	2000	\$400.00
One Species, Cool Season, Introduced Perennial Grass	2313	Introduced, cool season perennial grass. Includes material and shipping only.	Acre	\$31.86	50	\$1,593.00

Practice: 327 - Conservation Cover

Scenario #73 - Native Species with Forgone Income

Scenario Description:

This practice applies on conventional or organically managed land needing permanent protective cover. This practice typically involves conversion from an intensive cropping system to permanent native vegetation (scenario includes native grass/legume mix). The typical size of the practice is 50 acres. This practice scenario is typically used to reduce soil erosion, reduce soil quality degradation, improve water quality, develop wildlife habitat, and reduce air quality impacts. Applies to conventional or organic systems.

Before Situation:

Crops such as vegetables and small fruit crops may be conventionally or organically grown and harvested. Full width tillage is utilized, weeds controlled mainly by cultivation. Soil surface residue amounts average 10% or less. Soil erosion exceeds tolerable rates and sediment may be moving offsite into surface water degrading water quality. Soil quality (soil organic matter) declines over time as a result of tillage practices, low residue, and long periods of bare soil. Air quality may be impacted during field operations by the creation of particulates. The system provides little to no wildlife habitat.

After Situation:

The 327 Implementation Requirements have been developed for the site and applied. Managed land covered with permanent native grass/legume mix vegetation has reduced soil erosion, reduced water/sediment runoff, and improved air quality due to the elimination of dust emissions. Plants sown for conservation cover may provide cover for beneficial insects and wildlife. This scenario does not apply to plantings for forage production or to critical area plantings.

Feature Measure: Area planted

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$30,248.75

Scenario Cost/Unit: \$604.98

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	150	\$1,705.50
Mechanical weed control, Vegetation termination	957	Mechanical operations, Includes: Roller/crimper, mower, shredder, etc. Includes equipment, power unit and labor costs.	Acre	\$20.95	100	\$2,095.00
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	50	\$1,089.00
Foregone Income						
Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	25	\$10,380.25
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	25	\$10,375.00
Materials						
Two Species Mix, Warm Season, Native Perennial Grass	2325	Native, warm season perennial grass. Includes material and shipping only.	Acre	\$92.08	50	\$4,604.00

Practice: 327 - Conservation Cover

Scenario #74 - Pollinator Species with Forgone Income

Scenario Description:

Permanent vegetation, including a mix of native grasses, legumes, and forbs (mix may also include non-native species), established on land needing permanent vegetative cover that provides habitat for pollinators. Typical practice size is variable depending on site; this scenario uses 1 ac as the typical size. In addition to providing pollinator habitat, this practice scenario may also reduce sheet and rill erosion, improve soil quality, improve water quality, and improve air quality. The practice may also provide wildlife habitat. Practice applicable on cropland, odd areas, corners, etc. Applies to conventional or organic systems.

Before Situation:

Crops such as vegetables and small fruit crops may be conventionally or organically grown and harvested. Full width tillage is utilized, weeds controlled mainly by cultivation. Soil surface residue amounts average 10% or less. Soil erosion exceeds tolerable rates and sediment may be moving offsite into surface water degrading water quality. Soil quality (soil organic matter) declines over time as a result of tillage practices, low residue, and long periods of bare soil. Air quality may be impacted during field operations by the creation of particulates. The system provides little to no wildlife or pollinator habitat.

After Situation:

The 327 Implementation Requirements have been developed for the site and applied. Managed land covered with permanent pollinator habitat including a mix of native grasses, legumes, and forbs (mix may also include non-native species). This practice may also reduce soil erosion, reduce water/sediment runoff, and improve air quality due to the elimination of dust emissions. Plants sown for pollinator habitat may also provide cover for beneficial insects and wildlife. This scenario does not apply to critical area plantings.

Feature Measure: Area planted

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$894.51

Scenario Cost/Unit: \$894.51

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	3	\$34.11
Mechanical weed control, Vegetation termination	957	Mechanical operations, Includes: Roller/crimper, mower, shredder, etc. Includes equipment, power unit and labor costs.	Acre	\$20.95	2	\$41.90
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.5	\$207.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.5	\$207.50
Materials						
Native Grass and Forb Mix, for Wildlife (including pollinators) or Ecosystem Restoration	2335	Native grass and forb/legume mix, including specialized species. Includes material and shipping only.	Acre	\$254.41	1.5	\$381.62

Practice: 328 - Conservation Crop Rotation

Scenario #1 - Basic Rotation Organic and Non-Organic

Scenario Description:

In this region this practice may be part of a conservation management system on both organic and non-organic operations to: 1) Reduce sheet, rill and wind erosion, 2) Maintain or increase soil health and organic matter content, 3) Reduce water quality degradation due to excess nutrients, 4) Improve soil moisture efficiency, 5) Reduce the concentration of salts and other chemicals from saline seeps, 6) Reduce plant pest pressures, 7) Provide feed and forage for domestic livestock, and 8) Provide food and cover habitat for wildlife, including pollinator forage, and nesting. This practice payment is provided to the producer for the time needed to plan and implement the logistics of changing the rotation to effectively implement a conservation crop rotation on a typical 200 acre cropland farm. No foregone income. Cost represents typical situations for conventional and organic producers.

Before Situation:

The rotation consists primarily of low residue producing row crops. Fields range from nearly flat to C and D slopes. Erosion, soil quality, and pest management are the primary concerns.

After Situation:

A rotation is established that provides additional high residue and/or perennial crops that may treat one or more of the following purposes: reduce sheet, rill and wind erosion, maintain or increase soil health and organic matter content, reduce water quality degradation due to excess nutrients, improve soil moisture efficiency, reduce the concentration of salts and other chemicals from saline seeps, reduce plant pest pressures, provide feed and forage for domestic livestock, or provide food and cover habitat for wildlife, including pollinator forage, and nesting.

Feature Measure: Area planted

Scenario Unit:: Acre

Scenario Typical Size: 200.0

Scenario Total Cost: \$1,163.40

Scenario Cost/Unit: \$5.82

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	30	\$1,163.40

Practice: 329 - Residue and Tillage Management, No-Till

Scenario #1 - No-Till/Strip-Till

Scenario Description:

This practice typically involves conversion from a clean-tilled (conventional tilled) system to no-till or strip-till system on 100 acres of cropland. This involves managing the amount, orientation and distribution of crop and other plant residue on the soil surface year round while limiting soil-disturbing activities used to establish and harvest crops. The practice is used to reduce sheet and rill erosion, reduce wind erosion, improve soil quality, reduce CO2 losses from the soil, reduce energy use, increase plant available moisture and provide food and escape cover for wildlife. The no-till/strip-till system includes non-tillage types of weed control and may also include a period of no till fallow. System is applicable in both irrigated and non-irrigated fields of organic and non-organic operations.

Before Situation:

Row crops or small grains are grown and harvested. Full width tillage is performed prior to planting and weed control during crop production is typically cultivation and chemical application. Fields are disked immediately following harvest, with additional operations in some fields to facilitate drainage, seedbed preparation or additional weed control. Residue amounts after tillage operations average 10% or less, resulting in bare soil being exposed to wind erosion and/or intense rainfall. Any crop residue that is present degrades and sediment/nutrient runoff from fields increases during rainfall events. Sheet and rill erosion occurs with visible rills by spring. Soil health (soil organic matter) declines over time as a result of tillage practices, low residue, and long periods of bare soil. This system will typically have a negative Soil Conditioning Index (SCI) and a high Soil Tillage Intensity Rating (STIR).

After Situation:

The Implementation Requirements for 329 Residue Management, No Till is prepared and installed. Managing crop residue on the surface of a field (typical 100 acre) year around according to the 329 practice plan while limiting soil disturbing activities to those which place nutrients, and plant crops that meet the minimum criteria in the 329 practice standard. All crops are seeded/planted with a no-till drill or no-till/strip-till planter, which minimizes soil disturbance while establishing good seed-soil contact. All residues are to be maintained on the soil surface in a uniform distribution over the entire field and not burned or removed. Crop residues provide soil surface cover throughout the year. Runoff and erosion are reduced and no rills are visible on the soil surface. Wind erosion is reduced by standing residues and surface cover. Over time, soil health is improved due to the additional biomass (crop residues), ground cover, and soil infiltration. Crop residues and/or cover crop residues left on the soil surface may maximize weed control by increasing allelopathic and mulching effect, and provides cover for wildlife. The practice would require reducing soil disturbance and erosion and increasing biomass returned to the soil in sufficient amounts to achieve increased SCI and decreased STIR.

Feature Measure: Area planted

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$2,050.50

Scenario Cost/Unit: \$20.51

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	50	\$1,089.00
Seeding Operation, No Till/Strip Till Planter	1230	No Till/Strip Till row planters for seeding. Includes all costs for equipment, power unit, and labor.	Acre	\$19.23	50	\$961.50



Practice: 330 - Contour Farming

Scenario #3 - Contour Farming

Scenario Description:

This scenario meets the specifications of the NRCS Contour Farming Standard. This scenario applies to fields greater than 5 acres. Payment reflects the extra labor and initial supervision costs in laying out and implementing contour farming. Annual erosion rates for the rotation exceeds tolerance levels. Excessive runoff leads to sedimentation of waterways

Before Situation:

The typical field size in this geographical region for this scenario is 30 acres. The field slope averages 6% while the slope length averages 160 feet. All farming operations on this cropland field including disking, bedding, planting, and cultivation are performed generally up and down the slope. Annual erosion rates for the rotation exceeds tolerance levels. Excessive runoff leads to sedimentation of waterways.

After Situation:

Implementation Requirements are prepared according to 330 Contour Farming and implemented. This practice is installed on the entire field. A survey is completed by trained and certified Federal, State, local personnel or consultant to determine and "stake" contour row arrangement. Permanent row markers are established to ensure that this practice is maintained for the life of this practice. All field operations including: disking, bedding, planting, and cultivation are performed on the contour which is near perpendicular to the field slope. The farm manager is initially on site to ensure that equipment operator is properly following contour methods. Soil erosion rates are reduced by nearly half and may be below tolerance depending on the rotation. Likewise, sedimentation has be significantly reduced.

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 30.0

Scenario Total Cost: \$249.01

Scenario Cost/Unit: \$8.30

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	1	\$22.22
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	5	\$110.45
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	3	\$116.34

Practice: 332 - Contour Buffer Strips

Scenario #12 - Native Species, Foregone Income (Organic and Non-organic)

Scenario Description:

Narrow strips of permanent, herbaceous vegetative cover established around the hill slope and alternated down the slope with wider cropped strips in between that are organically or non-organically farmed on the contour. This practice applies to all cropland. Practice includes seedbed prep and planting of native species. The area of the contour grass strip is taken out of production.

Before Situation:

The NRCS water erosion prediction software indicates that there is a significant amount of sheet and rill erosion and/or a significant amount of sediment potentially delivered to the downslope edge of the field. A secondary concern is that there may not be enough wildlife/pollinator habitat, food source or refugia in the field or farm.

After Situation:

Native grasses, legumes and forbs will be established in strips in the field to meet the Contour buffer Strips (332) criteria, resource needs, and producer objectives. Minimum widths shall be based on NRCS local design criteria specific to the purpose for installing the practice. Native species shall be selected that do not function as a host for diseases of a field crop and have physical characteristics necessary to control water erosion to tolerable levels in the cropped area of the field.

Feature Measure: number of acres

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$427.17

Scenario Cost/Unit: \$427.17

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.5	\$207.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.5	\$207.50
FI, Hay, General Grass	2122	General Grass Hay is Primary Land Use	Ton	\$42.52	-2	(\$85.04)
Materials						
One Species, Warm Season, Native Perennial Grass	2322	Native, warm season perennial grass. Includes material and shipping only.	Acre	\$69.06	1	\$69.06

Practice: 332 - Contour Buffer Strips

Scenario #13 - Introduced Species, Foregone Income (Organic and Non-Organic)

Scenario Description:

Narrow strips of permanent, herbaceous vegetative cover established around the hill slope and alternated down the slope with wider cropped strips in between that are farmed on the contour. This practice applies to all cropland. Practice includes seedbed prep and planting of native species. The area of the contour grass strip is taken out of production. This applies to both organic and non-organic.

Before Situation:

The NRCS water erosion prediction software indicates that there is a significant amount of sheet and rill erosion and/or a significant amount of sediment potentially delivered to the downslope edge of the field. A secondary concern is that there may not be enough wildlife/pollinator habitat, food source or refugia in the field or farm.

After Situation:

Introduced grasses and legumes will be established in strips in the field to meet the Contour buffer Strips (332) criteria, resource needs, and producer objectives. Minimum widths shall be based on NRCS local design criteria specific to the purpose for installing the practice. Introduced species shall be selected that do not function as a host for diseases of a field crop and have physical characteristics necessary to control water erosion to tolerable levels in the cropped area of the field.

Feature Measure: Number of acres

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$510.71

Scenario Cost/Unit: \$510.71

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.5	\$207.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.5	\$207.50
Materials						
Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.43	30	\$12.90
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.45	20	\$9.00
Sulfate of Potash	263	Approved for Organic Systems - Muriate of Potash	Pound	\$0.69	20	\$13.80
One Species, Cool Season, Introduced Perennial Grass	2313	Introduced, cool season perennial grass. Includes material and shipping only.	Acre	\$31.86	1	\$31.86

Practice: 332 - Contour Buffer Strips

Scenario #14 - Wildlife/Pollinator, Foregone Income (Organic and Non-Organic)

Scenario Description:

Narrow strips of permanent, herbaceous vegetative cover established around the hill slope and alternated down the slope with wider cropped strips in between that are farmed on the contour. This practice applies to all cropland. Practice includes seedbed prep and planting of mainly pollinator friendly species. The area of the field border is taken out of production. This applies to organic and no-organic.

Before Situation:

Water Erosion Calculator (e.g. RUSLE2) indicates that there is a significant amount of sheet and rill erosion and/or a significant amount of sediment potentially delivered to the downslope edge of the field. A secondary concern is that there may not be enough wildlife/pollinator habitat, food source or refugia in the field or farm.

After Situation:

Plant species will be established in strips in the field to meet the Contour buffer Strips (332) criteria, resource needs, producer objectives, and the targeted wildlife/pollinators necessary food and/or cover. Minimum widths shall be based on NRCS local design criteria specific to the purpose for installing the practice. Species selected shall meet the wildlife/pollinator habitat requirements of the state and be adapted to site; not function as a host for diseases of a field crop and; have physical characteristics necessary to control sheet and rill erosion to tolerable levels on the cropped area of the field.

Feature Measure: Number of acres

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$658.31

Scenario Cost/Unit: \$658.31

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Foregone Income						
Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.5	\$207.61
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.5	\$207.50
Materials						
Three plus Species Mix, Warm Season, Native Perennial	2327	Native, warm season perennial grass. Includes material and shipping only.	Acre	\$215.16	1	\$215.16

Practice: 338 - Prescribed Burning

Scenario #1 - Grassland, > 10 acres

Scenario Description:

Applying a prescribed burn according to designed burn plan and NRCS Prescribed Burning (338) standard and specifications in order to control undesirable species, improve wildlife habitat, improve plant productivity and/or quality, facilitate grazing distribution and maintain ecological processes. This scenario is based on a burn area consisting of herbaceous and/or low volatile woody fuel. Constructed firebreak cost is not included in cost of burn. Refer to Firebreak (394) standard and cost scenarios.

Before Situation:

Desirable plant composition is lacking due to reduced plant vigor, invasive species or improper livestock distribution.

After Situation:

Desirable plant composition is restored, plant vigor improved and invasive species reduced. Forage production and quality for livestock and /or wildlife is improved.

Feature Measure: Acres planned

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: \$1,247.69

Scenario Cost/Unit: \$31.19

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	4	\$88.88
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	4	\$115.36
Water tank, portable	1602	Portable water tank transported in a pick up truck. Typically with 200 gallon capacity includes tank with pump, hose and sprayer. Does not include the pickup truck. Equipment only.	Hour	\$2.47	4	\$9.88
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	16	\$565.76
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	8	\$310.24
Materials						
Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	\$4.32	5	\$21.60
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: 338 - Prescribed Burning

Scenario #2 - Grassland, Small acreage (&lt;=10 acres)

**Scenario Description:**

Applying a prescribed burn according to designed burn plan and NRCS Prescribed Burning (338) standard and specifications in order to control undesirable species, improve wildlife habitat, improve plant productivity and/or quality, facilitate grazing distribution and maintain ecological processes. This scenario is based on a burn area consisting of herbaceous and/or low volatile woody fuel. Constructed firebreak cost is not included in cost of burn. Refer to Firebreak (394) standard and cost scenarios.

**Before Situation:**

Desirable plant composition is lacking due to reduced plant vigor, invasive species or improper livestock distribution.

**After Situation:**

Desirable plant composition is restored, plant vigor improved and invasive species reduced. Forage production and quality for livestock and /or wildlife is improved.

Feature Measure: Acres planned

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$391.32

Scenario Cost/Unit: \$39.13

**Cost Details:**

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Acquisition of Technical Knowledge</b>						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
<b>Equipment Installation</b>						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	1	\$22.22
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	1	\$28.84
Water tank, portable	1602	Portable water tank transported in a pick up truck. Typically with 200 gallon capacity includes tank with pump, hose and sprayer. Does not include the pickup truck. Equipment only.	Hour	\$2.47	1	\$2.47
<b>Labor</b>						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	4	\$141.44
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78
<b>Materials</b>						
Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	\$4.32	5	\$21.60
<b>Mobilization</b>						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: 338 - Prescribed Burning

Scenario #3 - Woodland, >10 acres

Scenario Description:

Applying a prescribed burn according to designed burn plan and NRCS Prescribed Burning (338) standard and specifications. A woodland burn can consume debris or leaf litter under controlled conditions that otherwise could burn uncontrollably and devastatingly. Prior to burning, unit may need to be treated to reduce slash height and quantities. Burn should be cool enough to not cause mortality to residual stand but still reduce litter and debris and promote desired plant community. Constructed firebreak cost is not included in cost of burn. Refer to Firebreak (394) standard and cost scenarios.

Before Situation:

Light slash accumulation in a open forest stand. Leaf litter and debris throughout stand. Small seedlings of various quantities may be present. Desirable plant composition is lacking due to reduced plant vigor and/or invasive species are becoming established.

After Situation:

Litter, debris and slash are consumed, small seedlings may be killed during active burning. Residual larger trees have little to no scorching. Post treatment fire danger is significantly reduced and desired plant community is promoted/restored.

Feature Measure: Acres planned

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: \$3,283.22

Scenario Cost/Unit: \$82.08

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	8	\$177.76
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	8	\$230.72
Trailer, water tank	1598	Mobile 5,000 gal water tank mounted on a trailer. Equipment only. Does not include towing equipment.	Hour	\$20.13	8	\$161.04
Water tank, portable	1602	Portable water tank transported in a pick up truck. Typically with 200 gallon capacity includes tank with pump, hose and sprayer. Does not include the pickup truck. Equipment only.	Hour	\$2.47	8	\$19.76
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	48	\$1,697.28
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	16	\$620.48
Materials						
Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	\$4.32	10	\$43.20
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 338 - Prescribed Burning

Scenario #4 - Woodland, Small acreage (<=10 acres)

Scenario Description:

Applying a prescribed burn according to designed burn plan and NRCS Prescribed Burning (338) standard and specifications. A woodland burn can consume debris or leaf litter under controlled conditions that otherwise could burn uncontrollably and devastatingly. Prior to burning, unit may need to be treated to reduce slash height and quantities. Burn should be cool enough to not cause mortality to residual stand but still reduce litter and debris and promote desired plant community. Constructed firebreak cost is not included in cost of burn. Refer to Firebreak (394) standard and cost scenarios.

Before Situation:

Light slash accumulation in a open forest stand. Leaf litter and debris throughout stand. Small seedlings of various quantities may be present. Desirable plant composition is lacking due to reduced plant vigor and/or invasive species are becoming established.

After Situation:

Litter, debris and slash are consumed, small seedlings may be killed during active burning. Residual larger trees have little to no scorching. Post treatment fire danger is significantly reduced and desired plant community is promoted/restored.

Feature Measure: Acres planned

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$1,182.52

Scenario Cost/Unit: \$118.25

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	2	\$57.68
Water tank, portable	1602	Portable water tank transported in a pick up truck. Typically with 200 gallon capacity includes tank with pump, hose and sprayer. Does not include the pickup truck. Equipment only.	Hour	\$2.47	2	\$4.94
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	16	\$565.76
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	4	\$155.12
Materials						
Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	\$4.32	5	\$21.60
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93



Practice: 340 - Cover Crop

Scenario #1 - Cover Crop - Basic and organic/non-organic

Scenario Description:

Typically a small grain or legume (may also use forage sorghum, radishes, turnips, buckwheat, etc.) will be planted as a cover crop immediately after harvest of a row crop, and will be followed by a row crop that will utilize the residue as a mulch. This scenario assumes that seed will be planted with a drill. The cover crop should be allowed to generate as much biomass as possible, without delaying planting of the following crop. The cover crop will be terminated using an approved herbicide prior to planting the subsequent crop.

Before Situation:

Row crops such as corn, soybeans, or cotton are grown and harvested in mid-late fall. Fields are disked immediately following harvest, with rows in some fields being hipped for drainage. Residue amounts after harvest average 30% or less, resulting in bare soil being exposed to wind erosion and/or intense rainfall during the fall, winter, and early spring. Over the winter residue degrades and sediment/nutrient runoff from fields increases. Erosion exceeds soil loss tolerances. Runoff from the fields flows into streams, water courses or other water bodies causing degradation to the receiving waters. Soil health (soil organic matter) declines over time as a result of tillage practices, low residue crops, and long periods of bare soil.

After Situation:

Implementation Requirements according to Cover Crop (340) are prepared and implemented. Within 30 days after harvest of the row crop, fields are planted with a small grain or legume cover crop (may also use forage sorghum, radishes, turnips, buckwheat, etc.), typically rye or clover. The average field size is 40 acres. The cover crop is seeded with a drill. No additional fertilizer is applied with the cover crop. The cover crop provides soil cover by late fall, throughout the winter, and into the early spring. Runoff and erosion are reduced. Wind erosion is reduced by standing residues. The cover crop is terminated with an approved herbicide prior to spring planting as late as feasible to maximize plant biomass production. Over time, soil health is improved due to the additional biomass, ground cover, soil infiltration, and plant diversity introduced to the cropping system. Cover crop residues left on the surface may maximize weed control by increasing allelopathic and mulching effect.

Feature Measure: Area planted

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: \$3,351.20

Scenario Cost/Unit: \$83.78

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	40	\$250.40
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	40	\$871.20
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	40	\$699.20
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	\$38.26	40	\$1,530.40

Practice: 342 - Critical Area Planting

Scenario #1 - Vegetation-normal tillage (Organic and Non-Organic)

Scenario Description:

Establishment of permanent vegetation (Native and Introduced) on a site (both organic and non-organic) that is void or nearly void of vegetation due to a natural occurrence or a newly constructed conservation practice. Costs include seedbed preparation with typical tillage implements, grass/legume seed, companion crop, and fertilizer and lime with application.

Before Situation:

Areas that are void or nearly void of vegetation, resulting in bare soil being exposed to erosive processes. The exposed areas may be caused from recent natural occurrences (fire, flood, wind, etc.) or due to newly constructed conservation practices such as waterways, terraces, water and sediment basins or dams. The exposed areas will be subject to wind and water erosion that exceed soil loss tolerances. Runoff from the area flows into streams, water courses or other water bodies causing degradation to the receiving waters. The soil typically has a pH imbalance and low fertility.

After Situation:

Implementation Requirements are prepared and implemented according to the Critical Area Planting (342) standard. This typical 1.0 acre critical area is stabilized by applying fertilizer, lime and seed. Soil amendments will be incorporated at a depth of four to six inches to improve fertility and ensure establishment of permanent vegetative cover. The site will be stabilized, erosion reduced, and offsite damages reduced/eliminated.

Feature Measure: area seeded

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$188.32

Scenario Cost/Unit: \$188.32

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	2	\$22.74
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.75	1	\$6.75
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	\$7.85	1	\$7.85
Materials						
Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.43	30	\$12.90
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.45	60	\$27.00
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.35	60	\$21.00
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	\$18.22	2	\$36.44
One Species, Cool Season, Introduced Perennial Grass	2313	Introduced, cool season perennial grass. Includes material and shipping only.	Acre	\$31.86	1	\$31.86

Practice: 345 - Residue and Tillage Management, Reduced Till

Scenario #2 - Residue and Tillage Management, Reduced Till

Scenario Description:

Mulch-till is managing the amount, orientation and distribution of crop and other plant residue on the soil surface year round while limiting the soil-disturbing activities used to grow crops in systems where the entire field surface is tilled by the planter/drill or tillage tools prior to planting. This practice includes tillage methods commonly referred to as mulch tillage, vertical tillage, chiseling and disking, or the use of high disturbance drills without additional tillage. It applies to stubble mulching on summer-fallowed land, to tillage for annually planted crops, to tillage for planted crops and to tillage for planting perennial crops. All residue shall be uniformly spread or managed over the surface throughout the critical erosion period(s). All residue shall be uniformly distributed over the entire field and not burned or removed. These periods of intensive tillage have led to excessive soil loss, often above the soil loss tolerance (T), due to the loss of crop residue on the soil surface. The NRCS erosion prediction model(s) will be used to review the farming operations and determine the amount of surface residue to manage throughout the rotation to keep soil loss below T. The producer will adopt a reduced till system to meet one or more of the practice purposes.

Before Situation:

Crops such as corn, soybeans, small grains, or cotton are grown and harvested. Fields are tilled immediately following harvest, with rows in some fields being hipped for drainage. Residue amounts after harvest average 30% or less, resulting in bare soil being exposed to wind erosion and/or intense rainfall during the fall, winter, and early spring. Over the winter residue degrades and sediment/nutrient runoff from fields increase. Sheet, rill and wind erosion occurs. Spring tillage and seedbed preparation activities occur as early as possible in the late winter and early spring. Runoff from the fields flows into streams, water courses or other water bodies causing water quality degradation. Soil health (soil organic matter) declines over time as a result of tillage practices, low residue monocultures, and long periods of bare soil.

After Situation:

The Implementation Requirements are prepared following the criteria in the 345 Residue and Tillage Management, Reduced Till conservation practice standard. Reduced till applies to all cropland and other lands where crops are planted. This scenario includes the use of a reduce till systems and high disturbance drills, such as a hoe drill, air seeder, or no-till drill that disturbs a large percentage of soil surface during the planting operation. The residue that remains on the soil surface provides soil cover during late fall, throughout the winter, and into the early spring. Runoff and water/wind erosion are reduced and water quality improves. Over time, soil health is improved due to less tillage, the additional biomass, ground cover, soil infiltration, and plant diversity in the cropping system.

Feature Measure: Area planted

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$2,178.00

Scenario Cost/Unit: \$21.78

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	100	\$2,178.00

Practice: 351 - Well Decommissioning

Scenario #1 - Hand Dug

Scenario Description:

Seal and permanently close an inactive, abandoned, or unusable hand dug or shallow water well to prevent excess nutrients in surface and groundwater and to eliminate pesticides transported to surface and ground water. Well will be cleared of all equipment and materials. Residual water column must be treated with chlorine concentration of >50 ppm or according to local, State, Tribal, or Federal regulations.

Before Situation:

Hand dug or shallow well with a 30" diameter casing that is inactive, abandoned, or unusable.

After Situation:

Procedures and sealing materials shall conform to ASTM D5299 and be compatible with all local, State, Tribal, and Federal requirements. Backfill shall be placed and compacted in a manner that minimizes segregation and bulking to prevent surface subsidence. Typical well is hand dug. Associated practices: 342 Critical Area Seeding

Feature Measure: Length of well casing

Scenario Unit:: Foot

Scenario Typical Size: 20.0

Scenario Total Cost: \$1,245.64

Scenario Cost/Unit: \$62.28

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	2.73	\$14.63
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	1	\$57.17
Grout pump	1334	Grout pump with tremie pipe. Equipment and power unit costs. Labor not included.	Hour	\$15.31	1	\$15.31
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	1	\$28.30
Materials						
Grout, cement	1333	Cement grout meeting ASTM specifications for well sealing. Includes both neat-cement grout and bentonite gout mixtures. Includes materials, equipment and labor to place.	Cubic Yard	\$795.82	1	\$795.82
Chlorine	1335	Liquid chlorine bleach. Includes materials only.	Gallon	\$2.76	1	\$2.76
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 351 - Well Decommissioning

Scenario #3 - Drilled <=100 ft

Scenario Description:

Seal and permanently close an inactive, abandoned, or unusable water well to prevent excess nutrients in surface and groundwater and to eliminate pesticides transported to surface and ground water. Well will be cleared of all equipment and materials. Residual water column must be treated with chlorine concentration of >50 ppm or according to local, State, Tribal, or Federal regulations.

Before Situation:

Drilled well with a 6" diameter casing that is inactive, abandoned, or unusable.

After Situation:

Procedures and sealing materials shall conform to ASTM D5299 and be compatible with all local, State, Tribal, and Federal requirements. Backfill shall be placed and compacted in a manner that minimizes segregation and bulking to prevent surface subsidence. Typical length of well casing is 100 feet or less. Associated practices: 342 Critical Area Seeding

Feature Measure: Length of well casing

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,016.14

Scenario Cost/Unit: \$1,016.14

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	1	\$57.17
Grout pump	1334	Grout pump with tremie pipe. Equipment and power unit costs. Labor not included.	Hour	\$15.31	1	\$15.31
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	1	\$28.30
Materials						
Grout, cement	1333	Cement grout meeting ASTM specifications for well sealing. Includes both neat-cement grout and bentonite gout mixtures. Includes materials, equipment and labor to place.	Cubic Yard	\$795.82	0.73	\$580.95
Chlorine	1335	Liquid chlorine bleach. Includes materials only.	Gallon	\$2.76	1	\$2.76
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 359 - Waste Treatment Lagoon

Scenario #1 - Waste Treatment Lagoon

Scenario Description:

A waste treatment lagoon is a component of a waste management system that provides biological treatment of manure and other byproducts of agricultural operations by reducing the pollution potential. Resource concern addressed is water quality by reducing the pollution potential to surface and groundwater by treating and storing liquid waste. Earthen lagoon liners are addressed with another standard. Potential Associated Practices: Pond Sealing or Lining, Bentonite Sealant (521C), Pond Sealing or Lining, Compacted Clay Treatment (521D), Pond Sealing or Lining, Flexible Membrane (521A), Pond Sealing or Lining, Soil Dispersant (521B), Fence (382), Critical Area Planting (342), Nutrient Management (590), Waste Transfer (634), Heavy Use Area Protection (561), and Solid/Liquid Waste Separation Facility (632).

Before Situation:

Operator presently has a confined animal feeding operation without a waste management system adequate to handle the waste stream leaving the animal production facilities. Manure and/or other agricultural waste by-products are not being utilized or controlled in an environmentally safe manner. The wastes are either accumulating at the source, or are being transported but not properly utilized or disposed of. This situation poses an environmental threat of excessive nutrients, organics, and pathogens being transported into surface and groundwater resources.

After Situation:

A waste treatment lagoon constructed from on-site material provides an environmentally safe facility for storing manure and other agricultural waste by-products. This facility provides the landowner a means of storing and treating waste until it can be utilized in a proper manner in accordance with a nutrient management plan. Typical design size : Design Volume 439,440 ft3; 260' X 208' (top); 3:1 inside and outside side slopes; cut/fill ratio = 1.25; total depth = 13'

Feature Measure: Total Storage Volume

Scenario Unit:: Cubic Foot

Scenario Typical Size: 492,128.0

Scenario Total Cost: \$75,247.23

Scenario Cost/Unit: \$0.15

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	2778	\$11,278.68
Earthfill, Dumped and Spread	51	Earthfill, dumped and spread without compaction effort, includes equipment and labor	Cubic Yard	\$3.33	8101	\$26,976.33
Stripping and stockpiling, topsoil	1199	Stripping and stockpiling of topsoil adjacent to stripping area. Includes equipment and labor.	Cubic Yard	\$0.91	1389	\$1,263.99
Excavation, common earth, large equipment, 150 ft	1223	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 150 feet. Includes equipment and labor.	Cubic Yard	\$3.85	9125	\$35,131.25
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
Materials						
Structural steel tubing, 2" diameter	1120	Structural steel tubing, 2" diameter, 1/8" wall thickness, materials only	Foot	\$3.51	8	\$28.08
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	1	\$498.18

Practice: 360 - Waste Facility Closure

Scenario #1 - Poultry House Soil Remediation

Scenario Description:

Remediation of the soil in an abandoned poultry structures previously used for production or to store poultry waste (litter) on an earthen floor. Payment includes all activities associated with structure removal and soil remediation. The purpose of the practice is to address resource concerns related to water quality degradation due to excess nutrient and pathogens in ground and/or surface waters and air quality impacts from greenhouse gases, particulate matter and associated precursors, and objectionable odors.

Before Situation:

Rainfall and nutrients on the floor of the house pose a risk to surface water from contaminated runoff or to ground water from seepage into the underlying soils.

After Situation:

This scenario is based on a 40' wide x 400' long poultry house with 1 foot depth of nutrient laden soil to remediate (16,000 CF). Payment under this scenario includes activities associated with the soil remediation and structure removal. Soil remediation activities in this scenario include removing the first 6 inches of soil beneath the litter floor and mixing wood chips with the remaining 6 inches of soil. Nutrient level testing and field application of the removed soil shall be performed according to nutrient planning in conformance with Nutrient Management, Code 590. The soil will be remediated in-situ by mixing in wood chips, at a rate of 33% of the volume of remaining soil, for the purpose of nitrogen sequestration. Shaping and crowning of the soil material on the disturbed area and critical area seeding (342) will be done to provide drainage, complete the site remediation and establish vegetation. Operation and maintenance of the site will include nutrient testing the following year to determine if the nutrients in the mixed soil have been remediated and surface and ground water resource concerns have been addressed. In this scenario, samples at four (4) locations will be taken at 6, 12, 18 and 24 inches at the end of Year 1. Associated practices: Nutrient Management (590), Critical Area Planting (342).

Feature Measure: Square feet area remediated

Scenario Unit:: Square Foot

Scenario Typical Size: 16,000.0

Scenario Total Cost: \$11,408.11

Scenario Cost/Unit: \$0.71

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Dumped and Spread	51	Earthfill, dumped and spread without compaction effort, includes equipment and labor	Cubic Yard	\$3.33	380	\$1,265.40
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	25	\$2,900.25
Manure, compost, application	955	Loading, hauling and spreading manure/compost by ground equipment. Includes equipment, power unit and labor costs.	Hour	\$114.93	19	\$2,183.67
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	\$58.85	1	\$58.85
Aggregate, Wood Chips	1098	Includes materials, equipment and labor	Cubic Yard	\$21.43	82	\$1,757.26
Front End Loader, 185 HP	1619	Wheeled front end loader with horsepower range of 160 to 210. Equipment and power unit costs. Labor not included.	Hour	\$95.55	6	\$573.30
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	1	\$22.09
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	25	\$707.50
Materials						
Test, Soil Test, Standard	299	Includes materials, shipping, labor, and equipment costs.	Each	\$10.04	16	\$160.64
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	3	\$782.79
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	2	\$996.36

Practice: 360 - Waste Facility Closure

Scenario #2 - Feedlot Closure

Scenario Description:

Remediation of the soil on an abandoned feedlot previously used to feed animals on a bare earthen lot. Payment includes activities associated with soil remediation of the feedlot area. The purpose of the practice is to address resource concerns related to water quality degradation due to excess nutrient and pathogens in ground and/or surface waters and air quality impacts from greenhouse gases, particulate matter and associated precursors, and objectionable odors.

Before Situation:

The feedlot is abandoned. Vegetation has not been reestablished. Rainfall and nutrients on the bare earth feedlot pose a risk to surface water from contaminated runoff or to ground water from seepage into the underlying soils.

After Situation:

This scenario is based on a 3 acre feedlot. Surveys and testing have determined the manure pack and contaminated soil is 12 inches. Payment under this scenario includes only activities associated with the soil remediation. Soil remediation activities in this scenario include, but are not limited to, removing the nutrient enriched manure pack and soil, an average of 12 inches below the existing surface (130,680 CF). The excavated surface will be vegetated with a mix of salt tolerant plants in conformance with Critical Area Planting, Code 342. Nutrient level testing and field application of the removed soil shall be performed according to nutrient planning in conformance with Nutrient Management, Code 590. Shaping and crowning of the soil material on the disturbed area and critical area seeding will be done to provide drainage, complete the site remediation and establish vegetation. Operation and maintenance of the site will include nutrient testing the following year to determine if the soil has been remediated and surface and ground water resource concerns have been addressed. In this scenario, samples at four (4) locations will be taken at 6, 12, 18 and 24 inches at the end of Year 1. Associated practices: Nutrient Management (590), Critical Area Planting (342).

Feature Measure: Square feet of closure

Scenario Unit:: Square Foot

Scenario Typical Size: 130,680.0

Scenario Total Cost: \$37,371.07

Scenario Cost/Unit: \$0.29

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	40	\$4,640.40
Manure, compost, application	955	Loading, hauling and spreading manure/compost by ground equipment. Includes equipment, power unit and labor costs.	Hour	\$114.93	269	\$30,916.17
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	40	\$1,132.00
Materials						
Test, Soil Test, Standard	299	Includes materials, shipping, labor, and equipment costs.	Each	\$10.04	16	\$160.64
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86



Practice: 360 - Waste Facility Closure

Scenario #3 - Demolition of Concrete Waste Storage Structure, Walls >6 ft

Scenario Description:

Demolition of a concrete waste storage structure. Payment includes all materials and labor to demolish the structure, remove the concrete and earth fill the site. The scenario does not include payment for removal of manure as this would be accomplished as part of normal operation and maintenance when the facility was operating. A concrete structure left full of manure creates a toxic situation that would not be in compliance with normal operation and maintenance. The purpose of the practice is to address resource concerns related to water quality degradation due to excess nutrient and pathogens in ground and/or surface waters and air quality impacts from greenhouse gases, particulate matter and associated precursors, and objectionable odors.

Before Situation:

An existing concrete waste storage structure is no longer functioning correctly or is not being used for its intended purpose. It poses a safety hazard for humans and livestock and is a threat to environmental sustainability by the potential for impacts to water and air quality.

After Situation:

This scenario assumes a concrete waste storage structure, with top dimensions of 60 ft x 60 ft with 10 ft vertical walls. The walls are 8 inches thick and the concrete floor is 5 inches thick. The total structural storage volume equals 36,000 cubic feet. The total volume of concrete to be demolished is 3,580 cubic feet ([4 X 60 ft X 10 ft) X 8in /12 in/ft] + [60 ft X 60 ft X 5in /12 in/ft]+ [240 X 2 sqft / ft footing]). The volume of earthwork (earthfill and/or excavation, final grading) required is approximately 50% of the structural volume. The concrete will be demolished and hauled off-site for recycling or disposal. Structural removal, as necessary, may include the sealing or removal and disposal of waste transfer components and other appurtenances associated with closure of the facility. All waste material shall be land applied in accordance with Nutrient Management (590). Excavated areas will be filled in. The disturbed areas shall be vegetated in accordance with Critical Area Planting (342). Demolition of the concrete waste structure will address water quality degradation, air quality impacts and safety hazards by removing and properly utilizing the waste from the impoundment. The site will also become available for another use. Associated practices: Nutrient Management (590), Critical Area Planting (342)

Feature Measure: Square Feet of structure (plan view)

Scenario Unit:: Square Foot

Scenario Typical Size: 3,600.0

Scenario Total Cost: \$8,374.57

Scenario Cost/Unit: \$2.33

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	667	\$2,708.02
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	8	\$928.08
Demolition, concrete	1498	Demolition and disposal of reinforced concrete structures including slabs and walls. Includes labor and equipment.	Cubic Yard	\$10.81	133	\$1,437.73
Hauling, bulk, highway truck	1615	Hauling of bulk earthfill, rockfill, waste or debris. One-way travel distance using fully loaded highway dump trucks (typically 16 CY or 20 TN capacity). Includes equipment and labor for truck only. Does not include cost for loading truck.	Cubic Yard Mile	\$0.34	3990	\$1,356.60
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	8	\$226.40
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	4	\$1,043.72
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	1	\$498.18

Practice: 360 - Waste Facility Closure

Scenario #4 - Earthen Basin Closure with Sludge Removal

Scenario Description:

Decommissioning of an earthen liquid waste impoundment (embankment or excavated type). Payment includes the removal and spreading of accumulated sludge and the removal of contaminated soil at the soil/sludge interface, and equipment and labor required to close the impoundment in an environmentally safe manner. If present, the synthetic liner will be removed and properly disposed of. The purpose of the practice is to address resource concerns related to water quality degradation due to excess nutrient and pathogens in ground and/or surface waters and air quality impacts from greenhouse gases, particulate matter and associated precursors, and objectionable odors.

Before Situation:

An existing lagoon or earthen waste storage basin is no longer functioning correctly or is not being used for its intended purpose. It poses a safety hazard for humans and livestock and is a threat to environmental sustainability by the potential for impacts to water and air quality.

After Situation:

This scenario assumes a waste storage basin, with top dimensions of 110 ft x 110 ft, 8 ft total depth with 3:1 side slopes. The 8 ft total depth is the height of the earthen berm above the bottom of the basin for a total structural storage volume equal to 63,500 cubic feet. The volume of sludge and contaminated soil is 20% of the structural volume, 12,700 cu ft. Decommissioning of a liquid waste storage impoundment includes agitating, removing, and spreading liquid/slurry waste material, removing solid/sludge waste remaining in the bottom. All waste material shall be land applied in accordance with Nutrient Management (590). The volume of earthwork (earthfill and excavation) required to fill in the impoundment and perform final grading of the site is approximately 40% of the structural volume, 25,400. Structural removal, as necessary, may include the removal and disposal of waste transfer components and other appurtenances associated with closure of the facility. All inflow devices and associated appurtenances will be removed and properly disposed of. The embankment will be excavated and used for levelling or manipulating the site so not to impound surface water. The disturbed areas shall be vegetated in accordance with Critical Area Planting (342). Closure of the waste impoundment will address water quality degradation, air quality impacts and safety hazards by removing and properly utilizing the waste from the impoundment. The site will also become available for another use. Associated practices: Nutrient Management (590), Critical Area Planting (342)

Feature Measure: Cubic feet of sludge removed

Scenario Unit:: Cubic Foot

Scenario Typical Size: 12,700.0

Scenario Total Cost: \$12,695.43

Scenario Cost/Unit: \$1.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	249	\$535.35
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	588	\$2,387.28
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	12	\$1,392.12
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.72	940	\$1,616.80
Spreading, manure sludge	1633	Loading, hauling and spreading manure solids/sludge by ground equipment on nearby fields. Includes equipment, power unit and labor costs.	Cubic Foot	\$0.30	17056	\$5,116.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	12	\$263.76
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	12	\$339.60
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	4	\$1,043.72

Practice: 360 - Waste Facility Closure

Scenario #5 - Earthen Basin Closure no Sludge Removal

Scenario Description:

Decommissioning of an earthen liquid waste impoundment (embankment or excavated type) where there is no accumulated sludge that needs to be removed. Payment includes equipment and labor required to close the impoundment in an environmentally safe manner. If present, the synthetic liner will be removed and properly disposed of. The purpose of the practice is to address resource concerns related to water quality degradation due to excess nutrient and pathogens in ground and/or surface waters and air quality impacts from greenhouse gases, particulate matter and associated precursors, and objectionable odors.

Before Situation:

An existing lagoon or earthen waste storage basin is no longer functioning correctly or is not being used for its intended purpose. It poses a safety hazard for humans and livestock and is a threat to environmental sustainability by the potential for impacts to water and air quality.

After Situation:

This scenario assumes a waste storage basin, with top dimensions of 110 ft x 110 ft, 8 ft total depth with 3:1 side slopes. The 8 ft total depth is the height of the earthen berm above the bottom of the basin for a total structural storage volume equal to 63,500 cubic feet. The volume of sludge and contaminated soil is such that removal is not necessary. The volume of earthwork (excavation) required to fill in the impoundment and perform final grading of the site is approximately 40% of the total structural storage volume (63,500 \* 0.4 = 25,400). Earthfill is assumed to be 50% of the excavation amount. Structural removal, as necessary, may include the removal and disposal of waste transfer components and other appurtenances associated with closure of the facility. All inflow devices and associated appurtenances will be removed and properly disposed of. The embankment will be excavated and used for levelling or manipulating the site so not to impound surface water. The disturbed areas shall be vegetated in accordance with Critical Area Planting (342). Closure of the waste impoundment will address water quality degradation, air quality impacts and safety hazards by removing and properly utilizing the waste from the impoundment. The site will also become available for another use. Associated practices: Nutrient Management (590), Critical Area Planting (342)

Feature Measure: Cubic feet of berm removed

Scenario Unit:: Cubic Foot

Scenario Typical Size: 25,400.0

Scenario Total Cost: \$6,042.34

Scenario Cost/Unit: \$0.24

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	470	\$1,908.20
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	12	\$1,392.12
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.72	940	\$1,616.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	12	\$263.76
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	12	\$339.60
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: 360 - Waste Facility Closure

Scenario #6 - Conversion to Freshwater Structure with Sludge Removal

Scenario Description:

This practice scenario is for the conversion of an earthen liquid waste impoundment (embankment or excavated type) to a freshwater impoundment where the site needs retrofitting to serve as a freshwater impoundment. Payment includes removal and spreading of manure sludge and the removal of contaminated soil at the soil/sludge interface, construction/excavation of stormwater diversions and principle spillway, and the removal of the waste transfer pipe and appurtenances as required to convert the impoundment in an environmentally safe manner. If present, the synthetic liner will be removed and properly disposed of. The purpose of the practice is to address resource concerns related to water quality degradation due to excess nutrient and pathogens in ground and/or surface waters and air quality impacts from greenhouse gases, particulate matter and associated precursors, and objectionable odors.

Before Situation:

An existing lagoon or waste storage basin is no longer functioning correctly or is not being used for its intended purpose. It poses a safety hazard for humans and livestock and is a threat to environmentally sustainability by the potential for impacts to water and air quality.

After Situation:

This scenario assumes a waste storage basin, with top dimensions of 110 ft x 110 ft, 8 ft total depth with 3:1 side slopes. The 8 ft total depth is the height of the earthen berm above the bottom of the basin for a total structural storage volume equal to 63,500 cubic feet. The volume of sludge and contaminated soil is 20% of the structural volume, 12,700 cu ft. Decommissioning of a liquid waste storage impoundment includes agitating, removing, and spreading liquid/slurry waste material, removing solid/sludge waste remaining in the bottom. All waste material shall be land applied in accordance with Nutrient Management (590). The volume of earthwork (earthfill and excavation) required to change or remove the stormwater diversions and provide stable principal spillway for the impoundment is approximately 10% of the structural volume. All inflow devices and associated appurtenances will be removed and properly disposed of. The disturbed areas shall be vegetated in accordance with Critical Area Planting (342). Closure of the waste impoundment will address water quality degradation, air quality impacts and safety hazards by removing and properly utilizing the waste from the impoundment. The site will also become available for another use. Associated practices: Nutrient Management (590), Critical Area Planting (342)

Feature Measure: Cubic feet of sludge removed

Scenario Unit:: Cubic Foot

Scenario Typical Size: 12,700.0

Scenario Total Cost: \$8,100.88

Scenario Cost/Unit: \$0.64

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	235	\$505.25
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	12	\$1,392.12
Spreading, manure sludge	1633	Loading, hauling and spreading manure solids/sludge by ground equipment on nearby fields. Includes equipment, power unit and labor costs.	Cubic Foot	\$0.30	17056	\$5,116.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	12	\$263.76
Materials						
Test, Soil Test, Standard	299	Includes materials, shipping, labor, and equipment costs.	Each	\$10.04	4	\$40.16
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	3	\$782.79

Practice: 360 - Waste Facility Closure

Scenario #18 - Demolition of Concrete Waste Storage Structure, Walls <= 6 Foot

Scenario Description:

Demolition of a concrete waste storage structure. Payment includes all materials and labor to demolish the structure, remove the concrete and earth fill the site. The scenario does not include payment for removal of manure as this would be accomplished as part of normal operation and maintenance when the facility was operating. A concrete structure left full of manure creates a toxic situation that would not be in compliance with normal operation and maintenance. The purpose of the practice is to address resource concerns related to water quality degradation due to excess nutrient and pathogens in ground and/or surface waters and air quality impacts from greenhouse gases, particulate matter and associated precursors, and objectionable odors.

Before Situation:

An existing concrete waste storage structure is no longer functioning correctly or is not being used for its intended purpose. It poses a safety hazard for humans and livestock and is a threat to environmental sustainability by the potential for impacts to water and air quality.

After Situation:

This scenario assumes a concrete waste storage structure, with plan view dimensions of 40 ft x 16 ft with 5 ft vertical walls. The walls are 8 inches thick and the concrete floor is 5 inches thick. The total structural storage volume equals 3,200 cubic feet. The total volume of concrete to be demolished is 883 cubic feet. The volume of earthwork (earth fill and/or excavation, final grading) required is approximately 50% of the structural volume. The concrete will be demolished and hauled off-site for recycling or disposal. Structural removal, as necessary, may include the sealing or removal and disposal of waste transfer components and other appurtenances associated with closure of the facility. All waste material shall be land applied in accordance with Nutrient Management (590). Excavated areas will be filled in. The disturbed areas shall be vegetated in accordance with Critical Area Planting (342). Demolition of the concrete waste structure will address water quality degradation, air quality impacts and safety hazards by removing and properly utilizing the waste from the impoundment. The site will also become available for another use. Associated practices: Nutrient Management (590), Critical Area Planting (342).

Feature Measure: Square Feet of Structure (plan view)

Scenario Unit:: Square Foot

Scenario Typical Size: 640.0

Scenario Total Cost: \$3,198.77

Scenario Cost/Unit: \$5.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	60	\$243.60
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	8	\$928.08
Demolition, concrete	1498	Demolition and disposal of reinforced concrete structures including slabs and walls. Includes labor and equipment.	Cubic Yard	\$10.81	33	\$356.73
Hauling, bulk, highway truck	1615	Hauling of bulk earthfill, rockfill, waste or debris. One-way travel distance using fully loaded highway dump trucks (typically 16 CY or 20 TN capacity). Includes equipment and labor for truck only. Does not include cost for loading truck.	Cubic Yard Mile	\$0.34	660	\$224.40
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	8	\$226.40
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	4	\$1,043.72

Practice: 362 - Diversion

Scenario #1 - Small, <2 CY/FT

Scenario Description:

An earthen channel constructed across long slopes with supporting ridge on lower side, to divert runoff away from farmsteads, agricultural waste systems, gullies, critical erosion areas, construction areas or other sensitive areas. Outlet may be waterway, underground outlet, or other suitable outlet. Scenario is for diversions requiring less than 2 CY of excavation per foot of diversion. Channel may be level or gradient and ridge may be vegetated or farmed. The quantity of excavation and fill is balanced.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Scenario assumes a typical installation of a diversion 1000 feet long installed using a dozer. Diversion is 2.5' tall with 4' wide top width and slopes 3:1. Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Underground Outlet (620), Mulching (484), and Subsurface Drainage (606).

Feature Measure: Length of Diversion

Scenario Unit:: Foot

Scenario Typical Size: 1,000.0

Scenario Total Cost: \$3,569.45

Scenario Cost/Unit: \$3.57

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Stripping and stockpiling, topsoil	1199	Stripping and stockpiling of topsoil adjacent to stripping area. Includes equipment and labor.	Cubic Yard	\$0.91	700	\$637.00
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.55	1000	\$2,550.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 362 - Diversion

Scenario #2 - Medium, 2 - 2.9 CY/FT

Scenario Description:

An earthen channel constructed across long slopes with supporting ridge on lower side, to divert runoff away from farmsteads, agricultural waste systems, gullies, critical erosion areas, construction areas or other sensitive areas. Outlet may be waterway, underground outlet, or other suitable outlet. Scenario is for diversions requiring 2 CY to 2.9 CY of excavation per foot of diversion. Channel may be level or gradient and ridge may be vegetated or farmed. The quantity of excavation and fill is balanced.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Scenario assumes a typical installation of a diversion 1000 feet long installed using a dozer. Diversion is 4' tall with 4' wide top width and slopes 3:1. Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Underground Outlet (620), Mulching (484), and Subsurface Drainage (606).

Feature Measure: Length of Diversion

Scenario Unit:: Foot

Scenario Typical Size: 1,000.0

Scenario Total Cost: \$7,667.45

Scenario Cost/Unit: \$7.67

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Stripping and stockpiling, topsoil	1199	Stripping and stockpiling of topsoil adjacent to stripping area. Includes equipment and labor.	Cubic Yard	\$0.91	1000	\$910.00
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.55	2500	\$6,375.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 362 - Diversion

Scenario #3 - Large, >=3 CY/FT

Scenario Description:

An earthen channel constructed across long slopes with supporting ridge on lower side, to divert runoff away from farmsteads, agricultural waste systems, gullies, critical erosion areas, construction areas or other sensitive areas. Outlet may be waterway, underground outlet, or other suitable outlet. Scenario is for diversions requiring greater than or equal to 3 CY of excavation per foot of diversion. Channel may be level or gradient and ridge may be vegetated or farmed. The quantity of excavation and fill is balanced.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Scenario assumes a typical installation of a diversion 1000 feet long installed using a dozer. Diversion is 5' tall with 4' wide top width and slopes 3:1. Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Underground Outlet (620), Mulching (484), and Subsurface Drainage (606).

Feature Measure: Length of Diversion

Scenario Unit:: Foot

Scenario Typical Size: 1,000.0

Scenario Total Cost: \$10,399.45

Scenario Cost/Unit: \$10.40

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Stripping and stockpiling, topsoil	1199	Stripping and stockpiling of topsoil adjacent to stripping area. Includes equipment and labor.	Cubic Yard	\$0.91	1200	\$1,092.00
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.55	3500	\$8,925.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93



Practice: 367 - Roofs and Covers

Scenario #2 - Roof Structure, 33 feet to 60 feet Wide

Scenario Description:

A timber or steel framed roof structure with a wood sheathing, steel "sheet" or fabric-like roof. Scenario does not include foundation costs. Manure is stored as a liquid in basins, tanks, and as a solid on concrete and earthen surfaces. Excess precipitation can cause premature filling of storages or cause nutrients to leach from solid manure piles leading to uncontrolled runoff as well as odor issues. Associated practices include Waste Storage Facility (313), Animal Mortality Facility (316), Composting Facility (317), Obstruction Removal (500), Roof Runoff Structure (558), and Waste Treatment (629).

Before Situation:

Applicable where the exclusion of precipitation from an animal waste storage and/or treatment facility will improve of an existing or planned system. Manure is stored as a liquid in basins, tanks, and as a solid on concrete and earthen surfaces. Excess precipitation can cause premature filling of storages or cause nutrients to leach from solid manure piles leading to uncontrolled runoff as well as odor issues.

After Situation:

A timber or steel framed roof structure with a wood sheathing, steel "sheet" or fabric-like roof. Engineered and installed in accordance with appropriate building codes and permits. Typical size is 7,500 square feet and is over an approved animal waste management facility as a component of a CNMP. It is designed to prevent precipitation to allow proper management of animal waste streams (manure or compost streams), thus mitigating the negative factors from the "before practice implementation".

Feature Measure: Roof Area

Scenario Unit:: Square Foot

Scenario Typical Size: 7,500.0

Scenario Total Cost: \$63,782.98

Scenario Cost/Unit: \$8.50

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Roof, Post Frame Building, 30' to 60' wide	1676	Post Frame Building, no sides, ~ 30' to 60' width. Building sites with expected snow loads up to 30 lbs per square foot and wind exposure in semi protected areas (wooded or terrain with numerous closely spaced obstructions). Includes materials, shipping	Square Foot	\$8.46	7500	\$63,450.00
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 367 - Roofs and Covers

Scenario #3 - Roof Structure, more than 60 feet Wide

Scenario Description:

A timber or steel framed roof structure with a wood sheathing, steel "sheet" or fabric-like roof. Scenario does not include foundation costs. Manure is stored as a liquid in basins, tanks, and as a solid on concrete and earthen surfaces. Excess precipitation can cause premature filling of storages or cause nutrients to leach from solid manure piles leading to uncontrolled runoff as well as odor issues. Associated practices include Waste Storage Facility (313), Animal Mortality Facility (316), Composting Facility (317), Obstruction Removal (500), Roof Runoff Structure (558), and Waste Treatment (629).

Before Situation:

Applicable where the exclusion of precipitation from an animal waste storage and/or treatment facility will improve of an existing or planned system. Manure is stored as a liquid in basins, tanks, and as a solid on concrete and earthen surfaces. Excess precipitation can cause premature filling of storages or cause nutrients to leach from solid manure piles leading to uncontrolled runoff as well as odor issues.

After Situation:

A timber or steel framed roof structure with a wood sheathing, steel "sheet" or fabric-like roof. Engineered and installed in accordance with appropriate building codes and permits. Typical size is 24,000 square feet and is over an approved animal waste management facility as a component of a CNMP. It is designed to prevent precipitation to allow proper management of animal waste streams (manure or compost streams), thus mitigating the negative factors from the "before practice implementation".

Feature Measure: Roof Area

Scenario Unit:: Square Foot

Scenario Typical Size: 24,000.0

Scenario Total Cost: \$117,932.98

Scenario Cost/Unit: \$4.91

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Roof, Post Frame Building, greater than 60' wide	1673	Post Frame Building, no sides, - greater than 60' width. Building sites with expected snow loads up to 30 lbs per square foot and wind exposure in semi protected areas (wooded or terrain with numerous closely spaced obstructions). Includes materials, sh	Square Foot	\$4.90	24000	\$117,600.00
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #1 - Ventilation - Exhaust

Scenario Description:

Replacement of an exhaust fan with a more efficient exhaust fan. Payment includes fan, controls, wiring, associated appurtenances and labor to install.

Before Situation:

Inefficient ventilation in an agricultural building.

After Situation:

High-efficiency ventilation system which reduces energy use. The new ventilation equipment will provide suitable air quality and reduce overall power requirements (kW) compared to the existing ventilation system as evidenced in an energy audit. Associated practices/activities: may include 122-AgEMP - HQ, 670- Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,417.53

Scenario Cost/Unit: \$1,417.53

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	3	\$106.08
Materials						
Fan, exhaust, 36" High Efficiency	1185	36 inch high efficiency exhaust fan, controls, wiring, and associated appurtenances. Materials only.	Each	\$1,172.02	0.25	\$293.01
Fan, exhaust, 42" High Efficiency	1186	42 inch high efficiency exhaust fan, controls, wiring, and associated appurtenances. Materials only.	Each	\$1,614.15	0.25	\$403.54
Fan, exhaust, 48" High Efficiency	1187	48 inch high efficiency exhaust fan, controls, wiring, and associated appurtenances. Materials only.	Each	\$1,360.53	0.25	\$340.13
Fan, exhaust, 54" High Efficiency	1188	54 inch high efficiency exhaust fan, controls, wiring, and associated appurtenances. Materials only.	Each	\$1,099.11	0.25	\$274.78

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #2 - Ventilation - Horizontal Air Flow/Stir Fan

Scenario Description:

A system of fans are installed where none exist to create a horizontal air circulation pattern, and remove air stratification. The new system promotes efficient heat and moisture distribution. Payment includes fan controls, wiring, associated appurtenances and labor to install.

Before Situation:

Inefficient air circulation system in a greenhouse or livestock house

After Situation:

High-efficiency air circulation system which reduces energy use. In a typical 10,000 square foot greenhouse, 10 HAF fans are needed. The new equipment will provide suitable air quality and reduce overall power requirements (kW) compared to the existing system as evidenced in an energy audit. Associated practices/activities: may include 122-AgEMP - HQ, 670- Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 4.0

Scenario Total Cost: \$913.12

Scenario Cost/Unit: \$228.28

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	8	\$282.88
Materials						
Fan, HAF, 1/10 to 1/15 HP	1189	High efficiency Horizontal Air Flow (HAF) fan, controls, wiring, and associated appurtenances. Materials only.	Each	\$157.56	4	\$630.24

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #3 - Ventilation - Cool Cell, Evaporative Cooling System

Scenario Description:

A cool cell evaporative cooling system is installed in a livestock barn to reduce total ventilation requirements in hot weather. Scenario is applicable where there is an existing, inefficient cooling system/ventilation system in place that will be replaced by the cool cell. Payment includes all materials and labor to install the evaporative cooling system.

Before Situation:

Inefficient ventilation temperature control in a poultry or livestock house

After Situation:

A cool cell evaporative cooling system reduces energy use by allowing lower ventilation rates that will result in net energy savings. The new equipment will provide suitable air quality and reduce overall power requirements (kW) compared to the existing system as evidenced in an energy audit. Associated practices/activities: may include 122-AgEMP - HQ, 670- Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Square Foot

Scenario Unit:: Square Foot

Scenario Typical Size: 520.0

Scenario Total Cost: \$15,458.56

Scenario Cost/Unit: \$29.73

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	96	\$3,394.56
Materials						
Evaporative Cooling System, Large	2400	Energy efficient cooling systems installed in ventilated livestock confinement or greenhouses for temperature control. Complete system with cooling pads, aluminum distribution and end panels, 1/3 HP submersible sump pump and plumbing kit. Greater than 9	Square Foot	\$23.20	520	\$12,064.00

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #4 - Refrigeration - Plate Cooler

Scenario Description:

The installation of all stainless steel dual pass plate cooler, type 316 stainless steel. Payment includes plate cooler and labor to install.

Before Situation:

Inefficient milk cooling (minimal pre-cooling of milk before entering the bulk tank).

After Situation:

High-efficiency milk cooling system which reduces energy use. The new milk cooling equipment will pre-cool the milk and reduce overall power requirements (kW) compared to the existing milk cooling system (where most of the cooling was accomplished in the bulk tank) as evidenced in an energy audit. Associated practices/activities: may include 122-AgEMP - HQ, 670- Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$5,220.50

Scenario Cost/Unit: \$5,220.50

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	8	\$282.88
Materials						
Plate Cooler, <= 499 gal/hr capacity	1176	Stainless Steel, dual pass plate cooler with < 499 gallon/hour capacity. Includes materials and shipping only.	Each	\$4,937.62	1	\$4,937.62

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #5 - Refrigeration - Scroll Compressor

Scenario Description:

Install a new comparably sized scroll compressor, associated controls, wiring, and materials to retrofit an existing refrigeration system. A new condenser is not included in this typical scenario. Payment includes compressor, controls, wiring, appurtenances and labor to install.

Before Situation:

Inefficient reciprocating compressor as a key component of the refrigeration system used to cool milk. The compressor is a critical part of a milk cooling system, affecting milk quality, system reliability, and system efficiency.

After Situation:

A more efficient scroll compressor, which will reduce energy use, is evidenced by the energy audit. A comparably sized scroll compressor provides refrigeration capacity at a higher efficiency than a reciprocating compressor. Newer scroll compressor systems typically reduce electricity use by 15 to 25 percent compared to reciprocating compressors. Associated practices/activities: may include 122-AgEMP - HQ, 670- Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Horsepower

Scenario Unit:: Horsepower

Scenario Typical Size: 5.0

Scenario Total Cost: \$4,364.99

Scenario Cost/Unit: \$873.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	4	\$141.44
Materials						
Scroll Compressor - 5 HP	1183	Scroll compressor, 5 Horsepower, controls, wiring, and appurtenances. Materials only.	Each	\$4,223.55	1	\$4,223.55

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #6 - Refrigeration - Compressor Heat Recovery System

Scenario Description:

Install a new comparably sized compressor heat recovery unit. The unit includes insulated storage tanks with heat exchangers added to a refrigeration system. The system utilizes the heat extracted from the fluid (e.g. milk) that passes through the hot gas refrigerant line from the refrigeration system's compressors, to pre-heat water to approximately 110°F before it enters a conventional water heater. Energy savings comes from the reduced heating required in a water heater. Low ambient controls and/or condenser variable speed drives are part of the installation. The actual number of heat recovery units and their location will depend on the operating hours of the compressor and the configuration of the existing system. Payment includes all materials and appurtenances and labor to install.

Before Situation:

Inefficient use of heat extracted from the milk during the cooling process

After Situation:

A more efficient compressor heat recovery system is installed, which will reduce energy use, is evidenced by the energy audit. Associated practices/activities: may include 122-AgEMP - HQ, 670- Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$3,927.24

Scenario Cost/Unit: \$3,927.24

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	8	\$282.88
Materials						
Compressor heat recovery (CHR) unit, High Efficiency	1899	Compressor heat recovery (CHR) units (insulated storage tanks with heat exchangers) added to a refrigeration system, use the heat extracted from a warm fluid (e.g., milk) that passes through the hot gas refrigerant line from the refrigeration system's c	Each	\$3,644.36	1	\$3,644.36



Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #7 - Controller - Variable Speed Drive for <=1 HP Motor

Scenario Description:

Installation of a variable speed drive (VSD) for a =1 horsepower electric motor typically used in small dairy operations. Payment includes appurtenances, such as hook-ups, control panels, wiring, control blocks, filters, switches, pads, etc. and labor to install. Payment does not include the cost of the motor.

Before Situation:

The system is inefficient when a motor operates at constant speed to satisfy a load which varies as to flow rate and/or pressure requirements.

After Situation:

An on-farm energy audit has determined that energy use can be reduced through use of a VSD to control electric motors. After the VSD is applied, the motor speed can be adjusted to reduce power requirements and better match varied flow or pressure requirements. Associated practices/activities: may include 122-AgEMP - HQ, 670-Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Horsepower

Scenario Unit:: Horsepower

Scenario Typical Size: 1.0

Scenario Total Cost: \$861.81

Scenario Cost/Unit: \$861.81

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	8	\$282.88
Materials						
Variable Speed Drive, 1 HP	2347	Variable speed drive for 1 Horsepower electric motor. Does not include motor. Materials only.	Each	\$578.93	1	\$578.93

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #8 - Controller - Variable Speed Drive for >1 to <10 HP Motor

Scenario Description:

Installation of a variable speed drive (VSD) for a >1 to <10 horsepower electric motor. Payment includes appurtances, such as hook-ups, control panels, wiring, control blocks, filters, switches, pads, etc. and labor to install. Payment does not include the cost of the motor.

Before Situation:

The system is inefficient when a motor operates at constant speed to satisfy a load which varies as to flow rate and/or pressure requirements.

After Situation:

An on-farm energy audit has determined that energy use can be reduced through use of a VSD to control electric motors. After the VSD is applied, the motor speed can be adjusted to reduce power requirements and better match varied flow or pressure requirements. Associated practices/activities: may include 122-AgEMP - HQ, 670-Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Horsepower

Scenario Unit:: Horsepower

Scenario Typical Size: 5.0

Scenario Total Cost: \$3,384.63

Scenario Cost/Unit: \$676.93

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	8	\$282.88
Materials						
Variable Speed Drive, 5 HP	2348	Variable speed drive for 5 Horsepower electric motor. Does not include motor. Materials only.	Horsepower	\$620.35	5	\$3,101.75

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #9 - Controller - Variable Speed Drive for 10 to <50 HP Motor

Scenario Description:

Installation of a variable speed drive (VSD) for a >10 to <50 horsepower electric motor typically used in small dairy operations. Payment includes appurtances, such as hook-ups, control panels, wiring, control blocks, filters, switches, pads, etc. and labor to install. Payment does not include the cost of the motor.

Before Situation:

The system is inefficient when a motor operates at constant speed to satisfy a load which varies as to flow rate and/or pressure requirements.

After Situation:

An on-farm energy audit has determined that energy use can be reduced through use of a VSD to control electric motors. After the VSD is applied, the motor speed can be adjusted to reduce power requirements and better match varied flow or pressure requirements. Associated practices/activities: may include 122-AgEMP - HQ, 670-Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Horsepower

Scenario Unit:: Horsepower

Scenario Typical Size: 10.0

Scenario Total Cost: \$3,891.68

Scenario Cost/Unit: \$389.17

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	8	\$282.88
Materials						
Variable Speed Drive, 10 HP	1287	Variable speed drive for 10 Horsepower electric motor. Does not include motor. Materials only.	Horsepower	\$360.88	10	\$3,608.80

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #10 - Controller - Variable Speed Drive for >= 50 HP Motor

Scenario Description:

Installation of a variable speed drive (VSD) for a >= 50 horsepower electric motor used to drive a ventilation fan, irrigation pumps, vacuum pump, or similar equipment involved with agricultural production. Payment includes appurtenances, such as hook-ups, control panels, wiring, control blocks, filters, switches, pads, etc. and labor to install.

Before Situation:

The system is inefficient when a motor operates at constant speed to satisfy a load which varies as to flow rate and/or pressure requirements.

After Situation:

An on-farm energy audit has determined that energy use can be reduced through use of a VSD to control electric motors. After the VSD is applied, the motor speed can be adjusted to reduce power requirements and better match varied flow or pressure requirements. Associated practices/activities: may include 122-AgEMP - HQ, 670-Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Horsepower

Scenario Unit:: Horsepower

Scenario Typical Size: 100.0

Scenario Total Cost: \$13,390.88

Scenario Cost/Unit: \$133.91

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	8	\$282.88
Materials						
Variable Speed Drive, 100 HP	1289	Variable speed drive for 100 Horsepower electric motor. Does not include motor. Materials only.	Horsepower	\$131.08	100	\$13,108.00

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #11 - Controller - Multi Function Single Environmental Condition

Scenario Description:

The typical scenario consists of a multiple function automatic control system to manage a single environmental condition installed on an existing manually controlled agricultural building control system. Environmental conditions are defined by the following: lighting, temperature, humidity and/or air quality. The controller will control a combination of the following devices to achieve single or multiple environmental condition control: fans, lights, curtains, dampers, heaters, sprinklers (cooling), etc. Typical components may include any of the following: wiring, sensors, data logger, logic controller, communication link, software, switches, and relay. Payment includes materials and appurtenances and labor to install.

Before Situation:

A manually controlled system is existing in an agricultural facility that causes the inefficient use of energy, as evidenced by an on-farm energy audit.

After Situation:

An on-farm energy audit has determined that energy use can be reduced through use of an automatic controller that helps regulates the energy consumption of the existing system. Associated practices/activities may include: 122-AgEMP - HQ, 670- Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Each system

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,272.71

Scenario Cost/Unit: \$1,272.71

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Switches and Controls, temp sensors	1192	Temperature and soil moisture sensors installed as part of an electronic monitoring (with or without wireless telecommunications) commonly used to control pumps and irrigation systems	Each	\$655.75	1	\$655.75
Switches and Controls, programmable controller	1193	Programmable logic controller (with or without wireless telecommunications) commonly used to control pumps and irrigation systems	Each	\$167.45	1	\$167.45
Switches and Controls, Wi-Fi system and software	1194	Software with built-in cellular or Wi-Fi communication commonly used to control pumps and irrigation systems	Each	\$449.51	1	\$449.51

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #12 - Controller - Mult Function Multiple Environmental Condition

Scenario Description:

The typical scenario consists of a multiple function automatic control system to manage multiple environmental conditions installed on an existing manually controlled agricultural building control system. Environmental conditions are defined by the following: lighting, temperature, humidity and/or air quality. The controller will control a combination of the following devices to achieve single or multiple environmental condition control: fans, lights, curtains, dampers, heaters, sprinklers (cooling), etc. Typical components may include any of the following: wiring, sensors, data logger, logic controller, communication link, software, switches, and relay. Payment includes materials and appurtenances and labor to install.

Before Situation:

A manually controlled system is existing in an agricultural facility that causes the inefficient use of energy, as evidenced by an on-farm energy audit.

After Situation:

An on-farm energy audit has determined that energy use can be reduced through use of an automatic controller that helps regulates the energy consumption of the existing system. Associated practices/activities may include: 122-AgEMP - HQ, 670- Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Each system

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$3,460.25

Scenario Cost/Unit: \$3,460.25

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Switches and Controls, temp sensors	1192	Temperature and soil moisture sensors installed as part of an electronic monitoring (with or without wireless telecommunications) commonly used to control pumps and irrigation systems	Each	\$655.75	4	\$2,623.00
Switches and Controls, programmable controller	1193	Programmable logic controller (with or without wireless telecommunications) commonly used to control pumps and irrigation systems	Each	\$167.45	5	\$837.25

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #13 - Motor - <= 1 HP Electric Motor Upgrade

Scenario Description:

Replacement of an existing electric motor with a upgraded electric motor typically used to drive a ventilation fan, irrigation pumps, vacuum pump, or similar equipment involved with agricultural production. The upgraded electric motor will be the same size as the existing less efficient motor it is replacing. This scenario is for motors <=1 horsepower. Payment includes motor, appurtenances and labor to install.

Before Situation:

The system is inefficient with a standard efficiency motor.

After Situation:

An on-farm energy audit has determined that energy use can be reduced through use of a NEMA premium efficiency motor. Associated practices/activities may include: 122-AgEMP - HQ, 670- Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Horsepower

Scenario Unit:: Horsepower

Scenario Typical Size: 1.0

Scenario Total Cost: \$631.74

Scenario Cost/Unit: \$631.74

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	4	\$141.44
Materials						
Motor, electric, NEMA Premium, 1 HP	1169	Premium NEMA approved electric motor, 1 Horsepower and all required appurtenances. Includes materials and shipping only.	Each	\$490.30	1	\$490.30

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #14 - Motor - > 1 to <10 HP Electric Motor Upgrade

Scenario Description:

Replacement of an existing electric motor with a upgraded electric motor typically used to drive a ventilation fan, irrigation pumps, vacuum pump, or similar equipment involved with agricultural production. The upgraded electric motor will be the same size as the existing less efficient motor it is replacing. This scenario is for motors ranging from >1 horsepower to <10 horsepower. Payment includes motor, appurtenances and labor to install.

Before Situation:

The system is inefficient with a standard efficiency motor.

After Situation:

An on-farm energy audit has determined that energy use can be reduced through use of a NEMA premium efficiency motor. Associated practices/activities may include: 122-AgEMP - HQ, 670- Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Horsepower

Scenario Unit:: Horsepower

Scenario Typical Size: 5.0

Scenario Total Cost: \$941.79

Scenario Cost/Unit: \$188.36

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	4	\$141.44
Materials						
Motor, electric, NEMA Premium, 5 HP	1171	Premium NEMA approved electric motor, 5 Horsepower and all required appurtenances. Includes materials and shipping only.	Each	\$800.35	1	\$800.35



Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #15 - Motor - 10 - <50 HP Electric Motor Upgrade

Scenario Description:

Replacement of an existing electric motor with a upgraded electric motor typically used to drive a ventilation fan, irrigation pumps, vacuum pump, or similar equipment involved with agricultural production. The upgraded electric motor will be the same size as the existing less efficient motor it is replacing. This scenario is for motors ranging from 10 horsepower to <50 horsepower. Payment includes motor, appurtenances and labor to install.

Before Situation:

The system is inefficient with a standard efficiency motor.

After Situation:

An on-farm energy audit has determined that energy use can be reduced through use of a NEMA premium efficiency motor. Associated practices/activities may include: 122-AgEMP - HQ, 670- Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Horsepower

Scenario Unit:: Horsepower

Scenario Typical Size: 10.0

Scenario Total Cost: \$1,547.09

Scenario Cost/Unit: \$154.71

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	8	\$282.88
Materials						
Motor, electric, NEMA Premium, 10 HP	1172	Premium NEMA approved electric motor, 10 Horsepower and all required appurtenances. Includes materials and shipping only.	Each	\$1,264.21	1	\$1,264.21

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #16 - Motor - >= 50 HP Electric Motor Upgrade

Scenario Description:

Replacement of an existing electric motor with a upgraded electric motor typically used to drive a ventilation fan, irrigation pumps, vacuum pump, or similar equipment involved with agricultural production. The upgraded electric motor will be the same size as the existing less efficient motor it is replacing. This scenario is for motors of 50 horsepower or greater. Payment includes motor, appurtenances and labor to install.

Before Situation:

The system is inefficient with a standard efficiency motor.

After Situation:

An on-farm energy audit has determined that energy use can be reduced through use of a NEMA premium efficiency motor. Associated practices/activities may include: 122-AgEMP - HQ, 670- Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Horsepower

Scenario Unit:: Horsepower

Scenario Typical Size: 100.0

Scenario Total Cost: \$8,551.74

Scenario Cost/Unit: \$85.52

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	16	\$565.76
Materials						
Motor, electric, NEMA Premium, 100 HP	1174	Premium NEMA approved electric motor, 100 Horsepower and all required appurtenances. Includes materials and shipping only.	Each	\$7,985.98	1	\$7,985.98

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #17 - Motor - Variable Speed Electric (Split Phase)

Scenario Description:

Installation of a multi speed electric motor typically used to drive a ventilation fan in a livestock production house. Payment includes motor and labor to install. Control panel is not included. Refer to associated control panel scenarios as needed.

Before Situation:

The system is inefficient when a motor operates at constant speed to satisfy a load which varies as to flow rate and/or pressure requirements.

After Situation:

An on-farm energy audit has determined that energy use can be reduced through use of a multi speed electric motor. After the motor is installed, the motor speed can be adjusted to reduce power requirements and better match varied flow or pressure requirements. Associated practices/activities: may include 122-AgEMP - HQ, 670-Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Horsepower

Scenario Unit:: Horsepower

Scenario Typical Size: 1.0

Scenario Total Cost: \$244.40

Scenario Cost/Unit: \$244.40

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	3	\$106.08
Materials						
Motor, electric, Multi Speed, 10 HP	1154	Multi speed electric motor, 10 Horsepower maximum output and all required appurtenances. Materials only.	Horsepower	\$138.32	1	\$138.32

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #18 - Heating - Radiant Systems

Scenario Description:

Replace "pancake" Brood Heaters in a poultry house with Radiant Tube Heaters, or similar. Replacement will require the materials and labor to remove existing heating system, re-plumb gas lines, cables and winch system to retrofit new radiant tube heaters, and miscellaneous items to complete the installation. Alternate acceptable radiant heating systems can include radiant brooders and quad radiant systems as indicated in the energy audit. Payment includes materials and labor to install the new system.

Before Situation:

Inefficient heat distribution equipment, such as conventional "pancake" brood heaters. The Pancake brooder, mounted at a low installation height, primarily warms the air. They provide a one-to-two foot perimeter at desired temperatures around each brooder. A large number of brooders are required to cover a significant percent of floor space. As the warmed air naturally rises it loses effectiveness for poultry on the ground.

After Situation:

Energy use is reduced through installation of a more efficient heater. Radiant tube heaters primarily warm objects within a direct line of sight (similar to the sun or an open fire). Air temperature is of relatively little importance for a radiant heating systems to be effective. As a result, radiant systems are typically installed 5' or more above the floor level. This height extends the distribution of the radiant heat over a larger area than is possible with pancake style heaters. A roughly 16' diameter radiant heat zone heats over twice that of a conventional pancake brooder. The typical scenario consists of the replacement of 28 brood heaters with 6 radiant tube heaters. Associated practices/activities may include: 122-AgEMP - HQ, 670- Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Rated Heat Output

Scenario Unit:: 1,000 BTU/Hour

Scenario Typical Size: 125.0

Scenario Total Cost: \$1,582.18

Scenario Cost/Unit: \$12.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
Materials						
Heater, radiant tube	1163	Radiant tube heater rated at 125,000 BTU/hour. Materials only.	Each	\$1,511.46	1	\$1,511.46

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #19 - Heating - Building

Scenario Description:

Replace existing low efficiency heaters with new high efficiency heaters. High-efficiency heating systems include any heating unit with efficiency rating of 80%+ for fuel oil and 90%+ for natural gas and propane. Applications may be air heating/building environment and hydronic (boiler) heating for agricultural operations, including under bench, or root zone heating. An alternative to heater replacement might be the addition of climate control system and electronic temperature controls with +/- 1 degree F differential, to reduce the annual run time. Payment includes heater and labor to install.

Before Situation:

Buildings heated with low efficiency heaters or heaters without proper electronic climate controls

After Situation:

Higher efficiency heaters reduce energy consumption, energy costs, and GHG emissions. These replacement systems can be fueled by natural gas, propane, or fuel oil. Associated practices/activities: 122-AgEMP - HQ 670- Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Rated Heat Output

Scenario Unit:: 1,000 BTU/Hour

Scenario Typical Size: 750.0

Scenario Total Cost: \$9,745.76

Scenario Cost/Unit: \$12.99

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	16	\$565.76
Materials						
Heater, high efficiency	1165	Natural gas, propane, or fuel oil unit heater or boiler and venting materials. Based on input kBTU/hour. Includes materials and shipping only.	1,000 BTU/Hour	\$12.24	750	\$9,180.00

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #20 - Heating - Attic Heat Recovery Vents

Scenario Description:

Install actuated inlets or automatic latching gravity inlets that draw warmer, drier air from the attic to assist with moisture and heat control when ventilation fans are being operated in poultry houses and swine barns. In certain situations it may be necessary to also upgrade the ventilation system in addition to the vent upgrades. Other systems to transfer heat, as detailed in ASABE S612-compliant energy audit may also be used. Payment includes materials and labor to install.

Before Situation:

Heated buildings with attic spaces but no means to transfer heat between the heated space, attic, and ambient (outside) air when relative conditions allow for reduced energy use.

After Situation:

Attic vents or inlets allow dry warm air from the attic to circulated through out the building in a 40' x 500' poultry house. By using pre-warmed air from the attic less energy is needed for heating 122-AgEMP - HQ 670- Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Each inlet

Scenario Unit:: Each

Scenario Typical Size: 14.0

Scenario Total Cost: \$2,463.54

Scenario Cost/Unit: \$175.97

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	24	\$848.64
Materials						
Inlet, Attic Ceiling	2414	Poultry house attic air inlets. Includes materials only.	Each	\$115.35	14	\$1,614.90

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #21 - Grain Dryer

Scenario Description:

A more efficient replacement continuous dryer rated for the present dryer bushel/per hour capacity to treat existing energy concerns. The operation includes a microcomputer-based control system that adjusts the amount of time the crop remains in the dryer in order to achieve a consistent and accurate moisture content in the dried product. Alternate types of replacement dryers which reduce energy use are acceptable as defined by the energy audit. The upgraded grain dryer will be the same size as the existing less efficient grain dryer it is replacing. Payment includes materials and labor needed for the installation.

Before Situation:

Current grain dryer identified in the Agricultural Energy Management Plan is inefficient.

After Situation:

Energy use is reduced through installation of a more efficient continuous dryer that uses a microcomputer-based controller to reduce overdrying and total time of operation. The typical operation requires a rated capacity of 860 bushels per hour. Associated practices/activities may include: 122-AgEMP - HQ, 670- Lighting System Improvement, 672- Building Envelope Improvement, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Feature Measure: Rated capacity of the dryer

Scenario Unit:: Bushel per Hour

Scenario Typical Size: 860.0

Scenario Total Cost: \$84,455.32

Scenario Cost/Unit: \$98.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	16	\$565.76
Materials						
Grain dryer, Axial, 12'	1158	Grain dryer, 12 foot Axial with rated capacity of 460 bushels/hour. Materials only.	Bushel per Hour	\$102.83	172	\$17,686.76
Grain dryer, Axial, 16'	1159	Grain dryer, 16 foot Axial with rated capacity of 600 bushels/hour. Materials only.	Bushel per Hour	\$88.78	172	\$15,270.16
Grain dryer, Centrifugal, 20'	1160	Grain dryer, 20 foot Centrifugal with rated capacity of 785 bushels/hour. Materials only.	Bushel per Hour	\$94.96	172	\$16,333.12
Grain dryer, Centrifugal, 24'	1161	Grain dryer, 24 foot Centrifugal with rated capacity of 860 bushels/hr. Materials only.	Bushel per Hour	\$101.70	172	\$17,492.40
Grain dryer, Axial 28'	1162	Grain dryer, 28 foot Axial with rated capacity of 990 bushels/hr. Materials only.	Bushel per Hour	\$99.46	172	\$17,107.12

Practice: 374 - FARMSTEAD ENERGY IMPROVEMENT

Scenario #67 - Controller - Single Function

Scenario Description:

The typical scenario consists of a single function controller with built in sensors for automatic on-off control that can be powered by a typical 120V electrical outlet. Controller does not typically include any communication link, data logging or wi-fi capabilities. The controller is typically installed on an existing manually controlled agricultural system including, but not limited to, building ventilation systems.

Before Situation:

A manually controlled system is existing in an agricultural facility that causes the inefficient use of energy, as evidenced by an on-farm energy audit.

After Situation:

An on-farm energy audit has determined that energy use can be reduced through use of an automatic controller that helps regulate the energy consumption of the existing system. Associated practices/activities may include: 128-AgEMP, 670 - Lighting System Improvement, 672 - Building envelope Improvement, and other activities within 374 - Farmstead Energy Improvement. The new controller is connected to the existing system and controls when the equipment is on or off. The resource concern of Inefficient Energy Use - Equipment and Facilities will be addressed with this practice by operating the equipment only when needed and therefore saving energy.

Feature Measure: each controller

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$135.95

Scenario Cost/Unit: \$135.95

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Materials						
Temperature Sensors	2462	Sensor used to measure and communicate temperature to the controlling mechanism in a refrigeration system. Includes materials and shipping only.	Each	\$91.99	1	\$91.99



Practice: 378 - Pond

Scenario #1 - Embankment, Tile Conduit

Scenario Description:

A low-hazard water impoundment structure on agricultural land to maintain or improve water quality and to provide water for livestock, fish and wildlife, recreation, fire control, developing renewable energy systems and other related uses. An earthen embankment will be constructed with a principle spillway conduit and earthen auxiliary spillway, as designed. The resource concerns addressed include inadequate livestock water, excessive suspended sediment and turbidity in surface water, damage from sediment deposition, and reduced capacity of conveyances by sediment deposition.

Before Situation:

Area exists where water could naturally pool or run off to create a pond for livestock, wildlife, fire control, developing renewable energy systems, and other related uses, and to maintain or improve water quality. Failure of the embankment will not result in loss of life or damages of any kind.

After Situation:

The typical low hazard pond is constructed by excavating the pool area, constructing the auxiliary spillway, preparing the foundation as designed, and using 3100 cubic yards to create an embankment. The product of the storage times the effective height of the dam is less than 3,000. The effective height of the dam is 35 feet or less. The principle spillway is 6" corrugated plastic tubing. The earthen auxiliary spillway will be constructed as designed. Vegetation will be completed under critical area planting (342). Other associated practices include 382, 516, 521A, 533, 614, 587, 396.

Feature Measure: Embankment Volume

Scenario Unit:: Cubic Yard

Scenario Typical Size: 3,100.0

Scenario Total Cost: \$10,262.94

Scenario Cost/Unit: \$3.31

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	20	\$107.20
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	\$126.50	56	\$7,084.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	4	\$464.04
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	60	\$1,698.00
Materials						
Pipe, PVC, 6", SCH 40	980	Materials: - 6" - PVC - SCH 40 - ASTM D1785	Foot	\$6.08	20	\$121.60
Pipe, HDPE, 6", CPT, Single Wall	1242	Pipe, Corrugated Plastic Tubing, Single Wall, 6" diameter - ASTM F405. Material cost only.	Foot	\$1.13	80	\$90.40
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: 378 - Pond

Scenario #3 - Embankment, 8in-12in Pipe

Scenario Description:

A low-hazard water impoundment structure on agricultural land to maintain or improve water quality and to provide water for livestock, fish and wildlife, recreation, fire control, developing renewable energy systems and other related uses. An earthen embankment will be constructed with a principle spillway conduit and earthen auxiliary spillway, as designed. The resource concerns addressed include inadequate livestock water, excessive suspended sediment and turbidity in surface water, damage from sediment deposition, and reduced capacity of conveyances by sediment deposition.

Before Situation:

Area exists where water could naturally pool or run off to create a pond for livestock, wildlife, fire control, developing renewable energy systems, and other related uses, and to maintain or improve water quality. Failure of the embankment will not result in loss of life or damages of any kind.

After Situation:

The typical low hazard pond is constructed by excavating the pool area, constructing the auxiliary spillway, preparing the foundation as designed, and using 5000 cubic yards to create an embankment. The product of the storage times the effective height of the dam is less than 3,000. The effective height of the dam is 35 feet or less. The principle spillway is installed using an approved conduit material. The earthen auxiliary spillway will be constructed as designed. Vegetation will be completed under critical area planting (342). Other associated practices include 382, 516, 521A, 533, 614, 587, 396.

Feature Measure: Embankment Volume

Scenario Unit:: Cubic Yard

Scenario Typical Size: 8,000.0

Scenario Total Cost: \$36,584.64

Scenario Cost/Unit: \$4.57

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	29	\$155.44
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	\$126.50	12	\$1,518.00
Dozer, 200 HP	928	Track mounted Dozer with horsepower range of 160 to 250. Equipment and power unit costs. Labor not included.	Hour	\$198.02	124	\$24,554.48
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	8	\$928.08
Scraper, pull, 7 CY	1206	Pull type earthmoving scraper with 7 CY capacity. Does not include pulling equipment or labor. Add Tractor or Dozer, 160 HP typically required for single scraper.	Hour	\$16.33	124	\$2,024.92

Labor

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	144	\$4,075.20

Materials

Pipe, PVC, 10", SCH 80	1351	Materials: - 10" - PVC - SCH 80 - ASTM D1785	Foot	\$21.22	100	\$2,122.00
------------------------	------	--	------	---------	-----	------------

Mobilization

Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	3	\$782.79

Practice: 380 - Windbreak/Shelterbelt Establishment

Scenario #5 - 1 row windbreak, containerized tree planting stock

Scenario Description:

One row of containerized hardwood and/or conifer trees planted for wind protection, odor management, energy conservation, wildlife habitat, air quality, snow management or to provide a visual screen. This practice is typically applied on cropland at field edges, around homesteads or around confinement facilities. Payment includes materials, labor and equipment needed to hand plant the stock and foregone income for land removed from crop production where windbreak is installed. Site preparation is not included and must be implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Before Situation:

Agricultural field, livestock paddock, feedlot or farmstead needing protection from wind, additional wildlife food and cover, odor mitigation, visual screening or management of snow deposition

After Situation:

A windbreak of containerized trees is installed by hand planting trees 20 ft apart. Wind velocity suitably reduced to reduce soil erosion, energy loss or to manage snow deposition. Additional wildlife food and cover, mixing of odor plumes and visual screening.

Feature Measure: length of windbreak row(s)

Scenario Unit:: Foot

Scenario Typical Size: 500.0

Scenario Total Cost: \$404.17

Scenario Cost/Unit: \$0.81

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	1.5	\$18.06
---------------------------	------	--	------	---------	-----	---------

Foregone Income

Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.12	\$49.83
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.12	\$49.80

Labor

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	1.5	\$32.97
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1.5	\$58.17

Materials

Tree, hardwood, seedling or transplant, potted or B&B, 2-3 gal.	1532	Potted or balled and burlapped hardwood tree, 2-3 gal. Includes materials and shipping only.	Each	\$7.15	13	\$92.95
Tree, conifer, seedling or transplant, potted or B&B, 2-3 gal.	1537	Potted or balled and burlapped conifer tree, 2-3 gal. Includes materials and shipping only.	Each	\$6.97	12	\$83.64
Wire flags	1586	Small vinyl flags attached to wire stakes, typically, 36" in length, for marking tree rows	Each	\$0.09	25	\$2.25
Fertilizer, tree, slow release, premix packet or spike	1594	Slow release fertilizer to gradually apply nutrients over time for tree establishment. 2.0 Oz Packet (Premixed: 16-16-16 or 16-8-8 ) or Fertilizer Spike	Each	\$0.66	25	\$16.50

Practice: 380 - Windbreak/Shelterbelt Establishment

Scenario #6 - 1 row windbreak, containerized tree planting stock, temporary irrigation

Scenario Description:

One row of containerized hardwood and/or conifer trees planted for wind protection, odor management, energy conservation, wildlife habitat, air quality, snow management or to provide a visual screen. This practice is typically applied on cropland at field edges, around homesteads or around confinement facilities. Payment includes materials, labor and equipment needed to hand plant the stock, a temporary irrigation system to aid in establishment, and foregone income for land removed from crop production where windbreak is installed. Tree planting in an area where supplemental water is needed for successful establishment. Generally these areas would be considered arid or drought stricken, but other factors may contribute to requiring supplemental water. Site preparation is not included and must be implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Before Situation:

Agricultural field, livestock paddock, feedlot or farmstead needing protection from wind, additional wildlife food and cover, odor mitigation, visual screening or management of snow deposition. The area generally includes arid or droughty conditions that greatly reduce the success of tree survival.

After Situation:

A windbreak of containerized trees is installed by hand planting trees 20 ft apart. Wind velocity suitably reduced to reduce soil erosion, energy loss or to manage snow deposition. Additional wildlife food and cover, mixing of odor plumes and visual screening. Greatly improved success rate of the windbreak due to the supplemental water during establishment.

Feature Measure: length of windbreak row(s)

Scenario Unit:: Foot

Scenario Typical Size: 500.0

Scenario Total Cost: \$1,026.15

Scenario Cost/Unit: \$2.05

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	1.5	\$18.06
Foregone Income						
Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.12	\$49.83
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.12	\$49.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2.5	\$54.95
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1.5	\$58.17
Materials						
Tree, hardwood, seedling or transplant, potted or B&B, 2-3 gal.	1532	Potted or balled and burlapped hardwood tree, 2-3 gal. Includes materials and shipping only.	Each	\$7.15	13	\$92.95
Tree, conifer, seedling or transplant, potted or B&B, 2-3 gal.	1537	Potted or balled and burlapped conifer tree, 2-3 gal. Includes materials and shipping only.	Each	\$6.97	12	\$83.64
Wire flags	1586	Small vinyl flags attached to wire stakes, typically, 36" in length, for marking tree rows	Each	\$0.09	25	\$2.25
Fertilizer, tree, slow release, premix packet or spike	1594	Slow release fertilizer to gradually apply nutrients over time for tree establishment. 2.0 Oz Packet (Premixed: 16-16-16 or 16-8-8 ) or Fertilizer Spike	Each	\$0.66	25	\$16.50
Micro Irrigation, drip irrigation system, small scale	2170	An above ground, small scale, micro-irrigation system. Includes miniature emitters, tubes, or applicators placed along a water delivery line. Includes materials and shipping only.	Square Foot	\$0.12	5000	\$600.00

Practice: 380 - Windbreak/Shelterbelt Establishment

Scenario #7 - 1 row windbreak, containerized shrub planting stock

Scenario Description:

One row of containerized shrubs planted for wind protection, odor management, energy conservation, wildlife habitat, air quality, snow management or to provide a visual screen. This practice is typically applied on cropland at field edges, around homesteads or around confinement facilities. Payment includes materials, labor and equipment needed to hand plant the stock and foregone income for land removed from crop production where windbreak is installed. Site preparation is not included and must be implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Before Situation:

Agricultural field, livestock paddock, feedlot or farmstead needing protection from wind, additional wildlife food and cover, odor mitigation, visual screening or management of snow deposition

After Situation:

A windbreak of containerized shrubs is installed by hand planting shrubs 6 ft apart. Wind velocity suitably reduced to reduce soil erosion, energy loss or to manage snow deposition. Additional wildlife food and cover, mixing of odor plumes and visual screening.

Feature Measure: length of windbreak row(s)

Scenario Unit:: Foot

Scenario Typical Size: 500.0

Scenario Total Cost: \$1,280.11

Scenario Cost/Unit: \$2.56

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	5	\$60.20
Foregone Income						
Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.12	\$49.83
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.12	\$49.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	5	\$109.90
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	5	\$193.90
Materials						
Shrub, seedling or transplant, potted or B&B, 2-3 gal.	1527	Potted or balled and burlapped shrub, 2-3 gal. Includes materials and shipping only.	Each	\$8.97	84	\$753.48
Wire flags	1586	Small vinyl flags attached to wire stakes, typically, 36" in length, for marking tree rows	Each	\$0.09	84	\$7.56
Fertilizer, tree, slow release, premix packet or spike	1594	Slow release fertilizer to gradually apply nutrients over time for tree establishment. 2.0 Oz Packet (Premixed: 16-16-16 or 16-8-8 ) or Fertilizer Spike	Each	\$0.66	84	\$55.44

Practice: 380 - Windbreak/Shelterbelt Establishment

Scenario #8 - 1 row windbreak, containerized shrub planting stock, temporary irrigation

Scenario Description:

One row of containerized shrubs planted for wind protection, odor management, energy conservation, wildlife habitat, air quality, snow management or to provide a visual screen. This practice is typically applied on cropland at field edges, around homesteads or around confinement facilities. Payment includes materials, labor and equipment needed to hand plant the stock, a temporary irrigation system to aid in establishment, and foregone income for land removed from crop production where windbreak is installed. Tree planting in an area where supplemental water is needed for successful establishment. Generally these areas would be considered arid or drought stricken, but other factors may contribute to requiring supplemental water. Site preparation is not included and must be implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Before Situation:

Agricultural field, livestock paddock, feedlot or farmstead needing protection from wind, additional wildlife food and cover, odor mitigation, visual screening or management of snow deposition. The area generally includes arid or droughty conditions that greatly reduce the success of tree survival.

After Situation:

A windbreak of containerized shrubs is installed by hand planting shrubs 6 ft apart. Wind velocity suitably reduced to reduce soil erosion, energy loss or to manage snow deposition. Additional wildlife food and cover, mixing of odor plumes and visual screening. Greatly improved success rate of the windbreak due to the supplemental water during establishment.

Feature Measure: length of windbreak row(s)

Scenario Unit:: Foot

Scenario Typical Size: 500.0

Scenario Total Cost: \$1,902.09

Scenario Cost/Unit: \$3.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	5	\$60.20
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.12	\$49.83
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.12	\$49.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	6	\$131.88
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	5	\$193.90
Materials						
Shrub, seedling or transplant, potted or B&B, 2-3 gal.	1527	Potted or balled and burlapped shrub, 2-3 gal. Includes materials and shipping only.	Each	\$8.97	84	\$753.48
Wire flags	1586	Small vinyl flags attached to wire stakes, typically, 36" in length, for marking tree rows	Each	\$0.09	84	\$7.56
Fertilizer, tree, slow release, premix packet or spike	1594	Slow release fertilizer to gradually apply nutrients over time for tree establishment. 2.0 Oz Packet (Premixed: 16-16-16 or 16-8-8 ) or Fertilizer Spike	Each	\$0.66	84	\$55.44
Micro Irrigation, drip irrigation system, small scale	2170	An above ground, small scale, micro-irrigation system. Includes miniature emitters, tubes, or applicators placed along a water delivery line. Includes materials and shipping only.	Square Foot	\$0.12	5000	\$600.00

Practice: 380 - Windbreak/Shelterbelt Establishment

Scenario #9 - 1 row windbreak, bare-root tree seedling planting stock

Scenario Description:

One row of bare-root trees planted for wind protection, odor management, energy conservation, wildlife habitat, air quality, snow management or to provide a visual screen. This practice is typically applied on cropland at field edges, around homesteads or around confinement facilities. Payment includes materials, labor and equipment needed to machine the stock and foregone income for land removed from crop production where windbreak is installed. Site preparation is not included and must be implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Before Situation:

Agricultural field, livestock paddock, feedlot or farmstead needing protection from wind, additional wildlife food and cover, odor mitigation, visual screening or management of snow deposition

After Situation:

A windbreak of bare-root trees is installed by machine planting trees 10 ft apart. Wind velocity suitably reduced to reduce soil erosion, energy loss or to manage snow deposition. Additional wildlife food and cover, mixing of odor plumes and visual screening.

Feature Measure: length of windbreak row(s)

Scenario Unit:: Foot

Scenario Typical Size: 500.0

Scenario Total Cost: \$191.17

Scenario Cost/Unit: \$0.38

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	0.5	\$11.11
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	0.5	\$12.64
Mechanical tree planter	1600	Mechanical tree planter. Requires a pulling unit of either tractor or small dozer depending upon site conditions. Does not include labor.	Hour	\$6.84	0.5	\$3.42
Foregone Income						
Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.12	\$49.83
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.12	\$49.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	0.5	\$10.99
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	0.5	\$19.39
Materials						
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.59	50	\$29.50
Wire flags	1586	Small vinyl flags attached to wire stakes, typically, 36" in length, for marking tree rows	Each	\$0.09	50	\$4.50

Practice: 380 - Windbreak/Shelterbelt Establishment

Scenario #10 - 1 row windbreak, bare-root tree seedling planting stock, temporary irrigation

Scenario Description:

One row of bare-root trees planted for wind protection, odor management, energy conservation, wildlife habitat, air quality, snow management or to provide a visual screen. This practice is typically applied on cropland at field edges, around homesteads or around confinement facilities. Payment includes materials, labor and equipment needed to machine the stock, a temporary irrigation system to aid in establishment, and foregone income for land removed from crop production where windbreak is installed. Tree planting in an area where supplemental water is needed for successful establishment. Generally these areas would be considered arid or drought stricken, but other factors may contribute to requiring supplemental water. Site preparation is not included and must be implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Before Situation:

Agricultural field, livestock paddock, feedlot or farmstead needing protection from wind, additional wildlife food and cover, odor mitigation, visual screening or management of snow deposition. The area generally includes arid or droughty conditions that greatly reduce the success of tree survival.

After Situation:

A windbreak of bare-root trees is installed by machine planting trees 10 ft apart. Wind velocity suitably reduced to reduce soil erosion, energy loss or to manage snow deposition. Additional wildlife food and cover, mixing of odor plumes and visual screening. Greatly improved success rate of the windbreak due to the supplemental water during establishment.

Feature Measure: length of windbreak row(s)

Scenario Unit:: Foot

Scenario Typical Size: 500.0

Scenario Total Cost: \$273.15

Scenario Cost/Unit: \$0.55

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	0.5	\$11.11
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	0.5	\$12.64
Mechanical tree planter	1600	Mechanical tree planter. Requires a pulling unit of either tractor or small dozer depending upon site conditions. Does not include labor.	Hour	\$6.84	0.5	\$3.42
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.12	\$49.83
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.12	\$49.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	1.5	\$32.97
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	0.5	\$19.39
Materials						
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.59	50	\$29.50
Wire flags	1586	Small vinyl flags attached to wire stakes, typically, 36" in length, for marking tree rows	Each	\$0.09	50	\$4.50
Micro Irrigation, drip irrigation system, small scale	2170	An above ground, small scale, micro-irrigation system. Includes miniature emitters, tubes, or applicators placed along a water delivery line. Includes materials and shipping only.	Square Foot	\$0.12	500	\$60.00



Practice: 380 - Windbreak/Shelterbelt Establishment

Scenario #11 - 1 row windbreak, bare-root shrub seedling planting stock

Scenario Description:

One row of bare-root shrubs planted for wind protection, odor management, energy conservation, wildlife habitat, air quality, snow management or to provide a visual screen. This practice is typically applied on cropland at field edges, around homesteads or around confinement facilities. Payment includes materials, labor and equipment needed to machine the stock and foregone income for land removed from crop production where windbreak is installed. Site preparation is not included and must be implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Before Situation:

Agricultural field, livestock paddock, feedlot or farmstead needing protection from wind, additional wildlife food and cover, odor mitigation, visual screening or management of snow deposition

After Situation:

A windbreak of bare-root shrubs is installed by machine planting shrubs 5 ft apart. Wind velocity suitably reduced to reduce soil erosion, energy loss or to manage snow deposition. Additional wildlife food and cover, mixing of odor plumes and visual screening.

Feature Measure: length of windbreak row(s)

Scenario Unit:: Foot

Scenario Typical Size: 500.0

Scenario Total Cost: \$269.72

Scenario Cost/Unit: \$0.54

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	1	\$22.22
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	1	\$25.27
Mechanical tree planter	1600	Mechanical tree planter. Requires a pulling unit of either tractor or small dozer depending upon site conditions. Does not include labor.	Hour	\$6.84	1	\$6.84
Foregone Income						
Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.12	\$49.83
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.12	\$49.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	1	\$21.98
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78
Materials						
Shrub, seedling or transplant, bare root, 6-18"	1506	Bare root hardwood trees 6-18" tall. Includes materials and shipping only.	Each	\$0.46	100	\$46.00
Wire flags	1586	Small vinyl flags attached to wire stakes, typically, 36" in length, for marking tree rows	Each	\$0.09	100	\$9.00

Practice: 380 - Windbreak/Shelterbelt Establishment

Scenario #12 - 1 row windbreak, bare-root shrub seedling planting stock, temporary irrigation system

Scenario Description:

One row of bare-root shrubs planted for wind protection, odor management, energy conservation, wildlife habitat, air quality, snow management or to provide a visual screen. This practice is typically applied on cropland at field edges, around homesteads or around confinement facilities. Payment includes materials, labor and equipment needed to machine the stock, a temporary irrigation system to aid in establishment, and foregone income for land removed from crop production where windbreak is installed. Tree planting in an area where supplemental water is needed for successful establishment. Generally these areas would be considered arid or drought stricken, but other factors may contribute to requiring supplemental water. Site preparation is not included and must be implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Before Situation:

Agricultural field, livestock paddock, feedlot or farmstead needing protection from wind, additional wildlife food and cover, odor mitigation, visual screening or management of snow deposition. The area generally includes arid or droughty conditions that greatly reduce the success of tree survival.

After Situation:

A windbreak of bare-root shrubs is installed by machine planting shrubs 5 ft apart. Wind velocity suitably reduced to reduce soil erosion, energy loss or to manage snow deposition. Additional wildlife food and cover, mixing of odor plumes and visual screening. Greatly improved success rate of the windbreak due to the supplemental water during establishment.

Feature Measure: length of windbreak row(s)

Scenario Unit:: Foot

Scenario Typical Size: 500.0

Scenario Total Cost: \$351.70

Scenario Cost/Unit: \$0.70

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	1	\$22.22
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	1	\$25.27
Mechanical tree planter	1600	Mechanical tree planter. Requires a pulling unit of either tractor or small dozer depending upon site conditions. Does not include labor.	Hour	\$6.84	1	\$6.84
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.12	\$49.83
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.12	\$49.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78
Materials						
Shrub, seedling or transplant, bare root, 6-18"	1506	Bare root hardwood trees 6-18" tall. Includes materials and shipping only.	Each	\$0.46	100	\$46.00
Wire flags	1586	Small vinyl flags attached to wire stakes, typically, 36" in length, for marking tree rows	Each	\$0.09	100	\$9.00
Micro Irrigation, drip irrigation system, small scale	2170	An above ground, small scale, micro-irrigation system. Includes miniature emitters, tubes, or applicators placed along a water delivery line. Includes materials and shipping only.	Square Foot	\$0.12	500	\$60.00

Practice: 381 - Silvopasture Establishment

Scenario #13 - Bareroot Trees and Shrubs, with Tree Shelters

Scenario Description:

Bare-root trees and/or shrubs to be planted or interplanted into an existing pasture to establish woody plants in any area where they can be grown as part of an agroforestry application establishing a combination of trees or shrubs and compatible forages on the same acreage. Resource concerns addressed are degraded plant condition -- undesirable plant productivity and health, and inadequate structure and composition and degraded wildlife habitat. Payment includes bare-root seedlings and equipment and labor to plant. Foregone income is not included with this scenario. Site preparation is implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching.

Before Situation:

A pasture with suitable forage for livestock; however there is very little protection from the elements (sun, wind, etc.) available to the livestock. Additionally, there are no long-term wood products being produced.

After Situation:

The site will be prepared using Tree/Shrub Site Preparation (490), if needed, and then trees will be planted, providing shade and wind protection to livestock and wildlife, and, in time, producing a viable wood products crop. Per the conservation practice standard, livestock grazing will be deferred until the trees reach adequate height to resist damage, or use exclusion measures until the trees are established. All Resource Concerns listed above are addressed.

Feature Measure: each tree/shrub established

Scenario Unit:: Each

Scenario Typical Size: 4,360.0

Scenario Total Cost: \$14,880.54

Scenario Cost/Unit: \$3.41

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	4	\$88.88
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	4	\$101.08
Trailer, enclosed, small	1503	Small enclosed trailer (typically less than 30' in length) pulled by a pickup to transport materials and equipment. Truck not included.	Hour	\$7.12	4	\$28.48
Mechanical tree planter	1600	Mechanical tree planter. Requires a pulling unit of either tractor or small dozer depending upon site conditions. Does not include labor.	Hour	\$6.84	4	\$27.36
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	12	\$263.76
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	4	\$88.36
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	4	\$155.12
Materials						
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.59	4360	\$2,572.40
Tree shelter, solid tube type, 3-1/4" x 30"	1560	3-1/4" x 30" tree tube for protection from animal damage. Materials only.	Each	\$1.79	4360	\$7,804.40
Cable ties, plastic	1575	Plastic cable ties (typ. 8-12") to assist in securing items. Materials only.	Each	\$0.05	8720	\$436.00
Stakes, wood, 3/4" x 3/4" x 36"	1581	3/4" x 3/4" x 36" wood stakes to fasten items in place. Includes materials only.	Each	\$0.72	4360	\$3,139.20
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

**Practice:** 381 - Silvopasture Establishment

**Scenario #14 - Bareroot Trees and Shrubs**

**Scenario Description:**

Bare-root trees and/or shrubs to be planted or interplanted into an existing pasture to establish woody plants in any area where they can be grown as part of an agroforestry application establishing a combination of trees or shrubs and compatible forages on the same acreage. Resource concerns addressed are degraded plant condition -- undesirable plant productivity and health, and inadequate structure and composition and degraded wildlife habitat. Payment includes bare-root seedlings and equipment and labor to plant. Foregone income is not included with this scenario. Site preparation is implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching.

**Before Situation:**

A pasture with suitable forage for livestock; however there is very little protection from the elements (sun, wind, etc.) available to the livestock. Additionally, there are no long-term wood products being produced.

**After Situation:**

The site will be prepared using Tree/Shrub Site Preparation (490), if needed, and then trees will be planted, providing shade and wind protection to livestock and wildlife, and, in time, producing a viable wood products crop. Per the conservation practice standard, livestock grazing will be deferred until the trees reach adequate height to resist damage, or use exclusion measures until the trees are established. All Resource Concerns listed above are addressed.

**Feature Measure:** Per Tree/Shrub planted

**Scenario Unit::** Each

**Scenario Typical Size:** 4,360.0

**Scenario Total Cost:** \$3,325.10

**Scenario Cost/Unit:** \$0.76

**Cost Details:**

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	4	\$88.88
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	4	\$101.08
Trailer, enclosed, small	1503	Small enclosed trailer (typically less than 30' in length) pulled by a pickup to transport materials and equipment. Truck not included.	Hour	\$7.12	4	\$28.48
Mechanical tree planter	1600	Mechanical tree planter. Requires a pulling unit of either tractor or small dozer depending upon site conditions. Does not include labor.	Hour	\$6.84	4	\$27.36
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	4	\$87.92
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	4	\$88.36
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	4	\$155.12
<b>Materials</b>						
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.59	4360	\$2,572.40
<b>Mobilization</b>						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: 381 - Silvopasture Establishment

Scenario #15 - Container Trees and Shrubs (3 gallon) with Tree Shelters

**Scenario Description:**

Container trees and/or shrubs (potted) to be planted or interplanted into an existing pasture to establish woody plants in any area where they can be grown as part of an agroforestry application establishing a combination of trees or shrubs and compatible forages on the same acreage. Resource concerns addressed are degraded plant condition -- undesirable plant productivity and health, and inadequate structure and composition and degraded wildlife habitat. Payment includes container trees/shrubs, tree shelters, and equipment and labor to plant. Foregone income is not included with this scenario. Site preparation is implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching.

**Before Situation:**

A pasture with suitable forage for livestock; however there is very little protection from the elements (sun, wind, etc.) available to the livestock. Additionally, there are no long-term wood products being produced.

**After Situation:**

The site will be prepared using Tree/Shrub Site Preparation (490), if needed, and then trees will be planted, providing shade and wind protection to livestock and wildlife, and, in time, producing a viable wood products crop. Per the conservation practice standard, livestock grazing will be deferred until the trees reach adequate height to resist damage, or use exclusion measures until the trees are established. All Resource Concerns listed above are addressed.

**Feature Measure:** each tree/shrub

**Scenario Unit::** Each

**Scenario Typical Size:** 100.0

**Scenario Total Cost:** \$1,661.68

**Scenario Cost/Unit:** \$16.62

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	6	\$72.24
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	12	\$263.76
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	6	\$232.68
<b>Materials</b>						
Tree, hardwood, seedling or transplant, potted or B&B, 2-3 gal.	1532	Potted or balled and burlapped hardwood tree, 2-3 gal. Includes materials and shipping only.	Each	\$7.15	100	\$715.00
Tree shelter, solid tube type, 5" x 48"	1571	5" x 48" tree tube for protection from animal damage. Materials only.	Each	\$2.11	100	\$211.00
Cable ties, plastic	1575	Plastic cable ties (typ. 8-12") to assist in securing items. Materials only.	Each	\$0.05	200	\$10.00
Stakes, wood, 3/4" x 3/4" x 60"	1583	3/4" x 3/4" x 60" wood stakes to fasten items in place. Includes materials only.	Each	\$1.57	100	\$157.00

Practice: 381 - Silvopasture Establishment

Scenario #16 - Container Trees and Shrubs (3 gallon)

Scenario Description:

Container trees and/or shrubs (potted) to be planted or interplanted into an existing pasture to establish woody plants in any area where they can be grown as part of an agroforestry application establishing a combination of trees or shrubs and compatible forages on the same acreage. Resource concerns addressed are degraded plant condition -- undesirable plant productivity and health, and inadequate structure and composition and degraded wildlife habitat. Payment includes container trees/shrubs and equipment and labor to plant. Foregone income is not included with this scenario. Site preparation is implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching.

Before Situation:

A pasture with suitable forage for livestock; however there is very little protection from the elements (sun, wind, etc.) available to the livestock. Additionally, there are no long-term wood products being produced.

After Situation:

The site will be prepared using Tree/Shrub Site Preparation (490), if needed, and then trees will be planted, providing shade and wind protection to livestock and wildlife, and, in time, producing a viable wood products crop. Per the conservation practice standard, livestock grazing will be deferred until the trees reach adequate height to resist damage, or use exclusion measures until the trees are established. All Resource Concerns listed above are addressed.

Feature Measure: each tree/shrub

Scenario Unit:: Each

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,151.80

Scenario Cost/Unit: \$11.52

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	6	\$72.24
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	6	\$131.88
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	6	\$232.68
Materials						
Tree, hardwood, seedling or transplant, potted or B&B, 2-3 gal.	1532	Potted or balled and burlapped hardwood tree, 2-3 gal. Includes materials and shipping only.	Each	\$7.15	100	\$715.00

Practice: 382 - Fence

Scenario #2 - Permanent Barbed Wire Multi Strand

Scenario Description:

Scenario is for the establishment of permanent multi strand barbed wire fence for livestock.

Before Situation:

On grazing lands health and vigor are negatively impacted by poor grazing distribution, timing of grazing and inadequate rest and recovery periods. Water quality is impacted by increased erosion and runoff, cattle access to water bodies is uncontrolled. Reduced vegetative cover increases the opportunity for encroachment of noxious and invasive weeds. Fence installation conditions are for difficult sites such as poor access, steep slopes, rocky sites, dense brush, wet conditions etc.

After Situation:

Installation of fence will allow for implementation of grazing management that allows for an adequate rest and recovery period, protection of sensitive area, improved water quality, reduction of noxious and invasive weeds. Fence includes posts, wire, fasteners, gates, brace posts, etc... Fence will be installed with wildlife friendly considerations. Associated Practices: Prescribed Grazing, Pipeline, Water Well, Spring Development, Heavy Use Area, Pumping Plant, Watering Facility, Forage and Biomass Planting, Critical Area Planting, Access Control

Feature Measure: Length of Fence

Scenario Unit:: Foot

Scenario Typical Size: 1,320.0

Scenario Total Cost: \$2,797.53

Scenario Cost/Unit: \$2.12

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	\$7.46	12	\$89.52
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	12	\$266.64
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	12	\$303.24
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	24	\$527.52
Materials						
Wire, Barbed, Galvanized, 12.5 Gauge, 1,320' roll	1	Galvanized 12.5 gauge, 1,320' roll. Includes materials and shipping only.	Each	\$71.19	5	\$355.95
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	\$6.26	68	\$425.68
Post, Wood, CCA treated, 5" x 8'	11	Wood Post, End 5" X 8', CCA Treated. Includes materials and shipping only.	Each	\$11.26	4	\$45.04
Fence, Wire Assembly, Barbed Wire	30	Brace pins, battens, clips, staples. Includes materials and shipping only.	Foot	\$0.17	1320	\$224.40
Gate, Pipe, 16'	1059	6 rail tube gate, 16 gauge. Includes materials and shipping only.	Each	\$208.54	1	\$208.54
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00

Practice: 382 - Fence

Scenario #3 - Permanent High Tensile Electric 2-3 Strand

Scenario Description:

Scenario is for the installation of a permanent high tensile electric fence of either 2 or 3 strands. Fence will allow for implementation of a grazing management that allows for an adequate rest and recovery period, protection of sensitive area, improved water quality, reduction of noxious and invasive weeds. Constructed using fencing materials rather than a pre-manufactured gate.

Before Situation:

On grazing lands health and vigor are negatively impacted by poor grazing distribution, timing of grazing and inadequate rest and recovery periods. Water quality is impacted by increased erosion and runoff, livestock access to water bodies is uncontrolled. Reduced vegetative cover increases opportunity for encroachment of noxious and invasive weeds.

After Situation:

Installation of fence will allow for implementation of a rotational grazing plan that allows for an adequate rest and recovery period, protection of sensitive area, improved water quality, reduction of noxious and invasive weeds. This scenario consists of installing a permanent high tensile electric fence with 2-3 wires with wooden post of 50' centers, battens between the post, single H brace assemblies, energizer, and all appurtenances. Associated Practices: Prescribed Grazing, Pipeline, Water Well, Spring Development, Heavy Use Area, Pumping Plant, Watering Facility, Forage and Biomass Planting, Critical Area Planting, Access Control

Feature Measure: Length of Fence

Scenario Unit:: Foot

Scenario Typical Size: 1,320.0

Scenario Total Cost: \$2,024.36

Scenario Cost/Unit: \$1.53

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	\$7.46	6	\$44.76
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	6	\$133.32
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	6	\$151.62
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	12	\$263.76
Materials						
Wire, High Tensile, 12.5 Gauge, 4,000' roll	2	High Tensile 12.5 gauge, 4,000' roll. Includes materials and shipping only.	Each	\$114.08	2	\$228.16
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	\$6.26	29	\$181.54
Post, Wood, CCA treated, 5" x 8'	11	Wood Post, End 5" X 8', CCA Treated. Includes materials and shipping only.	Each	\$11.26	4	\$45.04
Electric, Energizer, 6 joule	29	Electric, Energizer, 6 joule for electric fence. Includes materials and shipping only.	Each	\$324.22	1	\$324.22
Fence, Wire Assembly, High Tensile, Electric, 2 Strand	33	Brace pins, springs, strainers, battens, clips, crimp sleeves, staples, insulators, wrap around sleeves. Includes materials and shipping only.	Foot	\$0.07	1320	\$92.40
Gate, Pipe, 16'	1059	6 rail tube gate, 16 gauge. Includes materials and shipping only.	Each	\$208.54	1	\$208.54
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00



Practice: 382 - Fence

Scenario #4 - Permanent High Tensile Electric Single Strand

Scenario Description:

Scenario is for the installation of a permanent high tensile electric single strand fence. Installation of fence will allow for implementation of a grazing management that allows for an adequate rest and recovery period, protection of sensitive area, improved water quality, reduction of noxious and invasive weeds.

Before Situation:

On grazing lands health and vigor are negatively impacted by poor grazing distribution, timing of grazing and inadequate rest and recovery periods. Water quality is impacted by increased erosion and runoff, cattle access to water bodies is uncontrolled. Reduced vegetative cover increases the opportunity for encroachment of noxious and invasive weeds.

After Situation:

Installation of fence will allow for implementation of grazing management that allows for an adequate rest and recovery period, protection of sensitive area, improved water quality, reduction of noxious and invasive weeds. Fence includes posts, wire, fasteners, gates, fence charger, etc. Fence will be installed with wildlife friendly considerations. Associated Practices: Prescribed Grazing, Pipeline, Water Well, Spring Development, Heavy Use Area, Pumping Plant, Watering Facility, Forage and Biomass Planting, Critical Area Planting, Access Control

Feature Measure: Length of Fence

Scenario Unit:: Foot

Scenario Typical Size: 1,320.0

Scenario Total Cost: \$1,375.79

Scenario Cost/Unit: \$1.04

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	\$7.46	3	\$22.38
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	3	\$66.66
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	3	\$75.81
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	6	\$131.88
Materials						
Wire, High Tensile, 12.5 Gauge, 4,000' roll	2	High Tensile 12.5 gauge, 4,000' roll. Includes materials and shipping only.	Each	\$114.08	1	\$114.08
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	\$6.26	24	\$150.24
Post, Wood, CCA treated, 5" x 8'	11	Wood Post, End 5" X 8', CCA Treated. Includes materials and shipping only.	Each	\$11.26	4	\$45.04
Electric, Ground Rods	20	Electric, Ground Rod for electric fence. Includes materials and shipping only.	Each	\$10.51	4	\$42.04
Electric, Ground Rod Clamps	21	Electric, Ground Rod Clamps for electric fence. Includes materials and shipping only.	Each	\$1.81	4	\$7.24
Electric, Lightening Diverter	22	Electric, Lightening diverter for electric fence. Includes materials and shipping only.	Each	\$10.27	1	\$10.27
Electric, Cutoff Switch	25	Electric, Cutoff Switch for electric fence. Includes materials and shipping only.	Each	\$8.53	1	\$8.53
Electric, Energizer, 6 joule	29	Electric, Energizer, 6 joule for electric fence. Includes materials and shipping only.	Each	\$324.22	1	\$324.22
Fence, Wire Assembly, High Tensile, Electric, 1 Strand	32	Brace pins, springs, strainers, battens, clips, crimp sleeves, staples, insulators, wrap around sleeves. Includes materials and shipping only.	Foot	\$0.02	1320	\$26.40
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00

Practice: 382 - Fence

Scenario #8 - Temporary/Portable Fence

Scenario Description:

Establishment of temporary or portable fence for livestock to facilitate a more intensive grazing system such as stockpiling or stripgrazing.

Before Situation:

This practice will be installed on grazing land. The resource concerns to be addressed by this practice are poor grazing distribution, inadequate water supply, and degraded site conditions leading to poor animal health.

After Situation:

Consists of installing a single strand polywire/polytape fence with step in/fiberglass posts on 50' centers, solar energizer, and all appurtenances. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated Practices: Prescribed Grazing, Pipeline, Water Well, Spring Development, Heavy Use Area, Pumping Plant, Watering Facility, Forage and Biomass Planting, Critical Area Planting, Access Control

Feature Measure: Length of Fence

Scenario Unit:: Foot

Scenario Typical Size: 1,320.0

Scenario Total Cost: \$627.85

Scenario Cost/Unit: \$0.48

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	1	\$22.22
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	1	\$21.98
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	\$47.61	2	\$95.22
Post, Fiberglass, 11/16" X 6'	19	Fiberglass line post, 11/16" diameter X 6' length. Includes materials and shipping only.	Each	\$6.50	26	\$169.00
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43

Practice: 382 - Fence

Scenario #10 - Temporary\_Portable for Small Livestock

Scenario Description:

Establishment of temporary or portable fence for small livestock to facilitate a more intensive grazing system such as stockpiling or stripgrazing.

Before Situation:

This practice will be installed on grazing land. The resource concerns to be addressed by this practice are poor grazing distribution, inadequate water supply, and degraded site conditions leading to poor animal health.

After Situation:

Consists of installing a prefabricated fence that has 10 horizontal twines; is 42 in. tall installed, and has plastic vertical struts every 12",solar energizer, and all appurtenances. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated Practices: Prescribed Grazing, Pipeline, Water Well, Spring Development, Heavy Use Area, Pumping Plant, Watering Facility, Forage and Biomass Planting, Critical Area Planting, Access Control

Feature Measure: Length of fence

Scenario Unit:: Foot

Scenario Typical Size: 1,320.0

Scenario Total Cost: \$1,894.83

Scenario Cost/Unit: \$1.44

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	1	\$22.22
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	1	\$21.98
Materials						
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43
Wire, Electric Netting, 42"	2382	Electric netting, 42" tall, 10 horizontal strands, vertical struts every 12 inches, single spike. Material only.	Foot	\$1.16	1320	\$1,531.20

Practice: 386 - Field Border

Scenario #14 - Field Border, Native Species, Forgone Income

Scenario Description:

A strip of permanent vegetation established at the edge or around the perimeter of an agricultural field. Practice includes seedbed prep and planting of native species. The area of the field border is taken out of production.

Before Situation:

Before practice conditions may vary widely. Fields may have erosion issues from wind or water, a field border may be needed to manage pest populations, protect soil and water quality, provide wildlife food and cover, provide pollinator habitat, or a field border may be used to increase carbon storage and improve air quality. Water quality, soil erosion and/or wildlife food and cover may all be primary resource concerns.

After Situation:

The 386 Implementation Requirements have been developed and applied for the site. This practice when applied around a field may support and connect other buffer practices within and between fields. Native grasses, legumes and forbs will be established in the field borders to the extent needed to meet the resource needs and producer objectives. Minimum field border widths shall be based on NRCS local design criteria specific to the purpose for installing the practice. Native species shall be selected that do not function as a host for diseases of a field crop and have physical characteristics necessary to control wind and water erosion to tolerable levels on the field border area.

Feature Measure: number of acres

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$540.06

Scenario Cost/Unit: \$540.06

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	3	\$34.11
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78

Foregone Income

FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.5	\$207.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.5	\$207.50

Materials

One Species, Warm Season, Native Perennial Grass	2322	Native, warm season perennial grass. Includes material and shipping only.	Acre	\$69.06	1	\$69.06
--	------	---	------	---------	---	---------

Practice: 386 - Field Border

Scenario #15 - Field Border, Introduced Species, Forgone Income

**Scenario Description:**

A strip of permanent vegetation established at the edge or around the perimeter of an agricultural field. Practice includes seedbed prep and planting of introduced species. The area of the field border is taken out of production.

**Before Situation:**

Before practice conditions may vary widely. Fields may have erosion issues from wind or water, a field border may be needed to manage pest populations, protect soil and water quality, provide wildlife food and cover, provide pollinator habitat, or a field border may be used to increase carbon storage and improve air quality. Water quality, soil erosion and/or wildlife food and cover may all be primary resource concerns.

**After Situation:**

The 386 Implementation Requirements have been developed and applied for the site. This practice when applied around a field may support and connect other buffer practices within and between fields. Introduced grasses and legumes will be established for the field border to the extent needed to meet the resource needs and producer objectives. Minimum field border widths shall be based on NRCS local design criteria specific to the purpose for installing the practice. Introduced species of grasses, legumes, forbs or shrubs shall be selected that are adapted to site, will not function as a host for diseases of a field crop and have physical characteristics necessary to control wind and water erosion to tolerable levels on the field border area.

Feature Measure: Number of acres

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$416.98

Scenario Cost/Unit: \$416.98

**Cost Details:**

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	1	\$11.37
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
<b>Forgone Income</b>						
Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.5	\$207.61
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.5	\$207.50
Fl, Hay, General Grass	2122	General Grass Hay is Primary Land Use	Ton	\$42.52	-2	(\$85.04)
<b>Materials</b>						
Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.43	30	\$12.90
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.45	20	\$9.00
One Species, Cool Season, Introduced Perennial Grass	2313	Introduced, cool season perennial grass. Includes material and shipping only.	Acre	\$31.86	1	\$31.86

Practice: 386 - Field Border

Scenario #16 - Field Border, Pollinator, Forgone Income

Scenario Description:

A strip of permanent vegetation established at the edge or around the perimeter of an agricultural field. Practice includes seedbed prep and planting of pollinator friendly herbaceous species. The area of the field border is taken out of production.

Before Situation:

Before practice conditions may vary widely. Fields may have erosion issues from wind or water, a field border may be needed to manage pest populations, protect soil and water quality, provide wildlife food and cover, provide pollinator habitat, or a field border may be used to increase carbon storage and improve air quality. Water quality, soil erosion and/or wildlife food and cover may all be primary resource concerns.

After Situation:

The 386 Implementation Requirements have been developed and applied for the site. This practice when applied around a field may support and connect other buffer practices within and between fields. Pollinator herbaceous plantings will provide species which flower throughout the growing season. This provides a source of nectar for adult pollinators and a diversity of herbaceous material for immature pollinator life stages and for nesting. Minimum field border widths shall be based on NRCS local design criteria specific to the purpose for installing the practice. Species selected shall meet the pollinator habitat requirements of the state and be adapted to site; not function as a host for diseases of a field crop and; have physical characteristics necessary to control wind and water erosion to tolerable levels on the field border area.

Feature Measure: Number of acres

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$597.45

Scenario Cost/Unit: \$597.45

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	3	\$34.11
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.5	\$207.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.5	\$207.50
Materials						
Untreated Conventional Seed, Pollinator Mix, Perennial Grass and Forb Mix	2503	Untreated conventional grass and legume pollinator mix. Includes material and shipping only.	Acre	\$126.45	1	\$126.45

Practice: 390 - Riparian Herbaceous Cover

Scenario #2 - Giant Canebreak Restoration

Scenario Description:

This scenario addresses inadequate herbaceous plant community function or diversity within the specific transitional zone between terrestrial and aquatic habitats in rangeland, pasture, cropland, and forest where natural seeding methods and/or management is unlikely to improve the plant community within a reasonable time period. This scenario applies to work not covered under NRCS Conservation Practice Forage and Biomass Planting (512), Critical Area Planting (342), Filter Strip (393), Restoration and Management of Rare and Declining Habitats (643), Streambank and Shoreline Protection ( 580), Vegetated Treatment Area (635), Wetland Enhancement ( 659), or Wetland Restoration (657). The typical setting for this scenario is usually a narrow strip between the aquatic and terrestrial habitats subject to intermittent flooding and saturated soils where the existing plant community has been disturbed, destroyed, or the species diversity is unable to provide proper function and/or adequate habitat. Giant Canebreak is planted using root balls. Where chemical control of undesirable vegetation, including invasives, is required to reduce competition for the desired plant community the Herbaceous Weed Control (315) practice should be used. Payment includes seedbed preparation, giant canebreak root balls and planting, and foregone income for land removed from production.

Before Situation:

The riparian zone, the specific area between terrestrial and aquatic habitats, is currently an undesirable or inadequate stand of perennial or annual vegetation and natural reseeding or vegetation management is unlikely to improve the plant community within a reasonable amount of time to adequately address streambank and/or shoreline stability, dissipate stream energy and trap sediment, improve and/or maintain water quality, and/or provide adequate habitat corridors, food and/or cover for fish, wildlife, pollinators, and/or livestock resource concern(s). Existing conditions often require suppression or eradication of current vegetation by conventional mechanical or chemical (Herbaceous Weed Control (315)) methods to ensure establishment success of the new planting.

After Situation:

The riparian zone, the transitional zone between the terrestrial and aquatic habitats, is established to an adapted, diverse vegetative plant community and is under close management to insure long term survival and ecological succession. The quality and quantity of the riparian zone components are managed to support the species that depend on it for habitat as well as the functions it performs for stabilizing the streambank and/or shoreline, dissipating stream energy and trapping sediment, and improving and/or maintaining water quality. These functions include: stream temperature moderation through shading, recruitment of non-woody organic matter, habitat for terrestrial insects and other riparian dependent species, streambank integrity, and filtration of contaminants from surface run-off into the stream.

Feature Measure: Acres of Riparian Herbaceous Cove

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,878.26

Scenario Cost/Unit: \$1,878.26

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	\$58.85	8	\$470.80
-------------------------------	-----	--	------	---------	---	----------

Foregone Income

FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.5	\$207.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.5	\$207.50

Labor

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
---------------	-----	--	------	---------	---	----------

Materials

One Species, Native Forb, Moderate/High Cost	2331	Native forb. Includes material and shipping only.	Acre	\$641.01	1	\$641.01
--	------	---	------	----------	---	----------

Mobilization

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50
-------------------------------	------	--	------	----------	---	----------

Practice: 390 - Riparian Herbaceous Cover

Scenario #3 - Native Grass

Scenario Description:

This scenario addresses inadequate herbaceous plant community function or diversity within the specific transitional zone between terrestrial and aquatic habitats in rangeland, pasture, cropland, and forest where natural seeding methods and/or management is unlikely to improve the plant community within a reasonable time period. This scenario applies to work not covered under NRCS Conservation Practice Forage and Biomass Planting (512), Critical Area Planting (342), Filter Strip (393), Restoration and Management of Rare and Declining Habitats (643), Streambank and Shoreline Protection ( 580), Vegetated Treatment Area (635), Wetland Enhancement ( 659), or Wetland Restoration (657). The typical setting for this scenario is usually a narrow strip between the aquatic and terrestrial habitats subject to intermittent flooding and saturated soils where the existing plant community has been disturbed, destroyed, or the species diversity is unable to provide proper function and/or adequate habitat. Native Grass is established by seeding. Where chemical control of undesirable vegetation, including invasives, is required to reduce competition for the desired plant community the Herbaceous Weed Control (315) practice should be used. Payment includes seedbed preparation, seed, and planting, and foregone income for land removed from production.

Before Situation:

The riparian zone, the specific area between terrestrial and aquatic habitats, is currently an undesirable or inadequate stand of perennial or annual vegetation and natural reseeding or vegetation management is unlikely to improve the plant community within a reasonable amount of time to adequately address streambank and/or shoreline stability, dissipate stream energy and trap sediment, improve and/or maintain water quality, and/or provide adequate habitat corridors, food and/or cover for fish, wildlife, pollinators, and/or livestock resource concern(s). Existing conditions often require suppression or eradication of current vegetation by conventional mechanical or chemical (Herbaceous Weed Control (315)) methods to ensure establishment success of the new planting.

After Situation:

The riparian zone, the transitional zone between the terrestrial and aquatic habitats, is established to an adapted, diverse vegetative plant community and is under close management to insure long term survival and ecological succession. The quality and quantity of the riparian zone components are managed to support the species that depend on it for habitat as well as the functions it performs for stabilizing the streambank and/or shoreline, dissipating stream energy and trapping sediment, and improving and/or maintaining water quality. These functions include: stream temperature moderation through shading, recruitment of non-woody organic matter, habitat for terrestrial insects and other riparian dependent species, streambank integrity, and filtration of contaminants from surface run-off into the stream.

Feature Measure: Acres of Riparian Herbaceous Cove

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$693.49

Scenario Cost/Unit: \$693.49

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78

Foregone Income

FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.5	\$207.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.5	\$207.50

Materials

Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	1	\$17.48
Three Species Mix, Cool Season, Native Perennial Grass	2316	Cool season, native grass mix. Includes material and shipping only.	Acre	\$140.78	1	\$140.78
Two Species Mix, Warm Season, Native Perennial Grass	2325	Native, warm season perennial grass. Includes material and shipping only.	Acre	\$92.08	1	\$92.08



Practice: 390 - Riparian Herbaceous Cover

Scenario #4 - Pollinator

Scenario Description:

This scenario addresses inadequate herbaceous plant community function or diversity within the specific transitional zone between terrestrial and aquatic habitats in rangeland, pasture, cropland, and forest where natural seeding methods and/or management is unlikely to improve the plant community within a reasonable time period. This scenario applies to work not covered under NRCS Conservation Practice Forage and Biomass Planting (512), Critical Area Planting (342), Filter Strip (393), Restoration and Management of Rare and Declining Habitats (643), Streambank and Shoreline Protection ( 580), Vegetated Treatment Area (635), Wetland Enhancement ( 659), or Wetland Restoration (657). The typical setting for this scenario is usually a narrow strip between the aquatic and terrestrial habitats subject to intermittent flooding and saturated soils where the existing plant community has been disturbed, destroyed, or the species diversity is unable to provide proper function and/or adequate habitat. Pollinator habitat is established by seeding. Where chemical control of undesirable vegetation, including invasives, is required to reduce competition for the desired plant community the Herbaceous Weed Control (315) practice should be used. Payment includes seedbed preparation, seed, and planting, and foregone income for land removed from production.

Before Situation:

The riparian zone, the specific area between terrestrial and aquatic habitats, is currently an undesirable or inadequate stand of perennial or annual vegetation and natural reseeding or vegetation management is unlikely to improve the plant community within a reasonable amount of time to adequately address streambank and/or shoreline stability, dissipate stream energy and trap sediment, improve and/or maintain water quality, and/or provide adequate habitat corridors, food and/or cover for fish, wildlife, pollinators, and/or livestock resource concern(s). Existing conditions often require suppression or eradication of current vegetation by conventional mechanical or chemical (Herbaceous Weed Control (315)) methods to ensure establishment success of the new planting. Soil quality may be reduced due to compaction and may require light tillage to prepare a proper seedbed.

After Situation:

The riparian zone, the transitional zone between the terrestrial and aquatic habitats, is established to an adapted, diverse vegetative plant community and is under close management to insure long term survival and ecological succession. The quality and quantity of the riparian zone components are managed to support the species that depend on it for habitat as well as the functions it performs for stabilizing the streambank and/or shoreline, dissipating stream energy and trapping sediment, and improving and/or maintaining water quality. These functions include: stream temperature moderation through shading, recruitment of non-woody organic matter, habitat for terrestrial insects and other riparian dependent species, streambank integrity, and filtration of contaminants from surface run-off into the stream.

Feature Measure: Acres of Riparian Herbaceous Cove

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$641.91

Scenario Cost/Unit: \$641.91

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.5	\$207.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.5	\$207.50
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	1	\$17.48
One Species, Native Forb, Low Cost	2329	Native forb. Includes material and shipping only.	Acre	\$181.28	1	\$181.28

Practice: 390 - Riparian Herbaceous Cover

Scenario #38 - Prairie Cordgrass Restoration

Scenario Description:

This scenario addresses inadequate herbaceous plant community function or diversity within the specific transitional zone between terrestrial and aquatic habitats in rangeland, pasture, cropland, and forest where natural seeding methods and/or management is unlikely to improve the plant community within a reasonable time period. This scenario applies to work not covered under NRCS Conservation Practice Forage and Biomass Planting (512), Critical Area Planting (342), Filter Strip (393), Restoration and Management of Rare and Declining Habitats (643), Streambank and Shoreline Protection ( 580), Vegetated Treatment Area (635), Wetland Enhancement ( 659), or Wetland Restoration (657). The typical setting for this scenario is usually a narrow strip between the aquatic and terrestrial habitats subject to intermittent flooding and saturated soils where the existing plant community has been disturbed, destroyed, or the species diversity is unable to provide proper function and/or adequate habitat. Prairie cordgrass (*Spartina pectinata*) is planted using plugs. Where chemical control of undesirable vegetation, including invasives, is required to reduce competition for the desired plant community the Herbaceous Weed Control (315) practice should be used. Payment includes seedbed preparation cordgrass plugs and planting, and foregone income for land removed from production.

Before Situation:

The riparian zone, the specific area between terrestrial and aquatic habitats, is currently an undesirable or inadequate stand of perennial or annual vegetation and natural reseeding or vegetation management is unlikely to improve the plant community within a reasonable amount of time to adequately address streambank and/or shoreline stability, dissipate stream energy and trap sediment, improve and/or maintain water quality, and/or provide adequate habitat corridors, food and/or cover for fish, wildlife, pollinators, and/or livestock resource concern(s). Existing conditions often require suppression or eradication of current vegetation by conventional mechanical or chemical (Herbaceous Weed Control (315)) methods to ensure establishment success of the new planting.

After Situation:

The riparian zone, the transitional zone between the terrestrial and aquatic habitats, is established to an adapted, diverse vegetative plant community and is under close management to insure long term survival and ecological succession. The quality and quantity of the riparian zone components are managed to support the species that depend on it for habitat as well as the functions it performs for stabilizing the streambank and/or shoreline, dissipating stream energy and trapping sediment, and improving and/or maintaining water quality. These functions include: stream temperature moderation through shading, recruitment of non-woody organic matter, habitat for terrestrial insects and other riparian dependent species, streambank integrity, and filtration of contaminants from surface run-off into the stream.

Feature Measure: Acres of Riparian Herbaceous Cove

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,092.83

Scenario Cost/Unit: \$1,092.83

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	2	\$22.74
----------------	-----	--	------	---------	---	---------

Foregone Income

FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.5	\$207.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.5	\$207.50

Labor

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	0.5	\$11.05

Materials

Native Aquatic Plants, Emergent or Submerged	2336	Native aquatic emergent or submerged. All required materials for establishing vegetation. Includes material and shipping.	Each	\$1.33	220	\$292.60
--	------	---	------	--------	-----	----------

Mobilization

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50
-------------------------------	------	--	------	----------	---	----------

Practice: 391 - Riparian Forest Buffer

Scenario #1 - Direct Seeding

Scenario Description:

Establish a buffer of trees and/or shrubs to restore riparian plant communities and associated benefits. The buffer will be located adjacent to and up-gradient from a watercourse or water body and extend the minimum required width. The planting will consist of trees or shrubs planted through direct seeding. Planting rate will be approximately 3000 seed per acre. Payment includes tree seed, equipment and labor to seed, and foregone income for the land taken out of crop production to install the riparian buffer. Site preparation is implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Before Situation:

Typical sites include former riparian forests and habitat used for forage, cropland, speculation property, or other nonforest condition which contains undesirable amounts or types of vegetation. Active bank erosion is depositing sediment, nutrients and organics in the riparian area. Water temperature is high due to lack of shade. Habitat is not desirable for wildlife.

After Situation:

A buffer of trees and shrubs will be established along the riparian corridor which will provide stability, filtration, shade, and desirable habitat to address the resource concerns of Soil Erosion - excessive bank erosion; Water Quality - excess sediment and organics in surface waters and elevated temperature; Degraded Plant Condition - inadequate structure and composition; and Inadequate Habitat for Fish and Wildlife - habitat degradation.

Feature Measure: Area of planting

Scenario Unit:: Acre

Scenario Typical Size: 5.0

Scenario Total Cost: \$3,903.04

Scenario Cost/Unit: \$780.61

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	8	\$177.76
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	8	\$202.16
Mechanical nut planter	1601	Mechanical nut planter for direct seeding of trees and shrubs. Requires a pulling unit of either tractor or small dozer depending upon site conditions. Does not include labor.	Hour	\$2.15	8	\$17.20
Foregone Income						
Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	2.5	\$1,038.03
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	2.5	\$1,037.50
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	8	\$176.72
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	8	\$310.24
Materials						
Trees and shrubs, seed	1871	Tree or shrub seed, e.g., acorns, to establish trees. Includes materials and shipping only.	Pound	\$4.55	150	\$682.50
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 391 - Riparian Forest Buffer

Scenario #3 - Bareroot trees, each

Scenario Description:

Establish a buffer of trees into a suitably prepared site to restore riparian plant communities and associated benefits. The buffer will be located adjacent to and up-gradient from a watercourse or water body and extend the minimum required width. The planting will consist of machine planted bare-root trees at spacings recommended in a tree/shrub planting plan. Payment includes trees, equipment and labor to plant, and foregone income for the land taken out of crop production to install the riparian buffer. Site preparation is implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Before Situation:

Typical sites include former riparian forests and habitat used for forage, cropland, speculation property, or other nonforest condition which contains undesirable amounts or types of vegetation. Active bank erosion is depositing sediment, nutrients and organics in the riparian area. Water temperature is high due to lack of shade. Habitat is not desirable for wildlife.

After Situation:

A buffer of trees and shrubs will be established along the riparian corridor which will provide stability, filtration, shade, and desirable habitat to address the resource concerns of Soil Erosion - excessive bank erosion; Water Quality - excess sediment and organics in surface waters and elevated temperature; Degraded Plant Condition - inadequate structure and composition; and Inadequate Habitat for Fish and Wildlife - habitat degradation.

Feature Measure: <Unknown>

Scenario Unit:: Each

Scenario Typical Size: 2,180.0

Scenario Total Cost: \$3,811.59

Scenario Cost/Unit: \$1.75

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	2	\$50.54
Mechanical tree planter	1600	Mechanical tree planter. Requires a pulling unit of either tractor or small dozer depending upon site conditions. Does not include labor.	Hour	\$6.84	2	\$13.68
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	2.5	\$1,038.03
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	2.5	\$1,037.50
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	2	\$44.18
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.59	2180	\$1,286.20
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: 391 - Riparian Forest Buffer

Scenario #4 - Bareroot shrubs, each

Scenario Description:

Establish a buffer of shrubs, in conjunction with planted or existing trees, into a suitably prepared site to restore riparian plant communities and associated benefits. The buffer will be located adjacent to and up-gradient from a watercourse or water body and extend the minimum required width. The planting will consist of machine planted bare-root shrubs at spacings recommended in a tree/shrub planting plan. Payment includes shrubs, equipment and labor to plant, and foregone income for the land taken out of crop production to install the riparian buffer. Site preparation is implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Before Situation:

Typical sites include former riparian forests and habitat used for forage, cropland, speculation property, or other nonforest condition which contains undesirable amounts or types of vegetation. Active bank erosion is depositing sediment, nutrients and organics in the riparian area. Water temperature is high due to lack of shade. Habitat is not desirable for wildlife.

After Situation:

A buffer of trees and shrubs will be established along the riparian corridor which will provide stability, filtration, shade, and desirable habitat to address the resource concerns of Soil Erosion - excessive bank erosion; Water Quality - excess sediment and organics in surface waters and elevated temperature; Degraded Plant Condition - inadequate structure and composition; and Inadequate Habitat for Fish and Wildlife - habitat degradation.

Feature Measure: Area of Treatment

Scenario Unit:: Each

Scenario Typical Size: 1,210.0

Scenario Total Cost: \$1,554.67

Scenario Cost/Unit: \$1.28

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	2	\$50.54
Mechanical tree planter	1600	Mechanical tree planter. Requires a pulling unit of either tractor or small dozer depending upon site conditions. Does not include labor.	Hour	\$6.84	2	\$13.68
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.5	\$207.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.5	\$207.50
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	2	\$44.18
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Shrub, seedling or transplant, bare root, 18"-36"	1507	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.57	1210	\$689.70
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: 391 - Riparian Forest Buffer

Scenario #5 - Container Tress and Shrubs (3 gallon), Each

Scenario Description:

Establish a buffer of trees and shrubs into a suitably prepared site to restore riparian plant communities and associated benefits. The buffer will be located adjacent to and up-gradient from a watercourse or water body and extend the minimum required width. The planting will consist of hand planting containerized shrubs and trees at spacings recommended in a tree/shrub planting plan. Payment includes shrubs/trees, equipment and labor to plant, and foregone income for the land taken out of crop production to install the riparian buffer. Site preparation is implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Before Situation:

Typical sites include former riparian forests and habitat used for forage, cropland, speculation property, or other nonforest condition which contains undesirable amounts or types of vegetation. Active bank erosion is depositing sediment, nutrients and organics in the riparian area. Water temperature is high due to lack of shade. Habitat is not desirable for wildlife.

After Situation:

A buffer of trees and shrubs will be established along the riparian corridor which will provide stability, filtration, shade, and desirable habitat to address the resource concerns of Soil Erosion - excessive bank erosion; Water Quality - excess sediment and organics in surface waters and elevated temperature; Degraded Plant Condition - inadequate structure and composition; and Inadequate Habitat for Fish and Wildlife - habitat degradation.

Feature Measure: Area of planting

Scenario Unit:: Each

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,982.01

Scenario Cost/Unit: \$19.82

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	6	\$72.24
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	1	\$415.21
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	1	\$415.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	6	\$131.88
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	6	\$232.68
Materials						
Tree, hardwood, seedling or transplant, potted or B&B, 2-3 gal.	1532	Potted or balled and burlapped hardwood tree, 2-3 gal. Includes materials and shipping only.	Each	\$7.15	100	\$715.00

Practice: 393 - Filter Strip

Scenario #14 - Filter Strip, Introduced species, Forgone Income

Scenario Description:

A strip or area of herbaceous vegetation that removes contaminants from overland flow. Practice includes seedbed prep and planting of introduced species. The area of the filter strip is taken out of production.

Before Situation:

Annual cropland, grazing land, or disturbed land (including forestland) allows for runoff of suspended solids, dissolved and/or associated contaminants into environmentally-sensitive areas such as wetlands, riparian zones, critical habitat and neighboring non-ag properties. Water Quality resource concerns are associated with this practice.

After Situation:

The 393 Implementation Requirements are developed for the site and applied. The planned filter strip will be established and maintained per the practice plan that will meet the criteria for the planned purpose(s). The vegetation will consist of introduced species. The filter strip will have adequate width to filter the planned pollutants. The practice includes seedbed preparation, seeding, and seed. Species selected shall be able to withstand partial burial by sediment and tolerant of herbicides used on contribution area while protecting environmentally-sensitive areas. The area of the filter strip is taken out of production.

Feature Measure: Number of acres

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$591.25

Scenario Cost/Unit: \$591.25

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	3	\$34.11
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.75	1	\$6.75
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	1.5	\$43.26
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.5	\$207.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.5	\$207.50
Materials						
Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.43	30	\$12.90
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.45	20	\$9.00
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2317	Cool season grass and legume mix. Includes material and shipping only.	Acre	\$48.34	1	\$48.34

Practice: 393 - Filter Strip

Scenario #15 - Filter Strip, Native species, Forgone Income

Scenario Description:

A strip or area of herbaceous vegetation that removes contaminants from overland flow. Practice includes seedbed prep and planting of native species. The area of the filter strip is taken out of production.

Before Situation:

Annual cropland, grazing land, or disturbed land (including forestland) allows for runoff of suspended solids, dissolved and/or associated contaminants into environmentally-sensitive areas such as wetlands, riparian zones, critical habitat and neighboring non-ag properties. Water Quality resource concerns are associated with this practice.

After Situation:

The 393 Implementation Requirements are developed for the site and applied. The planned filter strip will be established and maintained per the practice plan that will meet the criteria for the planned purpose(s). The vegetation will consist of native species. The filter strip will have adequate width to filter the planned pollutants. The practice includes seedbed preparation, seeding, and seed. Species selected shall be able to withstand partial burial by sediment and tolerant of herbicides used on the contribution area while protecting environmentally-sensitive areas. The area of the filter strip is taken out of production.

Feature Measure: number of acres

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$606.34

Scenario Cost/Unit: \$606.34

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	3	\$34.11
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	1.5	\$43.26
Foregone Income						
Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.5	\$207.61
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.5	\$207.50
Materials						
Two Species Mix, Warm Season, Native Perennial Grass	2325	Native, warm season perennial grass. Includes material and shipping only.	Acre	\$92.08	1	\$92.08



Practice: 394 - Firebreak

Scenario #1 - Constructed - Light Equipment

Scenario Description:

Installation of a bare-ground firebreak of a minimum width of 15' around a 20 acre field/farm using farm equipment (2 passes). Generally water control devices such as water bars are not needed due either to the lack of steep terrain or the temporary nature of the firebreak. Resource concerns include Wildfire hazard from excessive biomass accumulation, Undesirable plant productivity and health, Inadequate plant structure and composition, and Habitat degradation.

Before Situation:

Tract, field, or farm lacks adequate firebreaks to either reduce the spread of wildfires or contain a prescribed burn. Installation will be accomplished by making two passes with the use of typical farm equipment such as tractors, plows, disks, or similar implements.

After Situation:

The property is adequately protected from wildfire or can be safely prescribe burned.

Feature Measure: Length of firebreak

Scenario Unit:: Foot

Scenario Typical Size: 4,000.0

Scenario Total Cost: \$232.12

Scenario Cost/Unit: \$0.06

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	2	\$22.74
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	\$16.94	2	\$33.88
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: 394 - Firebreak

Scenario #2 - Constructed - Medium equipment, flat-medium slopes

Scenario Description:

Use of medium equipment such as small dozers to blade, disk, plow, etc. bare-soil firebreaks on slopes less than 15%. Generally, water control devices such as water bars are limited to 10 or less per 1,000 feet when properly planned and installed using the same equipment. Resource concerns include Wildfire hazards from excessive biomass accumulation, Undesirable plant productivity and health, Inadequate plant structure and composition, and Habitat degradation.

Before Situation:

Tract, field, or farm lacks adequate firebreaks to either reduce the spread of wildfires or contain a prescribed burn. Conditions such as topography, the presence of brush and trees, etc. make the use of typical farm equipment impractical.

After Situation:

The property is adequately protected from wildfire or can be safely prescribe burned and the potential for excessive erosion from the firebreak is negligible.

Feature Measure: Length of firebreak

Scenario Unit:: Foot

Scenario Typical Size: 3,000.0

Scenario Total Cost: \$1,072.93

Scenario Cost/Unit: \$0.36

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$67.45	4	\$269.80
Water Bars	1500	Installation of graded trail water controlling structures such as water bars, broad based dips for erosion control. Typical cross section is 1.5 feet high with 4:1 side slopes yielding about 0.33 CY/ft of length.	Foot	\$2.86	150	\$429.00
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	4	\$113.20
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 394 - Firebreak

Scenario #4 - Vegetated permanent firebreak

Scenario Description:

Establishing a 20 foot wide strip of permanent vegetation that will serve as a green firebreak. Scenario includes clearing the site, preparing the seedbed, seeding (typically cool season grasses and/or legumes), and applying needed soil amendments. Clearing will be achieved using chemical and/or mechanical means. Seedbed preparation and vegetation establishment will be accomplished with farm equipment. Soil amendments will be applied according to local FOTG guidance. This scenario does not include follow-up maintenance operations such as weed control, mowing, etc. Resource concerns include Wildfire hazard from excessive biomass accumulation, Soil erosion, and Excessive sediment in surface waters.

Before Situation:

Tract, field, or farm lacks adequate firebreaks to either reduce the spread of wildfires or contain a prescribed burn.

After Situation:

The property is adequately protected from wildfire or can be safely prescribe burned. Wildlife habitat will also be enhanced and the potential for erosion from the firebreak is minimized.

Feature Measure: Length of firebreak

Scenario Unit:: Foot

Scenario Typical Size: 3,000.0

Scenario Total Cost: \$478.54

Scenario Cost/Unit: \$0.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1.4	\$8.76
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.75	1.4	\$9.45
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1.4	\$30.49
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	4	\$87.92
Materials						
Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.43	30	\$12.90
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.45	60	\$27.00
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.35	60	\$21.00
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	\$18.22	2	\$36.44
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	1.4	\$24.47
One Species, Cool Season, Introduced Perennial Grass	2313	Introduced, cool season perennial grass. Includes material and shipping only.	Acre	\$31.86	1.4	\$44.60
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: 394 - Firebreak

Scenario #6 - Constructed - Handline

Scenario Description:

Installation of a bare-ground firebreak of a minimum width of 5' around a 20 acre woodland burn unit with the dominant fuel being hardwood leaf litter. Generally water control devices such as water bars are not needed due either to the lack of steep terrain or the temporary nature of the firebreak. The firebreak will be installed with hand tools such as broom rakes and/or leaf blowers. Resource concerns include Wildfire hazard from excessive biomass accumulation, Undesirable plant productivity and health, Inadequate plant structure and composition, and Habitat degradation.

Before Situation:

Field lacks adequate firebreaks to contain a prescribed burn. Fuel, weather, and/or topographic conditions do not warrant the use of heavy equipment.

After Situation:

The property can be safely prescribe burned and the potential for excessive erosion from the firebreak is minimized.

Feature Measure: <Unknown>

Scenario Unit:: Foot

Scenario Typical Size: 4,000.0

Scenario Total Cost: \$432.52

Scenario Cost/Unit: \$0.11

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	12	\$53.40
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	4	\$115.36
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	12	\$263.76

Practice: 410 - Grade Stabilization Structure

Scenario #2 - Embankment 8in-12in Pipe

Scenario Description:

An earthen embankment dam with a principal spillway pipe (PVC or Steel) of 8" to 12" with antiseep collars. To stabilized the grade and control erosion in natural or artificial channels, to prevent the formation or advancing of gullies, and to enhance environmental quality and reduce pollution hazards. Applied in areas where the concentration and flow velocity of water require structures to stabilize the grade in channels or to control gully erosion. Cost estimate is based upon a typical amount of earthfill of 8000 cubic yards(including core trench backfill), and 100 feet of pipe 10" PVC pipe with a canopy inlet. A small, non-lined plunge pool protects the outlet channel. Disturbed areas and earthfill surfaces are protected with permanent vegetative cover. Addresses resource concerns such as soil erosion-concentrated flow erosion and water quality degradation.

Before Situation:

The operator presently has gullies forming and/or worsening on the farmland and impacting the useable area and the downstream water quality. Erosion from the gullies is allowing soil and possibly nutrients to be transported to downstream receiving waters degrading water quality and causing soil loss.

After Situation:

Area is stabilized. The advancement and/or formation of gullies is stopped, soil from gullies no longer leaves the farm, useable farm area is increased, sedimentation and other pollution hazards are decreased, and water quality downstream is protected. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as: Fence (382), Grassed Waterway (412) will use the corresponding Standard(s) as appropriate.

Feature Measure: Cubic Yards of Earthfill

Scenario Unit:: Cubic Yard

Scenario Typical Size: 8,000.0

Scenario Total Cost: \$36,531.74

Scenario Cost/Unit: \$4.57

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	29	\$155.44
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	\$126.50	12	\$1,518.00
Dozer, 200 HP	928	Track mounted Dozer with horsepower range of 160 to 250. Equipment and power unit costs. Labor not included.	Hour	\$198.02	124	\$24,554.48
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	8	\$928.08
Scraper, pull, 7 CY	1206	Pull type earthmoving scraper with 7 CY capacity. Does not include pulling equipment or labor. Add Tractor or Dozer, 160 HP typically required for single scraper.	Hour	\$16.33	124	\$2,024.92
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	144	\$4,075.20
Materials						
Steel, Plate, 1/8"	1047	Flat Steel Plate, 1/8" thick, materials only.	Square Foot	\$3.89	72	\$280.08
Pipe, PVC, 10", SCH 80	1351	Materials: - 10" - PVC - SCH 80 - ASTM D1785	Foot	\$21.22	100	\$2,122.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

### Scenario #6 - Pipe Drop, Smooth Steel or CMP

A full flow pipe drop (i.e.: riser and barrel) grade stabilization structure designed and constructed with a sand diaphragm. This is typically a earthen dry dam structure with no permanent storage (water or sediment), however some structures may have some permanent pool / storage but do not have 35 years of sediment life. Payment rate is based upon the riser weir length (Diameter x 3.14) in feet times the length of the pipe barrel in (feet). Installed to stabilize the grade and control erosion in natural or artificial channels, to prevent the formation or advancing of gullies, and to enhance environmental quality and reduce pollution hazards. Applied in areas where the concentration and flow velocity of water require structures to stabilize the grade in channels or to control gully erosion. Cost estimate is based upon a smooth steel or corrugated metal pipe drop structure with a 36", 12' tall riser and a 100' long 24" barrel (Riser Weir length x Barrel Length =  $3\text{ft} \times 3.14 \times 100\text{ft} = 942$ ). Disturbed areas and earthfill surfaces are protected with permanent vegetative cover. Addresses resource concerns such as soil erosion-concentrated flow erosion and water quality degradation.

The operator presently has gullies forming and/or worsening on the farmland and impacting the useable area and the downstream water quality. Erosion from the gullies is allowing soil and possibly nutrients to be transported to downstream receiving waters degrading water quality and causing soil loss.

Area is stabilized. The advancement and/or formation of gullies is stopped, soil from gullies no longer leaves the farm, useable farm area is increased, sedimentation and other pollution hazards are decreased, and water quality downstream is protected. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Pond (378), Dam (402), Fence (382), Channel Bed Stabilization (584), Dike (356), Grassed Waterway (412), Structure for Water Control (587), and Irrigation Canal or Lateral (320) will use the corresponding Standard(s) as appropriate.

Scenario Unit:: Square Foot

**Scenario Total Cost:** \$12,502.65

**Scenario Cost/Unit:** \$13.27

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	1.4	\$384.47
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	600	\$2,436.00
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	100	\$536.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	4	\$464.04
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	11	\$388.96
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	4	\$113.20
Materials						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic Yard	\$25.23	36	\$908.28
Steel, Plate, 3/16"	1048	Flat Steel Plate, 3/16" thick, materials only.	Square Foot	\$5.84	16	\$93.44
Pipe, Steel, 24", Std Wt, USED	1360	Materials: - USED - 24" - Steel Std Wt	Foot	\$49.83	100	\$4,983.00
Pipe, Steel, 36", Std Wt, USED	1362	Materials: - USED - 36" - Steel Std Wt	Foot	\$100.02	12	\$1,200.24
Steel, Angle, 2 1/2" x 2 1/2" x 1/4"	1372	Materials: Angle, 2 1/2" x 2 1/2" x 1/4", Meets ASTM A36	Foot	\$3.39	10	\$33.90
Steel, Plate, 3/8"	1375	Flat steel plate, 3/8" thickness. Materials only.	Square Foot	\$11.33	3	\$33.99
Lumber, planks, posts and timbers, treated	1609	Treated dimension lumber with nominal thickness greater than 2". Includes lumber and fasteners. Does not include labor.	Board Foot	\$1.55	288	\$446.40
Mobilization						

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93
--------------------------------	------	---	------	----------	---	----------

Practice: 410 - Grade Stabilization Structure

Scenario #9 - Rock Rip Rap Chute

Scenario Description:

A full flow chute structure with rip rap, geotextile fabric, and earthfill/earthmoving. To stabilized the grade and control erosion in natural or artificial channels, to prevent the formation or advancing of gullies, and to enhance environmental quality and reduce pollution hazards. Applied in areas where the concentration and flow velocity of water require structures to stabilize the grade in channels or to control gully erosion. Cost estimate is based upon typical chute designed to handle 90 cfs (20' BW, 5:1 Chute Slope, 5' Drop, 18" rock thickness). Amount of rock required is 86 CY (129 tons). Disturbed areas and earthfill surfaces are protected with permanent vegetative cover. Cost data is applicable to organic and convention agricultural production systems.

Before Situation:

The operator presently has gullies forming and/or worsening on the farmland and impacting the useable area and the downstream water quality. Erosion from the gullies is allowing soil and possibly nutrients to be transported to downstream receiving waters degrading water quality and causing soil loss.

After Situation:

Area is stabilized. The advancement and/or formation of gullies is stopped, soil from gullies no longer leaves the farm, useable farm area is increased, sedimentation and other pollution hazards are decreased, and water quality downstream is protected. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Pond (378), Dam (402), Fence (382), Channel Bed Stabilization (584), Dike (356), Grassed Waterway (412), Structure for Water Control (587), Subsurface Drain (606), and Underground Outlet (620) will use the corresponding Standard(s) as appropriate.

Feature Measure: Cubic Yards of rip rap installed

Scenario Unit:: Cubic Yard

Scenario Typical Size: 86.0

Scenario Total Cost: \$6,044.30

Scenario Cost/Unit: \$70.28

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.39	197	\$470.83
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	100	\$406.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	6	\$696.06
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	6	\$169.80
Materials						
Rock Riprap, graded, angular, material and shipping	1200	Graded Rock Riprap for all gradation ranges. Includes materials and delivery only.	Ton	\$29.96	129	\$3,864.84
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93



Practice: 410 - Grade Stabilization Structure

Scenario #11 - Gabion Chute

Scenario Description:

A full flow chute structure with rock filled gabion baskets, geotextile fabric, and earthfill/earthmoving. To stabilized the grade and control erosion in natural or artificial channels, to prevent the formation or advancing of gullies, and to enhance environmental quality and reduce pollution hazards. Applied in areas where the concentration and flow velocity of water require structures to stabilize the grade in channels or to control gully erosion. Cost estimate is based upon typical chute with 12' BW, 4:1 chute slope, 6' drop to handle design flow of 100 cfs. 25 CY of gabion baskets. Disturbed areas and earthfill surfaces are protected with permanent vegetative cover. Cost data is applicable to organic and convention agricultural production systems.

Before Situation:

The operator presently has gullies forming and/or worsening on the farmland and impacting the useable area and the downstream water quality. Erosion from the gullies is allowing soil and possibly nutrients to be transported to downstream receiving waters degrading water quality and causing soil loss.

After Situation:

Area is stabilized. The advancement and/or formation of gullies is stopped, soil from gullies no longer leaves the farm, useable farm area is increased, sedimentation and other pollution hazards are decreased, and water quality downstream is protected. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Pond (378), Dam (402), Fence (382), Channel Bed Stabilization (584), Dike (356), Grassed Waterway (412), Structure for Water Control (587), Subsurface Drain (606), and Underground Outlet (620) will use the corresponding Standard(s) as appropriate.

Feature Measure: Cubic Yards of gabion baskets

Scenario Unit:: Cubic Yard

Scenario Typical Size: 25.0

Scenario Total Cost: \$7,665.85

Scenario Cost/Unit: \$306.63

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.39	85	\$203.15
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	200	\$812.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	12	\$1,392.12
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	12	\$339.60
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	\$65.40	12	\$784.80
Gabion basket or mat	1378	Gabion baskets or mats installed and filled on grade, includes materials, transport, equipment, and labor, does not include geotextile fabric.	Cubic Yard	\$154.93	25	\$3,873.25
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 410 - Grade Stabilization Structure

Scenario #12 - Geotextile Reinforced Vegetated Outlet

**Scenario Description:**

A full flow chute structure with geotextile fabric, erosion control blanket, riprap outlet and earthfill/earthmoving. To stabilized the grade and control erosion in natural or artificial channels, to prevent the formation or advancing of gullies, and to enhance environmental quality and reduce pollution hazards. Applied in areas where the concentration and flow velocity of water require structures to stabilize the grade in channels or to control gully erosion. Cost estimate is based upon typical chute designed to handle 50 cfs (16' BW, 6:1 Chute Slope, 6' Drop). Amount of geotextile required is 1050 SF. Disturbed areas and earthfill surfaces are protected with permanent vegetative cover. Cost data is applicable to organic and convention agricultural production systems.

**Before Situation:**

The operator presently has gullies forming and/or worsening on the farmland and impacting the useable area and the downstream water quality. Erosion from the gullies is allowing soil and possibly nutrients to be transported to downstream receiving waters degrading water quality and causing soil loss.

**After Situation:**

Area is stabilized. The advancement and/or formation of gullies is stopped, soil from gullies no longer leaves the farm, useable farm area is increased, sedimentation and other pollution hazards are decreased, and water quality downstream is protected. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Pond (378), Dam (402), Fence (382), Channel Bed Stabilization (584), Dike (356), Grassed Waterway (412), Structure for Water Control (587), Subsurface Drain (606), and Underground Outlet (620) will use the corresponding Standard(s) as appropriate.

**Feature Measure:** Square Ft of Geotextile lined area

**Scenario Unit::** Square Foot

**Scenario Typical Size:** 1,050.0

**Scenario Total Cost:** \$2,819.42

**Scenario Cost/Unit:** \$2.69

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.39	163	\$389.57
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	100	\$406.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	6	\$696.06
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	6	\$169.80
Materials						
Rock Riprap, graded, angular, material and shipping	1200	Graded Rock Riprap for all gradation ranges. Includes materials and delivery only.	Ton	\$29.96	17	\$509.32
Erosion Control Blanket, biodegradable	1213	Biodegradable erosion control blanket, typically a composite of natural fibers with reinforcing polymer netting. Materials and shipping only.	Square Yard	\$1.30	163	\$211.90
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 410 - Grade Stabilization Structure

Scenario #15 - Concrete Drop Structure

Scenario Description:

A Straight or Box Drop structure composed of reinforced concrete used to stabilized the grade and control erosion in natural or artificial channels, to prevent the formation or advancing of gullies, and to enhance environmental quality and reduce pollution hazards. Applied in areas where the concentration and flow velocity of water require structures to stabilize the grade in channels or to control gully erosion. Cost estimate is based upon a concrete box drop structure with a drop of 4ft and weir length of 16ft. The unit of payment measurement is cubic yards of concrete placed. Disturbed areas and earthfill surfaces are protected with permanent vegetative cover. Addresses resource concerns such as soil erosion-concentrated flow erosion and water quality degradation.

Before Situation:

The operator presently has gullies forming and/or worsening on the farmland and impacting the useable area and the downstream water quality. Erosion from the gullies is allowing soil and possibly nutrients to be transported to downstream receiving waters degrading water quality and causing soil loss.

After Situation:

Area is stabilized. The advancement and/or formation of gullies is stopped, soil from gullies no longer leaves the farm, useable farm area is increased, sedimentation and other pollution hazards are decreased, and water quality downstream is protected. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Pond (378), Dam (402), Fence (382), Channel Bed Stabilization (584), Dike (356), Grassed Waterway (412), Structure for Water Control (587), Subsurface Drain (606), and Underground Outlet (620) will use the corresponding Standard(s) as appropriate.

Feature Measure: Cubic Yard of Concrete

Scenario Unit:: Cubic Yard

Scenario Typical Size: 12.0

Scenario Total Cost: \$10,032.25

Scenario Cost/Unit: \$836.02

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	12	\$5,125.32
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.39	20	\$47.80
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	300	\$1,218.00
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$167.73	8	\$1,341.84
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	8	\$226.40
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	3	\$76.71
Rock Riprap, graded, angular, material and shipping	1200	Graded Rock Riprap for all gradation ranges. Includes materials and delivery only.	Ton	\$29.96	50	\$1,498.00
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	1	\$498.18

Practice: 410 - Grade Stabilization Structure

Scenario #16 - Concrete Block Chute

Scenario Description:

A full flow chute structure with concrete blocks, geotextile fabric, and earthfill/earthmoving. To stabilized the grade and control erosion in natural or artificial channels, to prevent the formation or advancing of gullies, and to enhance environmental quality and reduce pollution hazards. Applied in areas where the concentration and flow velocity of water require structures to stabilize the grade in channels or to control gully erosion. Cost estimate is based upon typical chute designed to handle 65 cfs (10' BW, 5' Drop). 518 Concrete blocks required. Disturbed areas and earthfill surfaces are protected with permanent vegetative cover. Cost data is applicable to organic and convention agricultural production systems.

Before Situation:

The operator presently has gullies forming and/or worsening on the farmland and impacting the useable area and the downstream water quality. Erosion from the gullies is allowing soil and possibly nutrients to be transported to downstream receiving waters degrading water quality and causing soil loss.

After Situation:

Area is stabilized. The advancement and/or formation of gullies is stopped, soil from gullies no longer leaves the farm, useable farm area is increased, sedimentation and other pollution hazards are decreased, and water quality downstream is protected. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Pond (378), Dam (402), Fence (382), Channel Bed Stabilization (584), Dike (356), Grassed Waterway (412), Structure for Water Control (587), Subsurface Drain (606), and Underground Outlet (620) will use the corresponding Standard(s) as appropriate.

Feature Measure: Square feet of concrete block lined

Scenario Unit:: Square Foot

Scenario Typical Size: 460.0

Scenario Total Cost: \$4,571.02

Scenario Cost/Unit: \$9.94

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.39	52	\$124.28
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	300	\$1,218.00
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	6	\$696.06
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	45	\$989.10
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	6	\$169.80
Materials						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic Yard	\$25.23	9	\$227.07
Block, concrete	253	Concrete block, hollow, normal weight, 3500 psi. Includes both full and partial sizes. Material only	Each	\$1.71	518	\$885.78
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 410 - Grade Stabilization Structure

Scenario #17 - Side Inlet

Scenario Description:

A side inlet drain structure. To stabilized the grade and control erosion in natural or artificial channels, to prevent the formation or advancing of gullies, and to enhance environmental quality and reduce pollution hazards. Applied in areas where the concentration and flow velocity of water require structures to stabilize the grade in channels or to control gully erosion. Typical length of pipe is 30 feet. Disturbed areas and earthfill surfaces are protected with permanent vegetative cover. Cost data is applicable to organic and convention agricultural production systems. See the "Grade Stabilization" conservation practice standard.

Before Situation:

The operator presently has gullies forming and/or worsening on the farmland and impacting the useable area and the downstream water quality. Erosion from the gullies is allowing soil and possibly nutrients to be transported to downstream receiving waters degrading water quality and causing soil loss.

After Situation:

Area is stabilized. The advancement and/or formation of gullies is stopped, soil from gullies no longer leaves the farm, useable farm area is increased, sedimentation and other pollution hazards are decreased, and water quality downstream is protected. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Pond (378), Dam (402), Fence (382), Grassed Waterway (412) will use the corresponding Standard(s) as appropriate.

Feature Measure: Length of Pipe installed

Scenario Unit:: Foot

Scenario Typical Size: 30.0

Scenario Total Cost: \$2,021.39

Scenario Cost/Unit: \$67.38

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	4	\$464.04
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	4	\$87.92
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	4	\$113.20
Materials						
Pipe, Steel, 18", Std Wt, USED	1358	Materials: - USED - 18" - Steel Std Wt	Foot	\$36.51	30	\$1,095.30
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

### Scenario #2 - 35-55 foot topwidth

Typical practice is 1 acre, 45' topwidth, 10:1 side slopes, 1.5' depth, 50% excavation. A grass waterway that is a shaped or graded channel and is established with suitable vegetation to carry surface water at a non-erosive velocity to a stable outlet. This practice addresses Concentrated Flow Erosion (Classic Gully & Ephemeral Erosion) and Excessive Sediment in surface waters. Waterway area measured from top of bank to top of bank. Seeding area is 20% greater than waterway area to account for disturbed areas. Costs include excavation and associated work to construct the overall shape and grade of the waterway.

The field has a small gully which is cutting deeper into the field as time goes on, so it needs to be stopped or controlled. Excessive sedimentation and soil erosion as a result from ephemeral or classic gully erosion. Gully has formed in field as a result of excessive runoff and poor cropping techniques. Grassed waterway is also commonly installed to convey runoff from concentrated flows, terraces, diversions, or water control structures or similar practices to a suitable, stable outlet.

Installed grassed waterway is 1 acre, 45' topwidth, 10:1 side slopes, 1.5' depth. The practice is installed using a dozer. Waterway area is fertilized and seeded for establishment of waterway vegetation. If erosion control blankets or mulching for seedbed establishment/protection are needed, use conservation practice Mulching (484). Drainage tile, if needed, will be installed according to Subsurface Drain (606). Outlets, if needed will be installed using Structure for Water Control (587). If inlet Structures are needed with the drainage tile, then those will be installed using Underground Outlet (620).

Scenario Unit:: Acre

**Scenario Total Cost:** \$3,417.07

**Scenario Cost/Unit:** \$3,417.07

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	1	\$11.37
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.75	1	\$6.75
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$10.84	1	\$10.84
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	\$7.85	1	\$7.85
Excavation, common earth, large equipment, 50 ft	1222	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$1.63	404	\$658.52
Excavation, common earth, large equipment, 150 ft	1223	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 150 feet. Includes equipment and labor.	Cubic Yard	\$3.85	404	\$1,555.40

FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.5	\$207.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.5	\$207.50

Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78
-----------------------	-----	--	------	---------	---	---------

Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.43	90	\$38.70
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.45	90	\$40.50
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.35	90	\$31.50
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	\$18.22	2	\$36.44
Three Species Mix, Cool Season, Introduced Perennial Grass	2315	Cool season, introduced grass mix. Includes material and shipping only.	Acre	\$45.35	1	\$45.35

## Mobilization

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	1	\$498.18
-------------------------------	------	--	------	----------	---	----------

### Scenario #3 - >55 foot topwidth

Typical practice is 1 acre, 60' topwidth, 10:1 side slopes, 2.0' depth, 50% excavation. A grass waterway that is a shaped or graded channel and is established with suitable vegetation to carry surface water at a non-erosive velocity to a stable outlet. This practice addresses Concentrated Flow Erosion (Classic Gully & Ephemeral Erosion) and Excessive Sediment in surface waters. Waterway area measured from top of bank to top of bank. Seeding area is 20% greater than waterway area to account for disturbed areas. Costs include excavation and associated work to construct the overall shape and grade of the waterway.

The field has a small gully which is cutting deeper into the field as time goes on, so it needs to be stopped or controlled. Excessive sedimentation and soil erosion as a result from ephemeral or classic gully erosion. Gully has formed in field as a result of excessive runoff and poor cropping techniques. Grassed waterway is also commonly installed to convey runoff from concentrated flows, terraces, diversions, or water control structures or similar practices to a suitable, stable outlet.

Installed grassed waterway is 1 acre, 60' topwidth, 10:1 side slopes, 2.0' depth. The practice is installed using a dozer. Waterway area is fertilized and seeded for establishment of waterway vegetation. If erosion control blankets or mulching for seedbed establishment/protection are needed, use conservation practice Mulching (484). Drainage tile, if needed, will be installed according to Subsurface Drain (606). Outlets, if needed will be installed using Structure for Water Control (587). If inlet Structures are needed with the drainage tile, then those will be installed using Underground Outlet (620).

Scenario Unit:: Acre

**Scenario Total Cost:** \$4,151.39

**Scenario Cost/Unit:** \$4,151.39

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	1	\$11.37
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.75	1	\$6.75
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$10.84	1	\$10.84
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	\$7.85	1	\$7.85
Excavation, common earth, large equipment, 50 ft	1222	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$1.63	538	\$876.94
Excavation, common earth, large equipment, 150 ft	1223	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 150 feet. Includes equipment and labor.	Cubic Yard	\$3.85	538	\$2,071.30

FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.5	\$207.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.5	\$207.50

Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78
-----------------------	-----	--	------	---------	---	---------

Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.43	90	\$38.70
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.45	90	\$40.50
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.35	90	\$31.50
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	\$18.22	2	\$36.44
Three Species Mix, Cool Season, Introduced Perennial Grass	2315	Cool season, introduced grass mix. Includes material and shipping only.	Acre	\$45.35	1	\$45.35

## Mobilization



Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	1	\$498.18
-------------------------------	------	--	------	----------	---	----------

Practice: 412 - Grassed Waterway

Scenario #5 - 35-55 foot topwidth with checks

Scenario Description:

Typical practice is 1 acre, 45' topwidth, 10:1 side slopes, 1.5' depth, half excavation. A grass waterway that is a shaped or graded channel and is established with suitable vegetation to carry surface water at a non-erosive velocity to a stable outlet. Stone checks are installed every 100 feet along the length of the waterway perpendicular to waterflow and are 2/3 the waterway top width to reduce maintenance and provide temporary protection until vegetation is established. This practice addresses Concentrated Flow Erosion (Classic Gully & Ephemeral Erosion) and Excessive Sediment in surface waters. Waterway area measured from top of bank to top of bank. Seeding area is 20% greater than waterway area to account for disturbed areas. Costs include excavation and associated work to construct the overall shape and grade of the waterway.

Before Situation:

The field has a small gully which is cutting deeper into the field as time goes on, so it needs to be stopped or controlled. Excessive sedimentation and soil erosion as a result from ephemeral or classic gully erosion. Gully has formed in field as a result of excessive runoff and poor cropping techniques. Grassed waterway is also commonly installed to covey runoff from concentrated flows, terraces, diversions, or water control structures or similar practices to a suitable, stable outlet.

After Situation:

Installed grassed waterway is 1 acre, 45' topwidth, 10:1 side slopes, 1.5' depth. Checks are installed every 100 feet along the length of the waterway. The practice is installed using a dozer. Stone checks are installed with small backhoe and labor. Waterway area is fertilized and seeded for establishment of waterway vegetation. If erosion control blankets or mulching for seedbed establishment/protection are needed, use conservation practice Mulching (484). Drainage tile, if needed, will be installed according to Subsurface Drain (606). Outlets, if needed will be installed using Structure for Water Control (587). If inlet Structures are needed with the drainage tile, then those will be installed using Underground Outlet (620).

Feature Measure: Acre of Waterway

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$4,532.78

Scenario Cost/Unit: \$4,532.78

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	1	\$11.37
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.75	1	\$6.75
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$10.84	1	\$10.84
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	\$7.85	1	\$7.85
Excavation, common earth, large equipment, 50 ft	1222	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$1.63	403.5	\$657.71
Excavation, common earth, large equipment, 150 ft	1223	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 150 feet. Includes equipment and labor.	Cubic Yard	\$3.85	403.5	\$1,553.48
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.5	\$207.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.5	\$207.50
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	\$65.40	16	\$1,046.40
Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.43	90	\$38.70
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.45	90	\$40.50
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.35	90	\$31.50

Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	\$18.22	2	\$36.44
Three Species Mix, Cool Season, Introduced Perennial Grass	2315	Cool season, introduced grass mix. Includes material and shipping only.	Acre	\$45.35	1	\$45.35
<b>Mobilization</b>						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	1	\$498.18

Practice: 412 - Grassed Waterway

Scenario #6 - >55 foot topwidth with checks

Scenario Description:

Typical practice is 1 acre, 60' topwidth, 10:1 side slopes, 2.0' depth, half excavation. A grass waterway that is a shaped or graded channel and is established with suitable vegetation to carry surface water at a non-erosive velocity to a stable outlet. Stone checks are installed every 100 feet along the length of the waterway perpendicular to waterflow and are 2/3 the waterway top width to reduce maintenance and provide temporary protection until vegetation is established. This practice addresses Concentrated Flow Erosion (Classic Gully & Ephemeral Erosion) and Excessive Sediment in surface waters. Waterway area measured from top of bank to top of bank. Seeding area is 20% greater than waterway area to account for disturbed areas. Costs include excavation and associated work to construct the overall shape and grade of the waterway.

Before Situation:

The field has a small gully which is cutting deeper into the field as time goes on, so it needs to be stopped or controlled. Excessive sedimentation and soil erosion as a result from ephemeral or classic gully erosion. Gully has formed in field as a result of excessive runoff and poor cropping techniques. Grassed waterway is also commonly installed to covey runoff from concentrated flows, terraces, diversions, or water control structures or similar practices to a suitable, stable outlet.

After Situation:

Installed grassed waterway is 1 acre, 60' topwidth, 10:1 side slopes, 2.0' depth. Checks are installed every 100 feet along the length of the waterway. The practice is installed using a dozer. Stone checks are installed with small backhoe and labor. Waterway area is fertilized and seeded for establishment of waterway vegetation. If erosion control blankets or mulching for seedbed establishment/protection are needed, use conservation practice Mulching (484). Drainage tile, if needed, will be installed according to Subsurface Drain (606). Outlets, if needed will be installed using Structure for Water Control (587). If Inlet Structures are needed with the drainage tile, then those will be installed using Underground Outlet (620).

Feature Measure: Acre of Waterway

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$5,204.44

Scenario Cost/Unit: \$5,204.44

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	1	\$11.37
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.75	1	\$6.75
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$10.84	1	\$10.84
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	\$7.85	1	\$7.85
Excavation, common earth, large equipment, 50 ft	1222	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$1.63	538	\$876.94
Excavation, common earth, large equipment, 150 ft	1223	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 150 feet. Includes equipment and labor.	Cubic Yard	\$3.85	538	\$2,071.30
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.5	\$207.61
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.5	\$207.50
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	\$65.40	15	\$981.00
Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.43	90	\$38.70
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.45	90	\$40.50
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.35	90	\$31.50

Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	\$18.22	2	\$36.44
Three Species Mix, Cool Season, Introduced Perennial Grass	2315	Cool season, introduced grass mix. Includes material and shipping only.	Acre	\$45.35	1	\$45.35
<b>Mobilization</b>						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	1	\$498.18

Practice: 422 - Hedgerow Planting

Scenario #2 - 1 row hedgerow, container trees planting stock

Scenario Description:

One row of container trees planted for wildlife habitat (corridor), pollinator habitat, reduction of particulate matter, chemical drift, or odor movement, and boundary delineation and contour guidelines. This practice is typically applied on cropland. Trees and/or shrubs will be planted into previously established bunch grasses that produce erect stems greater than 3' in height and will persist over winter. This herbaceous component will be established according to the guidelines in 327 Conservation Cover. Payment includes materials, labor and equipment needed to hand plant the stock and foregone income for land removed from crop production where hedgerow is installed. Site preparation is not included and must be implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Before Situation:

Habitat patches lack connectivity. Cover is inadequate to allow wildlife to exploit cropland food resources. Berries and mast are limited.

After Situation:

Inadequate habitat for fish and wildlife is addressed for needs identified in the resource assessment. Habitat patches are connected by dense hedgerow vegetation. Food resources in crop fields are made available by their proximity to hedgerow cover. Planting may include fruit and mast bearing species, improving food supply, depending on needs being addressed.

Feature Measure: length of hedgerow

Scenario Unit:: Foot

Scenario Typical Size: 500.0

Scenario Total Cost: \$500.74

Scenario Cost/Unit: \$1.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	3	\$36.12
---------------------------	------	--	------	---------	---	---------

Foregone Income

Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.12	\$49.83
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.12	\$49.80

Labor

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	3	\$65.94
---------------	-----	--	------	---------	---	---------

Materials

Tree, hardwood, seedling or transplant, potted, 1/2 to 1 gal.	1531	Potted hardwood tree, 1/2 to 1 gal. Includes materials and shipping only.	Each	\$4.54	50	\$227.00
---	------	---	------	--------	----	----------

Mobilization

Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
------------------------------------	------	--	------	---------	---	---------

Practice: 422 - Hedgerow Planting

Scenario #3 - 1 row hedgerow, container shrubs planting stock

Scenario Description:

One row of container shrubs planted for wildlife habitat (corridor), pollinator habitat, reduction of particulate matter, chemical drift, or odor movement, and boundary delineation and contour guidelines. This practice is typically applied on cropland. Trees and/or shrubs will be planted into previously established bunch grasses that produce erect stems greater than 3' in height and will persist over winter. This herbaceous component will be established according to the guidelines in 327 Conservation Cover. Payment includes materials, labor and equipment needed to hand plant the stock and foregone income for land removed from crop production where hedgerow is installed. Site preparation is not included and must be implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Before Situation:

Habitat patches lack connectivity. Cover is inadequate to allow wildlife to exploit cropland food resources. Berries and mast are limited.

After Situation:

Inadequate habitat for fish and wildlife is addressed for needs identified in the resource assessment. Habitat patches are connected by dense hedgerow vegetation. Food resources in crop fields are made available by their proximity to hedgerow cover. Planting may include fruit and mast bearing species, improving food supply, depending on needs being addressed.

Feature Measure: length of hedgerow

Scenario Unit:: Foot

Scenario Typical Size: 500.0

Scenario Total Cost: \$827.80

Scenario Cost/Unit: \$1.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	6	\$72.24
---------------------------	------	--	------	---------	---	---------

Foregone Income

Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.12	\$49.83
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.12	\$49.80

Labor

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	6	\$131.88
---------------	-----	--	------	---------	---	----------

Materials

Shrub, seedling or transplant, potted, 1/2 to 1 gal.	1526	Potted shrub, 1/2 to 1 gal. Includes materials and shipping only.	Each	\$4.52	100	\$452.00
--	------	---	------	--------	-----	----------

Mobilization

Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
------------------------------------	------	--	------	---------	---	---------

Practice: 422 - Hedgerow Planting

Scenario #5 - 1 row hedgerow, bare-root tree seedling planting stock

Scenario Description:

One row of bare-root trees planted for wildlife habitat (corridor), pollinator habitat, reduction of particulate matter, chemical drift, or odor movement, and boundary delineation and contour guidelines. This practice is typically applied on cropland. Trees and/or shrubs will be planted into previously established bunch grasses that produce erect stems greater than 3' in height and will persist over winter. This herbaceous component will be established according to the guidelines in 327 Conservation Cover. Payment includes materials, labor and equipment needed to machine plant the stock and foregone income for land removed from crop production where hedgerow is installed. Site preparation is not included and must be implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Before Situation:

Habitat patches lack connectivity. Cover is inadequate to allow wildlife to exploit cropland food resources. Berries and mast are limited.

After Situation:

Inadequate habitat for fish and wildlife is addressed for needs identified in the resource assessment. Habitat patches are connected by dense hedgerow vegetation. Food resources in crop fields are made available by their proximity to hedgerow cover. Planting may include fruit and mast bearing species, improving food supply, depending on needs being addressed.

Feature Measure: length of hedgerow

Scenario Unit:: Foot

Scenario Typical Size: 500.0

Scenario Total Cost: \$167.22

Scenario Cost/Unit: \$0.33

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	0.5	\$12.64
Mechanical tree planter	1600	Mechanical tree planter. Requires a pulling unit of either tractor or small dozer depending upon site conditions. Does not include labor.	Hour	\$6.84	0.5	\$3.42
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.12	\$49.83
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.12	\$49.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	0.5	\$10.99
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	0.5	\$11.05
Materials						
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.59	50	\$29.50



Practice: 422 - Hedgerow Planting

Scenario #6 - 1 row hedgerow, bare-root shrub seedling planting stock

Scenario Description:

One row of bare-root shrubs planted for wildlife habitat (corridor), pollinator habitat, reduction of particulate matter, chemical drift, or odor movement, and boundary delineation and contour guidelines. This practice is typically applied on cropland. Trees and/or shrubs will be planted into previously established bunch grasses that produce erect stems greater than 3' in height and will persist over winter. This herbaceous component will be established according to the guidelines in 327 Conservation Cover. Payment includes materials, labor and equipment needed to machine plant the stock and foregone income for land removed from crop production where hedgerow is installed. Site preparation is not included and must be implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Before Situation:

Habitat patches lack connectivity. Cover is inadequate to allow wildlife to exploit cropland food resources. Berries and mast are limited.

After Situation:

Inadequate habitat for fish and wildlife is addressed for needs identified in the resource assessment. Habitat patches are connected by dense hedgerow vegetation. Food resources in crop fields are made available by their proximity to hedgerow cover. Planting may include fruit and mast bearing species, improving food supply, depending on needs being addressed.

Feature Measure: length of hedgerow

Scenario Unit:: Foot

Scenario Typical Size: 500.0

Scenario Total Cost: \$232.81

Scenario Cost/Unit: \$0.47

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	1	\$25.27
Mechanical tree planter	1600	Mechanical tree planter. Requires a pulling unit of either tractor or small dozer depending upon site conditions. Does not include labor.	Hour	\$6.84	1	\$6.84
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.12	\$49.83
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.12	\$49.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	1	\$21.98
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	1	\$22.09
Materials						
Shrub, seedling or transplant, bare root, 18"-36"	1507	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.57	100	\$57.00

Practice: 430 - Irrigation Pipeline

Scenario #1 - Micro Irrigation Pipeline

Scenario Description:

Below ground installation of plastic pipeline installed underground between the location of the water pump and the area of irrigation to serve a micro irrigation system. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included as 10% of pipe material. Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements. Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use.

Before Situation:

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

After Situation:

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use. Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

Feature Measure: Ft of pipe

Scenario Unit:: Foot

Scenario Typical Size: 1,500.0

Scenario Total Cost: \$4,465.54

Scenario Cost/Unit: \$2.98

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, 12" x 48"	53	Trenching, earth, 12" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$1.26	1500	\$1,890.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.77	1109	\$1,962.93
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 430 - Irrigation Pipeline

Scenario #2 - Pipe System <=8 in Diameter, >50 ft Installation

Scenario Description:

Below ground installation of plastic pipeline installed underground between the location of the water pump and the area of irrigation to serve an irrigation system. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included as 10% of pipe material. Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements. Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use.

Before Situation:

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

After Situation:

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use. Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

Feature Measure: Ft of pipe

Scenario Unit:: Foot

Scenario Typical Size: 1,500.0

Scenario Total Cost: \$20,268.73

Scenario Cost/Unit: \$13.51

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$2.89	1500	\$4,335.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.77	8656	\$15,321.12
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 430 - Irrigation Pipeline

Scenario #3 - Pipe System <= 8 in Diameter, <= 50 ft Installation

Scenario Description:

Below ground installation of plastic pipeline installed underground between the location of the water pump and the area of irrigation to serve an irrigation system. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included as 10% of pipe material. Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements. Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use.

Before Situation:

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

After Situation:

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use. Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

Feature Measure: Ft of pipe

Scenario Unit:: Foot

Scenario Typical Size: 50.0

Scenario Total Cost: \$1,092.80

Scenario Cost/Unit: \$21.86

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$2.89	50	\$144.50
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.77	289	\$511.53
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 430 - Irrigation Pipeline

Scenario #4 - Pipe System 10-12 in Diameter, >50 ft Installation

Scenario Description:

Below ground installation of plastic pipeline installed underground between the location of the water pump and the area of irrigation to serve an irrigation system. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included as %10 of pipe material. Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements. Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use.

Before Situation:

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

After Situation:

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use. Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

Feature Measure: Ft of pipe

Scenario Unit:: Foot

Scenario Typical Size: 1,500.0

Scenario Total Cost: \$26,755.20

Scenario Cost/Unit: \$17.84

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$2.89	1500	\$4,335.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	20	\$439.60
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.77	12271	\$21,719.67
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 430 - Irrigation Pipeline

Scenario #5 - Pipe System 10-12 in Diameter, <= 50ft Installation

Scenario Description:

Below ground installation of plastic pipeline installed underground between the location of the water pump and the area of irrigation to serve an irrigation system. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included as 10% of pipe material. Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements. Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use.

Before Situation:

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

After Situation:

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use. Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

Feature Measure: Ft of pipe

Scenario Unit:: Foot

Scenario Typical Size: 50.0

Scenario Total Cost: \$1,343.85

Scenario Cost/Unit: \$26.88

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$2.89	50	\$144.50
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.77	406	\$718.62
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 430 - Irrigation Pipeline

Scenario #6 - Pipe System >=15 in, >50 ft Installation

Scenario Description:

Below ground installation of plastic pipeline installed underground between the location of the water pump and the area of irrigation to serve an irrigation system. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included as 10% of pipe material. Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements. Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use.

Before Situation:

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

After Situation:

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use. Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

Feature Measure: Ft of pipe

Scenario Unit:: Foot

Scenario Typical Size: 1,500.0

Scenario Total Cost: \$40,727.06

Scenario Cost/Unit: \$27.15

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$2.89	1500	\$4,335.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	48	\$1,055.04
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.77	19817	\$35,076.09
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 430 - Irrigation Pipeline

Scenario #7 - Pipe System >=15 in, <= 50ft Installation

Scenario Description:

Below ground installation of plastic pipeline installed underground between the location of the water pump and the area of irrigation to serve an irrigation system. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included as 10% of pipe material. Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements. Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use.

Before Situation:

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

After Situation:

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use. Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

Feature Measure: Ft of pipe

Scenario Unit:: Foot

Scenario Typical Size: 50.0

Scenario Total Cost: \$2,102.92

Scenario Cost/Unit: \$42.06

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$2.89	50	\$144.50
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	24	\$527.52
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.77	661	\$1,169.97
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93



Practice: 441 - Irrigation System, Microirrigation

Scenario #2 - Specialty Crop Microirrigation System

Scenario Description:

An irrigation system for vegetables or other specialty crops typically of small acreage (2 acre). Water delivery to the plants by surface lines and/or subsurface applicators. Spacing of the plants will vary, w/ lateral lines spaced 24". Area in question is being converted from other means of less efficient irrigation. Payment includes on-ground mainline and drip tape, fittings, and appurtenances. Surface placed drip tape will not meet the 441 practice life and will normally need replacement every year. After first installation, drip tape will be replaced as operation and maintenance as required for proper operation of the system. Pump & supply line is not included in this payment and may be offered through associated practices 533 Pumping plant and 430 Irrigation Pipeline, or existing pump & supply lines will be used. Cost represents typical situations for conventional, organic, and transitioning to organic producers.

Before Situation:

A production field has an inefficient surface flood irrigation system causing irrigation water loss that impacts water quality and water quantity.

After Situation:

A surface placed microirrigation system is utilized to provide highly efficient irrigation to an field. Water applications are reduced and runoff eliminated. Offsite water quality is improved, and on site water use is reduced. Resource Concerns: Insufficient Water - Inefficient use of irrigation water, Degraded Plant Condition - Undesirable plant productivity and health, Water Quality Degradation - Excessive sediment in surface waters, and Inefficient Energy Use - Equipment and facilities. Associated Practices: 533-Pumping Plant, 449- Irrigation Water Management, 430 - Irrigation Pipeline

Feature Measure: Acres in System

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: \$4,011.38

Scenario Cost/Unit: \$2,005.69

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68
Materials						
Micro Irrigation, surface drip tape	2522	Tape is installed above ground for surface drip irrigation on annual crops, includes installation, and connections to the supply and flushing laterals.?? Tape is a minimum of 10 mil thick and has emitters built in.	Foot	\$0.07	47916	\$3,354.12
Micro Irrigation, screen or disc filter, < 3"	2524	Micro Irrigation, small manual flush screen or disc filter, <3 inch nominal size. Includes materials only.	Each	\$152.79	2	\$305.58

Practice: 441 - Irrigation System, Microirrigation

Scenario #4 - Seasonal High Tunnel Microirrigation System

Scenario Description:

An irrigation system for vegetables or other specialty crops, irrigating inside of a high-tunnel poly-house typically 2,178 sq ft in size. Water delivery to the plants by surface lines and/or subsurface applicators. Spacing of the plants will vary, w/ delivery lines spaced 60". Area in question is being converted from other means of less efficient irrigation. Payment includes on-ground mainline and drip tape, fittings, and appurtenances. Pump & supply line is not included in this payment and may be offered through associated practices 533 Pumping plant and 430 Irrigation Pipeline, or existing pump & supply lines will be used. Cost represents typical situations for conventional, organic, and transitioning to organic producers.

Before Situation:

A high tunnel has an inefficient overhead sprinkler irrigation system causing irrigation water loss that impacts water quality and water quantity.

After Situation:

A microirrigation system is utilized to provide highly efficient irrigation to crops grown in a high tunnel. Water applications are reduced and runoff eliminated. Offsite water quality is improved, and on site water use is reduced. Resource Concerns: Insufficient Water - Inefficient use of irrigation water, Degraded Plant Condition - Undesirable plant productivity and health, Water Quality Degradation - Excessive sediment in surface waters, and Inefficient Energy Use - Equipment and facilities. Associated Practices: 533-Pumping Plant, 449- Irrigation Water Management, 430 - Irrigation Pipeline

Feature Measure: Each High Tunnel

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$349.28

Scenario Cost/Unit: \$349.28

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	4	\$87.92
Materials						
Micro Irrigation, drip irrigation system, small scale	2170	An above ground, small scale, micro-irrigation system. Includes miniature emitters, tubes, or applicators placed along a water delivery line. Includes materials and shipping only.	Square Foot	\$0.12	2178	\$261.36

Practice: 442 - Sprinkler System

Scenario #1 - Conversion to Center Pivot or Linear Move System

Scenario Description:

A surface irrigated field is converted to a center pivot sprinkler irrigation system or a linear move irrigation system to improve efficiency and uniformity of applied irrigation water to maintain adequate soil water for the desired level of plant growth and water quality impairment.

Before Situation:

A 160 acre field is flood irrigated. Application of irrigation water is inefficient and non-uniform. Irrigation water is typically over applied in some parts of the field, and under applied in others. Deep percolation from the excess irrigation delivers excess nutrients salts, and chemicals to the ground water. Runoff from the field contains excess nutrients and degrades the receiving waters. Irrigated induced erosion is excessive.

After Situation:

The existing surface irrigation system is converted to a low pressure center pivot. Corners are converted to non-irrigated cropland. The pivot is 1300 feet in length with pressure regulators and low pressure sprinklers on drops. The new irrigation system has a coefficient of uniformity above 85%. Irrigation water is efficiently and uniformly applied to maintain adequate soil water for the desired level of plant growth. Deep percolation and field runoff is eliminated and there are no excess nutrients, salts or pathogens delivered to the receiving waters. Irrigation induced runoff is eliminated. Resource concerns include: Soil Erosion (Concentrated flow erosion e.g. irrigation induced), Insufficient Water (Inefficient use of irrigation water), Water Quality Degradation (Excess nutrients in surface and ground waters, Excessive salts in surface and ground waters, Excess pathogens and chemicals from manure, bio-solids or compost applications). Associated Practices: Irrigation Pipeline (430), Pumping Plant (533), Irrigation Water Management (449)

Feature Measure: Length of Center Pivot Lateral

Scenario Unit:: Acre

Scenario Typical Size: 160.0

Scenario Total Cost: \$98,476.53

Scenario Cost/Unit: \$615.48

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Irrigation, Center pivot system with appurtenances, fixed cost portion	317	Fixed cost portion of the center pivot system with appurtenances. This portion includes the following items: pivot point, pipe, towers, pad, controls, sprinklers, installation.	Each	\$6,441.55	1	\$6,441.55
Irrigation, Center pivot system with appurtenances, variable cost portion	318	Variable cost portion of the center pivot system with appurtenances. This portion includes the following items: pivot point, pipe, towers, pad, controls, sprinklers, installation.	Foot	\$70.54	1300	\$91,702.00
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 442 - Sprinkler System

Scenario #2 - Sprinkler Conversion to Low Pressure

Scenario Description:

Center Pivot and Linear Move sprinkler systems are used in large crop fields with fairly regular field borders and flat topography. The scenario involves changing nozzles on center pivot or lateral move irrigation systems to low-pressure systems to improve efficiency of water use and reduce energy use. This scenario is intended for cropland areas where the objective is water conservation. Scenario includes end booms renozzled with low-pressure nozzles

Before Situation:

A center pivot or lateral move system has high pressure sprinklers. The nozzles are worn and water is applied non-uniformly. Water runs off the field and degrades the receiving waters. Deep percolation in some parts of the field degrades the ground water quality. The runoff from the field causes soil erosion. The high pressure requirement for the system requires excess energy use.

After Situation:

A Center Pivot or Linear Move sprinkler system with a span of 1300 linear feet is re-nozzled with low-pressure nozzles. The irrigation water is applied efficiently and uniformly to maintain adequate soil moisture for optimum plant growth. Runoff and deep percolation are eliminated, and the surface and ground water is no longer degraded. The irrigation induced soil erosion caused by runoff is also eliminated. The lower pressure requirements of the sprinklers reduces the energy used by the pump. Resource concerns include: Soil Erosion (Concentrated flow erosion e.g. irrigation induced), Insufficient Water (Inefficient use of irrigation water), Water Quality Degradation (Excess nutrients in surface and ground waters, Excessive salts in surface and ground waters, Excess pathogens and chemicals from manure, bio-solids or compost applications), Inefficient Energy Use (Equipment and facilities e.g. pumping) Associated Practices: Irrigation Pipeline (430), Pumping Plant (533), Irrigation Water Management (449)

Feature Measure: Length of Lateral Retrofitted

Scenario Unit:: Foot

Scenario Typical Size: 1,300.0

Scenario Total Cost: \$9,874.05

Scenario Cost/Unit: \$7.60

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Irrigation, Sprinkler Package, Renozzle or Retrofit, with drops and pressure regulators	1480	Sprinkler Package - Rennovation including sprinkler nozzle addition, and/or replacement, including new pressure regulators and drops.	Foot	\$7.54	1300	\$9,802.00
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: 443 - Irrigation System, Surface and Subsurface

Scenario #1 - Surge Valve & Controller

Scenario Description:

Installation and utilization of a surge valve with automated controller (including all appurtenances) and installation labor needed to convert from a conventional surface irrigated system to a surge irrigation system. The surging action increases rate of advance along set length, reduces deep percolation at upper end of field, increases uniformity of application along row length, and on lower intake soils can significantly reduce runoff losses. The result is improved irrigation efficiency, reduced leaching and erosion losses, and conserved energy. Resource Concerns: Insufficient Water - Inefficient use of irrigation water, and Degraded Plant Condition - Undesirable plant productivity and health, Water Quality Degradation- Excess nutrients in surface and ground waters, Water Quality Degradation - Excessive sediment in surface waters, and Inefficient Energy Use - Equipment and facilities

Before Situation:

Unacceptable irrigation application uniformity along existing surface irrigation system furrow or border length caused by excessive run length or soil infiltration rate when operated with continuous inflow on existing system. System is over irrigated in attempt to adequately irrigate low end of field.

After Situation:

A surge surface irrigation system is in place. After implementation, distribution uniformity and irrigation efficiency is improved, by reducing irrigation application volume and deep percolation losses. Runoff reductions, reduced energy use, and air quality improvements can also result. Associated Practices: 464-Irrigation Land leveling, 533-Pumping Plant, 449- Irrigation Water Management, 430 - Irrigation Pipeline, 328-Conservation Crop Rotation, and 590 Nutrient Management.

Feature Measure: Number of Surge Valves

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$2,223.41

Scenario Cost/Unit: \$2,223.41

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Materials						
Surge Valve And Controller	1477	Surge Valve and Controller, with appurtenances. Material cost includes valve, controller, all appurtenances, and mobilization.	Each	\$2,179.45	1	\$2,179.45

Practice: 443 - Irrigation System, Surface and Subsurface

Scenario #2 - Multiple Inlet Irrigation

Scenario Description:

Practice involves running above ground pipe to deliver water to individual basins to reduce runoff and improve irrigation efficiency in rice fields that are split into paddies. Payment includes 15" 10mil pipe and plastic flap gates. Resource Concerns: Insufficient Water - Inefficient use of irrigation water, and Degraded Plant Condition - Undesirable plant productivity and health, Water Quality Degradation- Excess nutrients in surface and ground waters, Water Quality Degradation - Excessive sediment in surface waters, and Inefficient Energy Use - Equipment and facilities

Before Situation:

Typical before situation would include a contour levee or basin surface irrigation system. Irrigation water is delivered to individual basins in a 40-acre rice field split into paddies using irrigation canals and field ditches.

After Situation:

After implementation irrigation efficiency is improved, while reducing irrigation application volume, runoff, evaporation losses, and cold water damage to crops. Reduced energy use and air quality improvements can also result. Associated Practices: 464-Irrigation Land leveling, 533-Pumping Plant, 449- Irrigation Water Management, 430 - Irrigation Pipeline, 328-Conservation Crop Rotation, and 590-Nutrient Management.

Feature Measure: Acres Irrigated

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: \$722.30

Scenario Cost/Unit: \$18.06

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Materials						
Pipe, PE, collapsible, weight priced	1385	Polyethylene (PE) compound manufactured into collapsible tubing	Pound	\$1.31	250	\$327.50
Flap gate, plastic, 2 1/2"	1424	2 1/2" plastic flap gate for poly irrigation tubing. Materials only.	Each	\$1.75	100	\$175.00

Practice: 449 - Irrigation Water Management

Scenario #1 - IWM for row crops

Scenario Description:

Implementation of a water management plan for producers using a checkbook method (crop grown, soil moisture conditions prior to irrigation, dates of irrigation start and stop, depths of irrigation applied, duration of irrigations, and amount of rainfall). Payment applies to irrigation water management on a row crop operation. Resource Concerns: Insufficient Water Supply-Inefficient use of irrigation water; Degraded Plant Condition-Undesirable plant productivity and health, and Inefficient Energy Use-Equipment and facilities.

Before Situation:

The irrigator decides when to irrigate based on general crop or soil appearance or limited soil moisture monitoring. System run times are based on past apparent success. The typical irrigated field is a 125 acre corn field with a sprinkler irrigation system.

After Situation:

Irrigations are scheduled based on measured crop water requirements. Records are used to evaluate results of past irrigation events and influence future irrigations. The irrigator keeps records of soil moisture, crop water use, rainfall amounts and irrigation timing and amounts. At the end of the irrigation season all the data has been reviewed and evaluated. Improvements planned for the next season have been determined. Associated Practices: 441-Irrigation System Microirrigation, 442-Irrigation System Sprinkler, 443-Irrigation System Surface and Subsurface.

Feature Measure: Irrigated Area Managed

Scenario Unit:: Acre

Scenario Typical Size: 125.0

Scenario Total Cost: \$1,416.80

Scenario Cost/Unit: \$11.33

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	32	\$1,240.96

Practice: 449 - Irrigation Water Management

Scenario #2 - IWM for microirrigation systems and specialty crops

Scenario Description:

Implementation of a water management plan for producers using a checkbook method (crop grown, soil moisture conditions prior to irrigation, dates of irrigation start and stop, depths of irrigation applied, duration of irrigations, and amount of rainfall). Payment applies to irrigation water management on a specialty crop operation, or an operation utilizing microirrigation. Resource Concerns: Insufficient Water Supply-Inefficient use of irrigation water; Degraded Plant Condition-Undesirable plant productivity and health, and Inefficient Energy Use-Equipment and facilities.

Before Situation:

The farmer decides when to irrigate based on general crop or soil appearance or limited soil moisture monitoring. System run times are based on past apparent success. The typical irrigated field is a 15 acre specialty crop field with a surface irrigation system.

After Situation:

Irrigations are scheduled based on measured crop water requirements. Records are used to evaluate results of past irrigation events and influence future irrigations. The irrigator keeps records of soil moisture, crop water use, rainfall amounts and irrigation timing and amounts. At the end of the irrigation season all the data has been reviewed and evaluated. Improvements planned for the next season have been determined. Associated Practices:441-Irrigation System Microirrigation, 442-Irrigation System Sprinkler, 443-Irrigation System Surface and Subsurface.

Feature Measure: Irrigated Area Managed

Scenario Unit:: Acre

Scenario Typical Size: 15.0

Scenario Total Cost: \$879.20

Scenario Cost/Unit: \$58.61

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Labor

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	40	\$879.20
---------------	-----	--	------	---------	----	----------



Practice: 449 - Irrigation Water Management

Scenario #3 - IWM for Seasonal High Tunnels

Scenario Description:

Implementation of a water management plan for producers using a checkbook method (crop grown, soil moisture conditions prior to irrigation, dates of irrigation start and stop, depths of irrigation applied, duration of irrigations, and amount of rainfall). Payment applies to irrigation water management in Seasonal High Tunnels. Resource Concerns: Insufficient Water Supply-Inefficient use of irrigation water; Degraded Plant Condition-Undesirable plant productivity and health, and Inefficient Energy Use-Equipment and facilities.

Before Situation:

The farmer decides when to irrigate based on general crop or soil appearance or limited soil moisture monitoring. System run times are based on past apparent success.

After Situation:

Irrigations are scheduled based on measured crop water requirements. Records are used to evaluate results of past irrigation events and influence future irrigations. The irrigator keeps records of soil moisture, crop water use, and irrigation timing and amounts. At the end of the irrigation season all the data has been reviewed and evaluated. Improvements planned for the next season have been determined. The typical irrigated area is approximately 2,000 sq ft under a Seasonal High Tunnel. Associated Practices: 441-Irrigation System Microirrigation, 442-Irrigation System Sprinkler, 443-Irrigation System Surface and Subsurface.

Feature Measure: Number of High Tunnels

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$439.60

Scenario Cost/Unit: \$439.60

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	20	\$439.60

Practice: 449 - Irrigation Water Management

Scenario #5 - Soil Moisture Sensors with Data Recorder

Scenario Description:

This practice includes the installation of electrical soil moisture sensors such as capacitance or resistance sensors that are monitored to determine soil moisture. The installation includes the purchase of soil moisture sensors, installation equipment (probe or auger), and a data logger to log continuous soil moisture data that can be downloaded to a personal computer and associated graphing software. Scenario also includes the labor associated with using the equipment for the first year. Typical Scenario involves installation of resistance sensor blocks in a 120 acre field of sprinkler irrigated cropland. Producer periodically monitors soil moisture sensors during the growing season. Resource Concerns: Insufficient Water - Inefficient use of irrigation water, and Degraded Plant Condition - Undesirable plant productivity and health, and Inefficient Energy Use - Equipment and facilities.

Before Situation:

Producer uses feel method to estimate soil moisture for scheduling irrigation in the field.

After Situation:

Producer has installed four sensors at each monitoring site to a depth of four feet with one sensor representing each foot of depth. Producer periodically downloads continuously recorded soil moisture measurements that are used to schedule irrigation more effectively resulting in improved irrigation water management and reduced energy use. Associated Practices: 441-Irrigation System Microirrigation, 442-Irrigation System Sprinkler, 443-Irrigation System Surface and Subsurface., 587-Structure for water Control, 328-Conservation Crop Rotation, and 590-Nutrient Management.

Feature Measure: Number of Measuring Sites

Scenario Unit:: Each

Scenario Typical Size: 2.0

Scenario Total Cost: \$3,702.21

Scenario Cost/Unit: \$1,851.11

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	12	\$263.76
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	40	\$1,551.20
Materials						
Data Logger	1453	Data Logger W/Graphic Output for water management. Materials only.	Each	\$760.64	2	\$1,521.28
Soil Moisture Sensor	1456	Soil moisture resistance sensor W/10' cables. Equipment only.	Each	\$36.74	8	\$293.92
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: 449 - Irrigation Water Management

Scenario #15 - Advanced IWM

Scenario Description:

A high intensity irrigation water management system for producers using a checkbook method with advanced methods of determining irrigation water applied, and estimating crop evapotranspiration, monitoring field soil moisture, or monitoring crop temperature stress. Typical methods include flow measurement, daily record keeping, and use of real-time evapotranspiration estimates (such as those provided dedicated weather stations) and/or soil moisture sensors with automated data logging to monitor field soil moisture content and/or crop temperature. For this scenario, soil moisture is determined by automated soil moisture monitoring stations equipped with telemetry data. Telemetry data is automatically sent to a computer with irrigation software. Irrigator also receives real time data via mobile phone applications. Some data such as total water applied may be entered into computer software manually. Resource Concerns: Insufficient Water Supply-Inefficient use of irrigation water; Degraded Plant Condition-Undesirable plant productivity and health, and Inefficient Energy Use-Equipment and facilities. Associated Practices: 441-Irrigation System, Microirrigation; 442-Irrigation System, Sprinkler; 443-Irrigation System, Surface and Subsurface.

Before Situation:

The farmer decides when to irrigate based on general crop or soil appearance or limited soil moisture monitoring. System run times are based on past apparent success. The typical irrigated field is a 125 acre corn field with sprinkler irrigation.

After Situation:

Irrigations are scheduled based on measured crop water requirements. Records are used to evaluate results of past irrigation events and influence future irrigations. The irrigator keeps records of soil moisture, crop water use, rainfall amounts and irrigation timing and amounts. At the end of the irrigation season all the data has been reviewed and evaluated. Improvements planned for the next season have been determined.

Feature Measure: Irrigated Area Managed

Scenario Unit:: Acre

Scenario Typical Size: 125.0

Scenario Total Cost: \$2,213.12

Scenario Cost/Unit: \$17.70

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	48	\$1,861.44

Practice: 464 - Irrigation Land Leveling

Scenario #1 - Irrigation Land Leveling

Scenario Description:

Reshaping of the surface of land to be irrigated to planned grades to permit uniform and efficient application of irrigation water to the leveled land. The field is leveled such that it is uniform and drains to a specifically targeted part of the field. Resource Concern: Excess/Insufficient - Inefficient Use of Irrigation Water

Before Situation:

Irregular field surface reduces uniformity of surface application and thus irrigation efficiency by localized ponding and/or excess runoff/runon.

After Situation:

Cropland will be reshaped to provide uniform distribution of irrigation water in order to promote irrigation efficiencies. Associated Conservation Practices: 449 - Irrigation Water Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 160.0

Scenario Total Cost: \$43,175.50

Scenario Cost/Unit: \$269.85

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	20000	\$43,000.00
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: 472 - Access Control

Scenario #2 - Animal exclusion from sensitive areas

Scenario Description:

Excluding animals from an area in order to address identified resource concerns. This is for facilitating exclusion of animals to protect or enhance natural resource values. Any need for permanent fencing will be planned and installed using the Fence practice (382). Clearing of brush and trees is not necessary. Resource concerns include Wildlife Habitat degradation, Undesirable plant productivity and health, and/or Excessive sediment in surface waters.

Before Situation:

Sensitive areas are threatened by the adverse actions of domestic and/or wild animals. The importance of the sensitive areas can include (but are not limited to): wildlife habitat, plant species composition, newly established trees and/or plants, stream bank stability, and/or water quality.

After Situation:

Sensitive areas are protected from the adverse actions of domestic and/or wild animals by excluding them from the area. Cost represents forgone income for typical situations for conventional, organic, and transitioning to organic producers. Associated Practices: Prescribed Grazing, Pipeline, Water Well, Spring Development, Heavy Use Area, Pumping Plant, Watering Facility, Forage and Biomass Planting, Critical Area Planting, Fence.

Feature Measure: Acres excluded

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$443.89

Scenario Cost/Unit: \$44.39

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	26	\$432.90
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	0.5	\$10.99

Practice: 484 - Mulching

Scenario #1 - Natural Material, Vegetation Establishment

Scenario Description:

Application of straw mulch or other state approved natural material to reduce erosion and facilitate the establishment of vegetative cover. Mulch provides a minimum of 70% ground coverage on a disturbed site around a newly constructed structural practice and is generally used with critical area planting.

Before Situation:

Typical scenario ranges from a 0.1 to 1.0 acre disturbed site around a newly constructed structural practice. The potential for soil erosion is high and mulch is needed to stabilize the soil and facilitate the establishment of vegetative cover.

After Situation:

Straw mulch has been applied to areas needing mulch. Erosion and sedimentation is reduced, water and soil quality is protected, and vegetative cover is established. Associated Practice: 342 Critical Area Planting

Feature Measure: Area Covered by Mulch

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$323.95

Scenario Cost/Unit: \$323.95

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	1	\$25.27
Mulcher, straw blower	1305	Straw bale mulcher/blower to mechanically spread small or large straw bales. Labor not included.	Hour	\$45.60	1	\$45.60
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	1	\$22.09
Materials						
Straw	1237	Small grain straw (non organic and certified organic). Includes materials only.	Ton	\$128.33	1.8	\$230.99

Practice: 484 - Mulching

Scenario #4 - Natural Material, Soil Moisture Management

Scenario Description:

Application of straw mulch or other state approved natural material (such as wood chips, compost, or hay) to conserve soil moisture, reduce erosion, moderate soil temperature and improve soil health. Typically used to provide partial coverage (either in-row or between rows) with tree/shrub plantings, irrigated orchards or vineyards, or annual and perennial specialty crops. Mulches applied around growing plants shall have 100 % ground cover. Thickness of the mulch shall be adequate to prevent evaporation. Payment based on total acres mulched, assuming 3-5 ft. swatch and 10-12 ft. row spacing.

Before Situation:

Site conditions vary. Typical conditions include no protective cover resulting in excessive erosion, increased soil temperature and reduced soil moisture.

After Situation:

Straw or other natural mulch is applied in rows by hand or by mechanized means. Soil moisture is conserved, energy use associated with irrigation is decreased, and soil health is improved.

Feature Measure: Area Covered by Mulch

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$424.25

Scenario Cost/Unit: \$424.25

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	0.5	\$11.11
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	4.2	\$92.32
Materials						
Straw	1237	Small grain straw (non organic and certified organic). Includes materials only.	Ton	\$128.33	2.5	\$320.83

Practice: 484 - Mulching

Scenario #5 - Synthetic Material, Soil Moisture Management

Scenario Description:

Installation of geotextile, biodegradable plastic, polyethylene plastic, or other state approved synthetic mulch to conserve soil moisture, reduce erosion, and moderate soil temperature. Typically used in-row with tree/shrub plantings, irrigated orchards or vineyards, or annual and perennial specialty crops. Payment based on actual area covered by mulching material.

Before Situation:

Site conditions vary. Typical conditions include no protective cover resulting in excessive erosion, increased soil temperature and reduced soil moisture.

After Situation:

Synthetic mulch is applied in rows with a mulch layer or by other mechanized means. Soil moisture is conserved and energy use associated with irrigation is decreased.

Feature Measure: Area Covered by Mulch

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,724.64

Scenario Cost/Unit: \$1,724.64

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Materials						
Mulch, biodegradable plastic, 0.8 mil	1304	0.8 mil starch-based biodegradable plastic mulch, with anchoring. Includes materials and shipping only.	Square Yard	\$0.32	4840	\$1,548.80



Practice: 484 - Mulching

Scenario #6 - Tree and Shrub, Individual Treatment, Soil Moisture Management

Scenario Description:

Weed barrier fabric or other suitable natural or synthetic mulch is installed with a new tree and shrub planting where planting material are not planted in rows, thus requiring each tree or shrub to be treated individually. Typically used to conserve soil moisture, reduce erosion, and moderate soil temperature. Rate is per tree/shrub and assumes 1 square yard of weed barrier fabric and 5 staples/tree. Typical scenario is an installation of 100 native trees and shrubs to enhance wildlife habitat.

Before Situation:

Site conditions vary. Sites are often remote and trees may not be planted in rows, requiring each tree to be treated individually. The lack of mulch causes reduced soil moisture requiring additional irrigation or poor growth and/or survival.

After Situation:

Weed barrier fabric squares are installed with 5 sod staples each, around individual trees and shrubs. Soil moisture is conserved and energy use associated with irrigation is decreased improving growth and survival of trees/shrubs.

Feature Measure: Number of Trees Mulched

Scenario Unit:: Each

Scenario Typical Size: 100.0

Scenario Total Cost: \$239.00

Scenario Cost/Unit: \$2.39

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.39	100	\$239.00

Practice: 484 - Mulching

Scenario #7 - Natural Material, Soil Moisture Management, Seasonal High Tunnel

Scenario Description:

Application of straw mulch or other state approved natural material (such as wood chips, compost, or hay) to conserve soil moisture, moderate soil temperature and improve soil health within a Season High Tunnel. Typically used to provide 100% coverage (in-row and between rows) to suppress weeds competing with annual and perennial crops crown in the high tunnel. Mulches applied around growing plants shall have 100% ground cover. Thickness of the mulch shall be adequate to prevent evaporation.

Before Situation:

Site conditions vary. Typical conditions include no protective cover resulting in increased soil temperature and reduced soil moisture.

After Situation:

Straw or other natural mulch is applied in tightly spaced rows by hand. Soil moisture is conserved, energy use associated with irrigation is decreased, and soil health is improved.

Feature Measure: Each Seasonal High Tunnel

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$38.78

Scenario Cost/Unit: \$38.78

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	0.5	\$11.11
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	0.5	\$10.99
Materials						
Straw	1237	Small grain straw (non organic and certified organic). Includes materials only.	Ton	\$128.33	0.13	\$16.68

Practice: 484 - Mulching

Scenario #8 - Synthetic Material, Soil Moisture Management, Seasonal High Tunnel

Scenario Description:

Installation of geotextile, biodegradable plastic, polyethylene plastic, or other state approved synthetic mulch to conserve soil moisture, and moderate soil temperature within a Seasonal High Tunnel. Typically used in row with annual and perennial crops crown in the high tunnel.

Before Situation:

Site conditions vary. Typical conditions include no protective cover resulting in increased soil temperature and reduced soil moisture.

After Situation:

Synthetic mulch is applied in rows by hand. Soil moisture is conserved and energy use associated with irrigation is decreased.

Feature Measure: Each Seasonal High Tunnel

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$76.65

Scenario Cost/Unit: \$76.65

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	0.5	\$11.11
---------------	-----	---	------	---------	-----	---------

Labor

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	1	\$21.98
---------------	-----	--	------	---------	---	---------

Materials

Mulch, polyethylene plastic, 1.0 mil	1303	1.0 mil polyethylene plastic mulch, with anchoring. Includes materials and shipping only.	Square Yard	\$0.36	121	\$43.56
--------------------------------------	------	---	-------------	--------	-----	---------

Practice: 490 - Tree/Shrub Site Preparation

Scenario #1 - Chemical Application

Scenario Description:

This practice involves the use of various herbicides applied using ground-based machinery in order to remove undesirable vegetation and improve site conditions for establishing trees and/or shrubs. Typical sites include abandoned fields, pastures, rangelands, agricultural fields or forestland that was recently harvested. This practice is typically used to address the following resource concerns: degraded plant condition - undesirable plant productivity and health and inadequate structure and composition.

Before Situation:

Undesirable vegetation is present on the site including herbaceous plants and woody vegetation. Noxious and invasive species may also be present on the site. If left uncontrolled, undesirable vegetation will inhibit successful establishment of target species of trees and/or shrubs.

After Situation:

Undesirable vegetation has been treated using appropriate herbicides, reducing competition for target trees and/or shrubs. Site conditions are favorable for successful establishment of trees and/or shrubs. The typical size of the practice is 40 acres. Associated practices may include: 612 Tree and Shrub Establishment, 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Feature Measure: Area of Treatment

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: \$2,201.50

Scenario Cost/Unit: \$55.04

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	40	\$250.40
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	40	\$699.20
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$25.63	40	\$1,025.20
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shi	Acre	\$1.28	40	\$51.20
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: 490 - Tree/Shrub Site Preparation

Scenario #2 - Light Mechanical

Scenario Description:

This practice involves the use of light/moderate machinery to clear above ground vegetation and to also rip/cut/lift underground root systems in order to improve site conditions for establishing trees and/or shrubs. Typical sites include abandoned fields, pastures, rangelands, agricultural fields or forestlands that have been harvested. This following resource concerns: soil quality degradation - compaction, soil erosion - sheet and rill, and degraded plant condition - undesirable plant productivity and health and inadequate structure and composition.

Before Situation:

Undesirable vegetation is present on the site including herbaceous plants and sparse woody competition. Noxious and invasive species may also be present on the site. If left uncontrolled, undesirable vegetation will inhibit successful establishment of target species of trees and/or shrubs. Soils are compacted as a result of harvesting heavy equipment activities or other land uses.

After Situation:

Undesirable vegetation has been removed using a bush hog to knock down stand vegetation and heavy tillage equipment is used to breakup and lift root systems, breakup plow pans (<18" deep), thus enhancing the conditions for planting and survival of trees and/or shrubs. Soil compaction has been alleviated, allowing penetration of moisture and allowing roots to grow properly. Site conditions are favorable for successful establishment of trees and/or shrubs. The typical size of the practice is 40 acres. Associated practices may include: 612 Tree and Shrub Establishment, 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Feature Measure: Area of Treatment

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: \$2,229.08

Scenario Cost/Unit: \$55.73

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	16	\$847.04
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	\$16.94	40	\$677.60
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	16	\$353.44
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00

Practice: 490 - Tree/Shrub Site Preparation

Scenario #3 - Light Mechanical with Chemical

Scenario Description:

This practice involves the use of light/moderate machinery to clear above ground vegetation and to also rip/cut/lift underground root systems followed by appropriate herbicide application in order to improve site conditions for establishing trees and/or shrubs. Typical sites include small trees (<2" dbh) and brush cover on less than 60% of area that is not appropriate to the site or providing the desired condition for the landowner. Typical sites include abandoned fields, pastures, rangelands, agricultural fields or forestlands that have been harvested. This following resource concerns: soil quality degradation - compaction, soil erosion - sheet and rill, and degraded plant condition - undesirable plant productivity and health and inadequate structure and composition.

Before Situation:

Undesirable vegetation is present on the site including herbaceous plants and sparse woody competition. Noxious and invasive species may also be present on the site. If left uncontrolled, undesirable vegetation will inhibit successful establishment of target species of trees and/or shrubs. Soils are compacted as a result of harvesting heavy equipment activities or other land uses.

After Situation:

Undesirable vegetation has been removed using a bush hog to knock down stand vegetation and heavy tillage equipment is used to breakup and lift root systems, breakup plow pans (<18" deep), thus enhancing the conditions for planting and survival of trees and/or shrubs. Soil compaction has been alleviated, allowing penetration of moisture and allowing roots to grow properly. Site conditions are favorable for successful establishment of trees and/or shrubs. The typical size of the practice is 40 acres. Associated practices may include: 612 Tree and Shrub Establishment, 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Feature Measure: Area of Treatment

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: \$4,430.58

Scenario Cost/Unit: \$110.76

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	16	\$847.04
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	\$16.94	40	\$677.60
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	40	\$250.40
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	16	\$353.44
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	40	\$699.20
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$25.63	40	\$1,025.20
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shi	Acre	\$1.28	40	\$51.20
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	3	\$526.50

Practice: 511 - Forage Harvest Management

Scenario #1 - Improved Forage Quality

Scenario Description:

Improved cultural practices and recordkeeping result in better forage quality and better livestock performance.

Before Situation:

Forage cutting heights are as close to the ground as equipment will allow resulting in very low stubble height. Plant regrowth is very slow. Forage quality tests are not regularly done. Records of forage quality components, cutting heights, moisture content, and harvest schedule are not regularly kept.

After Situation:

Forage cutting heights are raised to leave at least 3-4" stubble height for cool season grasses and 6" - 8" (use a boot on the mower) for warm season grasses. Increased residual forage results in much faster plant regrowth. Forage quality tests are submitted to an accredited lab for analysis. Records of forage quality components, cutting heights, moisture content, and harvest schedule are regularly kept to track increased forage quality and improved livestock performance.

Feature Measure: Improved Relative Feed Value

Scenario Unit:: Acre

Scenario Typical Size: 30.0

Scenario Total Cost: \$148.50

Scenario Cost/Unit: \$4.95

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	1	\$35.36
Materials						
Test, Plant Tissue Test	301	Tissue analysis for crops. Includes materials and shipping only.	Each	\$24.61	2	\$49.22

Practice: 511 - Forage Harvest Management

Scenario #2 - Preemptive Harvest

Scenario Description:

Preemptive harvest of forage crops to prevent damage from insects (such as leafhopper on alfalfa) or other pests results in better forage quality and better livestock performance.

Before Situation:

Forage pests are usually controlled with pesticides.

After Situation:

Forage pests are controlled by executing a preemptive harvest before pests can damage forage quality. Forage yields are reduced because of immature stage of forage growth. Forage tests are submitted to an accredited lab for analysis. Records of forage quality components are used to adjust feeding rations.

Feature Measure: Relative Feed Value Maintained

Scenario Unit:: Acre

Scenario Typical Size: 30.0

Scenario Total Cost: \$148.50

Scenario Cost/Unit: \$4.95

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	1	\$35.36
Materials						
Test, Plant Tissue Test	301	Tissue analysis for crops. Includes materials and shipping only.	Each	\$24.61	2	\$49.22



Practice: 511 - Forage Harvest Management

Scenario #3 - Perennial Crops - Delayed Mowing

Scenario Description:

In perennial forage crops, delaying the harvest of the first cutting to promote the reproduction of ground nesting birds. The delayed harvest results in a decrease in overall forage quality (33% reduction assumed), making the forage crop less palatable and lower in relative feed value. The selected fields should be large enough to promote ground nesting birds. After young have fledged the field will be harvested for dry forages.

Before Situation:

Perennial forage crops are produced and harvested; ground nesting birds are disturbed and/or fledgling birds are killed in the process.

After Situation:

Perennial crops are harvested with a delayed mowing; forage quality is compromised, however, the survival of ground nesting birds is promoted.

Feature Measure: Increased grassland bird populatio

Scenario Unit:: Acre

Scenario Typical Size: 30.0

Scenario Total Cost: \$173.48

Scenario Cost/Unit: \$5.78

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	1.5	\$24.98
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	1	\$35.36
Materials						
Test, Plant Tissue Test	301	Tissue analysis for crops. Includes materials and shipping only.	Each	\$24.61	2	\$49.22

Practice: 511 - Forage Harvest Management

Scenario #5 - Doublecropping - Delayed harvest and subsequent planting

Scenario Description:

In doublecropped annual forages, delaying the harvest of the first crop will provide feed and shelter for ground nesting birds. Delaying the harvest results in a decrease in overall forage quality, making the forage crop less palatable and lower in relative feed value. The selected fields should be large enough to promote ground nesting birds. After the young have fledged the second crop will be planted, approximately one month later than normal. Subsequently, the harvest of the second crop will cause an approximately 20% yield decline. The selected area should be large enough to buffer adults and nestlings from silage chopping in adjacent areas or fields. After young have fledged the field will be chopped and used as grain or silage. This practice is best planned cooperatively with the farmer and appropriate wildlife agencies far enough in advance to reduce disturbance to ground nesting birds.

Before Situation:

Double cropped annual forage crops are produced and harvested; ground nesting birds are disturbed and/or fledgling birds are killed in the process.

After Situation:

Double cropped annual crops are harvested with a delayed harvest and a subsequent later planting of the second crop; forage quality is compromised somewhat, however, the survival of ground nesting birds is promoted.

Feature Measure: Increased grassland bird populatio

Scenario Unit:: Acre

Scenario Typical Size: 30.0

Scenario Total Cost: \$185.13

Scenario Cost/Unit: \$6.17

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	2.2	\$36.63
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	1	\$35.36
Materials						
Test, Plant Tissue Test	301	Tissue analysis for crops. Includes materials and shipping only.	Each	\$24.61	2	\$49.22

Practice: 512 - Forage and Biomass Planting

Scenario #1 - Interseeding Legumes and/or forbs

Scenario Description:

Interseed legumes and/or forbs into an existing grass stand for the purpose of increasing plant diversity, soil quality and fertility, and plant health and enhancing the quality of forage. Scenario is appropriate for conventional production. Payment includes seed, seeding and fertility for interseeding establishment.

Before Situation:

Existing grass stand that needs additional species diversity.

After Situation:

A more diverse grass stand provides improved forage quality and availability, and improved soil condition. Payment scenario is based on red and ladino clover interseeded into a 20 acre cool season grass stand. Inputs are based on medium to low existing fertility.

Feature Measure: Acres of Forage and Biomass Plant

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: \$3,584.80

Scenario Cost/Unit: \$179.24

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.75	20	\$135.00
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$10.84	20	\$216.80
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	20	\$435.60
Materials						
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.45	700	\$315.00
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.35	2000	\$700.00
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	\$18.22	40	\$728.80
Two Species Mix, Cool Season Annual (1 grass and 1 legume)	2314	Cool season annual grass and legume mix. Includes material and shipping only.	Acre	\$52.68	20	\$1,053.60

Practice: 512 - Forage and Biomass Planting

Scenario #3 - Introduced Grass Establishment or Renovation

Scenario Description:

Establishing a new stand or renovating a poor stand to introduced grass, or grass with legumes and/or forbs to improve or maintain livestock/wildlife nutrition and health, extend the length of the grazing season, and provide soil cover to reduce erosion. Scenario is appropriate for conventional production. Payment includes site preparation, seed, seeding fertilizer, lime, and foregone income for loss of production during establishment/renovation

Before Situation:

Existing grass stand does not meet the forage demands, particularly during periods of low forage production. Resource concerns may include undesirable plant productivity and health, inadequate feed and forage for livestock, soil erosion, and soil quality.

After Situation:

Establish introduced grass and legume mix stand to improve livestock nutrition through improved forage quality and availability, and improved soil condition. Payment scenario is based on converting an existing poor condition sod to introduced grass/legume/forb mix using mechanical or chemical activities.

Feature Measure: Acres of Forage and Biomass Planti

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: \$4,656.40

Scenario Cost/Unit: \$232.82

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	20	\$125.20
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.75	20	\$135.00
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$10.84	20	\$216.80
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	20	\$435.60
Foregone Income						
Fl, Hay, General Grass	2122	General Grass Hay is Primary Land Use	Ton	\$42.52	20	\$850.40
Materials						
Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.43	1000	\$430.00
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.45	860	\$387.00
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.35	1660	\$581.00
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	\$18.22	40	\$728.80
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	20	\$349.60
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2319	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	\$20.85	20	\$417.00

Practice: 512 - Forage and Biomass Planting

Scenario #7 - Native Grass Establishment or Renovation - with fertility

Scenario Description:

Establishing a new stand or renovating a poor stand to native grass, or grass with legumes and/ to improve or maintain livestock/wildlife nutrition and health, extend the length of the grazing season, and provide soil cover to reduce erosion. Scenario is appropriate for conventional production on sites where fertilizer is needed for establishment. Payment includes site preparation, seed, seeding, fertilizer, lime and foregone income for loss of production during establishment/renovation

Before Situation:

Existing grass stand does not meet the forage demands, particularly during periods of low forage production. Resource concerns may include undesirable plant productivity and health, inadequate feed and forage for livestock, soil erosion, and soil quality.

After Situation:

Establish native grass and legume and/or forbs mix stand to improve livestock nutrition through improved forage quality and availability, and improved soil condition. Payment scenario is based on converting an existing poor condition sod to native grass/legume/forb mix using mechanical or chemical activities.

Feature Measure: Acres of Forage and Biomass Planti

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: \$8,828.00

Scenario Cost/Unit: \$441.40

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	20	\$125.20
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$10.84	20	\$216.80
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	20	\$435.60
Foregone Income						
Fl, Hay, General Grass	2122	General Grass Hay is Primary Land Use	Ton	\$42.52	40	\$1,700.80
Materials						
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.45	860	\$387.00
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.35	1660	\$581.00
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	\$18.22	40	\$728.80
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	20	\$349.60
Three plus Species Mix, Warm Season, Native Perennial	2327	Native, warm season perennial grass. Includes material and shipping only.	Acre	\$215.16	20	\$4,303.20

Practice: 512 - Forage and Biomass Planting

Scenario #9 - Pasture Renovation Utilizing Interim Seeding

Scenario Description:

Renovation of an existing pasture where an interim stand is established for one year prior to the perennial stand being established. Scenario is appropriate for renovating an existing stand of endophyte infected fescue using the spray - smother - spray technique (spray existing grass before heading in early spring, plant a smother crop, spray smother crop in the fall, plant new grass stand into the stubble). Scenario is also appropriate for situations where any interim species is established and then the perennial is seeded after. Payment includes chemical operations, interim crop establishment and termination, and seeding of new renovated grass stand, including fertilizer and lime needed for a successful establishment.

Before Situation:

Existing grass stand is primarily endophyte infected fescue or unwanted vegetative cover in decreased animal health and productivity.

After Situation:

Stand is renovated without the loss of production. Annual grass planted as a smother crop would be grazed, extending the grazing season. Stand is renovated to a non-endophyte introduced grass/legume stand using the spray-smother-spray technique.

Feature Measure: Acres of Forage and Biomass Planti

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: \$6,620.40

Scenario Cost/Unit: \$331.02

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	40	\$250.40
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.75	20	\$135.00
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$10.84	20	\$216.80
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	40	\$871.20
Foregone Income						
Fl, Hay, General Grass	2122	General Grass Hay is Primary Land Use	Ton	\$42.52	20	\$850.40
Materials						
Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.43	1000	\$430.00
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.45	860	\$387.00
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.35	1660	\$581.00
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	\$18.22	40	\$728.80
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	40	\$699.20
Two Species Mix, Cool Season Annual (1 grass and 1 legume)	2314	Cool season annual grass and legume mix. Includes material and shipping only.	Acre	\$52.68	20	\$1,053.60
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2319	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	\$20.85	20	\$417.00

Practice: 516 - Livestock Pipeline

Scenario #1 - Above Ground Pipeline

Scenario Description:

An above ground plastic pipeline is installed to convey water from a source of supply to points of use for livestock in a prescribed grazing system or wildlife for temporary watering locations.

Before Situation:

Livestock have an inadequate or unacceptable water supply which can lead to compromised animal health. Water can be supplied from a central source(s) by piping to one or more locations in the pasture. Water locations are temporary and occur during non-freezing times of the year.

After Situation:

An above ground plastic pipeline is installed to convey water from a water source to point of use for temporary watering. Payment incorporates pipe and quick connect coupler and fittings. The pipeline is installed as a facilitating practice for supplying water in a managed grazing system, to reduce soil erosion, improve water quality, improve health and vigor of key forage plant species and improve or maintain animal health. The pipeline is to be protected from UV radiation damage, as well as damage from vehicles, animals, people, and fire. The landowner is responsible for repair or replacement of the pipeline as necessary under O&M during the specified life span of the practice. Cost data is applicable to organic and conventional agricultural production systems. Associated practices include Fencing (382), Prescribed Grazing (528), Trails and Walkways (575), Access Control (472), Pumping Plant (533), Water Well (642), Heavy Use Area (561) and Watering Facility (614).

Feature Measure: Foot

Scenario Unit:: Foot

Scenario Typical Size: 2,000.0

Scenario Total Cost: \$2,135.65

Scenario Cost/Unit: \$1.07

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Materials						
Pipe, HDPE, smooth wall, weight priced	1379	High Density Polyethylene (HDPE) compound manufactured into smooth wall pipe. Materials only.	Pound	\$2.10	878	\$1,843.80
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: 516 - Livestock Pipeline

Scenario #2 - Buried Pipeline, < 2in Plastic

Scenario Description:

Installation of a plastic pipeline, less than 2" diameter, to convey water from a source of supply to points of use for livestock in a prescribed grazing system or for wildlife. Installation is by trenching, or by backhoe across a stream or other locations where installation of the pipeline by trenching is not feasible.

Before Situation:

Livestock have an inadequate or unacceptable water supply which can lead to compromised animal health. Water can be supplied from a central source(s) by piping to one or more locations in the pasture. Soil conditions are suitable for pipe installation without bedding.

After Situation:

A 1½ inch diameter, Schedule 40 PVC plastic pipeline for stockwatering, 4165 ft long is installed for supplying water in a managed grazing system, to reduce soil erosion, improve water quality, improve health and vigor of key forage plant species and improve or maintain animal health. Payment includes couplers and fittings. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated practices include Fencing (382), Prescribed Grazing (528), Trails and Walkways (575), Access Control (472), Pumping Plant (533), Water Well (642), Heavy Use Area (561) and Watering Facility (614).

Feature Measure: Foot

Scenario Unit:: Foot

Scenario Typical Size: 4,165.0

Scenario Total Cost: \$10,228.36

Scenario Cost/Unit: \$2.46

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	12	\$686.04
Trencher, 8"	936	Equipment and power unit costs. Labor not included.	Hour	\$91.63	34	\$3,115.42
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	42	\$923.16
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	34	\$751.06
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	9	\$254.70
Materials						
Pipe, PVC, 1 1/2", SCH 40	975	Materials: - 1 1/2" - PVC - SCH 40 - ASTM D1785	Foot	\$1.00	4165	\$4,165.00
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93



Practice: 516 - Livestock Pipeline

Scenario #3 - Buried Pipeline, 2in - 3in Plastic

Scenario Description:

Installation of a 2" - 3" diameter plastic pipeline to convey water from a source of supply to points of use for livestock in a prescribed grazing system or for wildlife. Installation is by trenching, or by backhoe across a stream or other locations where installation of the pipeline by trenching is not feasible.

Before Situation:

Livestock have an inadequate or unacceptable water supply which can lead to compromised animal health. Water can be supplied from a central source(s) by piping to one or more locations in the pasture. Soil conditions are suitable for pipe installation without bedding.

After Situation:

A 2½ inch diameter, Schedule 40 PVC plastic pipeline for stockwatering, 3300 ft long is installed for supplying water in a managed grazing system, to reduce soil erosion, improve water quality, improve health and vigor of key forage plant species and improve or maintain animal health. Payment includes couplers and fittings. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated practices include Fencing (382), Prescribed Grazing (528), Trails and Walkways (575), Access Control (472), Pumping Plant (533), Water Well (642), Heavy Use Area (561) and Watering Facility (614).

Feature Measure: Foot

Scenario Unit:: Foot

Scenario Typical Size: 3,300.0

Scenario Total Cost: \$11,752.08

Scenario Cost/Unit: \$3.56

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	12	\$686.04
Trencher, 8"	936	Equipment and power unit costs. Labor not included.	Hour	\$91.63	25	\$2,290.75
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	33	\$725.34
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	25	\$552.25
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	12	\$339.60
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.77	3856	\$6,825.12
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 516 - Livestock Pipeline

Scenario #4 - Buried Pipeline, >3in

Scenario Description:

Installation of a large diameter plastic pipeline to convey livestock water from a spring development to a watering facility to service a prescribed grazing system.

Before Situation:

Livestock have an inadequate or unacceptable water supply which can lead to compromised animal health. Water can be supplied from a central source such as a spring by piping to a watering facility. Soil conditions are suitable for pipe installation without bedding.

After Situation:

A delivery pipe (typically 4" diameter, Schedule 40 PVC Plastic) from a spring development to a watering facility, or from water source to watering facility for gravity flow systems. The pipeline is installed as a facilitating practice for supplying water in a managed grazing system, to reduce soil erosion, improve water quality, improve health and vigor of key forage plant species and improve or maintain animal health. Payment incorporates couplers and fittings. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated practices include Fencing (382), Prescribed Grazing (528), Trails and Walkways (575), Access Control (472), Pumping Plant (533), Water Well (642), Heavy Use Area (561) and Watering Facility (614).

Feature Measure: Foot

Scenario Unit:: Foot

Scenario Typical Size: 800.0

Scenario Total Cost: \$5,112.11

Scenario Cost/Unit: \$6.39

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, 12" x 60"	1459	Trenching, earth, 12" wide x 60" depth, includes equipment and labor for trenching, laying 3"-6" CPP drain line with envelope, and backfilling.	Foot	\$1.99	800	\$1,592.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.77	1742	\$3,083.34
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 516 - Livestock Pipeline

Scenario #6 - Cased Pipeline with Boring

Scenario Description:

Installation of a 2"- 3" plastic pipeline within an outer casing, bored under a road or other obstruction to convey water from a source of supply to points of use for livestock in a prescribed grazing system or wildlife.

Before Situation:

Livestock have an inadequate or unacceptable water supply which can lead to compromised animal health. Water can be supplied from a central source(s) by piping to one or more locations in the pasture. Soil conditions or location require boring to facilitate pipe installation.

After Situation:

The typical installation consists of installing 60 feet of a 2.5 inch, Schedule 40 PVC plastic pipe with a 4 inch outer casing under a roadbed. Pipeline boring includes all pipe under roadbed and labor and equipment involved during installation of pipe. The pipeline is installed as a facilitating practice for supplying water in a managed grazing system, to reduce soil erosion, improve water quality, improve health and vigor of key forage plant species and improve or maintain animal health. Payment incorporates couplers and fittings. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated practices include Fencing (382), Prescribed Grazing (528), Trails and Walkways (575), Access Control (472), Pumping Plant (533), Water Well (642), Heavy Use Area (561) and Watering Facility (614).

Feature Measure: Foot

Scenario Unit:: Foot

Scenario Typical Size: 60.0

Scenario Total Cost: \$6,386.99

Scenario Cost/Unit: \$106.45

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	1	\$57.17
Horizontal Boring, Greater Than 3" diameter	1132	Includes equipment, labor and setup.	Foot	\$87.53	60	\$5,251.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	1	\$28.30
Materials						
Pipe, PE, 4", DR 9	1002	Materials: - 4" - PE - 160 psi - ASTM D3035 DR 9	Foot	\$6.00	60	\$360.00
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.77	70	\$123.90
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: 521B - Pond Sealing or Lining, Soil Dispersant

Scenario #1 - Soil Dispersant - Uncovered

Scenario Description:

Construction of a compacted soil liner, treated with a soil dispersant, to reduce seepage from ponds or waste storage impoundment structures. Practice implementation includes incorporation of the dispersant with the soil liner under proper moisture conditions and compaction to the designed liner thickness. Practice implementation may require filter compatibility with the subgrade (graded filter or geotextile). Associated practice PS378, PS313.

Before Situation:

In-place soils at site exhibit seepage rates in excess of acceptable limits. Soils are suitable for treatment with dispersants.

After Situation:

Water conservation and environmental protection provided by limiting seepage losses from ponds or waste storage impoundments.

Feature Measure: Volume of Liner Material

Scenario Unit:: Cubic Yard

Scenario Typical Size: 1,613.0

Scenario Total Cost: \$10,915.45

Scenario Cost/Unit: \$6.77

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	1613	\$6,548.78
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	\$58.85	6	\$353.10
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	6	\$132.54
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	8	\$310.24
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50
Materials						
Soil Dispersant	1490	Soil Amendment (tetrasodium pyrophosphate (TSPP), sodium tripolyphosphate (STPP), or soda ash or approved equivalent)	Ton	\$478.31	6.53	\$3,123.36
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 528 - Prescribed Grazing

Scenario #1 - Low Intensity, > 7 Day Rotation Frequency

Scenario Description:

Design and implementation of a grazing system that will enhance pasture condition and ecosystem function as well as optimize efficiency and economic return through monitoring (ex:photo points, stubble height after grazing, etc.) & record keeping. Livestock graze each pasture for more than seven (7) days in rotation and adequate rest is provided for the forages.

Before Situation:

Current grazing system exhibits undesirable and inefficient use of forage plants and such use has a negative impact on pasture condition as well as soil and water resources. Inefficient use results in overgrazing, spot grazing, livestock trailing, concentration areas, uncontrolled access to streams and ponds, ephemeral erosion, gully erosion, streambank erosion. Stocking rates are higher than the current level of production and efficiency of use can support without management changes. There is currently no monitoring plan in place to evaluate change on the landscape.

After Situation:

Typical scenario is based on a grazing system consisting of a 30 animal unit cow/calf operation (including bull(s), calves and replacement females) on 80 acres. Activities include farm labor to mow or clip pastures; monitor and measure forage growth; complete record keeping; analyze plant growth and animal performance; and make decisions or other management techniques. Management techniques reduce the use of supplemental feed, control weeds, and reduce energy requirements. Prescribed grazing system is designed to protect the health and vigor of the plant communities that are in place. Livestock are managed in a way that enhances pasture condition and function through protection of sensitive areas and efficient harvest of forage resources. Runoff, sediment and nutrient loss are reduced by improving plant density, diversity and percent cover. Grazing system success is evaluated through short term monitoring and maintaining grazing stop height requirements. Acquisition of technical knowledge needed to effectively implement prescribed grazing. Costs and activities are typical for conventional and organic producers. Associated Practices: (511) Forage Harvest Management, (512) Forage and Biomass Planting, (590) Nutrient Management, (595) Integrated Pest Management, (561) Heavy Use Area Protection, (382) Fence, (614) Watering Facility, (378) Pond, (642) Water Well, (314) Brush Management, (315) Herbaceous Weed Control, (338) Prescribed Burning.

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 80.0

Scenario Total Cost: \$2,251.75

Scenario Cost/Unit: \$28.15

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Equipment Installation						
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	10	\$288.40
Rangeland/grassland field monitoring kit	967	Miscellaneous tools needed to complete rangeland/grassland monitoring. Materials may include camera, clippers, plot frame, scale, tape measure, etc. Includes materials and shipping only.	Each	\$50.23	1	\$50.23
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	15	\$530.40
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	60	\$1,318.80

Practice: 528 - Prescribed Grazing

Scenario #2 - Medium Intensity, 7-3 Days Rotation Frequency

Scenario Description:

Design and implementation of a grazing system that will enhance pasture condition and ecosystem function as well as optimize efficiency and economic return through monitoring (ex:photo points, stubble height after grazing, etc.) & record keeping. Livestock graze each pasture from three (3) to seven (7) days in rotation. Rotation is based on monitoring livestock demand and supply.

Before Situation:

Current grazing system exhibits undesirable and inefficient use of forage plants and such use has a negative impact on pasture condition, as well as soil and water resources. Inefficient use results in overgrazing, spot grazing, livestock trailing, concentration areas, uncontrolled access to streams and ponds, ephemeral erosion, gully erosion, streambank erosion. Stocking rates are higher than the current level of production and efficiency of use can support without management changes. There is currently no monitoring plan in place to evaluate change on the landscape.

After Situation:

Typical scenario is based on a grazing system consisting of a 30 animal unit cow/calf operation (including bull(s), calves and replacement females) on 80 acres. Scenario results in an increase (above the low intensity option) in labor required to complete the following activities: farm labor to mow or clip pastures; monitor and measure forage growth; complete record keeping; analyze plant growth and animal performance; and make decisions or other management techniques. Management techniques reduce the use of supplemental feed, control weeds, and reduce energy requirements. Prescribed grazing system is designed to protect the health and vigor of the plant communities that are in place. Livestock are managed in a way that enhances pasture condition and function through protection of sensitive areas and efficient harvest of forage resources. Runoff, sediment and nutrient loss are reduced by improving plant density, diversity and percent cover. Grazing system success is evaluated through short term monitoring and maintaining grazing stop height requirements. Acquisition of technical knowledge needed to effectively implement prescribed grazing. Costs and activities are typical for conventional and organic producers. Associated Practices: (511) Forage Harvest Management, (512) Forage and Biomass Planting, (590) Nutrient Management, (595) Integrated Pest Management, (561) Heavy Use Area Protection, (382) Fence, (614) Watering Facility, (378) Pond, (642) Water Well, (314) Brush Management, (315) Herbaceous Weed Control, (338) Prescribed Burning.

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 80.0

Scenario Total Cost: \$3,446.23

Scenario Cost/Unit: \$43.08

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	20	\$576.80
Rangeland/grassland field monitoring kit	967	Miscellaneous tools needed to complete rangeland/grassland monitoring. Materials may include camera, clippers, plot frame, scale, tape measure, etc. Includes materials and shipping only.	Each	\$50.23	1	\$50.23
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	30	\$1,060.80
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	80	\$1,758.40

Practice: 528 - Prescribed Grazing

Scenario #3 - High Intensity, <=2 Day Rotation Frequency

Scenario Description:

Design and implementation of a grazing system that will enhance pasture condition and ecosystem function as well as optimize efficiency and economic return through monitoring (ex:photo points, stubble height after grazing, etc.) & record keeping. Livestock graze each pasture/paddock from less than three (3) days in rotation. Rotation is based on monitoring livestock demand and supply.

Before Situation:

Current grazing system exhibits undesirable and inefficient use of forage plants and such use has a negative impact on pasture condition, as well as soil and water resources. Inefficient use results in overgrazing, spot grazing, livestock trailing, concentration areas, uncontrolled access to streams and ponds, ephemeral erosion, gully erosion, streambank erosion. Stocking rates are higher than the current level of production and efficiency of use can support without management changes. There is currently no monitoring plan in place to evaluate change on the landscape.

After Situation:

Typical scenario is based on a grazing system consisting of a 30 animal unit cow/calf operation (including bull(s), calves and replacement females) on 80 acres. Scenario results in an increase (above the medium intensity option) in labor required to complete the following activities: farm labor to mow or clip pastures; monitor stop grazing heights and measure forage growth; complete record keeping; analyze plant growth and animal performance; and make decisions or other management techniques. Management techniques reduce the use of supplemental feed, control weeds, and reduce energy requirements. Prescribed grazing system is designed to protect the health and vigor of the plant communities that are in place. Livestock are managed in a way that enhances pasture condition and function through protection of sensitive areas and efficient harvest of forage resources. Runoff, sediment and nutrient loss are reduced by improving plant density, diversity and percent cover. Grazing system success is evaluated through short term monitoring and maintaining grazing stop height requirements. Acquisition of technical knowledge needed to effectively implement prescribed grazing. Costs and activities are typical for conventional and organic producers. Associated Practices: (511) Forage Harvest Management, (512) Forage and Biomass Planting, (590) Nutrient Management, (595) Integrated Pest Management, (561) Heavy Use Area Protection, (382) Fence, (614) Watering Facility, (378) Pond, (642) Water Well, (314) Brush Management, (315) Herbaceous Weed Control, (338) Prescribed Burning.

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 80.0

Scenario Total Cost: \$4,896.39

Scenario Cost/Unit: \$61.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	3	\$191.76
Equipment Installation						
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	30	\$865.20
Rangeland/grassland field monitoring kit	967	Miscellaneous tools needed to complete rangeland/grassland monitoring. Materials may include camera, clippers, plot frame, scale, tape measure, etc. Includes materials and shipping only.	Each	\$50.23	1	\$50.23
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	45	\$1,591.20
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	100	\$2,198.00

Practice: 528 - Prescribed Grazing

Scenario #4 - Enhanced - Strip Grazing

Scenario Description:

Design and implementation of a grazing system that will enhance pasture condition and ecosystem function as well as optimize efficiency and economic return through monitoring (ex: photos points, stubble height after grazing, etc.) & record keeping. Livestock are part of a managed grazing system which includes utilization of management techniques such as stockpiling/strip grazing to assist in extending the grazing season and improve animal demand and supply efficiency, or summer strip grazing on mature pasture to improve soil health by maintaining and/or improving ideal cover, plant diversity, organic matter and soil temperatures favorable for sustained microbial life.

Before Situation:

Current grazing system exhibits undesirable and inefficient use of forage plants and such use has a negative impact on pasture condition, as well as soil and water resources. Inefficient use results in overgrazing, spot grazing, livestock trailing, concentration areas, uncontrolled access to streams and ponds, ephemeral erosion, gully erosion, streambank erosion. Stocking rates are higher than the current level of production and efficiency of use can support without management changes. There is currently no monitoring plan in place to evaluate change on the landscape.

After Situation:

Typical scenario is based on a grazing system consisting of a 30 animal unit cow/calf operation (including bull(s), calves and replacement females) on 80 acres for a 200 to 290 day grazing season. Scenario results in an increase (above the Standard option) in labor required to complete the following activities: farm labor to mow or clip pastures; monitor and measure forage growth; complete record keeping; analyze plant growth and animal performance; and make decisions or other management techniques. Management techniques reduce the use of supplemental feed, control weeds, and reduce energy requirements. Prescribed grazing system is designed to protect the health and vigor of the plant communities that are in place. Livestock are managed in a way that enhances pasture condition and function through protection of sensitive areas and efficient harvest of forage resources. Runoff, sediment and nutrient loss are reduced by improving plant density, diversity and percent cover. Grazing system success is evaluated through short term monitoring. Acquisition of technical knowledge needed to effectively implement prescribed grazing. Consultant or TSP used to develop detailed grazing plan. Costs and activities are typical for conventional and organic producers. Associated Practices: (511) Forage Harvest Management, (512) Forage and Biomass Planting, (590) Nutrient Management, (595) Integrated Pest Management, (561) Heavy Use Area Protection, (382) Fence, (614) Watering Facility, (378) Pond, (642) Water Well, (314) Brush Management, (315) Herbaceous Weed Control, (338) Prescribed Burning.

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 80.0

Scenario Total Cost: \$5,803.75

Scenario Cost/Unit: \$72.55

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	3	\$191.76
Equipment Installation						
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	30	\$865.20
Rangeland/grassland field monitoring kit	967	Miscellaneous tools needed to complete rangeland/grassland monitoring. Materials may include camera, clippers, plot frame, scale, tape measure, etc. Includes materials and shipping only.	Each	\$50.23	1	\$50.23
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	45	\$1,591.20
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	100	\$2,198.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	8	\$746.00
Materials						
Nutritional Balance Analyzer, fecal sample analysis only	1127	NIRS fecal analysis, animal performance report. Includes materials and shipping only.	Each	\$40.34	4	\$161.36



Practice: 528 - Prescribed Grazing

Scenario #5 - High Density Grazing

Scenario Description:

An improved grazing management system where livestock are grazed on pasture and managed at a stock density of at least 50,000 lbs for 75% of the grazing days. Pastures will be managed for a livestock utilization rate of 60% per grazing event. The grazing days will be identified in the Prescribed Grazing Plan.

Before Situation:

Current grazing system exhibits undesirable and inefficient use of forage plants and such use has a negative impact on pasture condition, as well as soil and water resources. Inefficient use results in overgrazing, spot grazing, livestock trailing, concentration areas, uncontrolled access to streams and ponds, ephemeral erosion, gully erosion, streambank erosion. Stocking rates are higher than the current level of production and efficiency of use can support without management changes. There is currently no monitoring plan in place to evaluate change on the landscape.

After Situation:

A grazing system for a 30 animal unit cow-calf operation (includes bull(s), calves and replacement females) on 80 acres and designed for a 300 day grazing season. The grazing system has a stock density of at least 50,000 pounds for 75% of the grazing days. Pastures will be monitored and measure pasture growth to ensure a livestock utilization rate of 60% or less per grazing event. Acquisition of technical knowledge needed to effectively implement prescribed grazing is included. Management techniques will improve soil condition, reduce soil compaction, reduce the use of supplemental feed, reduce the need for weed control, and reduce energy requirements. Consultant or TSP used to develop detailed grazing plan. Costs and activities are typical for conventional and organic producers. Associated Practices: (511) Forage Harvest Management, (512) Forage and Biomass Planting, (590) Nutrient Management, (595) Integrated Pest Management, (561) Heavy Use Area Protection, (382) Fence, (614) Watering Facility, (378) Pond, (642) Water Well, (314) Brush Management, (315) Herbaceous Weed Control, (338) Prescribed Burning.

Feature Measure: ac

Scenario Unit:: Acre

Scenario Typical Size: 80.0

Scenario Total Cost: \$6,549.75

Scenario Cost/Unit: \$81.87

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	3	\$191.76
Equipment Installation						
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	30	\$865.20
Rangeland/grassland field monitoring kit	967	Miscellaneous tools needed to complete rangeland/grassland monitoring. Materials may include camera, clippers, plot frame, scale, tape measure, etc. Includes materials and shipping only.	Each	\$50.23	1	\$50.23
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	45	\$1,591.20
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	100	\$2,198.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	16	\$1,492.00
Materials						
Nutritional Balance Analyzer, fecal sample analysis only	1127	NIRS fecal analysis, animal performance report. Includes materials and shipping only.	Each	\$40.34	4	\$161.36

Practice: 528 - Prescribed Grazing

Scenario #6 - Deferment for Wildlife

Scenario Description:

Defer grazing of the pasture for a minimum of 90 days to manage for any of the following purposes: invasive weed control; improve the health of the forage plants; or provide cover for wildlife species. Keep records of dates out and monitor to determine when desired objectives of deferment are met. Does not include the purpose of deferment for the establishment of forages.

Before Situation:

Current grazing system exhibits undesirable and inefficient use of forage plants and such use has a negative impact on pasture condition, as well as soil and water resources. Inefficient use results in overgrazing, spot grazing, livestock trailing, concentration areas, uncontrolled access to streams and ponds, ephemeral erosion, gully erosion, streambank erosion. Stocking rates are higher than the current level of production and efficiency of use can support without management changes. There is currently no monitoring plan in place to evaluate change on the landscape.

After Situation:

Scenario describes activities completed to restrict grazing for a defined period during the normal grazing period to provide benefits for invasive weed control, improvement in the health of the forage plants or providing cover for wildlife species. Activities include moving livestock to alternate locations, sampling and analyzing pasture condition, recordkeeping. Forgone Income used represents the acreage of usable forage not utilized during the deferment period as a proportion of the grazing season. Typical size of 80 acre pasture operation with 30 animal units where 50% of the acreage (or 40 acres) is deferred from grazing for 90 days. Costs and activities are typical for conventional and organic producers. Associated Practices: (511) Forage Harvest Management, (512) Forage and Biomass Planting, (590) Nutrient Management, (595) Integrated Pest Management, (561) Heavy Use Area Protection, (382) Fence, (614) Watering Facility, (378) Pond, (642) Water Well, (314) Brush Management, (315) Herbaceous Weed Control, (338) Prescribed Burning.

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: \$2,404.21

Scenario Cost/Unit: \$60.11

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	8	\$177.76
Trucking, moving livestock to new paddock	961	Livestock transportation costs to implement a grazing rotation using a gooseneck trailer 6'8" x 24'. Includes equipment, power unit and labor costs.	Mile	\$4.38	50	\$219.00
Rangeland/grassland field monitoring kit	967	Miscellaneous tools needed to complete rangeland/grassland monitoring. Materials may include camera, clippers, plot frame, scale, tape measure, etc. Includes materials and shipping only.	Each	\$50.23	1	\$50.23

Foregone Income

FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	90	\$1,498.50
------------------	------	---------------------------------	-------------------	---------	----	------------

Labor

Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	8	\$282.88
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84

Practice: 528 - Prescribed Grazing

Scenario #7 - Long Term Deferment

Scenario Description:

Defer the pasture for 210 days and up to a growing season to manage for invasive weeds when necessary, to improve the health of the plants and/or provide nesting habitat for wildlife species. Keep records of dates out and monitor to determine when desired objectives of deferment are met. Does not include the purpose of deferment for the establishment of forages.

Before Situation:

Current grazing system exhibits undesirable and inefficient use of forage plants and such use has a negative impact on pasture condition, as well as soil and water resources. Inefficient use results in overgrazing, spot grazing, livestock trailing, concentration areas, uncontrolled access to streams and ponds, ephemeral erosion, gully erosion, streambank erosion. Stocking rates are higher than the current level of production and efficiency of use can support without management changes. There is currently no monitoring plan in place to evaluate change on the landscape.

After Situation:

Scenario describes activities completed to restrict grazing for a defined period during the normal grazing period to provide benefits for invasive weed control, improvement in the health of the forage plants or providing cover for wildlife species. Activities include moving livestock to alternate locations, sampling and analyzing pasture condition, recordkeeping. Foregone Income used represents the acreage of usable forage not utilized during the deferment period as a proportion of the grazing season. Typical size of 80 acre pasture operation with 30 animal units where 75% of the acreage (or 60 acres) is deferred from grazing for 210 days. Costs and activities are typical for conventional and organic producers. Associated Practices: (511) Forage Harvest Management, (512) Forage and Biomass Planting, (590) Nutrient Management, (595) Integrated Pest Management, (561) Heavy Use Area Protection, (382) Fence, (614) Watering Facility, (378) Pond, (642) Water Well, (314) Brush Management, (315) Herbaceous Weed Control, (338) Prescribed Burning.

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 60.0

Scenario Total Cost: \$4,860.93

Scenario Cost/Unit: \$81.02

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	8	\$177.76
Trucking, moving livestock to new paddock	961	Livestock transportation costs to implement a grazing rotation using a gooseneck trailer 6'8" x 24'. Includes equipment, power unit and labor costs.	Mile	\$4.38	50	\$219.00
Rangeland/grassland field monitoring kit	967	Miscellaneous tools needed to complete rangeland/grassland monitoring. Materials may include camera, clippers, plot frame, scale, tape measure, etc. Includes materials and shipping only.	Each	\$50.23	1	\$50.23

Foregone Income

FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	210	\$3,496.50
------------------	------	---------------------------------	-------------------	---------	-----	------------

Labor

Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	16	\$565.76
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68

Practice: 528 - Prescribed Grazing

Scenario #8 - Biological Control with Grazing Animals

Scenario Description:

Management of herbaceous and/or woody plant species through the use of livestock such as goats, sheep or other grazing animal that will graze on the undesirable species. Payment is based on impacted acres only. Payment is based on the use of goats for problems where a stocking rate equivalent of 50 goats can adequately clear 1 acre of undesirable herbaceous species in one day (or equivalent stocking; for example 5 goats for 1 week to clear an acre), or equivalent number of other livestock. Costs are related to transportation of livestock, setting up temporary fencing and/or watering system. Cost represents typical situations for conventional, organic, and transitioning to organic producers.

Before Situation:

Area consists of herbaceous and/or woody weed species such as, but not limited to sericia lespedeza, japanese stilt grass, periwinkle, ironweed, ragweed, Amur cork tree, Siberian elm, callery pear, autumn olive, multiflora rose, barberry, burning bush, or honeysuckle, etc. that exceed the desirable ecological site condition degrading forage quality, promoting noxious and invasive species, increasing risk of soil erosion and degrading wildlife habitat. Undesirable species can contribute to degraded plant condition, inadequate feed & forage, and potential animal health issues.

After Situation:

Livestock grazing is managed to limit the regrowth of weed species and achieve a desirable plant community based on species composition, structure, density, and canopy cover or height. Ecological site condition is progressing in an upward trend and plant health and vigor is returning to near normal levels.

Feature Measure: Acres treated

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$834.34

Scenario Cost/Unit: \$834.34

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Materials						
Animals used for biological weed control	1130	Goats, Llamas, Sheep - Includes all support: fence, water, dog, mob, etc. Includes materials and shipping only.	Head per day	\$13.17	50	\$658.50

Practice: 533 - Pumping Plant

Scenario #1 - Wastewater Pump < 1 Hp

Scenario Description:

Scenario is for the implementation of a electric chopper screw pump of less than 1 horsepower. Implementation examples include, but are not limited to, pumping wastewater from the source to a storage facility such as in a dairy milk parlor, or pumping supernatant from the sump of a settling basin to a level spreader device upstream of a Vegetated Treatment Area, in flat topography where gravity flow from the settling basin is not feasible. Payment includes the pump and controls, installation and concrete pad base for the pump.

Before Situation:

Dairy milk parlor wastewater is not managed properly, or feedlot runoff enters a nearby stream, causing water quality concerns through excessive nutrients, organics, and pathogen. The resource concerns to be addressed are for water quality, air quality, and domestic animal health.

After Situation:

Practice typically installed for transfer of wastewater to a storage facility using 3/4 HP chopper/screw pump. Dairy milk parlor wastewater is directed to a waste storage facility, or feedlot runoff is directed to a solid/liquid settling basin, and supernatant is pumped from the sump of the settling basin to a Vegetated Treatment Area. Contaminated water no longer enters the stream. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated Practices include: 374 - Farmstead Energy Improvement; 313 - Waste Storage Facility; 634 - Waste Transfer; 633 Waste Utilization; 632 Solid/liquid Waste Separation Facility; 635 Vegetated Treatment Area

Feature Measure: Per Pump

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,253.94

Scenario Cost/Unit: \$1,253.94

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	0.25	\$68.66
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Materials						
Pump, Wastewater, Solids Handling < 1 HP	2514	Wastewater solid handling pump less than 1 horsepower. Pumping capacity of 20 gallons per minute at 30 feet of Total Dynamic Head. Includes materials and shipping only.	Each	\$1,141.32	1	\$1,141.32

Practice: 533 - Pumping Plant

Scenario #2 - Wastewater Pump 1-5 Hp

Scenario Description:

Scenario is for the implementation of a electric chopper screw pump of 1-5 horsepower. Implementation examples include, but are not limited to, pumping wastewater from the source to a storage facility such as in a dairy milk parlor, or pumping supernatant from the sump of a settling basin to a level spreader device upstream of a Vegetated Treatment Area, in flat topography where gravity flow from the settling basin is not feasible. Payment includes the pump and controls, installation and concrete pad base for the pump.

Before Situation:

Dairy milk parlor wastewater is not managed properly, or feedlot runoff enters a nearby stream, causing water quality concerns through excessive nutrients, organics, and pathogen. The resource concerns to be addressed are for water quality, air quality, and domestic animal health.

After Situation:

Practice typically installed for transfer of wastewater to a storage facility using 3 HP chopper/screw pump. Dairy milk parlor wastewater is directed to a waste storage facility, or feedlot runoff is directed to a solid/liquid settling basin, and supernatant is pumped from the sump of the settling basin to a Vegetated Treatment Area. Contaminated water no longer enters the stream. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated Practices include: 374 - Farmstead Energy Improvement; 313 - Waste Storage Facility; 634 - Waste Transfer; 633 Waste Utilization; 632 Solid/liquid Waste Separation Facility; 635 Vegetated Treatment Area

Feature Measure: Per Pump

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$3,288.84

Scenario Cost/Unit: \$3,288.84

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	0.25	\$68.66
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Materials						
Pump, Wastewater, Solids Handling, 1 to 5 HP	2515	Wastewater solid handling pump with 1 to 5 horsepower. Pumping capacity of 100 gallons per minute at 30 feet of Total Dynamic Head. Includes materials and shipping only.	Each	\$3,176.22	1	\$3,176.22

Practice: 533 - Pumping Plant

Scenario #3 - Manure Pump >5 Hp

Scenario Description:

Scenario is for the implementation of a electric chopper screw pump of >5 horsepower to pump manure from the source to a storage facility. Implementation examples include, but are not limited to, situations where a dairy or swine operation is pumping manure to an above ground storage facility. Payment includes the pump and controls, installation and concrete pad.

Before Situation:

Manure is not managed properly, or feedlot runoff enters a nearby stream, causing water quality concerns through excessive nutrients, organics, and pathogen. The resource concerns to be addressed are for water quality, air quality, and domestic animal health.

After Situation:

Practice typically installed for transfer of manure to a storage facility using 10 HP chopper/screw pump. Manure is directed to a waste storage facility, or feedlot runoff is directed to a solid/liquid settling basin, and supernatant is pumped from the sump of the settling basin to a Vegetated Treatment Area. Contaminated water no longer enters the stream. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated Practices include: 374 - Farmstead Energy Improvement; 313 - Waste Storage Facility; 634 - Waste Transfer; 633 Waste Utilization; 632 Solid/liquid Waste Separation Facility; 635 Vegetated Treatment Area

Feature Measure: Per Pump

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$7,957.13

Scenario Cost/Unit: \$7,957.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	0.25	\$68.66
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Materials						
Pump, Wastewater, Solids Handling, > 5 HP	2516	Wastewater solid handling pump greater than 5 horsepower. Pumping capacity of 400 gallons per minute at 40 feet of Total Dynamic Head. Includes materials and shipping only.	Each	\$7,844.51	1	\$7,844.51

Practice: 533 - Pumping Plant

Scenario #4 - Small Wastewater Fuel Driven Pump <= 50 Hp

Scenario Description:

Scenario is for the implementation of a fuel or PTO-driven pump of ≤ 50 horsepower for transferring manure or wastewater. Implementation examples include, but are not limited to, pumping wastewater from a storage facility to an end use such as a field, or transferring manure and wastewater from a shallow pit under a hog confinement building to a deep pit manure storage on the headquarters site. Payment includes all controls and appurtenances needed to mount the pump and connect the pump to the piping system. The piping system and any associated reception tank is specified under 634 - Waste Transfer.

Before Situation:

Various types of semi-solid or liquid waste at the headquarters is uncollected causing surface and ground water issues. Resource concerns are water quality degradation - excess nutrients in surface and ground waters.

After Situation:

For semi-solid or liquid waste, wastes that have been collected through a waste transfer system are now efficiently transferred to appropriate treatment or storage facilities or crop application. Due to topography, gravity transfer is not possible and a properly sized pump is needed to transfer waste as part of a waste transfer system. Associated Practices include: 374 - Farmstead Energy Improvement; 313 - Waste Storage Facility; 634 - Waste Transfer

Feature Measure: Per Pump

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$24,687.06

Scenario Cost/Unit: \$24,687.06

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	0.25	\$68.66
Materials						
Pump, < 50 HP, Pump & ICE power unit	1027	Materials, labor, controls: < 50 HP Pump & ICE power unit	Horsepower	\$615.46	40	\$24,618.40



Practice: 533 - Pumping Plant

Scenario #5 - Large Wastewater Fuel Driven Pump > 50 Hp

Scenario Description:

Scenario is for the implementation of a fuel or PTO-driven pump of >50 horsepower for transferring manure or wastewater. Implementation examples include, but are not limited to, moving wastewater from a waste holding pond to a dragline field application system, supplying wastewater to a sprinkler irrigation system, or any other transfer of wastewater from a storage facility to an end use. Includes all controls and appurtenances needed to mount the pump and connect the pump to the piping system. The piping system and any associated reception tank is specified under 634 - Waste Transfer.

Before Situation:

Various types of semi-solid or liquid waste at the headquarters is uncollected causing surface and ground water issues. Resource concerns are water quality degradation - excess nutrients in surface and ground waters.

After Situation:

For semi-solid or liquid waste, wastes that have been collected through a waste transfer system are now efficiently transferred to appropriate treatment or storage facilities or crop application. Due to topography, gravity transfer is not possible and a properly sized pump is needed to transfer waste as part of a waste transfer system. Associated Practices include: 374 - Farmstead Energy Improvement; 313 - Waste Storage Facility; 634 - Waste Transfer

Feature Measure: Per Pump

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$31,901.16

Scenario Cost/Unit: \$31,901.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	0.25	\$68.66
Materials						
Pump, > 70 HP, Pump & ICE power unit	1029	Materials, labor, controls: > 70 HP Pump & ICE power unit	Horsepower	\$374.50	85	\$31,832.50

Practice: 533 - Pumping Plant

Scenario #8 - Solar Pump for Shallow Well or Spring Development

Scenario Description:

The scenario is for the installation of a solar panel array, pump, pressure tank, and appurtenances in a shallow well or spring development for supplying water to livestock in situations where standard electric power is inaccessible The installation includes the pump, wiring, drop pipe, solar panels, mounts, inverter, and all appurtenances. Payment does not include battery backup.

Before Situation:

Practice to be installed on grazing land. Current conditions include inadequate water supply, poor water quality, degraded site conditions leading to erosion concerns, poor grazing distribution, and poor livestock health. The resource concerns to be addressed are Inadequate supply of water, grazing distribution, and degraded site conditions leading to poor animal health.

After Situation:

The typical scenario assumes installation of a 200-watt photovoltaic (PV) panel. The installation includes the pump, wiring, pipeline in the well, solar panels, frame mounts, inverter, and all appurtenances. Water will be pumped to an existing storage tank at a higher elevation from which it will be used to pressurize the Livestock Pipeline (516) or Irrigation Pipeline (430). Grazing - Livestock exclusion from surface water will result in improved surface water quality and reduced erosion. Associated Practices include: 516 - Livestock Pipeline; 642 Water Well, 528 Prescribed Grazing and, 614 - Watering Facility.

Feature Measure: Pump

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$3,295.19

Scenario Cost/Unit: \$3,295.19

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	3	\$65.94
Materials						
Pump, <= 5 HP, pump and motor, fixed cost portion	1009	Fixed cost portion of a pump less than or equal to 5 HP pump and motor. This portion is a base cost and is not dependant on horsepower. The total cost of any pump will include this fixed cost plus a variable cost portion. The completed pump and motor will	Each	\$549.88	1	\$549.88
Pump, <= 5 HP, pump and motor, variable cost portion	1010	Variable cost portion of a pump less than or equal to 5 HP pump and motor. This portion IS dependent on the total horsepower for the pump. The total cost of any pump will include this variable cost plus the fixed cost portion. The completed pump and moto	Horsepower	\$413.86	0.25	\$103.47
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will incl	Each	\$460.51	1	\$460.51
Pressure Tank, 40 gallon	1038	Pressure Tank, 40 gallon. Includes materials and shipping only.	Each	\$463.67	1	\$463.67
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all ma	Kilowatt	\$8,258.60	0.2	\$1,651.72

Practice: 533 - Pumping Plant

Scenario #10 - Livestock Water, Shallow Well Pump (&lt;= 25 ft deep)

**Scenario Description:**

The scenario is for the installation of a pump and pressure tank in a shallow well ( $\leq 25$  feet deep) or collection for supplying water to livestock. Payment includes pump, controls, pressure tank and installation.

**Before Situation:**

Practice to be installed on grazing land. Current conditions include inadequate water supply, poor water quality, degraded site conditions leading to erosion concerns, poor grazing distribution, and poor livestock health. The resource concerns to be addressed are Inadequate supply of water, grazing distribution, and degraded site conditions leading to poor animal health.

**After Situation:**

Practice typically installed for 30 animal units and consists of installing a centrifugal pump, pressure tank, and appurtenances for a shallow draw watering system. Conservation benefits of the installation is proper grazing distribution, which will allow a degraded site to be restored. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated practices: 528 Prescribed Grazing, 516 Pipeline, 614 Watering Facility, 642 Water Well; 574 Spring Development

Feature Measure: per pump

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,493.35

Scenario Cost/Unit: \$1,493.35

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	3	\$65.94
<b>Materials</b>						
Pump, <= 5 HP, pump and motor, fixed cost portion	1009	Fixed cost portion of a pump less than or equal to 5 HP pump and motor. This portion is a base cost and is not dependant on horsepower. The total cost of any pump will include this fixed cost plus a variable cost portion. The completed pump and motor will	Each	\$549.88	1	\$549.88
Pump, <= 5 HP, pump and motor, variable cost portion	1010	Variable cost portion of a pump less than or equal to 5 HP pump and motor. This portion IS dependent on the total horsepower for the pump. The total cost of any pump will include this variable cost plus the fixed cost portion. The completed pump and moto	Horsepower	\$413.86	1	\$413.86
Pressure Tank, 40 gallon	1038	Pressure Tank, 40 gallon. Includes materials and shipping only.	Each	\$463.67	1	\$463.67

Practice: 533 - Pumping Plant

Scenario #11 - Livestock Water, Shallow Well Pump (<= 25ft deep) with Above Ground Pump House

Scenario Description:

The scenario is for the installation of a pump and pressure tank in a shallow well (≤25 feet deep) or collection for supplying water to livestock. Payment includes pump, controls, pressure tank and installation. Payment also includes a pump house installed above ground for situations where there is not an existing sheltered location for the pump to be installed.

Before Situation:

Practice to be installed on grazing land. Current conditions include inadequate water supply, poor water quality, degraded site conditions leading to erosion concerns, poor grazing distribution, and poor livestock health. The resource concerns to be addressed are Inadequate supply of water, grazing distribution, and degraded site conditions leading to poor animal health.

After Situation:

Practice typically installed for 30 animal units and consists of installing a centrifugal pump, pressure tank, and appurtenances for a shallow draw watering system. A 5' x 4' x 5' (100 cu ft) prefabricated concrete above ground pump house is installed above ground on a 8' x 8' x 1' gravel pad. An above ground pump house is utilized where burying is not feasible in a cost effective manner due to shallow soils. Conservation benefits of the installation is proper grazing distribution, which will allow a degraded site to be restored. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated practices: 528 Prescribed Grazing, 516 Pipeline, 614 Watering Facility, 642 Water Well; 574 Spring Development.

Feature Measure: per pump

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$2,404.13

Scenario Cost/Unit: \$2,404.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	7	\$153.86
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	2.4	\$61.37
Pump, <= 5 HP, pump and motor, fixed cost portion	1009	Fixed cost portion of a pump less than or equal to 5 HP pump and motor. This portion is a base cost and is not dependant on horsepower. The total cost of any pump will include this fixed cost plus a variable cost portion. The completed pump and motor will	Each	\$549.88	1	\$549.88
Pump, <= 5 HP, pump and motor, variable cost portion	1010	Variable cost portion of a pump less than or equal to 5 HP pump and motor. This portion IS dependent on the total horsepower for the pump. The total cost of any pump will include this variable cost plus the fixed cost portion. The completed pump and moto	Horsepower	\$413.86	1	\$413.86
Pressure Tank, 40 gallon	1038	Pressure Tank, 40 gallon. Includes materials and shipping only.	Each	\$463.67	1	\$463.67
Pump House, Above Ground	2470	Above ground prefabricated pump house. Includes material and shipping only.	Each	\$761.49	1	\$761.49

**Practice:** 533 - Pumping Plant

**Scenario** #13 - Livestock Water, Deep Well Pump (>25 ft deep)

**Scenario Description:**

The scenario is for the installation of a pump and pressure tank in a deep well (> 25 feet) for supplying water to livestock. Payment includes pump, controls, pressure tank and installation.

**Before Situation:**

Practice to be installed on grazing land. Current conditions include inadequate water supply, poor water quality, degraded site conditions leading to erosion concerns, poor grazing distribution, and poor livestock health. The resource concerns to be addressed are Inadequate supply of water, grazing distribution, and degraded site conditions leading to poor animal health.

**After Situation:**

Practice typically installed for 30 animal units and consists of installing a jet or submersible pump, pressure tank, and appurtenances for a watering system. When utilizing a pond or stream a sump will be installed and used rather than a well. Conservation benefits of the installation is proper grazing distribution, which will allow a degraded site to be restored. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated practices: 528 Prescribed Grazing, 516 Pipeline, 614 Watering Facility, 642 Water Well

**Feature Measure:** per pump

**Scenario Unit::** Each

**Scenario Typical Size:** 1.0

**Scenario Total Cost:** \$1,892.62

**Scenario Cost/Unit:** \$1,892.62

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	3	\$65.94
<b>Materials</b>						
Pump, <= 5 HP, pump and motor, fixed cost portion	1009	Fixed cost portion of a pump less than or equal to 5 HP pump and motor. This portion is a base cost and is not dependant on horsepower. The total cost of any pump will include this fixed cost plus a variable cost portion. The completed pump and motor will	Each	\$549.88	1	\$549.88
Pump, <= 5 HP, pump and motor, variable cost portion	1010	Variable cost portion of a pump less than or equal to 5 HP pump and motor. This portion IS dependent on the total horsepower for the pump. The total cost of any pump will include this variable cost plus the fixed cost portion. The completed pump and moto	Horsepower	\$413.86	1.5	\$620.79
Pressure Tank, 80 gallon	1039	Pressure Tank, 80 gallon. Includes materials and shipping only.	Each	\$656.01	1	\$656.01

Practice: 533 - Pumping Plant

Scenario #14 - Livestock Water, Deep Well Pump (> 25ft deep) with Above Ground Pump House

Scenario Description:

The scenario is for the installation of a pump and pressure tank in a deep well (> 25 feet) for supplying water to livestock. Payment includes pump, controls, pressure tank and installation. Payment also includes a pump house installed above ground for situations where there is not an existing sheltered location for the pump to be installed.

Before Situation:

Practice to be installed on grazing land. Current conditions include inadequate water supply, poor water quality, degraded site conditions leading to erosion concerns, poor grazing distribution, and poor livestock health. The resource concerns to be addressed are Inadequate supply of water, grazing distribution, and degraded site conditions leading to poor animal health.

After Situation:

Practice typically installed for 30 animal units and consists of installing a jet or submersible pump, pressure tank, and appurtenances for a watering system. A 5' x 4' x 5' (100 cu ft) prefabricated concrete above ground pump house is installed above ground on a 8' x 8' x 1' gravel pad. An above ground pump house is utilized where burying is not feasible in a cost effective manner due to shallow soils. Conservation benefits of the installation is proper grazing distribution, which will allow a degraded site to be restored. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated practices: 528 Prescribed Grazing, 516 Pipeline, 614 Watering Facility, 642 Water Well

Feature Measure: per pump

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$2,803.40

Scenario Cost/Unit: \$2,803.40

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	7	\$153.86
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	2.4	\$61.37
Pump, <= 5 HP, pump and motor, fixed cost portion	1009	Fixed cost portion of a pump less than or equal to 5 HP pump and motor. This portion is a base cost and is not dependant on horsepower. The total cost of any pump will include this fixed cost plus a variable cost portion. The completed pump and motor will	Each	\$549.88	1	\$549.88
Pump, <= 5 HP, pump and motor, variable cost portion	1010	Variable cost portion of a pump less than or equal to 5 HP pump and motor. This portion IS dependent on the total horsepower for the pump. The total cost of any pump will include this variable cost plus the fixed cost portion. The completed pump and moto	Horsepower	\$413.86	1.5	\$620.79
Pressure Tank, 80 gallon	1039	Pressure Tank, 80 gallon. Includes materials and shipping only.	Each	\$656.01	1	\$656.01
Pump House, Above Ground	2470	Above ground prefabricated pump house. Includes material and shipping only.	Each	\$761.49	1	\$761.49

Practice: 533 - Pumping Plant

Scenario #17 - Milk Transfer Pump

Scenario Description:

The typical scenario is for the installation of a 1 HP motor and transfer pump with appurtances, used in a dairy milking system to transfer milk from the milk receiver to the bulk tank. The motor will be used in conjunction with a VSD. This practice is to be used exclusively for implementing recommendations from on-farm energy audits. Payment includes pump, controls and labor to install.

Before Situation:

The system is inefficient when a motor operates at constant speed to satisfy a load which varies as to flow rate and/or pressure requirements.

After Situation:

An on-farm energy audit has determined that energy use can be reduced through use of a more efficient motor and pump combination. A VSD will be used with the motor/pump combination so that the motor speed can be adjusted to reduce power requirements and better match varied flow or pressure requirements. Associated practices/activities: may include 122-AgEMP - HQ, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612. Associated Practice: 374 Farmstead Energy Improvement

Feature Measure: per pump

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$591.66

Scenario Cost/Unit: \$591.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Pump, Transfer, 1 HP, Pump and Motor	2472	Transfer pump with a 1 horsepower, 3 phase motor. Includes materials, labor, and controls.	Each	\$591.66	1	\$591.66

Practice: 533 - Pumping Plant

Scenario #18 - Vacuum Pump

Scenario Description:

The typical scenario is for the installation of a 10 HP motor and vacuum pump with appurtances, used in a dairy milking system to transfer the milk from the animal to the milk receiver. The motor will be used in conjunction with a VSD. This practice is to be used exclusively for implementing recommendations from on-farm energy audits. Payment includes pump, controls and labor to install.

Before Situation:

The system is inefficient when a motor operates at constant speed to satisfy a load which varies as to flow rate and/or pressure requirements.

After Situation:

An on-farm energy audit has determined that energy use can be reduced through use of a more efficient motor and pump combination. A VSD will be used with the motor/pump combination so that the motor speed can be adjusted to reduce power requirements and better match varied flow or pressure requirements. Associated practices/activities: may include 122-AgEMP - HQ, and other activities within 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612. Associated Practice: 374 Farmstead Energy Improvement

Feature Measure: per pump

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$5,416.71

Scenario Cost/Unit: \$5,416.71

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Pump, Vacuum, 10 HP, Pump and Motor	2473	Vacuum pump including a 10 horsepower, 3 phase motor. Includes materials, labor, and controls.	Each	\$5,416.71	1	\$5,416.71



Practice: 533 - Pumping Plant

Scenario #62 - Solar Pump for Deep Well

Scenario Description:

The scenario is for the installation of a solar panel array, pump, and appurtenances in a deep well for supplying water to livestock in situations where standard electric power is inaccessible. The installation includes the pump, wiring, drop pipe, solar panels, mounts, inverter, and all appurtenances. Payment does not include battery backup.

Before Situation:

Practice to be installed on grazing land. Current conditions include inadequate water supply, poor water quality, degraded site conditions leading to erosion concerns, poor grazing distribution, and poor livestock health. The resource concerns to be addressed are Inadequate supply of water, grazing distribution, and degraded site conditions leading to poor animal health.

After Situation:

The typical scenario assumes installation of a 500-watt photovoltaic (PV) panel. Pump TDH 200ft at 5 gallon per minute. The installation includes the pump, wiring, pipeline in the well, solar panels, frame mounts, inverter, and all appurtenances. Water will be pumped to an existing storage tank at a higher elevation from which it will be used to pressurize the Livestock Pipeline (516) or Irrigation Pipeline (430). Grazing - Livestock exclusion from surface water will result in improved surface water quality and reduced erosion. Associated Practices include: 516 - Livestock Pipeline; 642 Water Well, 528 Prescribed Grazing and, 614 - Watering Facility.

Feature Measure: Pump

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$10,538.87

Scenario Cost/Unit: \$10,538.87

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will incl	Each	\$460.51	1	\$460.51
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all ma	Kilowatt	\$8,258.60	0.5	\$4,129.30
Solar Pumping System, Fixed Cost Portion	2495	Fixed cost portion of a solar powered pumping system. This portion is a base cost for a complete system including the photovoltaic panels, pumping plant, support braces, electric controllers, service drop, etc., and is not dependant on KiloWatt. The tot	Each	\$2,896.94	1	\$2,896.94
Solar Pumping System, Variable Cost Portion	2496	Variable cost portion of a solar powered pumping system. This portion IS dependent upon the total kilowatts of the photovoltaic panels, but also includes the pumping plant, support braces, electric controllers, service drop, etc. The total cost will inc	Kilowatt	\$5,752.56	0.5	\$2,876.28

Practice: 533 - Pumping Plant

Scenario #63 - Livestock Non-Electric Pump

Scenario Description:

A non-electric pump (nose pump, sling pump, water ram, etc.) is located in a pasture for the purpose of providing water to cattle. For a permanent installation, it is typical to also install Heavy Use Area Protection (561) (separate contract item) where the cattle congregate around the pump. The objective is to provide water to the cattle outside of a live stream or other natural water source thereby eliminating a significant erosion situation and while also improving water quality. The cattle thus have access to drinking water without having to enter the stream. Generally one pump is adequate for 20 cattle. Resource Concerns: Insufficient stockwater; Inefficient energy use - Equipment and facilities. Associated Practices include: 374 - Farmstead Energy Improvement; 382 - Fence; 516 - Livestock Pipeline; 561 - Heavy Use Area Protection; and, 614 - Watering Facility.

Before Situation:

Livestock have open access to a live stream or other existing natural water supply. Water supply is contaminated due to animal activity and stream banks are eroded on a daily basis. Improper cattle distribution results in poor water quality, poor grazing distribution, over grazing, and soil erosion.

After Situation:

One non electric pump is installed with all appurtenances anchored to concrete pad with 6"x6"x10 Gauge reinforcement wire (9 ft x 4 ft x 5 in) or other appropriate secure base to supply water to cattle for improved livestock herd management. Additional Heavy Use Area Protection (561) in the form of crushed rock and at least 5 feet wide, may be installed (separate contract item) surrounding the concrete pad. Improved: water quality, soil quality, grazing management, plant diversity, and animal health.

Feature Measure: Number of Pumps

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,175.29

Scenario Cost/Unit: \$1,175.29

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	0.5	\$137.31
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	8	\$177.76
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	8	\$310.24
Materials						
Nose Pump	1052	Materials and delivery.	Each	\$374.14	1	\$374.14

Practice: 554 - Drainage Water Management

Scenario #1 - >10 Acres per Structure

Scenario Description:

This scenario describes the management of a drainage water system in a row crop field with subsurface drainage system already installed or planned to be installed with control structures, or a surface water management system with berms or levees around the field and control structures. Drainage conditions consist of gentle slopes with few variations in drainage characteristics and surface slopes. Subsurface drainage pattern consists of fewer secondary main lines. Implementation of DWM results in improved water quality by reducing nutrient losses from the soil through ground or surface water outside of the growing season. Management of the water table results in more ground water available for crops during the growing season while lowering the water table prior to crop planting and crop harvest to avoid causing compaction.

Before Situation:

In this scenario the gently sloping cropland is drained with pattern subsurface drainage (typically perforated corrugated plastic tubing). The purpose of the drainage system is to decrease soil moisture conditions during planting and harvesting of crop. Subsurface drainage is not restricted at anytime during the year resulting in a permanently lowered water table which is typically 3-4 feet below the surface and well below the crop root zone. Excess ground water is discharged directly to adjacent receiving streams. Excess subsurface drainage contributes to degraded water quality from excessive nutrient discharge; less vigorous crop growth from lowered water table.

After Situation:

Typical systems consist of a 75 acre field with existing drainage tile lines and 5 installed water control structures. The operator walks the field in order to adjust water control structures (riser boards). While on site the date and adjustment information is recorded/logged. The number of yearly adjustments is based on 6 trips to a field 5 miles from headquarters. The field time to make and record each adjustment is 0.5 hours per structure (including travel time). The typical field will contain 5 water control structures. Scenario includes the cost of participant attending a workshop to gain knowledge about implementing the practice. Resource Concern: Water Quality - Excess Nutrients in surface and ground waters. Insufficient Water - Insufficient Moisture Management. Associated Practices: 329:Residue Management - No Till/Strip Till; 606-Subsurface Drain; 607-Surface Drain, Field Ditch; 608-Surface Drain, Main or Lateral; 587-Structure for Water Control; 590-Nutrient Management.

Feature Measure: Acres of Managed Drainage

Scenario Unit:: Acre

Scenario Typical Size: 75.0

Scenario Total Cost: \$530.40

Scenario Cost/Unit: \$7.07

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	15	\$530.40

Practice: 554 - Drainage Water Management

Scenario #3 - <=10 Acres per Structure

Scenario Description:

This scenario describes the management of a drainage water system in a row crop field with subsurface drainage system already installed or planned to be installed with control structures, or a surface water management system with berms or levees around the field and control structures. Drainage conditions consist of gentle to moderately slopes with many variations in drainage characteristics and surface slopes. Subsurface drainage pattern consists of many secondary main lines due to changes in drainage patterns. Implementation of DWM results in improved water quality by reducing nutrient losses from the soil through ground or surface water outside of the growing season. Management of the water table results in more ground water available for crops during the growing season while lowering the water table prior to crop planting and crop harvest to avoid causing compaction.

Before Situation:

In this scenario the gently to moderately sloping cropland is drained with pattern subsurface drainage (typically perforated corrugated plastic tubing). The purpose of the drainage system is to decrease soil moisture conditions during planting and harvesting of crop. Subsurface drainage is not restricted at anytime during the year resulting in a permanently lowered water table which is typically 3-4 feet below the surface and well below the crop root zone. Excess ground water is discharged directly to adjacent receiving streams. Excess subsurface drainage contributes to degraded water quality from excessive nutrient discharge; less vigorous crop growth from lowered water table.

After Situation:

Typical systems consist of a 50 acre field with existing drainage tile lines and 5 installed water control structures. The operator walks the field in order to adjust water control structures (riser boards). While on site the date and adjustment information is recorded/logged. The number of yearly adjustments is based on 6 trips to a field 5 miles from headquarters. The field time to make and record each adjustment is 0.5 hours per structure (including travel time). The typical field will contain 5 water control structures. Resource Concern: Water Quality - Excess Nutrients in surface and ground waters. Insufficient Water - Insufficient Moisture Management. Associated Practices: 329:Residue Management - No Till/Strip Till; 606-Subsurface Drain; 607-Surface Drain, Field Ditch; 608-Surface Drain, Main or Lateral; 587-Structure for Water Control; 590-Nutrient Management.

Feature Measure: Acres of Managed Drainage

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$530.40

Scenario Cost/Unit: \$10.61

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	15	\$530.40

Practice: 561 - Heavy Use Area Protection

Scenario #2 - Geocell and Gravel HUA

Scenario Description:

Installation of a geocell and gravel heavy use pad to provide a stable, non-eroding surface for areas frequently used by livestock, people or vehicles.

Before Situation:

A 30 head cow/calf operation with a frequently used area that is unstable with an eroding surface. The area lacks vegetation and has severe compaction concerns as well as deep mud. Concentration of nutrients cannot be spread on adjacent fields due to the unstable surface. Livestock health is compromised as additional energy is being used to travel through mud. A need exists to improve water quality, air quality, livestock health, as well as reduce soil erosion.

After Situation:

The stabilization of an area frequently and intensively used by people, animals or vehicles by installing a gravel surface with geocells to reduce soil erosion and improve livestock health. Typical size is 3900 square feet. 4" of gravel is placed into a 4" geocell "matting material" and surfaced with a 3" layer of fines. Payment incorporates site preparation through grading and shaping, gravel (7" depth total with gravel and fines) and geoweb "matting material". An additional 8 hours of general labor is added to put the geocells in place. Cost data is applicable to organic and conventional agricultural production systems.

Feature Measure: Area of rock-gravel GeoCell GeoTex

Scenario Unit:: Square Foot

Scenario Typical Size: 3,900.0

Scenario Total Cost: \$15,447.59

Scenario Cost/Unit: \$3.96

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	72	\$154.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	85	\$2,173.45
GeoCell, 4"	1054	4-inch thick cellular confinement system, three-dimensional, expandable panels made from high-density polyethylene (HDPE), polyester or another polymer material. Includes materials, labor and equipment for the geocell only, does not include backfill	Square Yard	\$29.29	433	\$12,682.57
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 561 - Heavy Use Area Protection

Scenario #8 - Gravel without Geotextile, Thick

Scenario Description:

Installation of a gravel heavy use pad to provide a stable, non-eroding surface for areas frequently used by livestock, people or vehicles.

Before Situation:

A 30 head cow/calf operation with a frequently used area that is unstable with an eroding surface. The area lacks vegetation and has severe compaction concerns as well as deep mud. Concentration of nutrients cannot be spread on adjacent fields due to the unstable surface. Livestock health is compromised as additional energy is being used to travel through mud. A need exists to improve water quality, air quality, livestock health, as well as reduce soil erosion and compaction.

After Situation:

The stabilization of areas frequently and intensively used by livestock by installing a gravel surface to reduce soil erosion, improve water quality, air quality, and livestock health. Typical size is 3,900 square feet. Gravel, 8" deep, is surfaced with a 3" layer of fines. Payment incorporates site preparation through grading and shaping, gravel and layer of fines. Cost data is applicable to organic and conventional agricultural production systems.

Feature Measure: Area of gravel

Scenario Unit:: Square Foot

Scenario Typical Size: 3,900.0

Scenario Total Cost: \$4,590.54

Scenario Cost/Unit: \$1.18

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	\$126.50	6	\$759.00
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	6	\$169.80
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	133	\$3,400.81
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 574 - Spring Development

Scenario #1 - Collection Structure

Scenario Description:

Develop a water source from a natural spring or seep to provide water for livestock and/or wildlife needs. This scenario includes excavating and exposing the water source at the spring/seep (typically on a hillside) and installing a water collection structure. Payment includes excavation and labor to expose the spring, concrete for collection box, lid and gravel backfill. Resource Concern: Livestock production limitation - Inadequate livestock water.

Before Situation:

Livestock operation with inadequate fresh water for livestock and an on-site undeveloped spring/seep.

After Situation:

Spring development system provides adequate water for the intended use. The system typically runs all year long in most zones. Site is excavated with a backhoe to expose the seep, a concrete collection box (3'x3'x4') is installed and gravel is backfilled between the spring source and collection box. Associated Practices: 516-Livestock Pipeline; 614-Watering Facility; 533 Pumping Plant

Feature Measure: Number of Developments

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,275.95

Scenario Cost/Unit: \$1,275.95

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	0.75	\$320.33
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	4	\$228.68
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	4	\$88.36
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	1	\$25.57
Spring Collection Box Cover, steel, 4' diameter	1281	4' diameter x 1/4" thick Steel lid with handle for spring collection box. Materials and fabrication.	Each	\$176.24	1	\$176.24
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 574 - Spring Development

Scenario #2 - Horizontal Collection Pipe

Scenario Description:

Develop a water source from a natural spring or seep to provide water for livestock and/or wildlife needs. This scenario includes excavating and exposing the water source at the spring/seep (typically on a hillside) and installing a horizontal water collection system. The collection system is commonly composed of perforated drainage pipe placed in an excavated collection trench that runs across the slope, and is piped directly to watering facilities (implemented through associated practice 614). Resource Concern: Livestock production limitation - Inadequate livestock water.

Before Situation:

Livestock operation with inadequate fresh water for livestock and an on-site undeveloped spring/seep.

After Situation:

Spring development system provides adequate water for the intended use. The system typically runs all year long in most zones. Horizontal water collection system is a 50 ft long, 4 inch diameter HDPE perforated pipe enclosed in a sand/gravel envelope overlaid by 2 ft wide filter fabric (50 ft long). Associated Practices: 516-Livestock Pipeline; 614-Watering Facility

Feature Measure: Number of Development

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$955.50

Scenario Cost/Unit: \$955.50

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.39	11	\$26.29
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	4	\$228.68
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	4	\$88.36
Materials						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic Yard	\$25.23	3	\$75.69
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	3	\$76.71
Pipe, HDPE, 4", PCPT, Single Wall	1270	Pipe, Corrugated Plastic Tubing, Single Wall, Perforated, 4" diameter - ASTM F405. Material cost only.	Foot	\$0.46	50	\$23.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93



Practice: 574 - Spring Development

Scenario #3 - Horizontal Pipe with Collection Box

Scenario Description:

Develop a water source from a natural spring or seep to provide water for livestock and/or wildlife needs. This scenario includes excavating and exposing the water source at the spring/seep (typically on a hillside) and installing a horizontal water collection system and a water storage structure. The collection system is commonly composed of perforated 4 inch diameter drainage pipe placed in an excavated collection trench that runs across the slope into the collection box. Resource Concern: Livestock production limitation - Inadequate livestock water.

Before Situation:

Livestock operation with inadequate fresh water for livestock and an on-site undeveloped spring/seep.

After Situation:

Spring development system provides adequate water for the intended use. The system typically runs all year long in most zones. Water is collected in a spring box (48 inch diameter x 6 ft long CMP). Horizontal water collection system is a 50 ft long, 4 inch diameter HDPE perforated pipe enclosed in a sand/gravel envelope overlaid by 2 ft wide filter fabric (50 ft long). Associated Practices: 516-Livestock Pipeline; 614-Watering Facility; 533 Pumping Plant

Feature Measure: Number of Developments

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$2,367.97

Scenario Cost/Unit: \$2,367.97

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	1	\$427.11
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.39	11	\$26.29
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	8	\$457.36
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	8	\$176.72
Materials						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic Yard	\$25.23	3	\$75.69
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	3	\$76.71
Pipe, PVC, 4", SCH 40	978	Materials: - 4" - PVC - SCH 40 - ASTM D1785	Foot	\$3.44	20	\$68.80
Pipe, HDPE, 4", PCPT, Single Wall	1270	Pipe, Corrugated Plastic Tubing, Single Wall, Perforated, 4" diameter - ASTM F405. Material cost only.	Foot	\$0.46	50	\$23.00
Pipe, CMP, 48", 14 Gauge	1280	48" Corrugated Metal Pipe, Galvanized, Uncoated, 14 gage. Material cost only.	Foot	\$41.24	6	\$247.44
Spring Collection Box Cover, steel, 4' diameter	1281	4' diameter x 1/4" thick Steel lid with handle for spring collection box. Materials and fabrication.	Each	\$176.24	1	\$176.24
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 574 - Spring Development

Scenario #4 - Vertical Collection & Storage Pipe

Scenario Description:

Develop a water source from a natural spring or seep to provide water for livestock and/or wildlife needs. Typically installed at the point source of a spring and provides for collection and storage of water. Payment includes the vertical excavation of the spring source, placement of vertical collection pipe and gravel around the pipe.  
Resource Concern: Livestock production limitation - Inadequate livestock water.

Before Situation:

Livestock operation with inadequate fresh water for livestock and an on-site undeveloped spring/seep.

After Situation:

Spring development system provides adequate water for the intended use. The system typically runs all year long in most zones. Water is collected in a vertical 48 inch diameter x 12 ft tall CMP. Associated Practices: 516-Livestock Pipeline; 614-Watering Facility; 533 Pumping Plant

Feature Measure: Number of Developments

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,994.52

Scenario Cost/Unit: \$1,994.52

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	8	\$457.36
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	8	\$176.72
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	3	\$76.71
Pipe, CMP, 48", 14 Gauge	1280	48" Corrugated Metal Pipe, Galvanized, Uncoated, 14 gage. Material cost only.	Foot	\$41.24	12	\$494.88
Spring Collection Box Cover, steel, 4' diameter	1281	4' diameter x 1/4" thick Steel lid with handle for spring collection box. Materials and fabrication.	Each	\$176.24	1	\$176.24
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 578 - Stream Crossing

Scenario #2 - Rip Rap Crossing

Scenario Description:

A stabilized area or structure constructed across a stream to provide a travel way for people, livestock, equipment, or vehicles. This practice applies to all land uses where an intermittent or perennial watercourse exists and a ford crossing is desired for livestock, people, and /or equipment. Stream bed in the channel reach containing the crossing must be vertically stable. Scenario is for stabilizing the bottom and slope of a stream channel using Rip Rap, gravel and geotextile. This scenario includes site preparation, dewatering, acquiring and installing rip rap and gravel on channel bottom and approaches. Scenario is based on a 20' wide x 50' long crossing. Use (396) Aquatic Organism Passage when the primary intent is biological concerns, not hydrologic.

Before Situation:

Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.

After Situation:

Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices: (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

Feature Measure: Crossing dimensions

Scenario Unit:: Square Foot

Scenario Typical Size: 1,000.0

Scenario Total Cost: \$3,286.80

Scenario Cost/Unit: \$3.29

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.72	37	\$63.64
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	2	\$56.60
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	\$65.40	37	\$2,419.80
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	19	\$485.83
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 578 - Stream Crossing

Scenario #4 - Concrete Crossing

Scenario Description:

A stabilized area or structure constructed across a stream to provide a travel way for people, livestock, equipment, or vehicles. This practice applies to all land uses where an intermittent or perennial watercourse exists and a ford crossing is desired for livestock, people, and /or equipment. Stream bed in the channel reach containing the crossing must be vertically stable. Scenario is for stabilizing the bottom and slope of a stream channel using concrete. This scenario includes site preparation, dewatering, acquiring and installing gravel and concrete channel bottom and approaches. Scenario is based on a 20' wide x 50' long crossing. Use (396) Aquatic Organism Passage when the primary intent is biological concerns, not hydrologic.

Before Situation:

Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.

After Situation:

Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices: (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

Feature Measure: Crossing dimensions

Scenario Unit:: Square Foot

Scenario Typical Size: 1,000.0

Scenario Total Cost: \$7,323.27

Scenario Cost/Unit: \$7.32

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	19	\$5,217.78
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	3	\$1,281.33
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.72	45	\$77.40
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	19	\$485.83
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 585 - Stripcropping

Scenario #3 - Stripcropping - wind and water erosion

Scenario Description:

This scenario describes the implementation of a strip cropping system that is designed specifically for the control of wind and water erosion or minimizing the transport of sediments or other water borne contaminants originating from runoff on cropland. The planned strip cropping system will meet the current 585 standard. Implementation will result in alternating strips of erosion susceptible crops with erosion resistant crops that are oriented as close to perpendicular to water flows as possible. The designed system will reduce erosion/sediment/contaminants to desired objectives. Payment for implementation is to defray the costs of designing the system, installing the strips on the landscape appropriately, and integrating a crop rotation that includes water erosion resistant species.

Before Situation:

In this geographic area, excessive water erosion is caused by raising crops in a manner that allows sheet water flows to travel down the slope causing sheet and rill erosion or concentrated flow conditions, degradation of soil health through loss of topsoil and organic matter, along with offsite negative impacts to water quality and aquatic wildlife habitat.

After Situation:

A strip cropping system that includes at least two or more strips within the planning slope will be designed to include parallel strips of approximately equal widths of water erosion resistant crop species with non-water erosion resistant crop species. Widths will be determined using current water erosion prediction technology to meet objectives. The design and implementation of a stripcropping system will minimize wind, sheet and rill erosion, protect soil quality, reduce offsite sedimentation, and benefit offsite aquatic wildlife habitat. Erosion prediction before and after practice application will be recorded showing the design and benefits of the practice. Erosion resistant strips in rotation must be managed to maintain the planned vegetative cover and surface roughness.

Feature Measure: area of strips

Scenario Unit:: Acre

Scenario Typical Size: 80.0

Scenario Total Cost: \$132.60

Scenario Cost/Unit: \$1.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	3	\$66.66
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	3	\$65.94

**Practice:** 587 - Structure for Water Control

**Scenario #1** - Inline Stoplog WCS, Surface Water Control, 6-10 in. dia. Pipe

**Scenario Description:**

An Inline Water Control Structure (WCS) composed of plastic that maintains a desired water surface elevation, controls the direction or rate of flow, or conveys water to address the resource concern: Inadequate habitat for Fish and Wildlife. The water surface elevation is controlled by addition or removal of slats or "stoplogs". This scenario is applicable to variable crest weir structures where the elevation is controlled at point along a pipe extending through an embankment, providing ease of access to the structure and provide better protection against beaver activity. There are commercially available models composed of plastic that are commonly used when the width of the is 24" or less. Cost estimate is based on a using a such a commercial product. The typical scenario is an inline structure with a width of 12", height of six feet, The pipe is 65' of 8" SCH 40 PVC (inlet and outlet combined).

**Before Situation:**

The landowner wishes to provide for a way to control the water surface elevation in a wetland area. The landowner wishes to enhance and enlarge the area to provide habitat for fish and wildlife.

**After Situation:**

A WCS is installed in a flow line allowing shallow water impoundments. A wetland area is enhanced and water levels can be varied to better accommodate wildlife needs. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Wetland Creation (658), Wetland Enhancement (659) Wetland Wildlife Habitat Management (644), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

**Feature Measure:** Number of structures

**Scenario Unit::** Each

**Scenario Typical Size:** 1.0

**Scenario Total Cost:** \$2,596.49

**Scenario Cost/Unit:** \$2,596.49

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	55	\$294.80
Hydraulic Excavator, .5 CY	930	Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included.	Hour	\$63.99	2	\$127.98
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	2	\$56.60
<b>Materials</b>						
Pipe, PVC, 8", SCH 40	981	Materials: - 8" - PVC - SCH 40 - ASTM D1785	Foot	\$8.54	65	\$555.10
Steel, Plate, 1/8"	1047	Flat Steel Plate, 1/8" thick, materials only.	Square Foot	\$3.89	36	\$140.04
Trash Guard, metal	1608	Trash Guard, fabricated-steel, includes materials, equipment, and labor to transport and place Conical shaped trash guard for drop inlet spillway. Typically fabricated of CMP and steel. Includes materials, equipment, and labor to fabricate and transport	Pound	\$2.32	40	\$92.80
Water Control Structure, Stoplog, Inline, fixed costs portion	2145	Fixed cost portion of Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Fixed cost portion. Materials only.	Each	\$312.56	1	\$312.56
Water Control Structure, Stoplog, Inline, variable cost portion	2146	Variable cost portion of a Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Calculate total variable costs by multiplying by the structure height x pipe diameter. Materials only.	Height x Diameter	\$12.08	48	\$579.84
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

**Practice:** 587 - Structure for Water Control

**Scenario #2** - Inline Stoplog WCS, Surface Water Control, 12-18 in. dia. Pipe

#### Scenario Description:

An Inline Water Control Structure (WCS) composed of plastic that maintains a desired water surface elevation, controls the direction or rate of flow, or conveys water to address the resource concern: Inadequate habitat for Fish and Wildlife. The water surface elevation is controlled by addition or removal of slats or "stoplogs". This scenario is applicable to variable crest weir structures where the elevation is controlled at point along a pipe extending through an embankment, providing ease of access to the structure and provide better protection against beaver activity. There are commercially available models composed of plastic that are commonly used when the width of the is 24" or less. Cost estimate is based on a using a such a commercial product. The typical scenario is an inline structure with a width of 20", height of six feet, The pipe is 65' of 15" SDR35 PVC (inlet and outlet combined).

#### Before Situation:

The landowner wishes to provide for a way to control the water surface elevation in a wetland area. The landowner wishes to enhance and enlarge the area to provide habitat for fish and wildlife.

#### After Situation:

A WCS is installed in a flow line allowing shallow water impoundments. A wetland area is enhanced and water levels can be varied to better accommodate wildlife needs. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Wetland Creation (658), Wetland Enhancement (659) Wetland Wildlife Habitat Management (644), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

**Feature Measure:** Number of Structures

**Scenario Unit::** Each

**Scenario Typical Size:** 1.0

**Scenario Total Cost:** \$4,317.72

**Scenario Cost/Unit:** \$4,317.72

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	55	\$294.80
Hydraulic Excavator, .5 CY	930	Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included.	Hour	\$63.99	2	\$127.98
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	2	\$56.60
<b>Materials</b>						
Steel, Plate, 1/8"	1047	Flat Steel Plate, 1/8" thick, materials only.	Square Foot	\$3.89	36	\$140.04
Steel, Plate, 3/8"	1375	Flat steel plate, 3/8" thickness. Materials only.	Square Foot	\$11.33	4	\$45.32
Trash Guard, metal	1608	Trash Guard, fabricated-steel, includes materials, equipment, and labor to transport and place Conical shaped trash guard for drop inlet spillway. Typically fabricated of CMP and steel. Includes materials, equipment, and labor to fabricate and transport	Pound	\$2.32	80	\$185.60
Pipe, PVC, 15", SDR 35	1722	Materials: 15" - PVC - SDR35 - ASTM D3034	Foot	\$25.09	65	\$1,630.85
Water Control Structure, Stoplog, Inline, fixed costs portion	2145	Fixed cost portion of Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Fixed cost portion. Materials only.	Each	\$312.56	1	\$312.56
Water Control Structure, Stoplog, Inline, variable cost portion	2146	Variable cost portion of a Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Calculate total variable costs by multiplying by the structure height x pipe diameter. Materials only.	Height x Diameter	\$12.08	90	\$1,087.20
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 587 - Structure for Water Control

Scenario #3 - Inline Stoplog WCS, Surface Water Control, >18 in. dia. Pipe

Scenario Description:

An Inline Water Control Structure (WCS) composed of plastic that maintains a desired water surface elevation, controls the direction or rate of flow, or conveys water to address the resource concern: Inadequate habitat for Fish and Wildlife. The water surface elevation is controlled by addition or removal of slats or "stoplogs". This scenario is applicable to variable crest weir structures where the elevation is controlled at point along a pipe extending through an embankment, providing ease of access to the structure and provide better protection against beaver activity. There are commercially available models composed of plastic that are commonly used when the width of the is 24" or less. Cost estimate is based on a using a such a commercial product. The typical scenario is an inline structure with a width of 31", height of six feet, The pipe is 65' of 24" used steel (inlet and outlet combined).

Before Situation:

The landowner wishes to provide for a way to control the water surface elevation in a wetland area. The landowner wishes to enhance and enlarge the area to provide habitat for fish and wildlife.

After Situation:

A WCS is installed in a flow line allowing shallow water impoundments. A wetland area is enhanced and water levels can be varied to better accommodate wildlife needs. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Wetland Creation (658), Wetland Enhancement (659) Wetland Wildlife Habitat Management (644), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

Feature Measure: Number of structures

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$7,201.63

Scenario Cost/Unit: \$7,201.63

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	55	\$294.80
Hydraulic Excavator, .5 CY	930	Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included.	Hour	\$63.99	2	\$127.98
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	10	\$353.60
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	2	\$56.60
Materials						
Steel, Plate, 1/8"	1047	Flat Steel Plate, 1/8" thick, materials only.	Square Foot	\$3.89	49	\$190.61
Pipe, Steel, 24", Std Wt, USED	1360	Materials: - USED - 24" - Steel Std Wt	Foot	\$49.83	65	\$3,238.95
Steel, Plate, 3/8"	1375	Flat steel plate, 3/8" thickness. Materials only.	Square Foot	\$11.33	8	\$90.64
Trash Guard, metal	1608	Trash Guard, fabricated-steel, includes materials, equipment, and labor to transport and place Conical shaped trash guard for drop inlet spillway. Typically fabricated of CMP and steel. Includes materials, equipment, and labor to fabricate and transport	Pound	\$2.32	155	\$359.60
Water Control Structure, Stoplog, Inline, fixed costs portion	2145	Fixed cost portion of Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Fixed cost portion. Materials only.	Each	\$312.56	1	\$312.56
Water Control Structure, Stoplog, Inline, variable cost portion	2146	Variable cost portion of a Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Calculate total variable costs by multiplying by the structure height x pipe diameter. Materials only.	Height x Diameter	\$12.08	144	\$1,739.52
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93



**Practice:** 587 - Structure for Water Control

**Scenario #4** - Weir Box Inlet WCS, Surface Water Control, <=16 in. dia. Pipe.

**Scenario Description:**

A structure in a water management system that conveys water, controls the direction or rate of flow, maintains a desired water surface elevation or measures water. This practice applies wherever a permanent structure is needed as an integral part of a water-control system. A fabricated weir box structure with a pipe of 16" diameter or less is placed in a levee to manage water level elevation. Payment incorporates pipe, anti seep collar, trash guard, animal guard, flap gate and weir box structure.

**Before Situation:**

The landowner wishes to provide for a way to control the water surface elevation in a wetland area. The landowner wishes to enhance and enlarge the area to provide habitat for fish and wildlife.

**After Situation:**

A weir box structure is placed in a levee to manage water level elevation. A wetland area is enhanced and water levels can be varied to better accommodate wildlife needs. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Wetland Creation (658), Wetland Enhancement (659) Wetland Wildlife Habitat Management (644), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

**Feature Measure:** Number of structures

**Scenario Unit::** Each

**Scenario Typical Size:** 1.0

**Scenario Total Cost:** \$3,809.18

**Scenario Cost/Unit:** \$3,809.18

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	55	\$294.80
Hydraulic Excavator, .5 CY	930	Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included.	Hour	\$63.99	2	\$127.98
<b>Labor</b>						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	8	\$282.88
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	2	\$56.60
<b>Materials</b>						
Steel, Plate, 1/8"	1047	Flat Steel Plate, 1/8" thick, materials only.	Square Foot	\$3.89	49	\$190.61
Steel, Plate, 3/16"	1048	Flat Steel Plate, 3/16" thick, materials only.	Square Foot	\$5.84	32	\$186.88
Pipe, Steel, 16", Std Wt, USED	1357	Materials: - USED - 16" - Steel Std Wt	Foot	\$29.16	65	\$1,895.40
Steel, Angle, 2 1/2" x 2 1/2" x 1/4"	1372	Materials: Angle, 2 1/2" x 2 1/2" x 1/4", Meets ASTM A36	Foot	\$3.39	30	\$101.70
Steel, Plate, 3/8"	1375	Flat steel plate, 3/8" thickness. Materials only.	Square Foot	\$11.33	4	\$45.32
Trash Guard, metal	1608	Trash Guard, fabricated-steel, includes materials, equipment, and labor to transport and place Conical shaped trash guard for drop inlet spillway. Typically fabricated of CMP and steel. Includes materials, equipment, and labor to fabricate and transport	Pound	\$2.32	82	\$190.24
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 587 - Structure for Water Control

Scenario #5 - Weir Box Inlet WCS, Surface Water Control, >16 in. dia. Pipe.

Scenario Description:

A structure in a water management system that conveys water, controls the direction or rate of flow, maintains a desired water surface elevation or measures water. This practice applies wherever a permanent structure is needed as an integral part of a water-control system. A fabricated weir box structure with a pipe of greater than 16" diameter is placed in a levee to manage water level elevation. Payment incorporates pipe, anti seep collar, trash guard, animal guard, flap gate and weir box structure.

Before Situation:

The landowner wishes to provide for a way to control the water surface elevation in a wetland area. The landowner wishes to enhance and enlarge the area to provide habitat for fish and wildlife.

After Situation:

A weir box structure is placed in a levee to manage water level elevation. A wetland area is enhanced and water levels can be varied to better accommodate wildlife needs. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Wetland Creation (658), Wetland Enhancement (659) Wetland Wildlife Habitat Management (644), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

Feature Measure: Number of structures

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$5,352.20

Scenario Cost/Unit: \$5,352.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	55	\$294.80
Hydraulic Excavator, .5 CY	930	Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included.	Hour	\$63.99	2	\$127.98
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	9	\$318.24
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	2	\$56.60
Materials						
Steel, Plate, 1/8"	1047	Flat Steel Plate, 1/8" thick, materials only.	Square Foot	\$3.89	36	\$140.04
Steel, Plate, 3/16"	1048	Flat Steel Plate, 3/16" thick, materials only.	Square Foot	\$5.84	32	\$186.88
Pipe, Steel, 24", Std Wt, USED	1360	Materials: - USED - 24" - Steel Std Wt	Foot	\$49.83	65	\$3,238.95
Steel, Angle, 2 1/2" x 2 1/2" x 1/4"	1372	Materials: Angle, 2 1/2" x 2 1/2" x 1/4", Meets ASTM A36	Foot	\$3.39	30	\$101.70
Steel, Plate, 3/8"	1375	Flat steel plate, 3/8" thickness. Materials only.	Square Foot	\$11.33	8	\$90.64
Trash Guard, metal	1608	Trash Guard, fabricated-steel, includes materials, equipment, and labor to transport and place Conical shaped trash guard for drop inlet spillway. Typically fabricated of CMP and steel. Includes materials, equipment, and labor to fabricate and transport	Pound	\$2.32	155	\$359.60
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 587 - Structure for Water Control

Scenario #6 - Weir Box Inlet WCS, Surface Water Control Using Existing Pipe (Box Only)

Scenario Description:

A structure in a water management system that conveys water, controls the direction or rate of flow, maintains a desired water surface elevation or measures water. This practice applies wherever a permanent structure is needed as an integral part of a water-control system. A fabricated weir box structure is installed on existing piping.

Before Situation:

The landowner wishes to provide for a way to control the water surface elevation in a wetland area. The landowner wishes to enhance and enlarge the area to provide habitat for fish and wildlife.

After Situation:

A weir box structure is placed in a levee over an existing subsurface system to manage water level elevation. A wetland area is enhanced and water levels can be varied to better accommodate wildlife needs. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Wetland Creation (658), Wetland Enhancement (659) Wetland Wildlife Habitat Management (644), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

Feature Measure: Number of structures

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$518.42

Scenario Cost/Unit: \$518.42

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	4	\$141.44
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Materials						
Steel, Plate, 3/16"	1048	Flat Steel Plate, 3/16" thick, materials only.	Square Foot	\$5.84	32	\$186.88
Steel, Angle, 2 1/2" x 2 1/2" x 1/4"	1372	Materials: Angle, 2 1/2" x 2 1/2" x 1/4", Meets ASTM A36	Foot	\$3.39	30	\$101.70

**Practice:** 587 - Structure for Water Control

**Scenario #7** - Watertight Flapgate Inflow WCS, Surface Water Control, <=15 in. dia. Pipe

#### Scenario Description:

A structure in a water management system that conveys water, controls the direction or rate of flow, maintains a desired water surface elevation or measures water. This practice applies wherever a permanent structure is needed as an integral part of a water-control system. A Flap/Slide Gate with a pipe of 15" diameter or less is placed in a levee to manage water level elevation. Payment incorporates pipe, anti seep collar, trash guard, animal guard, and flap gate.

#### Before Situation:

A wetland or other area is in need of a flap gate to control the flow of water through a pipe to provide habitat for fish and wildlife. The landowner wishes to provide a way for water to flow into a managed wetland pool yet automatically prevent flow from leaving the pool when the water source inflow head becomes less than the pool head.

#### After Situation:

A WCS pipe with flap gate 15" or less in diameter is installed. The pipe is installed through a water management embankment allowing shallow water impoundments to take on water from a higher elevation such as floodwater. When the surface of the inflow water source drops to an elevation that is lower than the wetland pool water surface, the flap gate automatically closes, preventing the loss of water from the wetland area. A wetland area is enhanced by having the ability to automatically fill with water when the hydrologic opportunity presents itself to better accommodate wildlife needs. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Wetland Creation (658), Wetland Enhancement (659) Wetland Wildlife Habitat Management (644), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

**Feature Measure:** Number of structures

**Scenario Unit::** Each

**Scenario Typical Size:** 1.0

**Scenario Total Cost:** \$3,235.97

**Scenario Cost/Unit:** \$3,235.97

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	6	\$343.02
<b>Labor</b>						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	4	\$141.44
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	12	\$263.76
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	6	\$169.80
<b>Materials</b>						
Steel, Plate, 1/8"	1047	Flat Steel Plate, 1/8" thick, materials only.	Square Foot	\$3.89	49	\$190.61
Steel, Plate, 3/8"	1375	Flat steel plate, 3/8" thickness. Materials only.	Square Foot	\$11.33	4	\$45.32
Trash Guard, metal	1608	Trash Guard, fabricated-steel, includes materials, equipment, and labor to transport and place Conical shaped trash guard for drop inlet spillway. Typically fabricated of CMP and steel. Includes materials, equipment, and labor to fabricate and transport	Pound	\$2.32	82	\$190.24
Pipe, PVC, 15", SDR 35	1722	Materials: 15" - PVC - SDR35 - ASTM D3034	Foot	\$25.09	65	\$1,630.85
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 587 - Structure for Water Control

Scenario #8 - Watertight Flapgate Inflow WCS, Surface Water Control, >15 in. dia. Pipe

Scenario Description:

A structure in a water management system that conveys water, controls the direction or rate of flow, maintains a desired water surface elevation or measures water. This practice applies wherever a permanent structure is needed as an integral part of a water-control system. A Flap/Slide Gate with a pipe of greater than 15" diameter is placed in a levee to manage water level elevation. Payment incorporates pipe, anti seep collar, trash guard, animal guard, and flap gate.

Before Situation:

A wetland or other area is in need of a flap gate to control the flow of water through a pipe to provide habitat for fish and wildlife. The landowner wishes to provide a way for water to flow into a managed wetland pool yet automatically prevent flow from leaving the pool when the water source inflow head becomes less than the pool head.

After Situation:

A WCS pipe with flap gate greater than 15" in diameter is installed. The pipe is installed through a water management embankment allowing shallow water impoundments to take on water from a higher elevation such as floodwater. When the surface of the inflow water source drops to an elevation that is lower than the wetland pool water surface, the flap gate automatically closes, preventing the loss of water from the wetland area. A wetland area is enhanced by having the ability to automatically fill with water when the hydrologic opportunity presents itself to better accommodate wildlife needs. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Wetland Creation (658), Wetland Enhancement (659) Wetland Wildlife Habitat Management (644), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

Feature Measure: Number of structures

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$3,948.16

Scenario Cost/Unit: \$3,948.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	6	\$343.02
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	5	\$176.80
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	12	\$263.76
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	6	\$169.80
Materials						
Steel, Plate, 1/8"	1047	Flat Steel Plate, 1/8" thick, materials only.	Square Foot	\$3.89	49	\$190.61
Pipe, PVC, 24", PS 46	1254	Pipe, PVC, PS 46, 24" Diameter - ASTM F679. Material cost only.	Each	\$32.20	65	\$2,093.00
Steel, Plate, 3/8"	1375	Flat steel plate, 3/8" thickness. Materials only.	Square Foot	\$11.33	8	\$90.64
Trash Guard, metal	1608	Trash Guard, fabricated-steel, includes materials, equipment, and labor to transport and place Conical shaped trash guard for drop inlet spillway. Typically fabricated of CMP and steel. Includes materials, equipment, and labor to fabricate and transport	Pound	\$2.32	155	\$359.60
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 587 - Structure for Water Control

Scenario #9 - Inline WCS, Subsurface Drainage Control, <=10 in. dia. Pipe

Scenario Description:

A subsurface drainage system on a field with a fairly flat slope (less than 2% and preferably less than 1%) outlets through a control structure which is operated with stoplogs. This allows the operator to keep the water in the soil profile when it is not critical to dry the soil. This retention time allows nutrients to be reduced by bacteria such that the nutrients do not leave with the water. A single stoplog structure may have its influence extended by buried float-activated structures which can be counted as structures also for a separate payment. Resource Concerns: Water Quality Degradation (Nutrients). Associated Practices: 606 - Subsurface Drain; 554 - Drainage Water Management

Before Situation:

The discharge from a subsurface drainage system enters ditches or streams, often laden with sediment and nutrients.

After Situation:

The discharge from a subsurface drainage system enters ditches or streams only when the soil profile needs to be dry. The retention time in the soil profile removes nutrients. Typical affected area for a single structure is 10-20 acres. A single structure with stoplogs may have its influence extended by use of buried float-activated control structures, which may be paid for as separate structures also.

Feature Measure: Number of Structures

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,720.51

Scenario Cost/Unit: \$1,720.51

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	3	\$171.51
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	3	\$116.34
Materials						
Pipe, PVC, 8" , SDR 35	994	Materials: - 8" - PVC - SDR 35 - ASTM D3034	Foot	\$8.02	40	\$320.80
Water Control Structure, Stoplog, Inline, fixed costs portion	2145	Fixed cost portion of Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Fixed cost portion. Materials only.	Each	\$312.56	1	\$312.56
Water Control Structure, Stoplog, Inline, variable cost portion	2146	Variable cost portion of a Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Calculate total variable costs by multiplying by the structure height x pipe diameter. Materials only.	Height x Diameter	\$12.08	48	\$579.84
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: 587 - Structure for Water Control

Scenario #10 - Inline WCS, Subsurface Drainage Control, >10 in. dia. Pipe

Scenario Description:

A subsurface drainage system on a field with a fairly flat slope (less than 2% and preferably less than 1%) outlets through a control structure which is operated with stoplogs. This allows the operator to keep the water in the soil profile when it is not critical to dry the soil. This retention time allows nutrients to be reduced by bacteria such that the nutrients do not leave with the water. A single stoplog structure may have its influence extended by buried float-activated structures which can be counted as structures also for a separate payment. Resource Concerns: Water Quality Degradation (Nutrients). Associated Practices: 606 - Subsurface Drain; 554 - Drainage Water Management

Before Situation:

The discharge from a subsurface drainage system enters ditches or streams, often laden with sediment and nutrients.

After Situation:

The discharge from a subsurface drainage system enters ditches or streams only when the soil profile needs to be dry. The retention time in the soil profile removes nutrients. Typical affected area for a single structure is 10-20 acres. A single structure with stoplogs may have its influence extended by use of buried float-activated control structures, which may be paid for as separate structures also.

Feature Measure: Number of Structures

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$2,362.23

Scenario Cost/Unit: \$2,362.23

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	3	\$171.51
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	3	\$116.34
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.77	380	\$672.60
Water Control Structure, Stoplog, Inline, fixed costs portion	2145	Fixed cost portion of Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Fixed cost portion. Materials only.	Each	\$312.56	1	\$312.56
Water Control Structure, Stoplog, Inline, variable cost portion	2146	Variable cost portion of a Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Calculate total variable costs by multiplying by the structure height x pipe diameter. Materials only.	Height x Diameter	\$12.08	72	\$869.76
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: 587 - Structure for Water Control

Scenario #12 - Straight Pipe, Surface Water Control, <=10 in. dia. Pipe (w/o adjustable control)

Scenario Description:

Used as an outlet for Wetland; no drop box; straight through 10" diameter PVC pipe; pipe is backfilled with #57 stone to 1' over the top of the pipe; 12" thick layer of Type D riprap is placed at the outlet end with 6" thick of #57 stone under it.

Before Situation:

The landowner wishes to establish a wetland area to provide habitat for fish and wildlife.

After Situation:

A straight pipe (principal spillway) is installed through an earth embankment to create a wetland. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Wetland Creation (658), Wetland Enhancement (659) Wetland Wildlife Habitat Management (644), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

Feature Measure: Feet of pipe installed

Scenario Unit:: Foot

Scenario Typical Size: 30.0

Scenario Total Cost: \$1,343.29

Scenario Cost/Unit: \$44.78

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	5	\$285.85
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	5	\$109.90
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	5	\$141.50
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	5	\$127.85
Pipe, PVC, 10", SDR 35	1251	Pipe, PVC, SDR 35, 10" Diameter - ASTM D3034. Material cost only.	Foot	\$12.56	30	\$376.80
Rock Riprap, graded, angular, material only	2131	Graded Rock Riprap for 12" to 24" size ranges. Includes material costs only. Shipping not included.	Ton	\$20.23	2	\$40.46
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93



Practice: 587 - Structure for Water Control

Scenario #13 - Straight Pipe, Surface Water Control, >=12 in. dia. Pipe (w/o adjustable control)

Scenario Description:

Used as an outlet for Wetland; no drop box; straight through 12" diameter PVC pipe; pipe is backfilled with #57 stone to 1' over the top of the pipe; 12" thick layer of Type D riprap is placed at the outlet end with 6" thick of #57 stone under it.

Before Situation:

The landowner wishes to establish a wetland area to provide habitat for fish and wildlife.

After Situation:

A straight pipe (principal spillway) is installed through an earth embankment to create a wetland. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Wetland Creation (658), Wetland Enhancement (659) Wetland Wildlife Habitat Management (644), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

Feature Measure: Feet of pipe installed

Scenario Unit:: Foot

Scenario Typical Size: 30.0

Scenario Total Cost: \$1,618.64

Scenario Cost/Unit: \$53.95

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	5	\$285.85
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	5	\$109.90
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	5	\$141.50
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	6	\$153.42
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.77	354	\$626.58
Rock Riprap, graded, angular, material only	2131	Graded Rock Riprap for 12" to 24" size ranges. Includes material costs only. Shipping not included.	Ton	\$20.23	2	\$40.46
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 590 - Nutrient Management

Scenario #1 - Basic NM (Non-Organic/Organic)

Scenario Description:

This scenario describes the implementation of a basic nutrient management system on > = 40 acres of cropland or hayland where there is no manure application. Scenario is applicable on non-organic and organic land. The planned NM system will meet the current Nutrient Management (590) CPS. Implementation will result in the proper rate, source, method of placement, and timing of nutrient application. Payment for implementation is to defray the costs of soil testing, analysis, and implementation of the nutrient management plan and recordkeeping. Records demonstrating implementation of the 4 R's of NM will be required.

Before Situation:

In this geographic area, a fertility program is either nonexistent or does not meet the Nutrient Management (590) CPS. Soil testing is not completed on a regular basis and applications of fertilizers are not based on land grant university recommendations or a nutrient budget. An environmental evaluation or risk assessment is not completed. Nutrients are transported to surface waters through runoff, drainage tile, or soil erosion, or to ground water from leaching in quantities that degrade water quality and limit use of intended purposes. Soil quality may be degraded by excess or inadequate nutrients. Fields have little or no erosion protection during critical periods often times resulting in sheet, rill, and ephemeral erosion.

After Situation:

A nutrient management system will be developed to meet the current Nutrient Management (590) CPS, when applicable system will also meet NOP regulations. Development and implementation of a nutrient management plan (NMP) will benefit plant productivity while also reducing potential for off-site degradation. A nutrient management budget will be developed for each field(s) based on soil test analysis and land grant university recommendations or crop removal rates. On planning units typically 40 acres or larger, soil testing is completed according to LGU recommendations. Records will be provided annually of the current soil test, analysis, application rates, forms and rates of nutrients for each field, including crop yields. Nutrient applications will be completed according to the Nutrient Management Plan that minimizes nutrient runoff and leaching or buildup of excess nutrient concentrations.

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: \$130.22

Scenario Cost/Unit: \$3.26

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	1	\$22.22
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	4	\$87.92
Materials						
Test, Soil Test, Standard	299	Includes materials, shipping, labor, and equipment costs.	Each	\$10.04	2	\$20.08

Practice: 590 - Nutrient Management

Scenario #2 - Basic NM with Manure Injection or Incorporation

Scenario Description:

This scenario describes the implementation of a basic nutrient management system on > = 40 acres of cropland or hayland where all applied nutrient sources (nitrogen, phosphorus, and potassium) are either incorporated using tillage at least 3-4 inches deep or injected into the soil at least 3-6 inches deep (Exceptions for incorporation or injection include: established close grown crops such as wheat or perennial crops such as hay or pasture). This scenario is applicable on non-organic and organic land for all nutrient sources (manure, compost, commercial fertilizers, and organic sources of nutrients). Micro-nutrients may be surface applied. The planned NM system will meet the current Nutrient Management (590) CPS. Implementation will result in the proper rate, source, method of placement (incorporation or injection), and timing of nutrient application. Payment for implementation is to defray the costs of soil testing, manure analysis, incorporation or injection of all nutrients, and the implementation of the nutrient management plan and recordkeeping. Records demonstrating implementation of the 4 R's of NM will be required. Scenario is designed to address the Nutrient Management (590) purposes for nitrogen losses via N2O emissions, nitrogen leaching, and nitrogen and phosphorus surface runoff. The basis for nutrient applications will be recommendations based on soil tests; and when applicable, plant tissue, manure, and compost analyses. Soil loss is controlled to the soil loss tolerance criteria or less for the significant soil map unit.

Before Situation:

In this geographic area, a fertility program is not properly managed to supply the proper rate, timing, method of application, and source to address air and water quality. Application of fertilizers, including manures, composts, and amendments, are surface applied and completed annually based upon tradition that does not specifically consider the detrimental effects of improper timing or rates of all nutrient sources, or excess nutrient buildup in the soil, emissions of N2O, surface runoff, or the leaching of nitrogen to ground or surface water via subsurface drainage. Fields are overwintered with little or no erosion protection often times resulting in sheet, rill, and ephemeral erosion by spring. Soil testing is not completed on a regular basis and applications of all nutrient sources are not based on land grant university recommendations or a nutrient budget. An environmental evaluation or risk assessment is not completed. Nutrients are transported to surface waters through runoff, drainage tile, soil erosion, or to ground water from leaching in quantities that degrade air and water quality. Soil quality may be degraded by excess or inadequate nutrients and erosion. Fields have little or no erosion protection during critical periods often times resulting in sheet, rill, and ephemeral erosion in excess of the planning criteria.

After Situation:

A nutrient management system is developed with the producer to meet the current Nutrient Management (590) CPS; and when applicable, the system will also meet NOP regulations. All nutrient sources will be incorporated with tillage at least 3-4 inches deep or injected at least 4-6 inches deep into the soil (Exceptions for incorporation or injection include: established close grown crops such as wheat or perennial crops such as hay or pasture). Implementation of the nutrient management plan (NMP) will benefit plant productivity while also reducing the potential for off-site degradation. A nutrient management budget will be developed for each field based on soil test analysis and land grant university recommendations or crop removal rates. On planning units typically 40 acres or larger, soil testing (and where applicable manure analyses, plant tissue analyses, etc.) is completed according to LGU recommendations. Applications of all phosphorus and nitrogen sources are based on risk assessments (PI - phosphorus index and leaching index). Records will be provided annually documenting current soil tests and other plant or manure analyses, date and rate of applications, form and placement of nutrients for each field, including post-harvest yields. Nutrient applications will be completed according to the NMP that minimizes nutrient runoff, nitrogen leaching, nitrogen emissions, or buildup of excess nutrient concentrations in the soil.

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: \$901.77

Scenario Cost/Unit: \$22.54

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	1	\$22.22
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	\$16.94	40	\$677.60
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	4	\$87.92
Materials						
Test, Soil Test, Standard	299	Includes materials, shipping, labor, and equipment costs.	Each	\$10.04	2	\$20.08
Test, Manure Analysis	306	Moisture, Total N, P, K. Includes materials and shipping only.	Each	\$44.78	1	\$44.78
Test, Compost Analysis	307	Moisture, Total N, P, K. Includes materials and shipping only.	Each	\$49.17	1	\$49.17

Practice: 590 - Nutrient Management

Scenario #4 - Basic NM with Manure and/or Compost (Non-Organic/Organic)

Scenario Description:

This scenario describes the implementation of a basic nutrient management system on > = 40 acres of cropland or hayland where manure and/or compost is utilized either alone or in conjunction with commercial fertilizer. Scenario is applicable on non-organic and organic land. The planned NM system will meet the current Nutrient Management (590) CPS. Implementation will result in the proper rate, source, method of placement, and timing of nutrient application. Payment for implementation is to defray the costs of soil testing, manure and/or compost analysis, and implementation of the nutrient management plan and recordkeeping. Records demonstrating implementation of the 4 R's of NM will be required. Scenario is designed to encourage producers to effectively utilize commercial fertilizers, organic fertilizers, manure, and/or compost appropriately improving soil quality and minimizing runoff of nutrients from fields to surface waters. The basis for nutrient applications will be recommendations based on soil, manure, and compost analyses.

Before Situation:

In this geographic area, a fertility program is either nonexistent or at a basic level. Application of fertilizers, including manures, composts, and amendments, are completed annually based upon tradition that does not specifically consider the detrimental effects of improper timing or rates of nutrients, or excess nutrient buildup in the soil. Fields are overwintered with little or no erosion protection often times resulting in sheet, rill, and ephemeral erosion by spring. Soil testing is not completed on a regular basis and applications of fertilizers are not based on land grant university recommendations or a nutrient budget. An environmental evaluation or risk assessment is not completed. Nutrients are transported to surface waters through runoff, drainage tile, or soil erosion, or to ground water from leaching in quantities that degrade water quality and limit use of intended purposes. Soil quality may be degraded by excess or inadequate nutrients. Fields have little or no erosion protection during critical periods often times resulting in sheet, rill, and ephemeral erosion.

After Situation:

A nutrient management system will be developed to meet the current Nutrient Management (590) CPS, when applicable system will also meet NOP regulations. Development and implementation of a nutrient management plan (NMP) will benefit plant productivity while also reducing potential for off-site degradation. A nutrient management budget will be developed for each field(s) based on soil test analysis and land grant university recommendations or crop removal rates. On planning units typically 40 acres or larger, soil testing is completed according to LGU recommendations. Records will be provided annually of the current soil test, analysis, application rate, forms and rates of nutrients for each field, including crop yields. Nutrient applications will be completed according to the Nutrient Management Plan that minimizes nutrient runoff and leaching or buildup of excess nutrient concentrations.

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: \$224.17

Scenario Cost/Unit: \$5.60

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	1	\$22.22
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	4	\$87.92
Materials						
Test, Soil Test, Standard	299	Includes materials, shipping, labor, and equipment costs.	Each	\$10.04	2	\$20.08
Test, Manure Analysis	306	Moisture, Total N, P, K. Includes materials and shipping only.	Each	\$44.78	1	\$44.78
Test, Compost Analysis	307	Moisture, Total N, P, K. Includes materials and shipping only.	Each	\$49.17	1	\$49.17

Practice: 590 - Nutrient Management

Scenario #5 - NM Nitrification/Urease Inhibitors, variable rate, grid/zone soil sampling, soil nitrate/plant tissue test (Non-Organic/Organic)

Scenario Description:

This scenario takes a conventional cropping system where either no nutrient management or only a very basic level of nutrient management is being practiced and improves it to address air quality (reduce emissions for N fertilizer) and/or minimize agricultural nonpoint source pollution of surface and groundwater. The planned NM system will meet the current Nutrient Management (590) CPS general and additional criteria. Nutrient management system includes such items as split applications, variable rate applications, nitrification or urease inhibitors, additional nutrient tests including PSNT (pre-side dress nitrogen test), CSNT (corn stalk nitrate test), and PPSN (pre-plant soil nitrate test), chlorophyll meters, and/or spectral analysis may be used to further refine nutrient applications. Payment for implementation is to defray the costs of grid or zone soil testing, additional testing and analysis, nitrification or urease inhibitors, equipment, implementation of the NMP and recordkeeping. Typical treatment area is 40 acres.

Before Situation:

In this geographic area, conventional fertility programs involve very little or no soil or manure testing. Application of fertilizers, including manures and amendments, are completed annually based upon tradition that does not specifically consider the detrimental affects of improper timing or rates of nutrients, nitrous oxide emissions or excess nutrient build-up in the soil. Fields are overwintered with little or no erosion protection often times resulting in sheet, rill, and ephemeral erosion by spring. Runoff flows into adjacent streams, water courses, tile drains, field surface drains, or other water courses causing degradation to receiving waters or leaching of nutrients to shallow ground water sources. There is typically no environmental evaluation of the potential for off-site movement. Soil quality may also be detrimentally affected.

After Situation:

A nutrient management system will be developed to meet the current Nutrient Management (590) CPS general and additional criteria, when applicable system will also meet NOP regulations. Development and implementation of a Nutrient Management Plan (NMP) base on the 4Rs will benefit plant productivity while reducing potential of off-site movement of nutrients, including the use of nitrification or urease inhibitors to reduce nitrogen emissions. NMP may include practices such as use of split applications, slow release nutrients, nitrification inhibitors, urease inhibitors, proper timing of application, more appropriate formulations, banding, etc. Additional nutrient tests including PSNT (pre-side dress nitrogen test), CSNT (corn stalk nitrate test), and PPSN (pre-plant soil nitrate test), chlorophyll meters, spectral analysis, etc., may also be used to further refine nutrient applications. Use of a post-harvest soil test or tissue tests will help establish the adequacy of the plan in meeting crop needs while minimizing P application rate and residual N, thus reducing the potential for off-site impacts. Potential for offsite movement of nutrient may be further reduced by identifying variability across the field(s) by using soil survey maps or other simple techniques to establish management zones, along with grid or zone soil testing. Nutrients are applied at rates based on soil test zone analyses. Nitrogen and Phosphorus risk assessment tools are completed and results included in the nutrient management system specifications as required by current NRCS 590 CPS criteria and any mitigation measures are included in the conservation plan if determined needed by risk assessment results. Soil testing is completed according to LGU recommendations. Analysis are completed at least once every three years for N-P-K, and for N annually. A nutrient budget is developed for each field or management zone annually. Records will be provided annually of the current soil test, analysis, application rates, forms and rates of nutrients for each field, including crop yields.

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: \$1,260.79

Scenario Cost/Unit: \$31.52

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	2	\$57.68
Chlorophyll Reader	1125	Applicator and chlorophyll sensor includes labor.?? No materials	Acre	\$11.09	40	\$443.60
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	4	\$87.92
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	1	\$93.25
Materials						
Nitrogen-Urease inhibitor	260	Nitrogen-Urease inhibitor	Acre	\$8.55	40	\$342.00
Test, Soil Test, Precision, Grid or Zone DELETION SCHEDULED for PS FY 2018 , USE CID 299	300	Includes materials, shipping, labor, and equipment costs. DELETION SCHEDULED for PS FY 2018 , USE CID 299	Each	\$10.31	15	\$154.65
Test, Plant Tissue Test	301	Tissue analysis for crops. Includes materials and shipping only.	Each	\$24.61	1	\$24.61
Test, Soil Nitrogen Testing	311	Pre-Side Dress/Deep Soil Testing. Includes materials and shipping only.	Each	\$12.64	1	\$12.64

Practice: 595 - Integrated Pest Management (IPM)

Scenario #1 - Basic IPM Field 1RC

Scenario Description:

A basic IPM plan with LGU-approved pest monitoring techniques and pest thresholds (where available) is applied in Large Scale Field/Forage Crops to address one identified resource concern (e.g. Water Quality - Impacts to Human Drinking Water) with either risk prevention (e.g. planned pesticides have no risk to the identified resource concern) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Before Situation:

Before practice conditions vary widely. Conditions range from the client is not using many pest suppression techniques (pesticides, tillage for weed control, burning, etc.) to the client is using many different pest suppression techniques for many different pests, but in all cases at least one planned pest suppression technique has risk to an identified resource concern (e.g. Water Quality – Impacts to Human Drinking Water).

After Situation:

After implementing the 595 practice, a basic IPM system has been implemented with Land Grant University approved pest monitoring techniques and pest thresholds (where available) to help meet the minimum criteria for one identified resource concern (e.g. Water Quality - Impacts to Human Drinking Water) with either risk prevention (e.g. planned pesticides have no risk to the identified resource concern) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Feature Measure: Acres of Implementation

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: \$443.72

Scenario Cost/Unit: \$11.09

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	4	\$373.00

Practice: 595 - Integrated Pest Management (IPM)

Scenario #2 - Basic IPM Field >1RC

Scenario Description:

A basic IPM plan with LGU-approved pest monitoring techniques and pest thresholds (where available) is applied in Large Scale Field/Forage Crops to address multiple identified resource concerns (e.g. Water Quality – Impacts to Human Drinking Water and Pollinator Impacts) with either risk prevention (e.g. planned pesticides have no risks to the identified resource concerns) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Before Situation:

Before practice conditions vary widely. Conditions range from the client is not using many pest suppression techniques (pesticides, tillage for weed control, burning, etc.) to the client is using many different pest suppression techniques for many different pests, but in all cases at least one planned pest suppression technique has risk to two or more identified resource concerns (e.g. Water Quality – Impacts to Human Drinking Water and Impacts on Pollinators).

After Situation:

After implementing the 595 practice, a basic IPM system has been implemented with Land Grant University approved pest monitoring techniques and pest thresholds (where available) to help meet the minimum criteria for two or more identified resource concerns (e.g. Water Quality - Impacts to Human Drinking Water and Impacts on Pollinators) with either risk prevention (e.g. planned pesticides have no risk to the identified resource concerns) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Feature Measure: Acres of Implementation

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: \$665.58

Scenario Cost/Unit: \$16.64

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	3	\$106.08
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	6	\$559.50

Practice: 595 - Integrated Pest Management (IPM)

Scenario #4 - Basic IPM Fruit/Veg 1RC

Scenario Description:

A basic IPM plan with LGU-approved pest monitoring techniques and pest thresholds (where available) is applied in Large Scale Small Fruit/Vegetable Crops to address one identified resource concern (e.g. Water Quality - Impacts to Human Drinking Water) with either risk prevention (e.g. planned pesticides no risk to the identified resource concern) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Before Situation:

Before practice conditions vary widely. Conditions range from the client is not using many pest suppression techniques (pesticides, tillage for weed control, burning, etc.) to the client is using many different pest suppression techniques for many different pests, but in all cases at least one planned pest suppression technique has risk to an identified resource concern (e.g. Water Quality – Impacts to Human Drinking Water).

After Situation:

After implementing the 595 practice, a basic IPM system has been implemented with Land Grant University approved pest monitoring techniques and pest thresholds (where available) to help meet the minimum criteria for at least one identified resource concern (e.g. Water Quality - Impacts to Human Drinking Water) with either risk prevention (e.g. planned pesticides have no risk to the identified resource concern) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Feature Measure: Acres of Implementation

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$797.32

Scenario Cost/Unit: \$79.73

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	12	\$424.32
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	4	\$373.00



Practice: 595 - Integrated Pest Management (IPM)

Scenario #5 - Basic IPM Fruit/Veg >1RC

Scenario Description:

A basic IPM plan with LGU-approved pest monitoring techniques and pest thresholds (where available) is applied in Large Scale Small Fruit/Vegetable Crops to address multiple identified resource concerns (e.g. Water Quality - Impacts to Human Drinking Water and Pollinator Impacts) with either risk prevention (e.g. planned pesticides have no risk to identified resource concerns) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Before Situation:

Before practice conditions vary widely. Conditions range from the client is not using many pest suppression techniques (pesticides, tillage for weed control, burning, etc.) to the client is using many different pest suppression techniques for many different pests, but in all cases at least one planned pest suppression technique has risk to two or more identified resource concerns (e.g. Water Quality – Impacts to Human Drinking Water and Impacts on Pollinators).

After Situation:

After implementing the 595 practice, a basic IPM system has been implemented with Land Grant University approved pest monitoring techniques and pest thresholds (where available) to help meet the minimum criteria for two or more identified resource concerns (e.g. Water Quality - Impacts to Human Drinking Water and Impacts on Pollinators) with either risk prevention (e.g. planned pesticides have no risk to the identified resource concerns) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Feature Measure: Acres of Implementation

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$1,684.76

Scenario Cost/Unit: \$168.48

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	16	\$565.76
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	12	\$1,119.00

Practice: 595 - Integrated Pest Management (IPM)

Scenario #7 - Basic IPM Orchard 1RC

Scenario Description:

A basic IPM plan with LGU-approved pest monitoring techniques and pest thresholds (where available) is applied in Large Scale Orchard/Specialty Crops to address one identified resource concern (e.g. Water Quality - Impacts to Human Drinking Water) with either risk prevention (e.g. planned pesticides have no risk to the identified resource concern) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Before Situation:

Before practice conditions vary widely. Conditions range from the client is not using many pest suppression techniques (pesticides, tillage for weed control, burning, etc.) to the client is using many different pest suppression techniques for many different pests, but in all cases at least one planned pest suppression technique has risk to an identified resource concern (e.g. Water Quality – Impacts to Human Drinking Water).

After Situation:

After implementing the 595 practice, a basic IPM system has been implemented with Land Grant University approved pest monitoring techniques and pest thresholds (where available) to help meet the minimum criteria for at least one identified resource concern (e.g. Water Quality - Impacts to Human Drinking Water) with either risk prevention (e.g. planned pesticides have no risk to the identified resource concern) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Feature Measure: Acres of Implementation

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$1,871.26

Scenario Cost/Unit: \$187.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	16	\$565.76
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	14	\$1,305.50

Practice: 595 - Integrated Pest Management (IPM)

Scenario #8 - Basic IPM Orchard >1RC

Scenario Description:

A basic IPM plan with LGU-approved pest monitoring techniques and pest thresholds (where available) is applied in Large Scale Orchard/Specialty Crops to address multiple identified resource concerns (e.g. Water Quality - Impacts to Human Drinking Water and Pollinator Impacts) with either risk prevention (e.g. planned pesticides have no risks to identified resource concerns) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Before Situation:

Before practice conditions vary widely. Conditions range from the client is not using many pest suppression techniques (pesticides, tillage for weed control, burning, etc.) to the client is using many different pest suppression techniques for many different pests, but in all cases at least one planned pest suppression technique has risk to two or more identified resource concerns (e.g. Water Quality – Impacts to Human Drinking Water and Impacts on Pollinators).

After Situation:

After implementing the 595 practice, a basic IPM system has been implemented with Land Grant University approved pest monitoring techniques and pest thresholds (where available) to help meet the minimum criteria for two or more identified resource concerns (e.g. Water Quality - Impacts to Human Drinking Water and Impacts on Pollinators) with either risk prevention (e.g. planned pesticides have no risk to the identified resource concerns) or risk mitigation (e.g. planned pesticides have appropriate mitigation planned from Agronomy Technical Note 5 for “Intermediate”, “High” or “Extra High” WIN-PST Final Hazard Ratings).

Feature Measure: Acres of Implementation

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$2,199.20

Scenario Cost/Unit: \$219.92

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	20	\$707.20
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	16	\$1,492.00

Practice: 600 - Terrace

Scenario #1 - Broadbase, with Topsoiling

Scenario Description:

An earthen embankment with channel constructed across the field slope as part of a system to shorten slope lengths and reduce sheet, rill, and gully erosion in a cropped field. Scenario is for the installation of a system of broadbase terraces where channel and berm are farmed. Topsoil is stripped and stockpiled during construction. A stable outlet is provided in the form of a Grassed Waterway, other open outlet or Underground Outlet through associated practices. Payment include all equipment and labor necessary to excavate, shape, and compact terraces, and stripping and stockpiling topsoil. This practice addresses Concentrated Flow Erosion and Excessive Sediment in surface waters.

Before Situation:

Long slope lengths contribute to excessive sedimentation and soil erosion in cropped fields as a result of gully, rill, and sheet erosion. The excessive erosion may lead to deterioration of receiving waters due to excessive sedimentation and nutrient transport.

After Situation:

A system of broadbased terraces measuring 2,500 feet in length, 2.5 height, and 5:1 front and back slopes is installed with spacing designed to intercept flow of water and shorten slope length to reduce erosion to acceptable levels. Work is done with dozer, scraper, or road grader. The installed terrace is typically farmed. Associated practices are Underground Outlet (620), Critical Area Planting (342) and Grassed Waterway (412).

Feature Measure: Length of Terrace

Scenario Unit:: Foot

Scenario Typical Size: 2,500.0

Scenario Total Cost: \$10,882.48

Scenario Cost/Unit: \$4.35

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Stripping and stockpiling, topsoil	1199	Stripping and stockpiling of topsoil adjacent to stripping area. Includes equipment and labor.	Cubic Yard	\$0.91	4500	\$4,095.00
Excavation, common earth, large equipment, 50 ft	1222	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$1.63	3750	\$6,112.50
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	5	\$176.80
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	1	\$498.18

Practice: 600 - Terrace

Scenario #2 - Broadbase, no Topsoiling

Scenario Description:

An earthen embankment with channel constructed across the field slope as part of a system to shorten slope lengths and reduce sheet, rill, and gully erosion in a cropped field. Scenario is for the installation of a system of broadbase terraces where channel and berm are farmed. A stable outlet is provided in the form of a Grassed Waterway, other open outlet or Underground Outlet through associated practices. Payment includes all equipment and labor necessary to excavate, shape, and compact terraces. This practice addresses Concentrated Flow Erosion and Excessive Sediment in surface waters.

Before Situation:

Long slope lengths contribute to excessive sedimentation and soil erosion in cropped fields as a result of gully, rill, and sheet erosion. The excessive erosion may lead to deterioration of receiving waters due to excessive sedimentation and nutrient transport.

After Situation:

A system of broadbased terraces measuring 2,500 feet in length, 2.5 height, and 5:1 front and back slopes is installed with spacing designed to intercept flow of water and shorten slope length to reduce erosion to acceptable levels. Work is done with dozer, scraper, or road grader. The installed terrace is typically farmed. Associated practices are Underground Outlet (620), Critical Area Planting (342) and Grassed Waterway (412).

Feature Measure: Length of Terrace

Scenario Unit:: Foot

Scenario Typical Size: 2,500.0

Scenario Total Cost: \$6,787.48

Scenario Cost/Unit: \$2.71

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, common earth, large equipment, 50 ft	1222	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$1.63	3750	\$6,112.50
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	5	\$176.80
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	1	\$498.18

Practice: 600 - Terrace

Scenario #10 - Grassed Front or Steep Backslope, with Topsoiling

Scenario Description:

An earthen embankment with channel constructed across the field slope as part of a system to shorten slope lengths and reduce sheet, rill, and gully erosion in a cropped field. Scenario is for the installation is a system of either grassed front or steep backslope (grassed backed) terraces where each terrace is constructed with one relatively flat (5:1) slope and one steep (2:1) slope constructed in a field. Topsoil is stripped from the borrow area and replaced upon completion of the terrace. The steep slopes are established to permanent vegetation and the flatter slopes are farmed. A stable outlet is provided in the form of a Grassed Waterway, other open outlet or Underground Outlet through associated practices Payment includes all equipment and labor necessary to excavate, shape, and compact terraces, and stripping and stockpiling topsoil. For the establishment of permanent vegetation on the terraces use associated practice Critical Area Planting (342). This practice addresses Concentrated Flow Erosion and Excessive Sediment in surface waters.

Before Situation:

Long slope lengths contribute to excessive sedimentation and soil erosion in cropped fields as a result of gully, rill, and sheet erosion. The excessive erosion may lead to deterioration of receiving waters due to excessive sedimentation and nutrient transport.

After Situation:

A system of terraces with one steep (2:1) and one flat (5:1) slope measuring 2,500 feet in length and 3.2' height is installed with spacing designed to intercept flow of water and shorten slope length to reduce erosion to acceptable levels. Work is done with dozer, scraper, or road grader. Associated practices are Critical Area Planting (342), Grassed Waterway (412), and Underground Outlet (620).

Feature Measure: Length of Terrace

Scenario Unit:: Foot

Scenario Typical Size: 2,500.0

Scenario Total Cost: \$10,067.48

Scenario Cost/Unit: \$4.03

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Stripping and stockpiling, topsoil	1199	Stripping and stockpiling of topsoil adjacent to stripping area. Includes equipment and labor.	Cubic Yard	\$0.91	4500	\$4,095.00
Excavation, common earth, large equipment, 50 ft	1222	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$1.63	3250	\$5,297.50
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	5	\$176.80
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	1	\$498.18

Practice: 600 - Terrace

Scenario #11 - Grassed Front or Steep Backslope, no Topsoiling

Scenario Description:

An earthen embankment with channel constructed across the field slope as part of a system to shorten slope lengths and reduce sheet, rill, and gully erosion in a cropped field. Scenario is for the installation is a system of either grassed front or steep backslope (grassed backed) terraces where each terrace is constructed with one relatively flat (5:1) slope and one steep (2:1) slope constructed in a field. The steep slopes are established to permanent vegetation and the flatter slopes are farmed. A stable outlet is provided in the form of a Grassed Waterway, other open outlet or Underground Outlet through associated practices Payment includes all equipment and labor necessary to excavate, shape, and compact terraces, and stripping and stockpiling topsoil. For the establishment of permanent vegetation on the terraces use associated practice Critical Area Planting (342). This practice addresses Concentrated Flow Erosion and Excessive Sediment in surface waters.

Before Situation:

Long slope lengths contribute to excessive sedimentation and soil erosion in cropped fields as a result of gully, rill, and sheet erosion. The excessive erosion may lead to deterioration of receiving waters due to excessive sedimentation and nutrient transport.

After Situation:

A system of terraces with one steep (2:1) and one flat (5:1) slope measuring 2,500 feet in length and 3.2' height is installed with spacing designed to intercept flow of water and shorten slope length to reduce erosion to acceptable levels. Work is done with dozer, scraper, or road grader. Associated practices are Critical Area Planting (342), Grassed Waterway (412), and Underground Outlet (620).

Feature Measure: Length of Terrace

Scenario Unit:: Foot

Scenario Typical Size: 2,500.0

Scenario Total Cost: \$5,972.48

Scenario Cost/Unit: \$2.39

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, common earth, large equipment, 50 ft	1222	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$1.63	3250	\$5,297.50
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	5	\$176.80
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	1	\$498.18

Practice: 606 - Subsurface Drain

Scenario #1 - <= 5in CPP

Scenario Description:

Description: Below ground installation of perforated HDPE (Corrugated Plastic Pipe) pipeline, using a trencher. Scenario describes the construction 2,000 feet of 5-inch, Single-Wall, perforated HDPE Corrugated Plastic Pipe (CPP), installed below ground to a minimum depth of 5 feet. Subsurface drainage is installed as a supporting practice for a number of associated conservation practices. Resource Concerns: Excess Water (Seasonal High Water Table); Degraded Plant Condition; Water Quality Degradation (Nutrients). Associated Practices: 608 - Surface Drain, Main or Lateral; 587 - Structure for Water Control, 533 - Pumping Plant; and 554 - Drainage Water Management; 620 - Underground Outlet; 412 - Grassed Waterway; 638 - Water and Sediment Control Basin; 342 - Critical Area Planting; 484 - Mulching; 410 - Grade Stabilization Structure; 468 - Lined Waterway or Outlet; 313 Waste Storage Facility

Before Situation:

Before installation soil conditions are excessively wet in the spring due to poor internal soil drainage. Excess soil water is causing crop stress and delay of field operations (seed bed preparation, planting, etc.). Conservation practice implementation including (but not limited to) grassed waterways have a high failure rate due to the prolonged wetness that prohibits plant germination and/or drowns new growth.

After Situation:

The drainage modifications result in reduced water in the upper horizons of the soil profile, allowing for sufficient aeration to allow vegetation to establish. Gully erosion and sediment transport are minimized by established vegetation, a direct result of removing excess water from the soil profile. Plant stress due to excessive wetness caused by a seasonal high water table is minimized, and drainage water quality is improved due to increased erosion control.

Feature Measure: length of pipe

Scenario Unit:: Foot

Scenario Typical Size: 2,000.0

Scenario Total Cost: \$4,180.93

Scenario Cost/Unit: \$2.09

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, 12" x 48"	53	Trenching, earth, 12" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$1.26	2000	\$2,520.00
Materials						
Pipe, HDPE, 5", PCPT, Single Wall	1271	Pipe, Corrugated Plastic Tubing, Single Wall, Perforated, 5" diameter - ASTM F405. Material cost only.	Foot	\$0.70	2000	\$1,400.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93



Practice: 606 - Subsurface Drain

Scenario #2 - 6in CPP

Scenario Description:

Description: Below ground installation of perforated HDPE (Corrugated Plastic Pipe) pipeline, using a trencher. Scenario describes construction of 2,000 feet of 6-inch, Single-Wall, perforated HDPE Corrugated Plastic Pipe (CPP), installed below ground to a minimum depth of 5 feet. Subsurface drainage is installed as a supporting practice for a number of associated conservation practices. Resource Concerns: Excess Water (Seasonal High Water Table); Degraded Plant Condition; Water Quality Degradation (Nutrients). Associated Practices: 608 - Surface Drain, Main or Lateral; 587 - Structure for Water Control, 533 - Pumping Plant; and 554 - Drainage Water Management; 620 - Underground Outlet; 412 - Grassed Waterway; 638 - Water and Sediment Control Basin; 342 - Critical Area Planting; 484 - Mulching; 410 - Grade Stabilization Structure; 468 - Lined Waterway or Outlet; 313 - Waste Storage Facility

Before Situation:

Before installation soil conditions are excessively wet in the spring due to poor internal soil drainage. Excess soil water is causing crop stress and delay of field operations (seed bed preparation, planting, etc.). Conservation practice implementation including (but not limited to) grassed waterways have a high failure rate due to the prolonged wetness that prohibits plant germination and/or drowns new growth.

After Situation:

The drainage modifications result in reduced water in the upper horizons of the soil profile, allowing for sufficient aeration to allow vegetation to establish. Gully erosion and sediment transport are minimized by established vegetation, a direct result of removing excess water from the soil profile. Plant stress due to excessive wetness caused by a seasonal high water table is minimized, and drainage water quality is improved due to increased erosion control.

Feature Measure: length of pipe

Scenario Unit:: Foot

Scenario Typical Size: 2,000.0

Scenario Total Cost: \$5,040.93

Scenario Cost/Unit: \$2.52

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, 12" x 48"	53	Trenching, earth, 12" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$1.26	2000	\$2,520.00
Materials						
Pipe, HDPE, 6", CPT, Single Wall	1242	Pipe, Corrugated Plastic Tubing, Single Wall, 6" diameter - ASTM F405. Material cost only.	Foot	\$1.13	2000	\$2,260.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 606 - Subsurface Drain

Scenario #3 - 8in CPP

Scenario Description:

Description: Below ground installation of perforated HDPE (Corrugated Plastic Pipe) pipeline, using a trencher. Scenario describes the construction 2,000 feet of 8-inch, Single-Wall, perforated HDPE Corrugated Plastic Pipe (CPP), installed below ground to a minimum depth of 5 feet. Subsurface drainage is installed as a supporting practice for a number of associated conservation practices. Resource Concerns: Excess Water (Seasonal High Water Table); Degraded Plant Condition; Water Quality Degradation (Nutrients). Associated Practices: 608 - Surface Drain, Main or Lateral; 587 - Structure for Water Control, 533 - Pumping Plant; and 554 - Drainage Water Management; 620 - Underground Outlet; 412 - Grassed Waterway; 638 - Water and Sediment Control Basin; 342 - Critical Area Planting; 484 - Mulching; 410 - Grade Stabilization Structure; 468 - Lined Waterway or Outlet; 313 - Waste Storage Facility

Before Situation:

Before installation soil conditions are excessively wet in the spring due to poor internal soil drainage. Excess soil water is causing crop stress and delay of field operations (seed bed preparation, planting, etc.). Conservation practice implementation including (but not limited to) grassed waterways have a high failure rate due to the prolonged wetness that prohibits plant germination and/or drowns new growth.

After Situation:

The drainage modifications result in reduced water in the upper horizons of the soil profile, allowing for sufficient aeration to allow vegetation to establish. Gully erosion and sediment transport are minimized by established vegetation, a direct result of removing excess water from the soil profile. Plant stress due to excessive wetness caused by a seasonal high water table is minimized, and drainage water quality is improved due to increased erosion control.

Feature Measure: length of pipe

Scenario Unit:: Foot

Scenario Typical Size: 2,000.0

Scenario Total Cost: \$11,960.93

Scenario Cost/Unit: \$5.98

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, 24" x 60"	1460	Trenching, earth, 24" wide x 60" depth, includes equipment and labor for trenching and backfilling.	Foot	\$3.88	2000	\$7,760.00
Materials						
Pipe, HDPE, 8", PCPT, Single Wall	1272	Pipe, Corrugated Plastic Tubing, Single Wall, Perforated, 8" diameter - ASTM F667. Material cost only.	Foot	\$1.97	2000	\$3,940.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 606 - Subsurface Drain

Scenario #4 - 10in CPP

Scenario Description:

Description: Below ground installation of perforated HDPE (Corrugated Plastic Pipe) pipeline, using a trencher. Scenario describes the construction 2,000 feet of 10-inch, Single-Wall, perforated HDPE Corrugated Plastic Pipe (CPP), installed below ground to a minimum depth of 5 feet. Subsurface drainage is installed as a supporting practice for a number of associated conservation practices. Resource Concerns: Excess Water (Seasonal High Water Table); Degraded Plant Condition; Water Quality Degradation (Nutrients). Associated Practices: 608 - Surface Drain, Main or Lateral; 587 - Structure for Water Control, 533 - Pumping Plant; and 554 - Drainage Water Management; 620 - Underground Outlet; 412 - Grassed Waterway; 638 - Water and Sediment Control Basin; 342 - Critical Area Planting; 484 - Mulching; 410 - Grade Stabilization Structure; 468 - Lined Waterway or Outlet; 313 - Waste Storage Facility

Before Situation:

Before installation soil conditions are excessively wet in the spring due to poor internal soil drainage. Excess soil water is causing crop stress and delay of field operations (seed bed preparation, planting, etc.). Conservation practice implementation including (but not limited to) grassed waterways have a high failure rate due to the prolonged wetness that prohibits plant germination and/or drowns new growth.

After Situation:

The drainage modifications result in reduced water in the upper horizons of the soil profile, allowing for sufficient aeration to allow vegetation to establish. Gully erosion and sediment transport are minimized by established vegetation, a direct result of removing excess water from the soil profile. Plant stress due to excessive wetness caused by a seasonal high water table is minimized, and drainage water quality is improved due to increased erosion control.

Feature Measure: length of pipe

Scenario Unit:: Foot

Scenario Typical Size: 2,000.0

Scenario Total Cost: \$15,800.93

Scenario Cost/Unit: \$7.90

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, 24" x 60"	1460	Trenching, earth, 24" wide x 60" depth, includes equipment and labor for trenching and backfilling.	Foot	\$3.88	2000	\$7,760.00
Materials						
Pipe, HDPE, 10", PCPT, Single Wall	1273	Pipe, Corrugated Plastic Tubing, Single Wall, Perforated, 10" diameter - ASTM F667. Material cost only.	Foot	\$3.89	2000	\$7,780.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 606 - Subsurface Drain

Scenario #5 - 12in CPP

Scenario Description:

Description: Below ground installation of perforated HDPE (Corrugated Plastic Pipe) pipeline, using a trencher. Scenario describes the construction 2,000 feet of 12-inch, Single-Wall, perforated HDPE Corrugated Plastic Pipe (CPP), installed below ground to a minimum depth of 5 feet. Subsurface drainage is installed as a supporting practice for a number of associated conservation practices. Resource Concerns: Excess Water (Seasonal High Water Table); Degraded Plant Condition; Water Quality Degradation (Nutrients). Associated Practices: 608 - Surface Drain, Main or Lateral; 587 - Structure for Water Control, 533 - Pumping Plant; and 554 - Drainage Water Management; 620 - Underground Outlet; 412 - Grassed Waterway; 638 - Water and Sediment Control Basin; 342 - Critical Area Planting; 484 - Mulching; 410 - Grade Stabilization Structure; 468 - Lined Waterway or Outlet; 313 - Waste Storage Facility

Before Situation:

Before installation soil conditions are excessively wet in the spring due to poor internal soil drainage. Excess soil water is causing crop stress and delay of field operations (seed bed preparation, planting, etc.). Conservation practice implementation including (but not limited to) grassed waterways have a high failure rate due to the prolonged wetness that prohibits plant germination and/or drowns new growth.

After Situation:

The drainage modifications result in reduced water in the upper horizons of the soil profile, allowing for sufficient aeration to allow vegetation to establish. Gully erosion and sediment transport are minimized by established vegetation, a direct result of removing excess water from the soil profile. Plant stress due to excessive wetness caused by a seasonal high water table is minimized, and drainage water quality is improved due to increased erosion control.

Feature Measure: length of pipe

Scenario Unit:: Foot

Scenario Typical Size: 2,000.0

Scenario Total Cost: \$17,740.93

Scenario Cost/Unit: \$8.87

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, 24" x 60"	1460	Trenching, earth, 24" wide x 60" depth, includes equipment and labor for trenching and backfilling.	Foot	\$3.88	2000	\$7,760.00
Materials						
Pipe, HDPE, 12", PCPT, Single Wall	1274	Pipe, Corrugated Plastic Tubing, Single Wall, Perforated, 12" diameter - ASTM F667. Material cost only.	Foot	\$4.86	2000	\$9,720.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 606 - Subsurface Drain

Scenario #6 - >/= 15in CPP

Scenario Description:

Description: Below ground installation of perforated HDPE (Corrugated Plastic Pipe) pipeline, using a trencher. Scenario describes the construction 2,000 feet of 15-inch, twin-Wall, perforated HDPE Corrugated Plastic Pipe (CPP), installed below ground to a minimum depth of 5 feet. Subsurface drainage is installed as a supporting practice for a number of associated conservation practices. Resource Concerns: Excess Water (Seasonal High Water Table); Degraded Plant Condition; Water Quality Degradation (Nutrients). Associated Practices: 608 - Surface Drain, Main or Lateral; 587 - Structure for Water Control, 533 - Pumping Plant; and 554 - Drainage Water Management; 620 - Underground Outlet; 412 - Grassed Waterway; 638 - Water and Sediment Control Basin; 342 - Critical Area Planting; 484 - Mulching; 410 - Grade Stabilization Structure; 468 - Lined Waterway or Outlet; 313 - Waste Storage Facility

Before Situation:

Before installation soil conditions are excessively wet in the spring due to poor internal soil drainage. Excess soil water is causing crop stress and delay of field operations (seed bed preparation, planting, etc.). Conservation practice implementation including (but not limited to) grassed waterways have a high failure rate due to the prolonged wetness that prohibits plant germination and/or drowns new growth.

After Situation:

The drainage modifications result in reduced water in the upper horizons of the soil profile, allowing for sufficient aeration to allow vegetation to establish. Gully erosion and sediment transport are minimized by established vegetation, a direct result of removing excess water from the soil profile. Plant stress due to excessive wetness caused by a seasonal high water table is minimized, and drainage water quality is improved due to increased erosion control.

Feature Measure: length of pipe

Scenario Unit:: Foot

Scenario Typical Size: 2,000.0

Scenario Total Cost: \$22,740.93

Scenario Cost/Unit: \$11.37

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, 24" x 60"	1460	Trenching, earth, 24" wide x 60" depth, includes equipment and labor for trenching and backfilling.	Foot	\$3.88	2000	\$7,760.00
Materials						
Pipe, HDPE, corrugated double wall, GTE115", soil tight, weight priced	1588	High Density Polyethylene (HDPE) compound manufactured into double wall corrugated pipe GTE-15" diameter. Materials only.	Pound	\$1.60	9200	\$14,720.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 612 - Tree/Shrub Establishment

Scenario #1 - Hardwood Establishment, Direct Seeding

Scenario Description:

This practice involves planting of tree and shrubs through direct seeding after the site has been prepared for seedling growth and establishment. Planting rate will be approximately 3000 seed per acre. The productivity of the site is good and will handle a medium density planting rate. The resource concerns addressed is degraded plant condition -- undesirable plant productivity and health, and inadequate structure and composition and degraded wildlife habitat. Payment includes tree seed, equipment and labor to seed, and foregone income for the land taken out of crop production. Site preparation is implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching

Before Situation:

The land has a little or no tree cover and has been intensively row cropped. Soil condition is degraded due to the loss of the native forest ecosystem (organic matter in top soil depleted). Native wildlife habitat is lacking. The main resource concern is degraded plant condition and inadequate structure and composition

After Situation:

Seed from native species are collected or purchased and planted at prescribed rates. 5 acres of land is established with permanent tree cover that will improve degraded plant condition, reduce soil erosion, establish wildlife habitat, sequester carbon and reduce invasive species presence. Establishing forest vegetation also creates corridors for wildlife movement.

Feature Measure: Area of Treatment

Scenario Unit:: Acre

Scenario Typical Size: 5.0

Scenario Total Cost: \$3,903.04

Scenario Cost/Unit: \$780.61

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	8	\$177.76
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	8	\$202.16
Mechanical nut planter	1601	Mechanical nut planter for direct seeding of trees and shrubs. Requires a pulling unit of either tractor or small dozer depending upon site conditions. Does not include labor.	Hour	\$2.15	8	\$17.20
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	2.5	\$1,038.03
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	2.5	\$1,037.50
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	8	\$176.72
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	8	\$310.24
Materials						
Trees and shrubs, seed	1871	Tree or shrub seed, e.g., acorns, to establish trees. Includes materials and shipping only.	Pound	\$4.55	150	\$682.50
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 612 - Tree/Shrub Establishment

Scenario #7 - Bareroot Trees and Shrubs, Each

Scenario Description:

Bare-root trees and/or shrubs to be planted or interplanted to establish woody plants in any area where they can be grown for wildlife, erosion control, water quality improvement, carbon sequestration, forest products, and aesthetics. Resource concerns addressed are degraded plant condition -- undesirable plant productivity and health, and inadequate structure and composition and degraded wildlife habitat. Payment includes bare-root seedlings and equipment and labor to plant. Foregone income is not included with this scenario. Site preparation is implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching.

Before Situation:

The land has little/no tree cover, is understocked, or is stocked with the wrong tree species. Competing vegetation is a before and after planting concern. Soil condition is degraded due to the loss of the native forest ecosystem (organic matter in top soil depleted). The main resource concerns are degraded plant condition and inadequate structure and composition

After Situation:

The land is established with permanent tree cover that will improve degraded plant condition, reduce soil erosion, establish wildlife habitat, sequester carbon and reduce invasive species presence. Establishing forest vegetation also creates corridors for wildlife movement.

Feature Measure: Area of Treatment

Scenario Unit:: Each

Scenario Typical Size: 4,360.0

Scenario Total Cost: \$3,325.10

Scenario Cost/Unit: \$0.76

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	4	\$88.88
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	4	\$101.08
Trailer, enclosed, small	1503	Small enclosed trailer (typically less than 30' in length) pulled by a pickup to transport materials and equipment. Truck not included.	Hour	\$7.12	4	\$28.48
Mechanical tree planter	1600	Mechanical tree planter. Requires a pulling unit of either tractor or small dozer depending upon site conditions. Does not include labor.	Hour	\$6.84	4	\$27.36
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	4	\$87.92
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	4	\$88.36
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	4	\$155.12
Materials						
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.59	4360	\$2,572.40
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: 612 - Tree/Shrub Establishment

Scenario #8 - Bareroot Tress and Shrubs, with Tree Shelters, Each

Scenario Description:

Bare-root trees and/or shrubs to be planted or interplanted to establish woody plants in any area where they can be grown for wildlife, erosion control, water quality improvement, carbon sequestration, forest products, and aesthetics. Seedlings are protected from deer browsing by installing tree tube shelters. Resource concerns addressed are degraded plant condition -- undesirable plant productivity and health, and inadequate structure and composition and degraded wildlife habitat. Payment includes bare-root seedlings, tree shelters, and equipment and labor to plant and install shelters. Foregone income is not included with this scenario. Site preparation is implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching.

Before Situation:

The land has little/no tree cover, is understocked, or is stocked with the wrong tree species. Competing vegetation is a before and after planting concern. Soil condition is degraded due to the loss of the native forest ecosystem (organic matter in top soil depleted). The main resource concerns are degraded plant condition and inadequate structure and composition

After Situation:

The land is established with permanent tree cover that will improve degraded plant condition, reduce soil erosion, establish wildlife habitat, sequester carbon and reduce invasive species presence. Establishing forest vegetation also creates corridors for wildlife movement.

Feature Measure: Area of Treatment

Scenario Unit:: Each

Scenario Typical Size: 4,360.0

Scenario Total Cost: \$14,880.54

Scenario Cost/Unit: \$3.41

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	4	\$88.88
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	4	\$101.08
Trailer, enclosed, small	1503	Small enclosed trailer (typically less than 30' in length) pulled by a pickup to transport materials and equipment. Truck not included.	Hour	\$7.12	4	\$28.48
Mechanical tree planter	1600	Mechanical tree planter. Requires a pulling unit of either tractor or small dozer depending upon site conditions. Does not include labor.	Hour	\$6.84	4	\$27.36
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	12	\$263.76
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	4	\$88.36
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	4	\$155.12
Materials						
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.59	4360	\$2,572.40
Tree shelter, solid tube type, 3-1/4" x 30"	1560	3-1/4" x 30" tree tube for protection from animal damage. Materials only.	Each	\$1.79	4360	\$7,804.40
Cable ties, plastic	1575	Plastic cable ties (typ. 8-12") to assist in securing items. Materials only.	Each	\$0.05	8720	\$436.00
Stakes, wood, 3/4" x 3/4" x 36"	1581	3/4" x 3/4" x 36" wood stakes to fasten items in place. Includes materials only.	Each	\$0.72	4360	\$3,139.20
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50



Practice: 612 - Tree/Shrub Establishment

Scenario #11 - Container Trees and Shrubs (3 gallon), Each

Scenario Description:

Containerized trees and/or shrubs (potted) to be planted or interplanted to establish woody plants in any area where they can be grown for wildlife, erosion control, water quality improvement, carbon sequestration, forest products, and aesthetics. Resource concerns are degraded plant condition - undesirable productivity and health, and Inadequate structure and composition; inadequate habitat for fish and wildlife. Payment includes 3 gallon containerized plants and equipment and labor to plant. Foregone income is not included with this scenario. Site preparation is implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching.

Before Situation:

The land has little/no tree cover, is understocked, or is stocked with the wrong tree species. Competing vegetation is a before and after planting concern. Soil condition is degraded due to the loss of the native forest ecosystem (organic matter in top soil depleted). The main resource concerns are degraded plant condition and inadequate structure and composition

After Situation:

The land is established with permanent tree cover that will improve degraded plant condition, reduce soil erosion, establish wildlife habitat, sequester carbon and reduce invasive species presence. Establishing forest vegetation also creates corridors for wildlife movement.

Feature Measure: Area of Treatment

Scenario Unit:: Each

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,151.80

Scenario Cost/Unit: \$11.52

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	6	\$72.24
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	6	\$131.88
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	6	\$232.68
Materials						
Tree, hardwood, seedling or transplant, potted or B&B, 2-3 gal.	1532	Potted or balled and burlapped hardwood tree, 2-3 gal. Includes materials and shipping only.	Each	\$7.15	100	\$715.00

Practice: 612 - Tree/Shrub Establishment

Scenario #12 - Container Tress and Shrubs (3 gallon) with tree shelters, Each

Scenario Description:

Containerized trees and/or shrubs (potted) to be planted or interplanted to establish woody plants in any area where they can be grown for wildlife, erosion control, water quality improvement, carbon sequestration, forest products, and aesthetics. Seedlings are protected from deer browsing by installing tree tube shelters. Resource concerns are degraded plant condition - undesirable productivity and health, and Inadequate structure and composition; inadequate habitat for fish and wildlife. Payment includes 3 gallon containerized plants, tree shelters, and equipment and labor to plant and install tree shelters. Foregone income is not included with this scenario. Site preparation is implemented through associated practice 490 Tree/Shrub Site Preparation. Additional associated practices may include: 315 Herbaceous Weed Control, 660 Tree/Shrub Pruning, 484 Mulching.

Before Situation:

The land has little/no tree cover, is understocked, or is stocked with the wrong tree species. Competing vegetation is a before and after planting concern. Soil condition is degraded due to the loss of the native forest ecosystem (organic matter in top soil depleted). The main resource concerns are degraded plant condition and inadequate structure and composition

After Situation:

The land is established with permanent tree cover that will improve degraded plant condition, reduce soil erosion, establish wildlife habitat, sequester carbon and reduce invasive species presence. Establishing forest vegetation also creates corridors for wildlife movement.

Feature Measure: Area of Treatment

Scenario Unit:: Each

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,661.68

Scenario Cost/Unit: \$16.62

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	6	\$72.24
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	12	\$263.76
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	6	\$232.68
Materials						
Tree, hardwood, seedling or transplant, potted or B&B, 2-3 gal.	1532	Potted or balled and burlapped hardwood tree, 2-3 gal. Includes materials and shipping only.	Each	\$7.15	100	\$715.00
Tree shelter, solid tube type, 5" x 48"	1571	5" x 48" tree tube for protection from animal damage. Materials only.	Each	\$2.11	100	\$211.00
Cable ties, plastic	1575	Plastic cable ties (typ. 8-12") to assist in securing items. Materials only.	Each	\$0.05	200	\$10.00
Stakes, wood, 3/4" x 3/4" x 60"	1583	3/4" x 3/4" x 60" wood stakes to fasten items in place. Includes materials only.	Each	\$1.57	100	\$157.00

Practice: 614 - Watering Facility

Scenario #2 - Portable Tank

Scenario Description:

Establishment of a portable watering facility for livestock as part of an intensively managed grazing system where the livestock are frequently moved. Payment includes materials and labor costs for installing the watering tank, float valve, and freeze proof hydrant. If needed, a stabilized area under and around the watering facility is not included and must be addressed through an associated practice of Heavy Use Area Protection (561). Payment is based on the number of watering points (i.e. hydrants) installed, not the number of portable tanks used in the watering facility installation.

Before Situation:

This practice applies to all land uses where there is a need for new or improved watering facilities for livestock and or wildlife, where water is not available in sufficient quantities at specific locations, and habitat, water quality, or plant productivity and health needs to be improved.

After Situation:

This practice is typically installed for 30 animal units. It consists of a portable trough of either durable plastic, steel, or rubber that provides adequate water and access for the livestock. The trough includes a float for control of inflow of water. All watering facilities are constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated practices: Pipeline (516), Critical Area Planting (342), Water Harvesting Catchment (636), Water Well (642), Pumping Plant (533), Spring Development (574), and Heavy Use Area Protection (561).

Feature Measure: Number of Watering Points

Scenario Unit:: Each

Scenario Typical Size: 6.0

Scenario Total Cost: \$1,201.30

Scenario Cost/Unit: \$200.22

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	9	\$199.98
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	9	\$197.82
Materials						
Freeze Proof Hydrant, <= 3' Bury	240	Freeze Proof Hydrant, 3 foot or less bury. Materials only.	Each	\$78.59	6	\$471.54
Tank, Polyethylene, 100 gallon	290	Portable heavy duty rubber stock tank.	Each	\$96.31	1	\$96.31
Dimension Lumber, Treated	1044	Treated dimension lumber with nominal thickness equal or less than 2". Includes lumber and fasteners	Board Foot	\$0.91	48	\$43.68
Post, Wood, CCA Treated, 4-5" X 7'	1050	Wood Post, Line 4-5" X 7', CCA Treated. Includes materials and shipping only.	Each	\$7.98	12	\$95.76
Tank, Float Valve Assembly	1077	Float Valve, Stem, Swivel, Float Ball	Each	\$24.16	1	\$24.16
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: 614 - Watering Facility

Scenario #3 - Tire Tank

Scenario Description:

A permanent watering facility constructed from a rubber tire that provides an adequate quantity and quality of water for storage and or direct drinking access. All watering facilities will be constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation. Payment includes materials and labor costs for installing the watering tank, float valve, wildlife escape ramp, and freeze proof hydrant. A stabilized area around the watering facility is not included and must be addressed through associated practices of Heavy Use Area Protection (561). This watering facility will address the resource concerns of inadequate supply of water for livestock and or wildlife, habitat degradation, water quality, and undesirable plant productivity and health.

Before Situation:

This practice applies to all land uses where there is a need for new or improved watering facilities for livestock and or wildlife, where water is not available in sufficient quantities at specific locations, and habitat, water quality, or plant productivity and health needs to be improved.

After Situation:

This practice is typically installed for 50 animal units. It consists of a necessarily large rubber tire trough, that provides adequate water and access for the livestock. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated practices: Pipeline (516), Critical Area Planting (342), Water Harvesting Catchment (636), Water Well (642), Pumping Plant (533), Spring Development (574), and Heavy Use Area Protection (561). Areas around watering facilities where animal concentrations will cause resource concerns will be protected by using Heavy Use Area Protection (561), as appropriate.

Feature Measure: Number of Watering Points

Scenario Unit:: Each

Scenario Typical Size: 5.0

Scenario Total Cost: \$5,920.74

Scenario Cost/Unit: \$1,184.15

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, formless, non reinforced	36	Non reinforced concrete cast-in-placed without forms by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$135.34	1.6	\$216.54
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	10	\$571.70
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	10	\$222.20
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	10	\$283.00
Materials						
Wildlife Escape Ramp	242	Pool size 15' x 30', for small mammals less than one pound	Each	\$24.70	5	\$123.50
Tank, Tire, 8' diameter	286	Tire, includes material cost for tank and shipping. Labor and other appurtenance costs not included.	Each	\$730.29	5	\$3,651.45
Tank, Float Valve Assembly	1077	Float Valve, Stem, Swivel, Float Ball	Each	\$24.16	5	\$120.80
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.77	101	\$178.77
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 614 - Watering Facility

Scenario #5 - Above Ground Storage, 1,000 - 3,000 gallons

Scenario Description:

A permanent watering facility constructed of approved materials having 1,000 to 3,000 gallons of water storage capacity for an adequate quantity and quality of water in situations where a lower capacity water supply source such as a spring or solar pump is the only feasible water source and backup capacity is needed during peak water demand periods. All watering facilities will be constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation. Payment includes materials and labor costs for installing the storage tank. A stabilized area under and around the watering facility is not included and must be addressed through an associated practice of Heavy Use Area Protection (561). This watering facility will address the resource concerns of inadequate supply of water for livestock, habitat degradation, water quality, and undesirable plant productivity and health.

Before Situation:

This practice applies to all land uses where there is a need for new or improved watering facilities for livestock and or wildlife, where water is not available in sufficient quantities at specific locations, and habitat, water quality, or plant productivity and health needs to be improved.

After Situation:

A permanent watering facility with water storage capacity of 1,000 to 3,000 gallons is typically installed for 30 animal units to provide adequate water storage capacity to ensure an adequate supply and quality of water for livestock or wildlife. Installation facilitates improved plant productivity and health, water quality, and habitat. All watering facilities are constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation and placed on a properly prepared foundation with required plumbing. All needed pipelines are installed using Pipeline (516). Any needed vegetation of disturbed areas will use Critical Area Planting (342). All collectors or catchments for collecting precipitation will be addressed by using Water Harvesting Catchment (636). Any needed water source installation will use Water Well (642), Pumping Plant (533), Spring Development (574), or Pipeline (516) as appropriate. Areas around watering facilities where animal concentrations will cause resource concerns will be protected by using Heavy Use Area Protection (561) as appropriate.

Feature Measure: Number of tanks

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$2,940.33

Scenario Cost/Unit: \$2,940.33

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	2	\$114.34
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	2	\$56.60
Materials						
Tank, Poly Enclosed Storage, >1,000	1075	Water storage tanks. Includes materials and shipping only.	Gallon	\$0.93	2500	\$2,325.00
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.77	13	\$23.01
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 614 - Watering Facility

Scenario #6 - Above Ground Storage, >3,000 gallons

Scenario Description:

Establishment of a large permanent watering facility having 3,001 to 5,000 gallons of water storage capacity for an adequate quantity and quality of water in situations where a lower capacity water supply source such as a spring or solar pump is the only feasible water source and backup capacity is needed during peak water demand periods. All watering facilities will be constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation. Payment includes materials and labor costs for installing the storage tank. A stabilized area under and around the watering facility is not included and must be addressed through an associated practice of Heavy Use Area Protection (561). This watering facility will address the resource concerns of inadequate supply of water for livestock, habitat degradation, water quality, and undesirable plant productivity and health.

Before Situation:

This practice applies to all land uses where there is a need for new or improved watering facilities for livestock and or wildlife, where water is not available in sufficient quantities at specific locations, and habitat, water quality, or plant productivity and health needs to be improved.

After Situation:

A permanent watering facility with water storage capacity of 3,001 to 5,000 gallons is typically installed for 50 animal units to provide adequate water storage capacity to ensure an adequate supply and quality of water for livestock or wildlife. Installation facilitates improved plant productivity and health, water quality, and habitat. All watering facilities are constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation and placed on a properly prepared foundation with required plumbing. All needed pipelines are installed using Pipeline (516). Any needed vegetation of disturbed areas will use Critical Area Planting (342). All collectors or catchments for collecting precipitation will be addressed by using Water Harvesting Catchment (636). Any needed water source installation will use Water Well (642), Pumping Plant (533), Spring Development (574), or Pipeline (516) as appropriate. Areas around watering facilities where animal concentrations will cause resource concerns will be protected by using Heavy Use Area Protection (561) as appropriate.

Feature Measure: Number of tanks

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$4,930.00

Scenario Cost/Unit: \$4,930.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	3	\$171.51
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	3	\$66.66
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	3	\$65.94
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	3	\$84.90
Materials						
Tank, Poly Enclosed Storage, >1,000	1075	Water storage tanks. Includes materials and shipping only.	Gallon	\$0.93	4500	\$4,185.00
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.77	13	\$23.01
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 614 - Watering Facility

Scenario #7 - Underground Storage Tank

Scenario Description:

A precast concrete tank used for storing water as part of a watering system. The storage tank will consist of 1 storage tank (2500 gal.) adequate base material and backfill around the tank, access riser with lid, and 20 ft of 4 inch for overflow pipe.

Before Situation:

This practice applies to all land uses where there is a need for new or improved watering facilities for livestock and or wildlife, where water is not available in sufficient quantities at specific locations, and habitat, water quality, or plant productivity and health needs to be improved.

After Situation:

A permanent watering facility for livestock constructed of approved materials with a 2,500 gallons of additional storage capacity for adequate quantity and quality of water for storage when backup capacity is needed peak water demand periods. All watering facilities are constructed from approved durable materials that have a life expectancy that meets or exceeds the planned useful life of the installation and placed on a properly prepared foundation with required plumbing. All needed pipelines are installed using Pipeline (516). Any needed vegetation of disturbed areas will use Critical Area Planting (342). Any needed water source installation will use Water Well (642), Pumping Plant (533), Spring Development (574), or Pipeline (516) as appropriate.

Feature Measure: Number of tanks

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$4,718.17

Scenario Cost/Unit: \$4,718.17

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	5	\$580.05
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	5	\$109.90
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	5	\$141.50
Materials						
Tank, Concrete, 2500 gallon	1055	Concrete tank for water storage, with riser and lid. Includes materials and delivery.	Each	\$3,210.43	1	\$3,210.43
Aggregate, Gravel, Ungraded, Quarry Run	1099	Includes materials, equipment and labor	Cubic Yard	\$17.63	2	\$35.26
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.77	40	\$70.80
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	1	\$498.18

Practice: 614 - Watering Facility

Scenario #9 - Access Ramp

Scenario Description:

The bank of the stream or pond is severely eroded and water quality is poor due to the unrestricted access of livestock or wildlife. A conservation plan includes provisions for controlled access to drinking water for livestock or wildlife to provide daily water requirements, improve animal distribution to better utilize grazing resources, or provide a water source that is an alternative to a sensitive resource.

Before Situation:

This practice applies to all land uses where there is a need for a watering facility for livestock or wildlife, where there is a source of water that is adequate in quantity and quality for the purpose, and where soils and topography are suitable for a facility to provide controlled access to drinking water for livestock or wildlife to provide daily water requirements, improve animal distribution to better utilize grazing resources, provide a water source that is an alternative to a sensitive resource.

After Situation:

A permanent watering ramp with a level section at the base is installed to provide drinking water for livestock or wildlife. The access ramp is constructed of approved materials consisting of rock and or gravel surfacing on geotextile fabric foundation, with a life expectancy that meets or exceeds the planned useful life of the installation. The resource concerns of inadequate supply of water for livestock or wildlife, soil erosion, habitat degradation, water quality, and undesirable plant productivity and health have been addressed. The watering facility includes all materials, equipment, and labor to shape the ramp and install the surfacing material. Seeding of berms and construction areas is to be specified using 342 - Critical Area Planting, and 484 - Mulching, as needed. Use 382 - Fence to limit livestock access.

Feature Measure: Area of access ramp

Scenario Unit:: Square Foot

Scenario Typical Size: 560.0

Scenario Total Cost: \$1,073.79

Scenario Cost/Unit: \$1.92

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.39	84	\$200.76
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	39	\$83.85
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	24	\$613.68
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50



Practice: 620 - Underground Outlet

Scenario #4 - 6in Diameter Pipe with Risers

Scenario Description:

Scenario is for the Installation of a 6" diameter approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Payment includes pipe, perforated PVC riser inlet, trench excavation, and trench backfill. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations.

After Situation:

Excessive sedimentation and soil erosion is controlled after UGO is installed in association with terraces or water and sediment control basin. Associated practices are Critical Area Planting (342), Grassed Waterway ( 412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Feature Measure: Length of Conduit

Scenario Unit:: Foot

Scenario Typical Size: 500.0

Scenario Total Cost: \$1,745.31

Scenario Cost/Unit: \$3.49

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, 12" x 48"	53	Trenching, earth, 12" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$1.26	500	\$630.00
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.20	2	\$4.40
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Pipe, PVC, 6", SDR 35	993	Materials: - 6" - PVC - SDR 35 - ASTM D3034	Foot	\$4.47	20	\$89.40
Pipe, HDPE, 6", CPT, Single Wall	1242	Pipe, Corrugated Plastic Tubing, Single Wall, 6" diameter - ASTM F405. Material cost only.	Foot	\$1.13	480	\$542.40
Inlet, riser, 6"	1261	Riser, polymer, complete vertical perforated UGO inlet with Tee, orifice plate if needed, 6" diameter. Materials only.	Each	\$70.31	2	\$140.62
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 620 - Underground Outlet

Scenario #8 - 10in Diameter Pipe with Risers

Scenario Description:

Scenario is for the Installation of a 10" diameter approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Payment includes pipe, perforated PVC riser inlet, trench excavation, and trench backfill. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations.

After Situation:

Excessive sedimentation and soil erosion is controlled after UGO is installed in association with terraces or water and sediment control basin. Associated practices are Critical Area Planting (342), Grassed Waterway ( 412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Feature Measure: Length of Conduit

Scenario Unit:: Foot

Scenario Typical Size: 500.0

Scenario Total Cost: \$4,540.47

Scenario Cost/Unit: \$9.08

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, clay, 24" x 48"	55	Trenching, earth, clay, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling and shoring/dewatering	Foot	\$3.41	500	\$1,705.00
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.20	2	\$4.40
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	4	\$155.12
Materials						
Pipe, PVC, 10", SDR 35	1251	Pipe, PVC, SDR 35, 10" Diameter - ASTM D3034. Material cost only.	Foot	\$12.56	20	\$251.20
Inlet, riser, 10"	1263	Riser, polymer, complete vertical perforated UGO inlet with Tee, orifice plate if needed, 10" diameter. Materials only.	Each	\$148.31	2	\$296.62
Pipe, HDPE, 10", PCPT, Single Wall	1273	Pipe, Corrugated Plastic Tubing, Single Wall, Perforated, 10" diameter - ASTM F667. Material cost only.	Foot	\$3.89	480	\$1,867.20
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 620 - Underground Outlet

Scenario #10 - >=12in Diameter Pipe with Risers

Scenario Description:

Scenario is for the Installation of a 12" diameter approved plastic pipe to convey storm water from one location to a suitable and stable outlet. Payment includes pipe, perforated PVC riser inlet, trench excavation, and trench backfill. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations.

After Situation:

Excessive sedimentation and soil erosion is controlled after UGO is installed in association with terraces or water and sediment control basin. Associated practices are Critical Area Planting (342), Grassed Waterway ( 412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Feature Measure: Length of Conduit

Scenario Unit:: Foot

Scenario Typical Size: 500.0

Scenario Total Cost: \$5,898.39

Scenario Cost/Unit: \$11.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, clay, 24" x 48"	55	Trenching, earth, clay, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling and shoring/dewatering	Foot	\$3.41	500	\$1,705.00
Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.20	2	\$4.40
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	4	\$155.12
Materials						
Pipe, PVC, 12", SDR 35	1252	Pipe, PVC, SDR 35, 12" Diameter - ASTM D3034. Material cost only.	Foot	\$17.97	20	\$359.40
Inlet, riser, 12"	1264	Riser, polymer, complete vertical perforated UGO inlet with Tee, orifice plate if needed, 12" diameter. Materials only.	Each	\$540.37	2	\$1,080.74
Pipe, HDPE, 12", PCPT, Single Wall	1274	Pipe, Corrugated Plastic Tubing, Single Wall, Perforated, 12" diameter - ASTM F667. Material cost only.	Foot	\$4.86	480	\$2,332.80
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 630 - Vertical Drain

Scenario #4 - Sinkhole, Minimal Excavation

Scenario Description:

A well, pipe, pit or bore in porous, underground strata into which drainage water can be discharged. Installation will provide a stable outlet for drainage water from a surface or subsurface drainage system. The practice is used to treat a sinkhole with a depth of less than 20 feet in shallow karst areas such as found in Perry, St. Genevieve, and Cape Girardeau counties in Missouri. The sinkhole is located in cropland within karst topography and is expanding through gully erosion. The scenario incorporates concrete, pipe and earthwork necessary to install the practice. Associated practices including, Filter strips (393), Grassed Waterway (412), and Sediment Basins (350) will be used as needed to provide suitable filtering and removing of sediment from water before entering well. Other associated practices are Critical area planting (342), Fence (382), Diversion (362), Open Channel (582), Subsurface Drain (606), Lined Waterway (468), Underground Outlet (620).

Before Situation:

A sinkhole is eroding, fields around sinkhole are flooding and ponding water with inadequate outlets and water is being contaminated with pesticides, nutrients, and sediment. Resource concerns include Water Quality: Excess nutrients in surface water or Excess nutrients in groundwater; Water Quality Degradation: Pesticides transported to surface water, or Pesticides transported to groundwater; Soil Erosion: Classic gully soil erosion, Excess Water: Ponding and Flooding.

After Situation:

Treatment of a 15 foot deep sinkhole. Installation includes a 20 foot long (includes 5 feet inlet height about ground surface), 12 inch diameter pipe, 8 Cubic yards of concrete for sealing creviced bedrock and stabilizing the pipe, excavation and earth backfill. The sinkhole treatment will provide an adequate outlet for drainage water, protect surface water quality and will also provide control of erosion caused by surface runoff into a natural sinkhole. Associated practices Filter strips (393), Grassed Waterway (412), and Sediment Basins (350) will be used as needed to provide suitable filtering and removing of sediment from water before entering well. Other associated practices include Critical area planting (342), Fence (382), Diversion (362), Open Channel (582), Subsurface Drain (606), Lined Waterway (468), Underground Outlet (620).

Feature Measure: Number of Sinkholes Treated

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$2,881.23

Scenario Cost/Unit: \$2,881.23

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, formless, non reinforced	36	Non reinforced concrete cast-in-placed without forms by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$135.34	7	\$947.38
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$67.45	4	\$269.80
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	3	\$348.03
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	7	\$153.86
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	7	\$198.10
Materials						
Pipe, Steel, 12", Std Wt, USED	1356	Materials: - USED - 12" - Steel Std Wt	Foot	\$22.11	20	\$442.20
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: 632 - Waste Separation Facility

Scenario #1 - Earthen Settling Structure

Scenario Description:

An earthen structure, such as a basin or a terrace or dike like structure, used to capture and separate a portion of the solids from a liquid stream from a feedlot or confinement facility. A concrete pad should be installed on the bottom of the basin and around outlet structures to facilitate cleanout. Removes as portion of the solids to facilitate waste handling and to address water quality concerns. Associated practices include Nutrient Management (590), Composting Facility (317), Anaerobic Digester (366), Waste Storage Facility (313), Waste Recycling (633), Waste Transfer (634), Vegetated Treatment Area (635), Pond Lining or Sealing (521A-D), and Waste Treatment (629).

Before Situation:

Applicable to situations where partitioning solids, liquids, and nutrients will facilitate the management of an animal waste management system, improve air quality (reduce odors), and address water quality concerns.

After Situation:

One earthen settling basin structure (60 ft wide by 200 ft long by 3 ft deep, with three screening outlet structures) constructed around or at a livestock feeding operation. Removes a portion of the solids that otherwise would leave with the runoff from an animal feeding operation. Part of an animal waste management system.

Feature Measure: Cubic Foot of Total Storage

Scenario Unit:: Cubic Foot

Scenario Typical Size: 30,000.0

Scenario Total Cost: \$9,549.69

Scenario Cost/Unit: \$0.32

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	12	\$3,295.44
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	1000	\$4,060.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	14	\$357.98
Weeping Wall	1765	Weeping wall or picket screen structure for solid settling basin. Materials only.	Foot	\$51.00	24	\$1,224.00
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 632 - Waste Separation Facility

Scenario #2 - Concrete Basin

Scenario Description:

A concrete structure, such as a basin with concrete walls and floor, used to capture and separate a portion of the solids from a liquid stream from a feedlot or confinement facility. Removes as portion of the solids to facilitate waste handling and to address water quality concerns. Associated practices include Nutrient Management (590), Composting Facility (317), Anaerobic Digester (366), Waste Storage Facility (313), Waste Recycling (633), Waste Transfer (634), Pumping Plant (533), Vegetated Treatment Area (635), Pond Lining or Sealing (521A-D), and Waste Treatment (629).

Before Situation:

Applicable to situations where partitioning solids, liquids, and nutrients will facilitate the management of an animal waste management system, improve air quality (reduce odors), and address water quality concerns.

After Situation:

One 3' deep concrete settling basin structure (20'x20' flat bottom with 3' walls on 2 sides, 10:1 ramps on other sides, 50'x50' overall footprint) and weeping wall/picket structure or outlet control) constructed at the outlet of a open feedlot. Removes a portion of the solids that otherwise would leave with the runoff from an animal feeding operation. Part of an animal waste management system.

Feature Measure: Cubic Foot of Total Storage

Scenario Unit:: Cubic Foot

Scenario Typical Size: 3,900.0

Scenario Total Cost: \$16,847.21

Scenario Cost/Unit: \$4.32

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	33	\$9,062.46
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	12	\$5,125.32
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	50	\$107.50
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	50	\$203.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	38	\$971.66
Weeping Wall	1765	Weeping wall or picket screen structure for solid settling basin. Materials only.	Foot	\$51.00	15	\$765.00
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 632 - Waste Separation Facility

Scenario #3 - Concrete Sand Settling Lane

Scenario Description:

A concrete structure, a concrete lane with curbs, used to capture and separate a portion of the solids, mainly sand, from a liquid stream from a confinement facility. Removes as portion of the solids to facilitate waste handling and to address water quality concerns. Associated practices include Nutrient Management (590), Composting Facility (317), Anaerobic Digester (366), Waste Storage Facility (313), Waste Recycling (633), Waste Transfer (634), Pumping Plant (533), Vegetated Treatment Area (635), Pond Lining or Sealing (521A-D), and Waste Treatment (629).

Before Situation:

Applicable to situations where partitioning solids, liquids, and nutrients will facilitate the management of an animal waste management system, improve air quality (reduce odors), and address water quality concerns.

After Situation:

One concrete settling lane structure (25 ft wide by 200 ft long by 0.5 ft thick with 18" walls on each side.) constructed around or at a livestock feeding operation. Removes a portion of the solids (sand) that otherwise would leave with the runoff from an animal feeding operation. Part of an animal waste management system.

Feature Measure: Square Foot of Settling Lane Footpr

Scenario Unit:: Square Foot

Scenario Typical Size: 5,000.0

Scenario Total Cost: \$37,007.83

Scenario Cost/Unit: \$7.40

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	78	\$21,420.36
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	30	\$12,813.30
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	180	\$387.00
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$4.06	90	\$365.40
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	62	\$1,585.34
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 632 - Waste Separation Facility

Scenario #4 - Gravity Tank

Scenario Description:

A concrete tank used for gravity separation of solid material in a dairy waste management system. The waste management system must utilize a "flush" type system in order to convey and agitate the material. The flush system is needed to maintain high solids removal. Associated practices include Nutrient Management (590), Composting Facility (317), Anaerobic Digester (366), Waste Storage Facility (313), Waste Recycling (633), Waste Transfer (634), Pumping Plant (533), Vegetated Treatment Area (635), Pond Lining or Sealing (521A-D), and Waste Treatment (629).

Before Situation:

Applicable to situations where partitioning solids, liquids, and nutrients will facilitate the management of an animal waste management system, improve air quality (reduce odors), and address water quality concerns.

After Situation:

A concrete tank 20' x 20' x 6' with a full width ramp of 20' x 72'. For a total structure capacity of 6,720 cu ft. Separator description: Dairy manure is flushed into the Gravity Tank (Pull Plug) Separator that utilizes a vertical pipe, surrounded by a baffle, that is open at the top. The vertical pipe maintains 4.5 feet of material in the tank. When the manure is flushed into the tank the level rises in the tank and slowly drains through the baffle, floating mat of fibrous material (roughage from the dairy manure) and the open top of the vertical pipe as the level returns to 4.5 feet. The liquid goes to a storage structure. This process is repeated each time the manure is flushed into the tank, typically 2 times per day. The floating material will form a mat on the surface of the separator, the heavy material will sink to the bottom of the separator. Eventually the floating mat and the heavy material will meet and the tank level will not return to 4.5 feet. The basin will continue to be used a few more weeks. This helps to dewater the separated solids. When the separator is ready to be cleaned out the vertical pipe (Pull Plug) is removed and the basin dewateres for 12 to 24 hours. The solids are removed. The vertical pipe installed and the process starts again.

Feature Measure: Total capacity of basin

Scenario Unit:: Cubic Foot

Scenario Typical Size: 6,720.0

Scenario Total Cost: \$29,142.12

Scenario Cost/Unit: \$4.34

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	20	\$5,492.40
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	50	\$21,355.50
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	250	\$537.50
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	42	\$1,073.94
Pipe, PVC, 6", SDR 35	993	Materials: - 6" - PVC - SDR 35 - ASTM D3034	Foot	\$4.47	36	\$160.92
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86



Practice: 632 - Waste Separation Facility

Scenario #9 - Mechanical Separation Facility

Scenario Description:

A small mechanical separation facility to partition solids, liquids, and/or associated nutrients from animal waste streams. The partitioning of the previously mentioned components facilitates the protection of air and water quality, protects animal health, and improves the management of an animal waste management system. Mechanical separators may include, but are not limited to: static inclined screens , vibratory screens, rotating screens, centrifuges, screw or roller presses, or other systems. Associated practices include Nutrient Management (590), Composting Facility (317), Anaerobic Digester (366), Waste Storage Facility (313), Waste Recycling (633), Waste Transfer (634), Amendments for the Treatment of Agricultural Waste (591), Pumping Plant (533), Vegetated Treatment Area (635), Pond Lining or Sealing (521A-D), and Waste Treatment (629).

Before Situation:

Applicable to situations where partitioning solids, liquids, and nutrients will facilitate the management of an animal waste management system, improve air quality (reduce odors), and address water quality concerns.

After Situation:

One small mechanical separation facility (a vibratory or rotating screen) installed at livestock facility before storage or treatment or after treatment, for example, after an anaerobic digester. Part of an animal waste management system.

Feature Measure: Item

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$35,429.70

Scenario Cost/Unit: \$35,429.70

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	10	\$2,746.20
--	----	--	------------	----------	----	------------

Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	16	\$565.76
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	32	\$703.36

Materials						
Vibratory or Rotating Screen	1948	Vibratory or Rotating Screen, includes materials, shipping and equipment.	Each	\$30,325.37	1	\$30,325.37

Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	3	\$216.15
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: 634 - Waste Transfer

Scenario #2 - Wastewater catch basin, less than 1000 gal.

Scenario Description:

Installation of a wastewater collection system that includes materials and structures to collect liquids of a design volume less than 1000 gallons such as silage leachate, lot runoff and other contaminated liquid effluent. This may include curbs, screens, precast manholes, sumps or catch basins. The wastewater will be transferred from the collection basin to a waste storage facility. Payment includes excavation, placement of bedding as needed, placement of structure and backfill with construction of concrete inlet collection area. Transfer pump if needed must be contracted under associated practice 533 Pumping Plant. This scenario addresses the potential for surface water and groundwater quality degradation from liquid wastewater running unchecked out of silage bunkers and off of animal feeding lots.

Before Situation:

Inadequate waste management system able to collect wastewater from an operation that may contaminate surface or groundwater resources.

After Situation:

This practice scenario is suitable where the estimated design volume for wastewater transfer is less than 1000 gallons of contaminated liquid that may flow from silage bunkers or animal production facilities. The practice scenario typically includes materials and installation of flat and formed concrete for curbs and/or gutters to collect liquids. With the installation of a precast manhole with lid or catch basin with grate. Associated practices may include: 313 Waste Storage Facility for storage structures; 533, Pumping Plant; 632, Waste Separation Facility; 590 Nutrient Management for waste application; 633, Waste Recycling.

Feature Measure: Collection volume installed

Scenario Unit:: Gallon

Scenario Typical Size: 1,000.0

Scenario Total Cost: \$6,103.35

Scenario Cost/Unit: \$6.10

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	4	\$1,098.48
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	2	\$854.22
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	8	\$457.36
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$67.45	4	\$269.80
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	\$58.85	4	\$235.40
Demolition, concrete	1498	Demolition and disposal of reinforced concrete structures including slabs and walls. Includes labor and equipment.	Cubic Yard	\$10.81	2	\$21.62
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	4	\$88.36
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	12	\$339.60
Materials						
Aggregate, Gravel, Ungraded, Quarry Run	1099	Includes materials, equipment and labor	Cubic Yard	\$17.63	5	\$88.15
Catch Basin, concrete, 60" dia.	1754	Precast 60-in diameter catch basin, 6' deep, with collar and grate cover. Materials only.	Each	\$2,038.09	1	\$2,038.09
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 634 - Waste Transfer

Scenario #4 - Concrete Channel, no footers

Scenario Description:

Installation of a concrete channel that consists of a slab with curb for the entire length of the channel to enable the facility manager to direct liquid waste to a collection basin and/or waste storage facility. Water quality concerns will be addressed by preventing liquid waste from entering surface waters, and to facilitate timely land application of manure and wastewater at agronomic rates according to the CNMP. This scenario addresses the potential for surface water and groundwater quality degradation.

Before Situation:

Current facility operations are allowing liquid waste to flow uncontrolled during periods of precipitation events or cleaning operations such that water resources can be contaminated.

After Situation:

Typical installation of a 12 foot wide 100' long concrete channel that consists of a 5" thick concrete slab with curbing on each side of the slab that is 2' high, 6" thick for the entire length. The purpose is to transfer liquids or manure slurry from one area to a collection basin or waste storage facility. Associated practices may include: 313 Waste Storage Facility for storage structures; 533, Pumping Plant; 632, Waste Separation Facility; 590 Nutrient Management for waste application; 633, Waste Recycling.

Feature Measure: Bottom surface area of concrete ch

Scenario Unit:: Square Foot

Scenario Typical Size: 1,200.0

Scenario Total Cost: \$10,547.08

Scenario Cost/Unit: \$8.79

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	19	\$5,217.78
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	9	\$3,843.99
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$67.45	8	\$539.60
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	8	\$226.40
Materials						
Aggregate, Gravel, Ungraded, Quarry Run	1099	Includes materials, equipment and labor	Cubic Yard	\$17.63	26	\$458.38
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 634 - Waste Transfer

Scenario #8 - Manure Flush System

Scenario Description:

Installation of a manure flush system consisting of a flushwater storage tank, flushing mechanism such as a valve, and flush water distribution. This practice scenario is suitable only where the water or wastewater supplies are available for operating a flush system to collect the animal waste deposited on the concrete surfaces. Payment includes tank, valve and distribution pipeline, site prep and concrete to support these structures. This scenario addresses the potential for surface water and groundwater quality degradation from animal waste.

Before Situation:

An animal production facility does not have an efficient method for collecting and transferring the animal waste produced. A source of sufficient water or wastewater resources are available to design a flush system to clean the production floor and collect the waste materials deposited.

After Situation:

The design flush volume for the flush system is less than 1000 gallons. Concrete slab to support the tank and distribution pipeline is 28ft x 12 ft x 5" thick. with 40 ft of above ground 8" pipe is used for distribution. Associated practices may include: 313 Waste Storage Facility for storage structures; 533, Pumping Plant; 632, Waste Separation Facility; 590 Nutrient Management for waste application; 633, Waste Recycling.

Feature Measure: 1000 Gallons of flush water

Scenario Unit:: Gallon

Scenario Typical Size: 1,000.0

Scenario Total Cost: \$5,601.77

Scenario Cost/Unit: \$5.60

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$274.62	5	\$1,373.10
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	8	\$457.36
Demolition, concrete	1498	Demolition and disposal of reinforced concrete structures including slabs and walls. Includes labor and equipment.	Cubic Yard	\$10.81	4	\$43.24
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	8	\$176.72
Materials						
Pipe, PVC, 8", SCH 40	981	Materials: - 8" - PVC - SCH 40 - ASTM D1785	Foot	\$8.54	40	\$341.60
Tank, Poly enclosed Storage, 300-1000 gal	1074	Water storage tanks. Includes materials and shipping only.	Gallon	\$0.90	1000	\$900.00
Plug Valve, 8"	2101	8" diameter plug valve. Materials only.	Each	\$1,697.14	1	\$1,697.14
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 634 - Waste Transfer

Scenario #9 - Wastewater Recycle System for Flush System, Pipes only

Scenario Description:

Installation of a wastewater recycle pipeline utilized with manure and wastewater flush system using recycled wastewater. Scenario is for the pipe system only to retrofit flush systems to utilize recycled water. Payment includes excavation, placement of bedding as needed, conveyance pipelines with valves and pipe backfill to transport water to the flush tank. This scenario addresses the potential for surface water and groundwater quality degradation from animal waste.

Before Situation:

An animal production facility does not have an efficient method for collecting and transferring the animal waste produced. Wastewater however is available in a sufficient quantity to provide a flush cycle to clean the production floor and collect the waste materials deposited.

After Situation:

Supplemental piping is needed to install the recycled flush water as a means to collect the animal waste deposited on the concrete production surfaces. The pipe design for the flush volume requires 300 feet of 3 inch diameter pipe for pressure flow. Associated practices may include: 313 Waste Storage Facility for storage structures; 533, Pumping Plant; 632, Waste Separation Facility; 590 Nutrient Management for waste application; 633, Waste Recycling.

Feature Measure: Flush - pipes

Scenario Unit:: Foot

Scenario Typical Size: 300.0

Scenario Total Cost: \$2,704.99

Scenario Cost/Unit: \$9.02

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, 12" x 48"	53	Trenching, earth, 12" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$1.26	300	\$378.00
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	12	\$686.04
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	12	\$265.08
Materials						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic Yard	\$25.23	11	\$277.53
Pipe, PVC, 3", SCH 40	977	Materials: - 3" - PVC - SCH 40 - ASTM D1785	Foot	\$2.49	300	\$747.00
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: 634 - Waste Transfer

Scenario #10 - Gravity or Low Pressure Flow Pipeline, Small

Scenario Description:

Gravity or low pressure flow pipeline used to transfer manure or wastewater according to the CNMP. Payment includes the pipe plus clean-out risers and fittings, trench excavation and backfill, labor and equipment for installation. Typical installation applies to soils with no special bedding requirements. This scenario addresses the transport of liquid waste to a waste storage or treatment facility to prevent a water quality resource concern of excessive nutrients/organics and harmful levels of pathogens in surface water and/or excessive nutrients/organics in ground water.

Before Situation:

There is a need to transport manure or wastewater within a waste management system.

After Situation:

Install a 100 foot long 8 inch diameter PVC gasket IPS pipe to transfer the manure wastewater. The transfer pipeline will deliver the manure slurry according to the CNMP, thereby protecting water quality resources. Associated practices may include: 313 Waste Storage Facility for storage structures; 533, Pumping Plant; 632, Waste Separation Facility; 590 Nutrient Management for waste application; 633, Waste Recycling; 635, Vegetated Treatment Area.

Feature Measure: Length of pipe installed

Scenario Unit:: Foot

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,686.06

Scenario Cost/Unit: \$16.86

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	8	\$42.88
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$2.89	100	\$289.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68
Materials						
Pipe, PVC, 8", SDR 35	994	Materials: - 8" - PVC - SDR 35 - ASTM D3034	Foot	\$8.02	125	\$1,002.50

Practice: 634 - Waste Transfer

Scenario #12 - Pressurized Pipeline

Scenario Description:

Pressure flow pipeline used to transfer manure wastewater by pumping from the waste storage pond to the field where it is to be applied according to the CNMP. The pressure pipe moves the water by pumping from the intake riser location, through a buried mainline with outlet risers. Payment includes the pipe plus an inlet riser structure, clean-out risers and outlet risers plus all other valves and fittings, trench excavation and backfill, labor and a equipment for installation. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves. Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements. This pipeline is part of a manure transfer system for a planned waste management or comprehensive nutrient management plan. This scenario addresses the transport of liquid waste to a waste storage or treatment facility to prevent a water quality resource concern of excessive nutrients/organics and harmful levels of pathogens in surface water and/or excessive nutrients/organics in ground water.

Before Situation:

There is a need to transport manure or wastewater within a waste management system. The pressure distribution pipeline is utilized in the land application aspect of the operation.

After Situation:

Install a 2000 foot long 8 inch diameter PVC gasket IPS pipe that has an SDR of 21 and is water tight under pressure flow to transfer the manure wastewater. An inlet riser and is located near the pump site of the waste storage pond and designed for the desired pressure and flow for the application system. The transfer pipeline will deliver the manure slurry to the fields for agronomic nutrient utilization according to the CNMP, thereby protecting water quality resources. Associated practices may include: 313 Waste Storage Facility for storage structures; 533, Pumping Plant; 632, Waste Separation Facility; 590 Nutrient Management for waste application; PS 633, Waste Recycling; PS 635, Vegetated Treatment Area.

Feature Measure: Length of pipe installed

Scenario Unit:: Foot

Scenario Typical Size: 2,000.0

Scenario Total Cost: \$35,690.94

Scenario Cost/Unit: \$17.85

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, formless, non reinforced	36	Non reinforced concrete cast-in-placed without forms by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$135.34	4	\$541.36
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic Yard	\$5.36	180	\$964.80
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$2.89	2000	\$5,780.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	80	\$1,758.40
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	20	\$775.60
Materials						
Pipe, PVC, 8", SDR 26	991	Materials: - 8" - PVC - SDR 26 160 psi - ASTM D2241	Foot	\$10.65	2000	\$21,300.00
Valve, Pressure Relief	1042	Materials for <2" Pressure Relief Valve	Each	\$170.74	1	\$170.74
Valve, Air Vacuum Release, Continuous	1106	Materials for <2" Automatic Air/Vacuum Relief Valve (3 - Way Air Vac)	Each	\$153.60	3	\$460.80
Plug Valve, 8"	2101	8" diameter plug valve. Materials only.	Each	\$1,697.14	1	\$1,697.14
Valve, sprinkler hydrant irrigation valve with riser, metal, 8" x 4" x 42"	2104	Irrigation hydrant valve assembly including saddle tee, coated metal riser and integral valve installed on a 8" dia. pipeline, 4" dia. X 42" long riser. Materials only.	Each	\$320.30	7	\$2,242.10

Practice: 634 - Waste Transfer

Scenario #38 - Cased Pipeline with Boring

Scenario Description:

Installation of a 6" plastic pipeline with an outer casing, bored under a road or other obstruction to convey wastewater from a storage structure to points of use.

Before Situation:

Waste material needs to be transported across a road from the storage facility.

After Situation:

The typical installation consists of installing 120 ft of 6" PVC SDR 21 pipe with a 10" outer casing under a roadbed. Pipeline boring includes all pipe under roadbed and labor and equipment involved during installation of pipe. The pipeline is installed as a facilitating practice for utilization of waste in a waste management system, to improve water quality. Payment incorporates couplers and fittings. Cost represents typical situations for conventional, organic, and transitioning to organic producers. Associated practices include Waste Storage Facility (313), Pumping Plant (533).

Feature Measure: foot

Scenario Unit:: Foot

Scenario Typical Size: 120.0

Scenario Total Cost: \$15,363.26

Scenario Cost/Unit: \$128.03

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	12	\$686.04
Horizontal Boring, Greater Than 3" diameter	1132	Includes equipment, labor and setup.	Foot	\$87.53	120	\$10,503.60
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	32	\$703.36
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	12	\$339.60
Materials						
Pipe, PVC, 6", SDR 21	987	Materials: - 6" - PVC - SDR 21 200 psi - ASTM D2241	Foot	\$7.75	120	\$930.00
Pipe, PVC, 10", SCH 40	1713	Materials: - 10" -PVC - SCH 40 - ASTM D1785	Foot	\$13.99	120	\$1,678.80
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86



Practice: 638 - Water and Sediment Control Basin

Scenario #1 - Base

Scenario Description:

Typical scenario for the construction of an earthen embankment or the rebuild of an existing WASCOB. Rebuild work includes the removal of accumulated sediment from the pool area to restore original capacity. Outlet is typically an underground outlet. An earthen embankment or combination ridge and channel generally constructed/rebuilt across the slope and minor watercourses to form a sediment trap and water detention basin. Work is done with dozer, scraper, or road grader. Costs include all equipment necessary to excavate, shape, grade and compact the Water and Sediment Control Basin and mobilization of equipment. Seeding not included. This practice is utilized to reduce watercourse and gully erosion, trap sediment, reduce and manage onsite and downstream runoff. Sheet and rill erosion will be controlled by other conservation practices.

Before Situation:

Farming fields with excessive slope length has resulted in multiple rills and/or ephemeral gullies that will continue to worsen over time. The excessive erosion may lead to deterioration of receiving waters due to excessive sedimentation and nutrient transport. Resource concerns addressed include soil erosion and water quality by trapping sediment and/or reducing erosion in a field to protect riparian areas and water bodies from sediment deposition. Surface water causes erosion and the sediment (and potentially pesticides) to be transported into the riparian areas and water bodies downstream.

After Situation:

Water and Sediment Control Basin is constructed or rebuilt by the excavation/earthfill with dozer, scraper and/or road grader. Rill and/or gully erosion is reduced. If riser and underground outlet are needed, then include Underground Outlet (620). Include Critical Area Planting (342) where necessary to prevent erosion following construction activities.

Feature Measure: CY of WASCOB Embankment

Scenario Unit:: Cubic Yard

Scenario Typical Size: 700.0

Scenario Total Cost: \$2,084.71

Scenario Cost/Unit: \$2.98

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.55	700	\$1,785.00
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 638 - Water and Sediment Control Basin

Scenario #2 - Topsoil

Scenario Description:

Typical scenarios for the construction of an earthen embankment or the rebuild of an existing WASCOB. Prior to constructing/reconstructing the embankment, 6 inches of topsoil is removed and stockpiled. Outlet is typically an underground outlet. An earthen embankment or combination ridge and channel generally constructed/rebuilt across the slope and minor watercourses to form a sediment trap and water detention basin. Topsoil is replaced following construction of the embankment. Costs include all equipment necessary to strip and stock pile topsoil, excavate, shape, grade and compact the Water and Sediment Control Basin, spread and replace topsoil after construction and mobilization of equipment. Seeding not included. This practice is utilized to reduce watercourse and gully erosion, trap sediment, reduce and manage onsite and downstream runoff. Sheet and rill erosion will be controlled by other conservation practices. Work is done with dozer, scraper, or road grader.

Before Situation:

Site has shallow topsoil which if removed by earthwork for construction of embankment will significantly impact yields. Farming fields with excessive slope length has resulted in multiple rills and/or ephemeral gullies that will continue to worsen over time. The excessive erosion may lead to deterioration of receiving waters due to excessive sedimentation and nutrient transport. Resource concern addressed includes soil erosion and water quality by trapping sediment and/or reduce erosion in a field to protect riparian areas and water bodies from sediment deposition. Surface water causes erosion and the sediment (and potentially pesticides) is being transported into the riparian areas and water bodies downstream.

After Situation:

Water and Sediment Control Basis is constructed or rebuilt by the excavation/earthfill with dozer, scraper and/or road grader. Rill and/or gully erosion is reduced. If riser and underground outlet are needed, then include Underground Outlet (620). Include Critical Area Planting (342) where necessary to prevent erosion following construction activities.

Feature Measure: CY of WASCOB Embankment

Scenario Unit:: Cubic Yard

Scenario Typical Size: 700.0

Scenario Total Cost: \$2,312.21

Scenario Cost/Unit: \$3.30

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Stripping and stockpiling, topsoil	1199	Stripping and stockpiling of topsoil adjacent to stripping area. Includes equipment and labor.	Cubic Yard	\$0.91	250	\$227.50
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.55	700	\$1,785.00
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 642 - Water Well

Scenario #1 - Large Diameter Drilled Well

Scenario Description:

Typical construction is for the drilling of a well using a bucket well drill rig. These wells are large diameter drilled wells. The purpose of the practice is to provide water for livestock. An average well depth is less than 100 foot at 36" diameter. These wells are typically implemented in glacial till areas where the ground water resource has slow recharge rate, and the large diameter of the well allows for storage of water to meet the demand.

Before Situation:

Livestock have insufficient water or are fenced from their water source.

After Situation:

A 48 ft, 36" diameter well is installed using a bucket drill rig. The large diameter of the well allows for storage of water in glacial till areas where the groundwater recharge rate is less than demand. The well is dug and then cased with concrete. Perforated concrete casing is used as a screen around the bottom of the well. Approximately 6" of gravel is placed around the screen. Sufficient water is available for livestock. Utilize Pumping Plant (533) and Pipeline (516) as associated practices. Use Critical Area Seeding (342) where necessary to prevent erosion following construction activities.

Feature Measure: Depth of Well

Scenario Unit:: Foot

Scenario Typical Size: 48.0

Scenario Total Cost: \$9,021.39

Scenario Cost/Unit: \$187.95

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Bucket Drill Rig with operator	2183	Bucket drill rig including equipment and power unit costs and labor.	Hour	\$559.03	10	\$5,590.30
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	4	\$102.28
Chlorine	1335	Liquid chlorine bleach. Includes materials only.	Gallon	\$2.76	5	\$13.80
Well Casing, Concrete	2173	Concrete tile 3" diameter x 8' long. Materials only.	Foot	\$58.98	40	\$2,359.20
Well Casing, Concrete, perforated	2174	Perforated concrete tile 3" diameter x 8' long. Materials only.	Foot	\$64.88	8	\$519.04
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 642 - Water Well

Scenario #2 - Shallow Drilled Well, <= 100 feet, <= 6in Diam

Scenario Description:

Typical construction is for the installation of a well, in areas where sufficient water is known to occur within 100 feet of the ground surface, and the flow is such that a smaller diameter well is sufficient. The well shall be drilled, dug, driven, bored, jetted or otherwise constructed to an aquifer for water supply. The purpose of the practice is to provide water for livestock.

Before Situation:

Livestock have insufficient water or are fenced from their water source.

After Situation:

An average well depth is 100 feet. Well casings are ≤ 6" in diameter. Sufficient water is available for livestock. Utilize Pumping Plant (533) and Pipeline (516) as associated practices. Use Critical Area Seeding (342) where necessary to prevent erosion following construction activities.

Feature Measure: Depth of Well

Scenario Unit:: Foot

Scenario Typical Size: 100.0

Scenario Total Cost: \$5,500.71

Scenario Cost/Unit: \$55.01

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Rotary Drill Rig	1595	Rotary drill rig including equipment and power unit costs. Labor not included.	Hour	\$346.22	10	\$3,462.20
Materials						
Grout, cement	1333	Cement grout meeting ASTM specifications for well sealing. Includes both neat-cement grout and bentonite gout mixtures. Includes materials, equipment and labor to place.	Cubic Yard	\$795.82	1	\$795.82
Chlorine	1335	Liquid chlorine bleach. Includes materials only.	Gallon	\$2.76	1	\$2.76
Well Cap, 6"	1786	Well cap, 6". Materials only.	Each	\$33.60	1	\$33.60
Well Casing, Plastic, 6"	1804	PVC or ABS non-threaded well casing, 6". Materials only.	Foot	\$6.52	70	\$456.40
Well Screen, plastic, 6"	1999	6" PVC well screen. Materials only.	Foot	\$16.30	30	\$489.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 642 - Water Well

Scenario #3 - Shallow Drilled Well, <= 100 feet, > 6in Diam

Scenario Description:

Typical construction is for the installation of a well, in areas where sufficient water is known to occur within 100 feet of the ground surface, and the flow is such that a larger diameter well is needed. The well shall be drilled, dug, driven, bored, jetted or otherwise constructed to an aquifer for water supply. The purpose of the practice is to provide water for livestock.

Before Situation:

Livestock have insufficient water or are fenced from their water source.

After Situation:

An average well depth is 100 feet. Well casings are 12" in diameter. Sufficient water is available for livestock. Utilize Pumping Plant (533) and Pipeline (516) as associated practices. Use Critical Area Seeding (342) where necessary to prevent erosion following construction activities.

Feature Measure: Depth of Well

Scenario Unit:: Foot

Scenario Typical Size: 100.0

Scenario Total Cost: \$6,576.21

Scenario Cost/Unit: \$65.76

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Rotary Drill Rig	1595	Rotary drill rig including equipment and power unit costs. Labor not included.	Hour	\$346.22	10	\$3,462.20
Materials						
Grout, cement	1333	Cement grout meeting ASTM specifications for well sealing. Includes both neat-cement grout and bentonite gout mixtures. Includes materials, equipment and labor to place.	Cubic Yard	\$795.82	1	\$795.82
Chlorine	1335	Liquid chlorine bleach. Includes materials only.	Gallon	\$2.76	1	\$2.76
Well Cap, 12"	1789	Well cap, 12". Materials only.	Each	\$113.30	1	\$113.30
Well Casing, Plastic, 12"	1807	PVC or ABS non-threaded well casing, 12". Materials only.	Foot	\$16.88	70	\$1,181.60
Well Screen, plastic, 8"	2000	8" PVC well screen. Materials only.	Foot	\$25.32	30	\$759.60
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 642 - Water Well

Scenario #4 - Deep Drilled Well, > 100 Feet

Scenario Description:

Typical construction is for the installation of a well, in areas where sufficient water is known to occur >100 feet of the ground surface. The well shall be drilled, dug, driven, bored, jetted or otherwise constructed to an aquifer for water supply. The purpose of the practice is to provide water for livestock.

Before Situation:

Livestock have insufficient water or are fenced from their water source.

After Situation:

An average well depth is 300 feet. Well casings are 4-6" in diameter. Well is dug into consolidated (bedrock or firm material) where casing and lining is installed to a depth of 240 feet. The remaining depth does not need lining or screening due to the "open hole" construction and nature of wells in this substrate. Sufficient water is available for livestock. Utilize Pumping Plant (533) and Pipeline (516) as associated practices. Use Critical Area Seeding (342) where necessary to prevent erosion following construction activities.

Feature Measure: Depth of Well

Scenario Unit:: Foot

Scenario Typical Size: 300.0

Scenario Total Cost: \$8,349.83

Scenario Cost/Unit: \$27.83

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Rotary Drill Rig	1595	Rotary drill rig including equipment and power unit costs. Labor not included.	Hour	\$346.22	16	\$5,539.52
------------------	------	--	------	----------	----	------------

Materials

Grout, cement	1333	Cement grout meeting ASTM specifications for well sealing. Includes both neat-cement grout and bentonite gout mixtures. Includes materials, equipment and labor to place.	Cubic Yard	\$795.82	1	\$795.82
Chlorine	1335	Liquid chlorine bleach. Includes materials only.	Gallon	\$2.76	1	\$2.76
Well Cap, 6"	1786	Well cap, 6". Materials only.	Each	\$33.60	1	\$33.60
Well Casing, Plastic, 6"	1804	PVC or ABS non-threaded well casing, 6". Materials only.	Foot	\$6.52	220	\$1,434.40
Well Casing, Metal, 6"	1810	Steel well casing, 6". Materials only.	Foot	\$14.14	20	\$282.80

Mobilization

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93
--------------------------------	------	---	------	----------	---	----------

Practice: 643 - Restoration and Management of Rare and Declining Habitats

Scenario #23 - Glade Restoration, Heavy

Scenario Description:

Removing or reducing woody plant canopy and utilizing chemical treatment (except for non-sprouting woody species) to promote herbaceous growth to restore and manage glades where the Ecological Site Description indicates a glade. Scenario is for glade restoration where greater than 50% canopy cover across the treatment area is in undesirable non-herbaceous cover. Payment is based on impacted acres only. This scenario is intended to restore and manage the ecological site for associated wildlife species that benefit from habitats such as glades. Associated practices may include, but are not limited to; Early Successional Habitat Management/Development (647), Prescribed Burning (338) and Conservation Cover (327).

Before Situation:

The understory has a minimal amount of herbaceous and early woody successional vegetation. Wildlife food, cover, and shelter are lacking, and woody cover control is needed to manage for associated wildlife species that benefit from habitats such as glades.

After Situation:

The glade habitat is restored and flora and fauna that depend on the glade habitat flourish.

Feature Measure: area treated

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$698.21

Scenario Cost/Unit: \$698.21

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	16	\$71.20
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	4	\$115.36
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	20	\$439.60
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: 643 - Restoration and Management of Rare and Declining Habitats

Scenario #25 - Glade Restoration, Light

Scenario Description:

Removing or reducing woody plant canopy and utilizing chemical treatment (except for non-sprouting woody species) to promote herbaceous growth to restore and manage glades where the Ecological Site Description indicates a glade. Scenario is for glade restoration where 10% - 50% canopy cover across the treatment area is in undesirable non-herbaceous cover. Payment is based on impacted acres only. This scenario is intended to restore and manage the ecological site for associated wildlife species that benefit from habitats such as glades. Associated practices may include, but are not limited to; Early Successional Habitat Management/Development (647), Prescribed Burning (338) and Conservation Cover (327).

Before Situation:

The understory has a minimal amount of herbaceous and early woody successional vegetation. Wildlife food, cover, and shelter are lacking, and woody cover control is needed to manage for associated wildlife species that benefit from habitats such as glades.

After Situation:

The glade habitat is restored and flora and fauna that depend on the glade habitat flourish.

Feature Measure: size of area

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$385.13

Scenario Cost/Unit: \$385.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	8	\$35.60
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	2	\$57.68
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05



Practice: 643 - Restoration and Management of Rare and Declining Habitats

Scenario #26 - Savanna or Prairie Restoration, Heavy

Scenario Description:

Removing or reducing woody plant canopy and utilizing chemical treatment (except for non-sprouting woody species) to promote herbaceous growth to restore and manage savannas or prairies where the Ecological Site Description indicates a savanna or prairie. Scenario is for savanna or prairie restoration where greater than 60% canopy cover across the treatment area is in undesirable non-herbaceous cover. Payment is based on impacted acres only. This scenario is intended to restore and manage the ecological site for associated wildlife species that benefit from habitats such as savannas or prairies Associated practices may include, but are not limited to; Early Successional Habitat Management/Development (647), Prescribed Burning (338) and Conservation Cover (327).

Before Situation:

The understory has a minimal amount of herbaceous and early woody successional vegetation. Wildlife food, cover and shelter are lacking and control is needed to manage for associated wildlife species that benefit from habitats such as savannas and prairies.

After Situation:

Savanna or prairie is restored and flora and fauna that depend on that habitat flourish.

Feature Measure: treated acres

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$2,401.19

Scenario Cost/Unit: \$240.12

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	8	\$35.60
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	5	\$111.10
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	20	\$1,058.80
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	10	\$288.40
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	38	\$835.24
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: 643 - Restoration and Management of Rare and Declining Habitats

Scenario #27 - Savanna or Prairie Restoration, Medium

Scenario Description:

Removing or reducing woody plant canopy and utilizing chemical treatment (except for non-sprouting woody species) to promote herbaceous growth to restore and manage savannas or prairies where the Ecological Site Description indicates a savanna or prairie. Scenario is for savanna or prairie restoration where 40% - 60% canopy cover across the treatment area is in undesirable non-herbaceous cover. Payment is based on impacted acres only. This scenario is intended to restore and manage the ecological site for associated wildlife species that benefit from habitats such as savannas or prairies Associated practices may include, but are not limited to; Early Successional Habitat Management/Development (647), Prescribed Burning (338) and Conservation Cover (327).

Before Situation:

The understory has a minimal amount of herbaceous and early woody successional vegetation. Wildlife food, cover and shelter are lacking and control is needed to manage for associated wildlife species that benefit from habitats such as savannas and prairies.

After Situation:

Savanna or prairie is restored and flora and fauna that depend on that habitat flourish

Feature Measure: acres treated

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$1,304.25

Scenario Cost/Unit: \$130.43

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	4	\$17.80
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	10	\$222.20
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	8	\$423.52
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	6	\$173.04
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	18	\$395.64
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: 643 - Restoration and Management of Rare and Declining Habitats

Scenario #28 - Savanna or Prairie Restoration, Light

Scenario Description:

Removing or reducing woody plant canopy and utilizing chemical treatment (except for non-sprouting woody species) to promote herbaceous growth to restore and manage savannas or prairies where the Ecological Site Description indicates a savanna or prairie. Scenario is for savanna or prairie restoration where 10% - 39% canopy cover across the treatment area is in undesirable non-herbaceous cover. Payment is based on impacted acres only. This scenario is intended to restore and manage the ecological site for associated wildlife species that benefit from habitats such as savannas or prairies Associated practices may include, but are not limited to; Early Successional Habitat Management/Development (647), Prescribed Burning (338) and Conservation Cover (327).

Before Situation:

The understory has a minimal amount of herbaceous and early woody successional vegetation. Wildlife food, cover and shelter are lacking and control is needed to manage for associated wildlife species that benefit from habitats such as savannas and prairies.

After Situation:

Savanna or prairie is restored and flora and fauna that depend on that habitat flourish.

Feature Measure: Area treated

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$710.21

Scenario Cost/Unit: \$71.02

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	5	\$111.10
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	5	\$264.70
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	3	\$86.52
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: 643 - Restoration and Management of Rare and Declining Habitats

Scenario #29 - Woodland Restoration, Heavy

Scenario Description:

Removing or reducing the tree canopy and utilizing chemical treatment (except for non-sprouting woody species) to promote herbaceous growth or early woody succession to benefit wildlife habitat where the Ecological Site Description indicates a woodland. Scenario is for open woodland restoration where basal area removal is >40 square feet per acre, or >400 stems per acre. This scenario is intended to restore and manage the ecological site for associated wildlife species that benefit from habitats such as open woodlands by felling the majority of the undesirable trees to allow installation of associated practices. Associated practices may include, but are not limited to; Early Successional Habitat Management/Development (647), Prescribed Burning (338) and Conservation Cover (327).

Before Situation:

A stand of trees is even aged and lacks structural diversity. The understory has a minimal amount of herbaceous and early woody successional vegetation. Wildlife food, cover and shelter are lacking, and woody cover control is needed to manage for associated wildlife species that benefit from habitats such as open woodlands.

After Situation:

The ecological site is restored and flora and fauna that depend on open woodland habitat flourish

Feature Measure: Treatment area

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$2,245.90

Scenario Cost/Unit: \$224.59

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	45	\$200.25
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	10	\$222.20
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	15	\$432.60
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	60	\$1,318.80
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: 643 - Restoration and Management of Rare and Declining Habitats

Scenario #30 - Woodland Restoration, Medium

Scenario Description:

Removing or reducing the tree canopy and utilizing chemical treatment (except for non-sprouting woody species) to promote herbaceous growth or early woody succession to benefit wildlife habitat where the Ecological Site Description indicates a woodland. Scenario is for open woodland restoration where basal area removal is 30 - 40 square feet per acre, or 200 - 400 stems per acre. This scenario is intended to restore and manage the ecological site for associated wildlife species that benefit from habitats such as open woodlands by felling the majority of the undesirable trees to allow installation of associated practices. Associated practices may include, but are not limited to; Early Successional Habitat Management/Development (647), Prescribed Burning (338) and Conservation Cover (327).

Before Situation:

A stand of trees is even aged and lacks structural diversity. The understory has a minimal amount of herbaceous and early woody successional vegetation. Wildlife food, cover and shelter are lacking, and woody cover control is needed to manage for associated wildlife species that benefit from habitats such as open woodlands.

After Situation:

The woodland ecological site is restored and flora and fauna that depend on open woodland habitat flourish.

Feature Measure: Area Treated

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$1,219.95

Scenario Cost/Unit: \$122.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	20	\$89.00
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	5	\$111.10
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	10	\$288.40
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	30	\$659.40
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: 643 - Restoration and Management of Rare and Declining Habitats

Scenario #31 - Woodland Restoration, Light

Scenario Description:

Removing or reducing the tree canopy and utilizing chemical treatment (except for non-sprouting woody species) to promote herbaceous growth or early woody succession to benefit wildlife habitat where the Ecological Site Description indicates a woodland. Scenario is for open woodland restoration where basal area removal is 20 - 29 square feet per acre, or 100 - 199 stems per acre. This scenario is intended to restore and manage the ecological site for associated wildlife species that benefit from habitats such as open woodlands by felling the majority of the undesirable trees to allow installation of associated practices. Associated practices may include, but are not limited to; Early Successional Habitat Management/Development (647), Prescribed Burning (338) and Conservation Cover (327).

Before Situation:

A stand of trees is even aged and lacks structural diversity. The understory has a minimal amount of herbaceous and early woody successional vegetation. Wildlife food, cover and shelter are lacking, and woody cover control is needed to manage for associated wildlife species that benefit from habitats such as open woodlands.

After Situation:

The woodland ecological site is restored and flora and fauna that depend on open woodland habitat flourish.

Feature Measure: Area Treated

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$1,087.80

Scenario Cost/Unit: \$108.78

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	15	\$66.75
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	5	\$111.10
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	10	\$288.40
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	25	\$549.50
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: 645 - Upland Wildlife Habitat Management

Scenario #1 - Macro Topography, deep

Scenario Description:

Establishment of a topographic feature on the landscape consisting of a small dam and pool or small excavated depression that will hold water to provide a source of water for wildlife, including habitat for reptiles and amphibians. Payment includes the equipment and labor associated with establishing the water feature.

Before Situation:

This practice will be installed on any area where seasonal or permanent water for wildlife is inadequate. The resource concerns to be addressed by this practice are inadequate water needed to meet the life needs of the target species or guild. Water storage during the critical period (season) is absent. No micro-ponding sites are available aquatic dependent invertebrates. Vertebrate wildlife habitat is lacking richness.

After Situation:

This practice consists of an excavated depression to collect water for wildlife to access. Excavated depressions are typically 1000 ft2 and 3 feet deep in center with 4:1 side slopes around edge. Associated practices: Critical Area Planting (342), Conservation Cover (327)

Feature Measure: Each deep macro-topography featu

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$880.13

Scenario Cost/Unit: \$880.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	\$126.50	4	\$506.00
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	4	\$113.20
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 646 - Shallow Water Development and Management

Scenario #1 - Management, Low Level

Scenario Description:

This scenario addresses inadequate habitat for fish and wildlife on cropland. The resource concern is addressed by providing shallow water habitat for wildlife such as shorebirds, waterfowl, wading birds, mammals, fish, reptiles, amphibians, and other species that require shallow water for at least part of their life cycle. Sites are flooded up to a depth of 18" with an average depth of 9". Before flooding, fields are prepared by rolling residue if necessary. Water is provided by natural flooding and/or precipitation.

Before Situation:

There is inadequate habitat to provide optimum resting, nesting, and feeding habitat for waterfowl, shorebirds, and other wildlife (amphibians, reptiles, mammals, invertebrates, etc.).

After Situation:

A single or series of shallow water areas that are managed per standard and specification. Water levels are regulated to maintain temporary wildlife habitat. Timing and duration of flooding and de-watering is dependent on specific species requirements. Water is pumped into area to be flooded. Flooded sites vary from mudflats to water depths of 18" with an average depth of 9". The hydrologic conditions of ponding and saturation (frequency, depth, duration, timing) provides optimum seasonal habitat for waterfowl, shorebirds, and other wildlife (amphibians, reptiles, mammals, invertebrates, etc.). Associated practices include Structure for Water Control (587) and Dike (356) if needed. Depending on local conditions, other Conservation Practices may also be required.

Feature Measure: Acre of shallow water

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: \$173.82

Scenario Cost/Unit: \$86.91

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	5	\$109.90



Practice: 647 - Early Successional Habitat Development/Management

Scenario #2 - Disking

Scenario Description:

This practice addresses inadequate wildlife habitat for species requiring early successional habitat. This scenario provides early successional habitat by setting back succession and manipulating species composition by disking vegetation and exposing bare ground. The typical setting for this scenario is at the edge of crop fields, in pastures, and in odd areas such as pivot corners. This scenario is applicable nationwide. Where the management of woody plants is require to create or maintain early successional habitat conservation practice 314 brush management should be used. Where chemical control of weeds, including invasives, is required to reduce competition for the desired plant community conservation practice 315 herbaceous weed control should be used. Where the seedbank is inadequate for natural regeneration and seeding is required, use conservation practice 327 Conservation Cover. Where the need is to create early successional habitat within or at the edge of woodland or forest use conservation practice 645 Upland Wildlife Habitat Management (edge feathering).

Before Situation:

The site is static or trending to higher successional plant species. The disturbance regime to maintain a lower successional stage is lacking. Pastures are often monotypic, lacking in diversity. Bare ground for seedling establishment is absent. Stands are often dense and inhibit the movements of younger wildlife species such as game bird chicks.

After Situation:

The application of this scenario improves wildlife habitat for species requiring early successional plant communities by reducing competition and creating bare ground for the establishment of early successional plants. Additionally, brood rearing habitat is improved both by the resultant food resources and the increased openness of the plant community that allows chicks to negotiate the terrain and exploit those food resources.

Feature Measure: width and length of treated area

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: \$198.24

Scenario Cost/Unit: \$99.12

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	2	\$22.74
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: 647 - Early Successional Habitat Development/Management

Scenario #4 - Mowing and Heavy Disking

Scenario Description:

This practice addresses inadequate wildlife habitat for species requiring early successional habitat. This scenario provides early successional habitat by setting back succession and manipulating species composition by mowing dense vegetation and then a heavy disking (multiple passes) to expose bare ground. All mowed areas are also disked. The typical setting for this scenario is at the edge of crop fields, in pastures, idle land and in odd areas such as pivot corners. This scenario is applicable nationwide. Where the management of woody plants is require to create or maintain early successional habitat conservation practice 314 brush management should be used. Where chemical control of weeds, including invasives, is required to reduce competition for the desired plant community conservation practice 315 herbaceous weed control should be used. Where the seedbank is inadequate for natural regeneration and seeding is required 327 Conservation Cover. Where the need is to create early successional habitat within or at the edge of woodland or forest use conservation practice 645 Upland Wildlife Habitat Management (edge feathering).

Before Situation:

The site is static or trending to higher successional plant species. The disturbance regime to maintain a lower successional stage is lacking. Pastures are often monotypic, lacking in diversity. Bare ground for seedling establishment is absent. Stands are often dense and inhibit the movements of younger wildlife species such as game bird chicks.

After Situation:

The application of this scenario improves wildlife habitat for species requiring early successional plant communities by reducing competition and creating bare ground for the establishment of early successional plants. Additionally, brood rearing habitat is improved both by the resultant food resources and the increased openness of the plant community that allows chicks to negotiate the terrain and exploit those food resources.

Feature Measure: Width and length of treated area

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: \$446.07

Scenario Cost/Unit: \$223.04

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	3	\$158.82
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	4	\$45.48
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	3	\$66.27
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: 649 - Structures for Wildlife

Scenario #6 - Fence Markers, Vinyl Undersill

Scenario Description:

Existing fences are retrofitted with vinyl markers that increase wire visibility and reduce mortality due to collision for wildlife species of concern. Markers are installed approximately every 3 feet along top wire. Scenario is typically implemented along fences in potential high risk areas (red areas in SGI Fence Collision Risk Model) or where a known problem exists.

Before Situation:

Wire fences located in high risk areas pose a collision threat to wildlife of special concern.

After Situation:

Fence related mortality of species of special concern is reduced.

Feature Measure: feet of fence marked

Scenario Unit:: Foot

Scenario Typical Size: 1,320.0

Scenario Total Cost: \$203.52

Scenario Cost/Unit: \$0.15

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	0.5	\$14.42
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	5	\$109.90
Materials						
Vinyl Undersill Strips	241	Marking material using the "undersill" strips of vinyl siding. Priced per foot of fence per each wire. Materials only.	Foot	\$0.06	1320	\$79.20

Practice: 649 - Structures for Wildlife

Scenario #8 - Downed Tree Structure

Scenario Description:

Downed tree structures will be created to provide shrubby/woody escape cover for wildlife. Felling of select trees and placement in selected locations to provide wildlife cover. Minimum 30' x 50' area for structure covered by interlocking limbs of trees at least 12" in diameter. Payment includes tree felling and placement. Facilitating practices may include but not limited to: Upland Wildlife Habitat Management (645), Wetland Creation (658), Wetland Restoration (657), Wetland Enhancement (659), Early Successional Habitat Management/Development (647), Prescribed Burning (338), Restoration and Management of Rare and Declining Habitats (643), and Conservation Cover (327).

Before Situation:

A 40 acre operation managing for quail and other small game habitat. Shrubby/woody escape cover is often the missing habitat component for bobwhite quail and other small game in fields managed for upland wildlife.

After Situation:

The installation of a downed tree structure enhances the overall habitat needs of quail and other small game species. These structures/features enhance habitat and improve species survivability.

Feature Measure: area covered by structure

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$258.70

Scenario Cost/Unit: \$258.70

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	2	\$8.90
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	\$58.85	2	\$117.70
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	4	\$87.92
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	2	\$44.18

Practice: 649 - Structures for Wildlife

Scenario #10 - Edgefeathering, heavy

Scenario Description:

Trees are cut and brush clipped in the border along a woodland edge using a tractor and chainsaw to create dense woody cover and a transitional area between a timbered edge and the adjacent land use such as cropland, pasture, or idle lands. The edge feathering will extend at least 30' wide, measured from the outside tree trunk, and at least 50' long -- resulting in a minimum area of 1500 square feet covered by interlocking woody branches. Cut stumps will be treated with brush herbicide. Some hand placement of the cut trees is necessary. Facilitating practices may include but not limited to: Upland Wildlife Habitat Management (645), Wetland Creation (658), Wetland Restoration (657), Wetland Enhancement (659), Early Successional Habitat Management/Development (647), Prescribed Burning (338), Restoration and Management of Rare and Declining Habitats (643), and Conservation Cover (327).

Before Situation:

Forested land with a hard edge of mature trees adjacent to cropland or pasture. Woody cover close to the ground is lacking for wildlife species such as rabbits, quail, songbirds and other wildlife species requiring dense woody cover near ground level. Average diameter of the main stand trees is greater than 4 inches.

After Situation:

Creation of woody debris and small piles improves the overall habitat needs of wildlife species requiring dense woody cover and increase survival and the population of these species.

Feature Measure: area covered by edgefeathering

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,033.79

Scenario Cost/Unit: \$1,033.79

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	14.5	\$64.53
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	\$58.85	7.25	\$426.66
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	17.4	\$382.45
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	7.25	\$160.15

Practice: 655 - Forest Trails and Landings

Scenario #1 - Water Bar Installation

Scenario Description:

Rehabilitation of existing forest access trails and landings by addressing erosion and sedimentation through the installation of water bars and light shaping/grading between water bars. Typically the trail is a single lane, existing 12-foot wide seasonal or temporary trail on a moderate slope (10%) on forestland requiring sustained erosion control measures applied by using traditional logging equipment such as a log skidder or dozer. The purpose is to hydrologically disconnect existing trail/landing system from the streams and natural drainages. This scenario applies to only those segments of the trail system that have resource concerns requiring rehabilitation. A typical water bar installed in this scenario is on a 75 to 80 foot spacing with a depth of about 1 foot. Some hand work (chainsaw) will be needed to allow the use of the equipment without causing damage to residual trees. The work will be supervised. No mobilization is required, as equipment and personnel are already on site. Other practices such as Stream Crossing, and Critical Area Planting, Access Road and Structure for Water Control can be adjacent/appurtenant but not part of this practice scenario . Resource concerns include: Excessive sedimentation in surface waters, Concentrated flow erosion, Sheet and rill erosion, and Degradation of wildlife species.

Before Situation:

Trails are delivering sediment to waterways, impacting riparian/wetlands and/or possibly affecting fish/T&E species. The usefulness of the trail/landing system is being adversely affected by erosion.

After Situation:

Trails and landings provide access and do not adversely affect the resources concerns.

Feature Measure: Number of water bars

Scenario Unit:: Each

Scenario Typical Size: 34.0

Scenario Total Cost: \$2,146.61

Scenario Cost/Unit: \$63.14

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	1	\$4.45
Log skidder	942	Equipment and power unit costs. Labor not included.	Hour	\$130.06	3	\$390.18
Water Bars	1500	Installation of graded trail water controlling structures such as water bars, broad based dips for erosion control. Typical cross section is 1.5 feet high with 4:1 side slopes yielding about 0.33 CY/ft of length.	Foot	\$2.86	510	\$1,458.60
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	1	\$21.98
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	3	\$84.90
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50

Practice: 655 - Forest Trails and Landings

Scenario #2 - Shaping and Grading

Scenario Description:

Rehabilitation of existing forest access trails and landings by addressing rutting, erosion, and sedimentation through shaping and grading and installing other widely spaced mitigating practices such as broad based drainage dips, water bars, and water turnouts. Typically the trail is a single lane, existing 12-foot wide seasonal or temporary trail on a relatively flat slopes (2%) on forestland requiring sustained erosion control measures applied by using traditional logging equipment such as a log skidder or dozer. The purpose is to hydrologically disconnect the existing trail/landing system from streams and natural drainages and to establish a vegetative cover. Some hand work (chainsaw) will be needed to allow the use of the equipment. The work will be supervised. Other practices such as Stream Crossing, and Critical Area Planting. Access Road and Structure for Water Control can be adjacent/appurtenant but not part of the practice scenario. Treatments are for long-term reduction of sediment, restore fish habitat, create fire access and to move routes off unstable slopes. Resource concerns include: Excessive sediment in surface waters, Concentrated and Sheet & rill flow erosion, Soil compaction, and Habitat degradation.

Before Situation:

Trail/landings are delivering sediment to waterways, impacting riparian/wetlands and/or possibly affecting fish/T&E species. The usefulness of the trail/landing system is being adversely affected by erosion.

After Situation:

A trail system is installed that provides access to the forested tract and does not cause excessive erosion or water quality concerns.

Feature Measure: Length of trail treated

Scenario Unit:: Foot

Scenario Typical Size: 2,640.0

Scenario Total Cost: \$1,292.51

Scenario Cost/Unit: \$0.49

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$67.45	4	\$269.80
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	1	\$4.45
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	1	\$21.98
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	4	\$113.20
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	1	\$93.25
Materials						
Aggregate, Gravel, Ungraded, Quarry Run	1099	Includes materials, equipment and labor	Cubic Yard	\$17.63	30	\$528.90
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 655 - Forest Trails and Landings

Scenario #3 - Shaping and Grading with Vegetation Establishment

Scenario Description:

Rehabilitation of existing forest access trails and landings by addressing rutting, erosion, and sedimentation through shaping and grading and installing other widely spaced mitigating practices such as broad based drainage dips, water bars, and water turnouts. It also includes seedbed preparation, seeding and soil amendments determined to be needed. Typically the trail is a single lane, existing 12-foot wide seasonal or temporary trail on a relatively flat slope (2%) on forestland requiring sustained erosion control measures applied by using traditional logging equipment such as a log skidder or dozer. The purpose is to hydrologically disconnect the existing trail/landing system from streams and natural drainages and to establish a vegetative cover. Some hand work (chainsaw) will be needed to allow the use of the equipment. The work will be supervised. Other practices such as Stream Crossing, and Critical Area Planting. Access Road and Structure for Water Control can be adjacent/appurtenant but not part of the practice scenario. Treatments are for long-term reduction of sediment, restore fish habitat, create fire access and to move routes off unstable slopes. Resource concerns include: Excessive sediment in surface waters, Concentrated and Sheet & rill flow erosion, Soil compaction, and Habitat degradation.

Before Situation:

Trail/landings are delivering sediment to waterways, impacting riparian/wetlands and/or possibly affecting fish/T&E species. The usefulness of the trail/landing system is being adversely affected by erosion.

After Situation:

A trail system is installed that provides access to the forested tract and does not cause excessive erosion or water quality concerns.

Feature Measure: Length of trail treated

Scenario Unit:: Foot

Scenario Typical Size: 2,640.0

Scenario Total Cost: \$1,891.37

Scenario Cost/Unit: \$0.72

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$67.45	4	\$269.80
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	1	\$4.45
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	0.73	\$8.30
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.75	0.73	\$4.93
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$10.84	0.73	\$7.91
Seeding Operation, Broadcast, Ground	959	Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs.	Acre	\$12.85	0.73	\$9.38
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	2	\$57.68
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	1	\$21.98
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	4	\$113.20
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	1	\$93.25
Materials						
Nitrogen (N), Ammonium Nitrate	69	Price per pound of N supplied by Ammonium Nitrate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.55	60	\$33.00
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.45	90	\$40.50
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.35	90	\$31.50
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	\$18.22	0.5	\$9.11
Aggregate, Gravel, Ungraded, Quarry Run	1099	Includes materials, equipment and labor	Cubic Yard	\$17.63	30	\$528.90



One Species, Warm Season, Introduced Perennial Grass (seed or sprigs)	2323	Introduced, warm season perennial grass seed or sprig. Includes material and shipping only.	Acre	\$62.40	0.73	\$45.55
<b>Mobilization</b>						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 655 - Forest Trails and Landings

Scenario #4 - Temporary Stream Crossing

Scenario Description:

The design and installation of a temporary stream crossing on small order streams that will meet the immediate forest management/conservation needs. Afterwards the crossing will be restored and stabilized. Improperly designed and/or installed stream crossings will, in the long term, adversely affect water quality and aquatic life. Approaches will also be stabilized for the use of the crossing and stabilized afterwards as necessary. Installation will be supervised. Permanent and/or high-traffic crossings will be designed and installed according to the Stream Crossing (578) Standard. Resource concerns include: Excessive sediment in surface waters and Habitat degradation.

Before Situation:

Access to a forested tract is not available for the installation of conservation practices or removal of forest products due to the lack of a suitable stream crossing(s).

After Situation:

Access was available to address other resource concerns/management needs and the stream is restored to its previous or better condition.

Feature Measure: Number of crossings

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$861.20

Scenario Cost/Unit: \$861.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Log skidder	942	Equipment and power unit costs. Labor not included.	Hour	\$130.06	2	\$260.12
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	2	\$56.60
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	14	\$357.98

### Scenario #62 - Log Landing Shaping and Grading with Vegetation Establishment

Rehabilitation of existing log landings by addressing rutting, erosion, and sedimentation through shaping and grading and establishing vegetative cover, including seedbed preparation, seeding and soil amendments determined to be needed. Typically the landing is 0.5 acres on a relatively flat slope (<2%) on forestland requiring sustained erosion control measures applied by using traditional logging equipment such as a log skidder or dozer. The purpose is to hydrologically disconnect the existing trail/landing system from streams and natural drainages and to establish a vegetative cover. Some hand work (chainsaw) will be needed to allow the use of the equipment. The work will be supervised. Other practices such as Stream Crossing, and Critical Area Planting. Access Road and Structure for Water Control can be adjacent/appurtenant but not part of the practice scenario. Treatments are for long-term reduction of sediment, restore fish habitat, create fire access and to move routes off unstable slopes. Resource concerns include: Excessive sediment in surface waters, Concentrated and Sheet & rill flow erosion, Soil compaction, and Habitat degradation.

Log landings are delivering sediment to waterways, impacting riparian/wetlands and/or possibly affecting fish/T&E species. The usefulness of the trail/landing system is being adversely affected by erosion.

The log landings are shaped/graded and established to permanent cover and do not cause excessive erosion or water quality concerns.

Scenario Unit:: Acre

**Scenario Total Cost:** \$867.18

Cost Details:

[illegible]

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: 657 - Wetland Restoration

Scenario #2 - Riverine Levee Removal, ditch plugs and foodplain features

Scenario Description:

A Riverine HGM tract on a large floodplain is to be restored. It has been converted to agricultural production by surface ditching and clearing of woody vegetation. The wetland extent is 60 acres. Resource Concerns are: 4-SOIL QUALITY DEGRADATION - Organic matter depletion, 11- WATER QUALITY DEGRADATION - Excess nutrients in surface and ground waters, 12 - WATER QUALITY DEGRADATION - Pesticides transported to surface and ground waters, 16 - WATER QUALITY DEGRADATION - Excessive sediment in surface waters, 18 - DEGRADED PLANT CONDITION - Undesirable plant productivity and health, 19 - DEGRADED PLANT CONDITION, Inadequate structure and composition, 22- INADEQUATE HABITAT FOR FISH AND WILDLIFE - Habitat degradation.

Before Situation:

A levee prevents floodwater from entering the tract. The original cover was forest. The site is drained by surface ditches which collect surface water and direct it to the river through a flap gate structure. The site has been completely cleared, and no suitable adjacent seedwall exists for natural regeneration of forest species. The lateral connectivity between the channel and floodplain has been altered by construction of levees along the reach.

After Situation:

The hydrology of the site is restored with the installation of ditch plugs, and the excavation of macrotopographic features with an average depth of 6" over 30% of the wetland area. Excavated spoil is placed adjacent to the features on the wetland and adjacent non-wetland area with a maximum depth of 24 inches. The levee has been breached at the upstream and downstream ends of the tract reach, restoring dynamic stream flooding. The breach length is 150 feet long at both locations. Both the wetland and non-wetland areas are planted with a Bottomland Hardwood species mix. The levee breaches are armored with rock riprap. Facilitating practices include Grade Stabilization Structure and Tree and Shrub Planting. Restoration of hydrology and plant community functions will improve the WATER QUALITY and DEGRADED PLANT CONDITION concerns listed above. The hydrologic and vegetative practices will address the SOIL QUALITY DEGRADATION and INADEQUATE HABITAT FOR FISH AND WILDLIFE concerns.

Feature Measure: Acres of wetland

Scenario Unit:: Acre

Scenario Typical Size: 60.0

Scenario Total Cost: \$80,620.87

Scenario Cost/Unit: \$1,343.68

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 200 HP	928	Track mounted Dozer with horsepower range of 160 to 250. Equipment and power unit costs. Labor not included.	Hour	\$198.02	36	\$7,128.72
Scraper, self propelled, 21 CY	1208	Self propelled earthmoving scraper with 21 CY capacity. Does not include labor.	Hour	\$383.83	113	\$43,372.79
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	30	\$12,456.30
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	30	\$12,450.00
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	149	\$4,216.70
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	2	\$996.36

Practice: 658 - Wetland Creation

Scenario #1 - Excavated

Scenario Description:

A wetland is created on a flat mineral upland at a location where surface runoff may be intercepted and ponded by excavation. Resource concerns are 22 - INDEQUATE HABITAT FOR FISH AND WILDLIFE - Habitat degradation.

Before Situation:

The site is in cropland on an upland, non floodplain site (interfluve).

After Situation:

An excavation with an average depth of 12" has created a shallow depression in a broad swale which intercepts surface runoff. The excavated material has been spread on adjacent areas. The INADEQUATE HABITAT FOR FISH AND WILDLIFE resource concern has been addressed with the provision of seasonal open water for terrestrial, aquatic, and waterfowl species.

Feature Measure: Acres of Wetland

Scenario Unit:: Acre

Scenario Typical Size: 5.0

Scenario Total Cost: \$19,917.76

Scenario Cost/Unit: \$3,983.55

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	8067	\$17,344.05
Foregone Income						
Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	2.5	\$1,038.03
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	2.5	\$1,037.50
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	1	\$498.18

Practice: 658 - Wetland Creation

Scenario #2 - Embankment

Scenario Description:

A wetland is created on a flat mineral upland at a location where surface runoff may be intercepted and ponded by excavation and with an embankment. Facilitating practices may include Structure for Water Control (587). Resource concerns are 22 - INDEQUATE HABITAT FOR FISH AND WILDLIFE - Habitat degradation.

Before Situation:

The site is in cropland on an upland, non floodplain site (interfluve).

After Situation:

An excavation/embankment with an average depth of 12" has created a shallow depression in a broad swale which intercepts surface runoff. The excavated material has been spread on adjacent areas and used to compact the embankment. The INADEQUATE HABITAT FOR FISH AND WILDLIFE resource concern has been addressed with the provision of seasonal open water for terrestrial, aquatic, and waterfowl species.

Feature Measure: <Unknown>

Scenario Unit:: Acre

Scenario Typical Size: 5.0

Scenario Total Cost: \$21,923.71

Scenario Cost/Unit: \$4,384.74

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	\$126.50	125	\$15,812.50
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	2.5	\$1,038.03
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	2.5	\$1,037.50
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	125	\$3,537.50
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	1	\$498.18

Practice: 659 - Wetland Enhancement

Scenario #2 - Riverine, Levee Removal, ditch plugs and foodplain features

Scenario Description:

A Riverine HGM tract on a large floodplain is to be enhanced. It has been converted to agricultural production by surface ditching and clearing of woody vegetation. The wetland extent is 60 acres. Resource Concerns are: 4-SOIL QUALITY DEGRADATION - Organic matter depletion, 11- WATER QUALITY DEGRADATION - Excess nutrients in surface and ground waters, 12 - WATER QUALITY DEGRADATION - Pesticides transported to surface and ground waters, 16 - WATER QUALITY DEGRADATION - Excessive sediment in surface waters, 18 - DEGRADED PLANT CONDITION - Undesirable plant productivity and health, 19 - DEGRADED PLANT CONDITION, Inadequate structure and composition, 22- INADEQUATE HABITAT FOR FISH AND WILDLIFE - Habitat degradation.

Before Situation:

A levee prevents floodwater from entering the tract. The original cover was forest. The site is drained by surface ditches which collect surface water and direct it to the river through a flap gate structure. The site has been completely cleared, and no suitable adjacent seedwall exists for natural regeneration of forest species. The lateral connectivity between the channel and floodplain has been altered by construction of levees along the reach.

After Situation:

The hydrology of the site is enhanced with the installation of ditch plugs, and the excavation of macrotopographic features with an average depth of 6" over 30% of the wetland area. Excavated spoil is placed adjacent to the features on the wetland and adjacent non-wetland area with a maximum depth of 24 inches. The levee has been breached at the upstream and downstream ends of the tract reach, restoring dynamic stream flooding. The breach length is 150 feet long at both locations. Both the wetland and non-wetland areas are planted with a Bottomland Hardwood species mix. The levee breaches are armored with rock riprap. Facilitating practices include Grade Stabilization Structure and Tree and Shrub Planting. Restoration of hydrology and plant community functions will improve the WATER QUALITY and DEGRADED PLANT CONDITION concerns listed above. The hydrologic and vegetative practices will address the SOIL QUALITY DEGRADATION and INADEQUATE HABITAT FOR FISH AND WILDLIFE concerns.

Feature Measure: Acres of Wetland

Scenario Unit:: Acre

Scenario Typical Size: 60.0

Scenario Total Cost: \$80,620.87

Scenario Cost/Unit: \$1,343.68

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 200 HP	928	Track mounted Dozer with horsepower range of 160 to 250. Equipment and power unit costs. Labor not included.	Hour	\$198.02	36	\$7,128.72
Scraper, self propelled, 21 CY	1208	Self propelled earthmoving scraper with 21 CY capacity. Does not include labor.	Hour	\$383.83	113	\$43,372.79
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	30	\$12,456.30
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	30	\$12,450.00
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	149	\$4,216.70
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	2	\$996.36



Practice: 666 - Forest Stand Improvement

Scenario #1 - Forest Stand Improvement, Light

Scenario Description:

All materials and labor required to manipulate species composition, stand structure and stocking on forestland. Light forest stand improvement will: Reduce basal area by 20 - 29 square feet per acre (or) Cut and/or kill 100 - 199 trees per acre (or) Release 10 - 20 crop trees per acre and/or kill any vines growing on crop trees by an approved method such as "cut stump" with herbicide to prevent resprouting. Use a current and approved Forest Management Plan for estimated basal area to be removed, number of trees needing to be cut and/or killed, crop trees needing to be released, and/or vines needing killed.

Before Situation:

Forest stand is slightly overstocked and/or composed of some undesirable species due to lack of forest management. This has negatively impacted forest health, productivity, and/or sustainability. Wildlife habitat, such as hard and soft mast production, browse, nesting cover, bedding areas, etc. is lacking.

After Situation:

After adjusting the stocking to an acceptable level, stand growth, condition, and overall quality is improved. In addition, wildlife habitat is improved with the resulting increase of sunlight reaching the forest floor.

Feature Measure: Area Treated

Scenario Unit:: Acre

Scenario Typical Size: 55.0

Scenario Total Cost: \$6,545.05

Scenario Cost/Unit: \$119.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	90	\$400.50
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	20	\$1,323.80
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	110	\$3,889.60
Materials						
Herbicide, Picloram	337	Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$16.93	55	\$931.15

Practice: 666 - Forest Stand Improvement

Scenario #2 - Forest Stand Improvement, Medium

Scenario Description:

All materials and labor required to manipulate species composition, stand structure and stocking on forestland. Medium forest stand improvement will: Reduce basal area by 30-40 square feet per acre (or) Cut and/or kill 200 - 400 trees per acre (or) Release 21 - 40 crop trees per acre and kill any vines growing on crop trees by an approved method such as "cut stump" with herbicide to prevent resprouting. Use a current and approved Forest Management Plan for estimated basal area to be removed, number of trees needing to be cut and/or killed, crop trees needing to be released, and/or vines needing killed.

Before Situation:

Forest stand is moderately overstocked and/or composed of an unacceptable level of undesirable species due to lack of forest management. This has negatively impacted forest health, productivity, and/or sustainability. Wildlife habitat, such as hard and soft mast production, browse, nesting cover, bedding areas, etc. is lacking.

After Situation:

After adjusting the stocking to an acceptable level, stand growth, condition, and overall quality is improved. In addition, wildlife habitat is improved with the resulting increase of sunlight reaching the forest floor.

Feature Measure: Area Treated

Scenario Unit:: Acre

Scenario Typical Size: 55.0

Scenario Total Cost: \$8,030.17

Scenario Cost/Unit: \$146.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	112	\$498.40
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	26	\$1,720.94
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	138	\$4,879.68
Materials						
Herbicide, Picloram	337	Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$16.93	55	\$931.15

Practice: 666 - Forest Stand Improvement

Scenario #3 - Forest Stand Improvement, Heavy

Scenario Description:

All materials and labor required to manipulate species composition, stand structure and stocking on forestland. Heavy forest stand improvement will: Reduce basal area by 41 or more square feet per acre (or) Cut and/or kill over 400 trees per acre (or) Release 41 or more crop trees per acre and kill any vines growing on crop trees by an approved method such as "cut stump" with herbicide to prevent resprouting. Use a current and approved Forest Management Plan for estimated basal area to be removed, number of trees needing to be cut and/or killed, crop trees needing to be released, and/or vines needing killed.

Before Situation:

Forest stand is heavily overstocked and/or composed of an unacceptable level of undesirable species due to lack of forest management. This has negatively impacted forest health, productivity, and/or sustainability. Wildlife habitat, such as hard and soft mast production, browse, nesting cover, bedding areas, etc. is lacking. Understory vegetation consists of mostly shade-tolerant species with little to no desirable regeneration present.

After Situation:

After adjusting the stocking to an acceptable level, stand growth, condition, and overall quality is improved. In addition, wildlife habitat is improved with the resulting increase of sunlight reaching the forest floor.

Feature Measure: Area Treated

Scenario Unit:: Acre

Scenario Typical Size: 55.0

Scenario Total Cost: \$10,156.30

Scenario Cost/Unit: \$184.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	145	\$645.25
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	34	\$2,250.46
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	179	\$6,329.44
Materials						
Herbicide, Picloram	337	Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$16.93	55	\$931.15

Practice: 666 - Forest Stand Improvement

Scenario #4 - Temporary Forest Openings, patch clearcuts

Scenario Description:

Creating 2 one acre patches in over-mature and/or degraded stands using hand tools such as chainsaws. Resource concerns include: Undesirable plant productivity and health, Inadequate structure and composition, and habitat degradation.

Before Situation:

The existing stand is overly mature and/or has been degraded in value by past harvesting practices. The level of acceptable growing stock is too low to justify managing this stand in its present condition. The present form, species composition and structure cannot meet the resource concerns and landowner objectives. Creating small openings by cutting all trees greater than 2" in diameter will foster the regeneration of high-value shade intolerant species. The work will be done with chainsaws.

After Situation:

A new, young stand of desirable species is established In addition, early successional wildlife habitat as well as forest type diversity are created.

Feature Measure: Area treated

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: \$422.88

Scenario Cost/Unit: \$211.44

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	16	\$71.20
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68

Practice: 670 - Lighting System Improvement

Scenario #1 - Lighting - Outdoor/High Bay Fixture Conversion

Scenario Description:

Installation of a lighting system consisting of an outdoor/high bay light such as, but not limited to, LED or pulse-start metal halide (PSMH) lamp with a matched ballast. Associated materials for installation of replacement fixtures are included. Appropriate disposal of existing lamps, ballasts and other materials is required. Payment includes lamp, fixtures and labor to install.

Before Situation:

Inefficient high-bay or exterior lighting (such as mercury vapor, T12 fluorescent, or similar) as evidenced by an on-farm energy audit.

After Situation:

High-efficiency lighting system which reduces energy use. The new lighting equipment will provide suitable light levels and reduce overall power requirements (KW) compared to the existing lighting system as evidenced by the energy audit. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612. Associated practices/activities: 122-AgEMP - HQ, 672 Building Envelope Improvement, and 374-Farmstead Energy Improvement.

Feature Measure: Each lamp replaced

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$433.78

Scenario Cost/Unit: \$433.78

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	3	\$106.08
Materials						
High Bay, LED,100 watt	2641	100 Watt, High Bay, Light Emitting Diode, typically 4,000K color temp and L70 lifespan. Includes materials only.	Each	\$327.70	1	\$327.70

Practice: 670 - Lighting System Improvement

Scenario #2 - Lighting - Indoor Bulb Replacement

Scenario Description:

Installation of dimmable LEDs or CFLs to replace incandescent lamps on a one-for-one basis. Light fixtures do not have to be replaced. LED requirements: minimum 6 Watt, 3700 Kelvin, dimmable, grow-out bulb; industrial grade; suitably protected from dirt accumulation. In high humidity environments or areas subject to wash down, gasketted or weatherproof housings are required to prevent corrosion and premature failure. Payment includes light bulb and labor to install.

Before Situation:

An inefficient lighting system such as one using incandescent lamps has been identified by an on-farm energy audit.

After Situation:

More efficient lighting is provided by Light-Emitting Diode (LED) lamps in order to reduce energy use as evidenced by the energy audit. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612. Associated practices/activities: 122-AgEMP - HQ, 672 Building Envelope Improvement, and 374-Farmstead Energy Improvement.

Feature Measure: Each lamp replaced

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$24.43

Scenario Cost/Unit: \$24.43

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	0.17	\$3.74
Materials						
Lighting, bulb, LED, 6 watt	1167	6 watt light emitting diode (LED), typically 3700 Kelvin, dimmable, grow-out bulb; industrial grade; suitably protected from dirt accumulation. Materials only.	Each	\$20.69	1	\$20.69

Practice: 670 - Lighting System Improvement

Scenario #3 - Lighting - Indoor Fixture Conversion

Scenario Description:

Installation of a lighting system consisting of a four-foot, three-lamp fixture with a single electronic ballast. The high-efficiency lighting system uses high-efficiency LED or T8 or T5 fluorescent lamps. Associated materials for installation of replacement fixtures are included. Appropriate disposal of existing lamps, ballasts and other materials is required. Payment includes lamps, ballast, fixtures and labor to install.

Before Situation:

Inefficient lighting (such as incandescent or T12 fluorescent tubes driven by magnetic ballasts) as evidenced by an on-farm energy audit.

After Situation:

High-efficiency lighting system which reduces energy use. The new lighting equipment will provide suitable light levels and reduce overall power requirements (kW) compared to the existing lighting system as evidenced by the energy audit. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612. Associated practices/activities: may include 122-AgEMP - HQ, 672 Building Envelope Improvement, and 374-Farmstead Energy Improvement.

Feature Measure: Each fixture replaced

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$381.50

Scenario Cost/Unit: \$381.50

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	1	\$35.36
Materials						
Lighting, Fixture, LED, 66 watt	2627	Fixture with 4 linear LED lamps (4 foot tall) rated at 1600 lumens and 16.5 watts each. Includes materials and shipping only.	Each	\$346.14	1	\$346.14

Practice: 670 - Lighting System Improvement

Scenario #4 - Lighting - Outdoor/High Bay Bulb Replacement

Scenario Description:

Installation of a lighting system consisting of an outdoor/high bay light such as, but not limited to, LED or pulse-start metal halide (PSMH) lamp. Light fixtures do not have to be replaced. Appropriate disposal of existing lamps, ballasts and other materials is required. Payment includes light bulb and labor to install.

Before Situation:

Inefficient high-bay or exterior lighting (such as mercury vapor, T12 fluorescent, or similar) as evidenced by an on-farm energy audit.

After Situation:

High-efficiency lighting system which reduces energy use. The new lighting equipment will provide suitable light levels and reduce overall power requirements (kW) compared to the existing lighting system as evidenced by the energy audit. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612. Associated practices/activities: may include 122-AgEMP - HQ, 672 Building Envelope Improvement, and 374-Farmstead Energy Improvement.

Feature Measure: Each fixture replaced

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$331.44

Scenario Cost/Unit: \$331.44

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	0.17	\$3.74
Materials						
High Bay, LED,100 watt	2641	100 Watt, High Bay, Light Emitting Diode, typically 4,000K color temp and L70 lifespan. Includes materials only.	Each	\$327.70	1	\$327.70



Practice: 672 - Building Envelope Improvement

Scenario #1 - Building Envelope - Attic Insulation

Scenario Description:

Install a minimum R-7 insulation in an existing attic or ceiling to reduce heat transfer. Increased insulation reduces seasonal heat loss and heat gain which reduces the respective need for heating and cooling equipment to operate. Payment includes materials, equipment and labor to install.

Before Situation:

An agriculture house with an inefficient building envelope with limited attic insulation.

After Situation:

A more effective and efficient building envelope can be created through addition of, or increased, attic insulation. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612. Associated practices/activities: 122-AgEMP - HQ, 670- Lighting System Improvement, and 374-Farmstead Energy Improvement.

Feature Measure: Area of Attic Insulated

Scenario Unit:: Square Foot

Scenario Typical Size: 20,000.0

Scenario Total Cost: \$16,400.00

Scenario Cost/Unit: \$0.82

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Insulation, Fiberglass or cellulose, R-15	1196	Fiberglass or cellulose insulation R-15, includes materials, equipment and labor to install.	Square Foot	\$0.82	20000	\$16,400.00

Practice: 672 - Building Envelope Improvement

Scenario #2 - Building Envelope - Wall Insulation

Scenario Description:

Enclose both sidewalls and endwalls from ceiling to floor in one of two manners: 1) metal exterior, 3.5" fiberglass batts (R-11), vapor barrier, & interior plywood or OSB sheathing, or 2) closed-cell polyurethane foam application (minimum 1" thickness (R-7) of 2.5 lbs/cu.ft. or higher density, (3.0 or higher density preferred) with a form of physical protective barrier on lower 2' (may be 6 lbs/cu.ft. or higher density 1/8" thick foam, or treated lumber). Payment includes materials, equipment and labor to install.

Before Situation:

An agriculture house with an inefficient building envelope with limited wall insulation.

After Situation:

A more effective and efficient building envelope can be created through addition of, or increased, insulation in a 40' x 400' poultry house. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612. Associated practices/activities: may include 122-AgEMP - HQ, 670-Lighting System Improvement, and 374-Farmstead Energy Improvement.

Feature Measure: Area of Wall Insulated

Scenario Unit:: Square Foot

Scenario Typical Size: 4,500.0

Scenario Total Cost: \$10,350.00

Scenario Cost/Unit: \$2.30

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Insulation, polyurethane, R-7, with sheathing skirt	1198	Closed-cell polyurethane foam insulation (minimum 1" thickness (R-7) with a protective sheeting barrier on lower 2 feet of wall height. Includes materials, equipment and labor to install.	Square Foot	\$2.30	4500	\$10,350.00

Practice: 672 - Building Envelope Improvement

Scenario #3 - Building Envelope - Sealant

Scenario Description:

Seal the gaps between walls, gables, ceiling, etc. in a poultry house or greenhouse. Payment includes materials, equipment and labor performed by a professional contractor.

Before Situation:

An agricultural facility with an inefficient building envelope with gaps between walls, ceiling, etc. for a total of 2400 linear feet.

After Situation:

A more effective and efficient building envelope can be created through interior sealing of the exterior walls at the footer plate, eaves, ridge cap, and gable ends. The sealant reduces seasonal heat loss and heat gain due to infiltration which reduces the respective need for heating and cooling equipment to operate. The unit basis of payment in this scenario is each house based on 60' x 500' poultry house with an assumed need of sealant to seal 2400 linear feet of gap. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612. Associated practices/activities: may include 122-AgEMP - HQ, 670-Lighting System Improvement, and 374-Farmstead Energy Improvement.

Feature Measure: Perimeter of heated structure

Scenario Unit:: Foot

Scenario Typical Size: 2,400.0

Scenario Total Cost: \$4,152.00

Scenario Cost/Unit: \$1.73

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Materials						
Sealant	1150	Greenhouse and building gap sealant. Performed by a professional contractor spraying the areas with an approved sealant for poultry production facilities. Includes materials, equipment and labor to install.	Foot	\$1.73	2400	\$4,152.00

Practice: 672 - Building Envelope Improvement

Scenario #4 - Building Envelope - Greenhouse Screens

Scenario Description:

Installation of a mechanical energy screen system associated with a greenhouse consisting of a drive motor, support cables, controls, and shade material, which may be woven, knitted, or non-woven strips of aluminum fiber, polyethylene, nylon or other synthetic material. The screen provides a means to better control solar heat gain and heat transfer during night or cold weather conditions to reduce energy use. Screens and similar devices may also be used to divide internal areas and allow for differentiated heating, ventilation, or cooling system operation to reduce energy use. Payment includes materials and labor to install.

Before Situation:

Heating and cooling of an existing greenhouse, or similar structure with conditioned spaces, is inefficient due to poorly regulated heat transfer. A need to regulate an entire space for uniform conditions when some portions have differing, intermittent requirements can also reduce efficiency.

After Situation:

The greenhouse is fitted with a mechanically controlled energy screen installed truss-to-truss or gutter-to-gutter, with side screens as necessary, reducing heat loss in the greenhouse. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612. Associated practices/activities: may include 122-AgEMP - HQ, 670- Lighting System Improvement, and 374-Farmstead Energy Improvement.

Feature Measure: Area of Screen

Scenario Unit:: Square Foot

Scenario Typical Size: 25,000.0

Scenario Total Cost: \$52,065.76

Scenario Cost/Unit: \$2.08

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	16	\$565.76
Materials						
Thermal blanket 10,001 - 50,000 square foot	1148	Thermal blanket greenhouse screens: mechanical energy screen system consists of a drive motor, support cables, controls, and shade material, which may be woven, knitted, or non-woven. Size Range is 10,001 to 50,000 square feet. Materials only.	Square Foot	\$2.06	25000	\$51,500.00

Practice: 672 - Building Envelope Improvement

Scenario #5 - Building Envelope - Greenhouse Unglazed Wall Insulation

Scenario Description:

Installation of insulation in greenhouse to address energy loss. The insulation can be either of the cellulose or bubble type (or equivalent). The increased insulation reduces seasonal heat loss and heat gain which reduces the respective need for heating and cooling equipment to operate. Payment includes materials and labor to install.

Before Situation:

Green house with standard glazing, plastic or polycarbonate walls and no insulation. Heating and cooling of an existing greenhouse is inefficient due to excessive heat loss.

After Situation:

The greenhouse is fitted with insulation installed truss-to-truss or gutter-to-gutter and/or non glazed endwalls and/or sidewalls, reducing heat loss and gain in the greenhouse. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612. Associated practices/activities: may include 122-AgEMP - HQ, 670- Lighting System Improvement, and 374-Farmstead Energy Improvement.

Feature Measure: Square Feet of insulation

Scenario Unit:: Square Foot

Scenario Typical Size: 25,000.0

Scenario Total Cost: \$8,065.76

Scenario Cost/Unit: \$0.32

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	16	\$565.76
Materials						
Insulation, Greenhouse, Reflective Bubble	2410	Double bubble reflective insulation with aluminum foil on both sides. Includes materials and shipping only.	Square Foot	\$0.30	25000	\$7,500.00

Practice: 672 - Building Envelope Improvement

Scenario #6 - Building Envelope - Insulated Door Upgrade

Scenario Description:

Replace an existing door with an insulated door, such as but not limited to a steel roll up door in a poultry building. Increased insulation reduces seasonal heat loss and heat gain which reduces the respective need for heating and cooling equipment to operate. Payment includes materials and labor to install.

Before Situation:

Agriculture building's existing door is inefficient

After Situation:

A 20 gauge 12' x 12' rolling service insulated steel door is installed as a replacement for an existing less efficient door on a poultry building. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612. Associated practices/activities may include: 122-AgEMP - HQ, 670-Lighting System Improvement, and 374-Farmstead Energy Improvement.

Feature Measure: Square foot

Scenario Unit:: Square Foot

Scenario Typical Size: 144.0

Scenario Total Cost: \$1,548.64

Scenario Cost/Unit: \$10.75

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	8	\$282.88
Materials						
Door, Insulated, Roll-up	2392	Rolling service insulated steel door, 20 gauge. Includes hardware required to install. Used to replace non insulated door in buildings. Materials only.	Square Foot	\$8.79	144	\$1,265.76

Practice: 672 - Building Envelope Improvement

Scenario #7 - Building Envelope - Insulated Curtain Upgrade

Scenario Description:

Replacement of an existing non-insulated curtain with a seven layer insulated curtain with an R- value of 3 for a livestock building. The curtain's two outer layers are vinyl and polyethylene and the five inner layers are composed of insulating materials with air trapping fibers and a vapor barrier. Payment includes curtain and labor to install. Payment does not includes mounting accessories because the scenario assumes the curtain is replacing a non-insulated curtain.

Before Situation:

Existing livestock curtain is inefficient.

After Situation:

A 7 layer insulated curtain is installed as a replacement for an existing less efficient curtain on a livestock building. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612. Associated practices/activities may include: 122-AgEMP - HQ, 670- Lighting System Improvement, and 374-Farmstead Energy Improvement.

Feature Measure: Square Foot

Scenario Unit:: Square Foot

Scenario Typical Size: 1,080.0

Scenario Total Cost: \$2,887.76

Scenario Cost/Unit: \$2.67

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	16	\$565.76
Materials						
Curtain , 7-Layer, R3 Insulated	2427	Seven layer insulated curtain with an R-value of 3 for a livestock building. Typical curtain size is 4' x 270'. The curtain's two outer layers are vinyl and polyethylene and the five inner layers are composed of insulating materials with air trapping fi	Square Foot	\$2.15	1080	\$2,322.00

Practice: 672 - Building Envelope Improvement

Scenario #8 - Building Envelope - Curtain Wall Conversion

Scenario Description:

Converting part or all of a curtain wall to solid insulated wall by installation of an insulated metal cover in a livestock building. Payment includes materials and labor for the installation of a weather proof exterior such as, but not limited to, corrugated steel, and insulation such as, but not limited to polyurethane R-7. Payment does not include upgrade to ventilation.

Before Situation:

Existing livestock curtain is inefficient.

After Situation:

An insulated metal wall is installed as a replacement for an existing less efficient curtain on a livestock building. Conversion is for an building that requires 3040 sq ft of wall to replace the curtains. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612. Associated practices/activities may include: 122-AgEMP - HQ, 670- Lighting System Improvement, and 374-Farmstead Energy Improvement.

Feature Measure: Square Foot

Scenario Unit:: Square Foot

Scenario Typical Size: 3,040.0

Scenario Total Cost: \$11,816.20

Scenario Cost/Unit: \$3.89

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	30	\$659.40
Materials						
Corrugated Steel, 28 gage	223	Corrugated or ribbed, galvanized, 28 gauge, includes fasteners, materials only.	Square Foot	\$1.37	3040	\$4,164.80
Insulation, polyurethane, R-7, with sheathing skirt	1198	Closed-cell polyurethane foam insulation (minimum 1" thickness (R-7) with a protective sheeting barrier on lower 2 feet of wall height. Includes materials, equipment and labor to install.	Square Foot	\$2.30	3040	\$6,992.00



Practice: B000BFF1 - Buffer Bundle#1

Scenario #1 - Buffer Bundle#1

Scenario Description:

Addresses water quality degradation, degraded plant condition, fish/wildlife inadequate habitat, and/or air quality impacts.

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 3.0

Scenario Total Cost: \$2,615.21

Scenario Cost/Unit: \$871.74

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	1	\$11.37
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	\$7.85	1	\$7.85
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	10	\$120.40
Foregone Income						
Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.41	\$170.24
Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.41	\$170.24
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.36	\$149.40
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.36	\$149.40
Fl, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.23	\$45.93
Fl, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.23	\$45.93
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	1	\$17.48
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$25.63	1	\$25.63

Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shi	Acre	\$1.28	1	\$1.28
Shrub, seedling or transplant, bare root, 18"-36"	1507	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.57	341	\$194.37
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.59	340	\$200.60
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	\$58.50	1	\$58.50
Untreated Conventional Seed, Pollinator Mix, Native Perennial Grasses and Forbs	2346	Untreated conventional native perennial grass and legume pollinator mix. May contain seed that are not available as certified organic. Includes material and shipping only.	Acre	\$254.41	1	\$254.41
<b>Mobilization</b>						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: B000BFF2 - Buffer Bundle#2

Scenario #1 - Buffer Bundle#2

Scenario Description:

Addresses water quality degradation, degraded plant condition, fish/wildlife inadequate habitat, and/or air quality impacts.

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 3.0

Scenario Total Cost: \$2,615.21

Scenario Cost/Unit: \$871.74

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	1	\$11.37
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	\$7.85	1	\$7.85
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	10	\$120.40
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.41	\$170.24
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.41	\$170.24
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.36	\$149.40
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.36	\$149.40
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.23	\$45.93
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.23	\$45.93
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	1	\$17.48
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$25.63	1	\$25.63

Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shi	Acre	\$1.28	1	\$1.28
Shrub, seedling or transplant, bare root, 18"-36"	1507	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.57	341	\$194.37
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.59	340	\$200.60
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	\$58.50	1	\$58.50
Untreated Conventional Seed, Pollinator Mix, Native Perennial Grasses and Forbs	2346	Untreated conventional native perennial grass and legume pollinator mix. May contain seed that are not available as certified organic. Includes material and shipping only.	Acre	\$254.41	1	\$254.41
<b>Mobilization</b>						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

**Practice:** B000CPL1 - Crop Bundle#1 - Precision Ag, No till

**Scenario #1** - Crop Bundle#1 - Precision Ag, No till

**Scenario Description:**

Addresses water quality degradation, air quality, and fish/wildlife inadequate habitat plus an option on soil erosion or soil quality degradation

**Before Situation:**

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 100.0

**Scenario Total Cost:** \$3,591.95

**Scenario Cost/Unit:** \$35.92

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Chemical, precision application	949	Chemical application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	\$10.05	100	\$1,005.00
Fertilizer, precision application	952	Fertilizer application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	\$10.88	100	\$1,088.00
<b>Foregone Income</b>						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.51	\$211.76
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.45	\$186.75
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.29	\$57.91
<b>Labor</b>						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	8	\$746.00
<b>Materials</b>						
Test, Soil Test, Precision, Grid or Zone DELETION SCHEDULED for PS FY 2018 , USE CID 299	300	Includes materials, shipping, labor, and equipment costs. DELETION SCHEDULED for PS FY 2018 , USE CID 299	Each	\$10.31	25	\$257.75

Practice: B000CPL2 - Crop Bundle#2 - Precision Ag, Reduced till

Scenario #1 - Crop Bundle#2 - Precision Ag, RT

Scenario Description:

Addresses water quality degradation, air quality, and fish/wildlife inadequate habitat plus an option on soil erosion or soil quality degradation

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$3,591.95

Scenario Cost/Unit: \$35.92

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, precision application	949	Chemical application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	\$10.05	100	\$1,005.00
Fertilizer, precision application	952	Fertilizer application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	\$10.88	100	\$1,088.00
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.51	\$211.76
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.45	\$186.75
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.29	\$57.91
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	8	\$746.00
Materials						
Test, Soil Test, Precision, Grid or Zone DELETION SCHEDULED for PS FY 2018 , USE CID 299	300	Includes materials, shipping, labor, and equipment costs. DELETION SCHEDULED for PS FY 2018 , USE CID 299	Each	\$10.31	25	\$257.75

Practice: B000CPL3 - Crop Bundle#3 - Soil health rotation, No till

Scenario #1 - Crop Bundle#3 - Soil health rotation, NT

Scenario Description:

Addresses soil quality degradation, insufficient water, water quality degradation, and fish/wildlife inadequate habitat

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$3,888.13

Scenario Cost/Unit: \$38.88

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, precision application	949	Chemical application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	\$10.05	100	\$1,005.00
Fertilizer, precision application	952	Fertilizer application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	\$10.88	100	\$1,088.00
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	13	\$1,212.25
Materials						
Test, Soil Test, Precision, Grid or Zone DELETION SCHEDULED for PS FY 2018 , USE CID 299	300	Includes materials, shipping, labor, and equipment costs. DELETION SCHEDULED for PS FY 2018 , USE CID 299	Each	\$10.31	25	\$257.75
Untreated Conventional Seed, Pollinator Mix, Native Perennial Grasses and Forbs	2346	Untreated conventional native perennial grass and legume pollinator mix. May contain seed that are not available as certified organic. Includes material and shipping only.	Acre	\$254.41	1	\$254.41

Practice: B000CPL4 - Crop Bundle#4 - Soil health rotation, Reduced till

Scenario #1 - Crop Bundle#4 - SH rotation, RT

Scenario Description:

Addresses soil quality degradation, insufficient water, water quality degradation, and fish/wildlife inadequate habitat

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$3,888.13

Scenario Cost/Unit: \$38.88

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, precision application	949	Chemical application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	\$10.05	100	\$1,005.00
Fertilizer, precision application	952	Fertilizer application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	\$10.88	100	\$1,088.00
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	13	\$1,212.25
Materials						
Test, Soil Test, Precision, Grid or Zone DELETION SCHEDULED for PS FY 2018 , USE CID 299	300	Includes materials, shipping, labor, and equipment costs. DELETION SCHEDULED for PS FY 2018 , USE CID 299	Each	\$10.31	25	\$257.75
Untreated Conventional Seed, Pollinator Mix, Native Perennial Grasses and Forbs	2346	Untreated conventional native perennial grass and legume pollinator mix. May contain seed that are not available as certified organic. Includes material and shipping only.	Acre	\$254.41	1	\$254.41



Practice: B000CPL5 - Crop Bundle#5 - Soil Health Assessment, No till

Scenario #1 - Crop Bundle#5 - SH Assessment, NT

Scenario Description:

Addresses soil quality degradation, insufficient water, water quality degradation, and fish/wildlife inadequate habitat

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$4,318.48

Scenario Cost/Unit: \$43.18

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, precision application	949	Chemical application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	\$10.05	100	\$1,005.00
Fertilizer, precision application	952	Fertilizer application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	\$10.88	100	\$1,088.00
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	16	\$1,492.00
Materials						
Test, Soil Test, Standard	299	Includes materials, shipping, labor, and equipment costs.	Each	\$10.04	15	\$150.60
Test, Soil Test, Precision, Grid or Zone DELETION SCHEDULED for PS FY 2018 , USE CID 299	300	Includes materials, shipping, labor, and equipment costs. DELETION SCHEDULED for PS FY 2018 , USE CID 299	Each	\$10.31	25	\$257.75
Untreated Conventional Seed, Pollinator Mix, Native Perennial Grasses and Forbs	2346	Untreated conventional native perennial grass and legume pollinator mix. May contain seed that are not available as certified organic. Includes material and shipping only.	Acre	\$254.41	1	\$254.41

**Practice:** B000CPL6 - Crop Bundle#6 - Soil Health Assessment, Reduced till

**Scenario #1** - Crop Bundle#6 - SH Assessment, RT

**Scenario Description:**

Addresses soil quality degradation, insufficient water, water quality degradation, and fish/wildlife inadequate habitat

**Before Situation:**

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 100.0

**Scenario Total Cost:** \$4,318.48

**Scenario Cost/Unit:** \$43.18

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Chemical, precision application	949	Chemical application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	\$10.05	100	\$1,005.00
Fertilizer, precision application	952	Fertilizer application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	\$10.88	100	\$1,088.00
<b>Labor</b>						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	16	\$1,492.00
<b>Materials</b>						
Test, Soil Test, Standard	299	Includes materials, shipping, labor, and equipment costs.	Each	\$10.04	15	\$150.60
Test, Soil Test, Precision, Grid or Zone DELETION SCHEDULED for PS FY 2018 , USE CID 299	300	Includes materials, shipping, labor, and equipment costs. DELETION SCHEDULED for PS FY 2018 , USE CID 299	Each	\$10.31	25	\$257.75
Untreated Conventional Seed, Pollinator Mix, Native Perennial Grasses and Forbs	2346	Untreated conventional native perennial grass and legume pollinator mix. May contain seed that are not available as certified organic. Includes material and shipping only.	Acre	\$254.41	1	\$254.41

Practice: B000FST1 - Forest Bundle#1

Scenario #1 - Forest Bundle#1

Scenario Description:

Addresses forest management on sites that are not adapted to natural fire disturbances. Addresses resource concerns air quality impacts, degraded plant condition and fish/wildlife inadequate habitat.

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 111.0

Scenario Total Cost: \$8,605.36

Scenario Cost/Unit: \$77.53

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	45	\$200.25
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	15	\$333.30
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	41	\$2,713.79
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	11	\$132.44

Foregone Income

Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.41	\$170.24
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.36	\$149.40
Fl, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.23	\$45.93

Labor

Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	7	\$247.52
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	49	\$1,077.02
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	12	\$1,119.00
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	17	\$1,222.13

Materials

Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	\$6.96	20	\$139.20
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	1	\$17.48
Herbicide, Picloram	337	Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$16.93	21	\$355.53

Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$25.63	1	\$25.63
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shi	Acre	\$1.28	1	\$1.28
Shrub, seedling or transplant, bare root, 18"-36"	1507	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.57	605	\$344.85
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.59	218	\$128.62

**Mobilization**

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50
-------------------------------	------	--	------	----------	---	----------

## Missouri

### Scenario #1 - Longleaf Pine Bundle#1

Improves conifer forest health through prescribed burning and grazing management. Addresses water quality degradation, degraded plant condition, and fish/wildlife inadequate habitat.

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Scenario Unit:: Acre

**Scenario Total Cost:** \$10,304.66

Cost Details:

### Acquisition of Technical Knowledge

## Equipment Installation

Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	\$7.46	5	\$37.30
-------------------------------	-----	---	------	--------	---	---------

Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	5	\$111.10
---------------	-----	---	------	---------	---	----------

Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
---------------	-----	---	------	---------	---	---------

Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
------------------------------	-----	---	------	--------	---	--------

Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and	Hour	\$25.27	5	\$126.35
------------------------------	-----	---	------	---------	---	----------

Tractor, agricultural, 60 HP	965	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	4	\$101.08
------------------------------	-----	---	------	---------	---	----------

All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	2	\$57.68
---------------------------	-----	---	------	---------	---	---------

dibble bars, planting shovel, hoe-dad. Equipment only. Labor not

gallon capacity includes tank with pump, hose and sprayer. Does not include the pickup truck. Equipment only.

Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.82	\$340.47
------------------	------	------------------------------	------	----------	------	----------

Fl. Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.46	\$91.86
-------------------	------	-------------------------------	------	----------	------	---------

Unit Month	2019	2018	2017	2016	2015	2014	2013	2012	2011	2010	2009	2008	2007	2006	2005	2004	2003	2002	2001	2000	1999	1998	1997	1996	1995	1994	1993	1992	1991	1990	1989	1988	1987	1986	1985	1984	1983	1982	1981	1980	1979	1978	1977	1976	1975	1974	1973	1972	1971	1970	1969	1968	1967	1966	1965	1964	1963	1962	1961	1960	1959	1958	1957	1956	1955	1954	1953	1952	1951	1950	1949	1948	1947	1946	1945	1944	1943	1942	1941	1940	1939	1938	1937	1936	1935	1934	1933	1932	1931	1930	1929	1928	1927	1926	1925	1924	1923	1922	1921	1920	1919	1918	1917	1916	1915	1914	1913	1912	1911	1910	1909	1908	1907	1906	1905	1904	1903	1902	1901	1900	1899	1898	1897	1896	1895	1894	1893	1892	1891	1890	1889	1888	1887	1886	1885	1884	1883	1882	1881	1880	1879	1878	1877	1876	1875	1874	1873	1872	1871	1870	1869	1868	1867	1866	1865	1864	1863	1862	1861	1860	1859	1858	1857	1856	1855	1854	1853	1852	1851	1850	1849	1848	1847	1846	1845	1844	1843	1842	1841	1840	1839	1838	1837	1836	1835	1834	1833	1832	1831	1830	1829	1828	1827	1826	1825	1824	1823	1822	1821	1820	1819	1818	1817	1816	1815	1814	1813	1812	1811	1810	1809	1808	1807	1806	1805	1804	1803	1802	1801	1800	1799	1798	1797	1796	1795	1794	1793	1792	1791	1790	1789	1788	1787	1786	1785	1784	1783	1782	1781	1780	1779	1778	1777	1776	1775	1774	1773	1772	1771	1770	1769	1768	1767	1766	1765	1764	1763	1762	1761	1760	1759	1758	1757	1756	1755	1754	1753	1752	1751	1750	1749	1748	1747	1746	1745	1744	1743	1742	1741	1740	1739	1738	1737	1736	1735	1734	1733	1732	1731	1730	1729	1728	1727	1726	1725	1724	1723	1722	1721	1720	1719	1718	1717	1716	1715	1714	1713	1712	1711	1710	1709	1708	1707	1706	1705	1704	1703	1702	1701	1700	1699	1698	1697	1696	1695	1694	1693	1692	1691	1690	1689	1688	1687	1686	1685	1684	1683	1682	1681	1680	1679	1678	1677	1676	1675	1674	1673	1672	1671	1670	1669	1668	1667	1666	1665	1664	1663	1662	1661	1660	1659	1658	1657	1656	1655	1654	1653	1652	1651	1650	1649	1648	1647	1646	1645	1644	1643	1642	1641	1640	1639	1638	1637	1636	1635	1634	1633	1632	1631	1630	1629	1628	1627	1626	1625	1624	1623	1622	1621	1620	1619	1618	1617	1616	1615	1614	1613	1612
------------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------

Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	7	\$247.52
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	16	\$565.76
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	32	\$1,131.52
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	33	\$725.34
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	4	\$88.36
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	5	\$110.45
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	4	\$155.12
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	8	\$310.24
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75
<b>Materials</b>						
Wire, Barbed, Galvanized, 12.5 Gauge, 1,320' roll	1	Galvanized 12.5 gauge, 1,320' roll. Includes materials and shipping only.	Each	\$71.19	4	\$284.76
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	\$6.26	20	\$125.20
Post, Wood, CCA treated, 6" x 8'	12	Wood Post, End 6" X 8', CCA Treated. Includes materials and shipping only.	Each	\$15.10	8	\$120.80
Post, Steel T, 1.33 lbs, 6'	15	Steel Post, Studded 6' - 1.33 lb. Includes materials and shipping only.	Each	\$6.68	90	\$601.20
Fence, Wire Assembly, Barbed Wire	30	Brace pins, battens, clips, staples. Includes materials and shipping only.	Foot	\$0.17	1320	\$224.40
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	1	\$17.48
Herbicide, Picloram	337	Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$16.93	1	\$16.93
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$25.63	1	\$25.63
Gate, Pipe, 12'	1057	6 rail tube gate, 16 gauge. Includes materials and shipping only.	Each	\$166.29	2	\$332.58
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shi	Acre	\$1.28	1	\$1.28
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.59	872	\$514.48
Tree shelter, solid tube type, 4" x 48"	1566	4" x 48" tree tube for protection from animal damage. Materials only.	Each	\$4.14	100	\$414.00
Stakes, wood, 1" x 1" x 48"	1578	1" x 1" x 48" wood stakes to fasten items in place. Includes materials only.	Each	\$2.04	100	\$204.00

Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	\$4.32	5	\$21.60
<b>Mobilization</b>						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: B000LLP2 - Longleaf Pine Bundle#2

Scenario #1 - Longleaf Pine Bundle#2

Scenario Description:

Improves conifer forest health through prescribed burning and forest stand management. Addresses air quality impacts, degraded plant condition, and fish/wildlife inadequate habitat.

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 125.0

Scenario Total Cost: \$10,776.50

Scenario Cost/Unit: \$86.21

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	150	\$667.50
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	7	\$31.15
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	15	\$333.30
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	1	\$22.22
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	3	\$198.57
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	2	\$57.68
Water tank, portable	1602	Portable water tank transported in a pick up truck. Typically with 200 gallon capacity includes tank with pump, hose and sprayer. Does not include the pickup truck. Equipment only.	Hour	\$2.47	2	\$4.94
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	16	\$565.76
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	7	\$247.52
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	150	\$3,297.00
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	30	\$2,797.50
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75



CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	17	\$1,222.13
<b>Materials</b>						
Herbicide, Picloram	337	Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$16.93	1	\$16.93
Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	\$4.32	5	\$21.60
Untreated Conventional Seed, Pollinator Mix, Native Perennial Grasses and Forbs	2346	Untreated conventional native perennial grass and legume pollinator mix. May contain seed that are not available as certified organic. Includes material and shipping only.	Acre	\$254.41	1	\$254.41
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: B000LLP3 - Longleaf Pine Bundle#3

Scenario #1 - Longleaf Pine Bundle#3

Scenario Description:

Improves forest health and wildlife habitat through forest stand management. Addresses air quality impacts, degraded plant condition, and fish/wildlife inadequate habitat.

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 125.0

Scenario Total Cost: \$13,794.39

Scenario Cost/Unit: \$110.36

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	7	\$31.15
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	150	\$667.50
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	1	\$22.22
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	72	\$1,599.84
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	15	\$333.30
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	3	\$198.57
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	2	\$57.68
Trailer, enclosed, small	1503	Small enclosed trailer (typically less than 30' in length) pulled by a pickup to transport materials and equipment. Truck not included.	Hour	\$7.12	72	\$512.64
Water tank, portable	1602	Portable water tank transported in a pick up truck. Typically with 200 gallon capacity includes tank with pump, hose and sprayer. Does not include the pickup truck. Equipment only.	Hour	\$2.47	2	\$4.94
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	7	\$247.52
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	16	\$565.76
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	150	\$3,297.00
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	48	\$1,055.04
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	30	\$2,797.50

Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	17	\$1,222.13
<b>Materials</b>						
Herbicide, Picloram	337	Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$16.93	1	\$16.93
Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	\$4.32	5	\$21.60
<b>Mobilization</b>						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: B000MRB1 - MRBI Bundle#1 - Irrigated Cropland

Scenario #1 - MRBI Bundle#1 - Irrigated Cropland

Scenario Description:

Addresses soil erosion, insufficient water, and water quality degradation

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$5,909.99

Scenario Cost/Unit: \$59.10

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	1	\$35.36
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	20	\$439.60
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	4	\$373.00
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will incl	Each	\$460.51	1	\$460.51
Switches and Controls, temp sensors	1192	Temperature and soil moisture sensors installed as part of an electronic monitoring (with or without wireless telecommunications) commonly used to control pumps and irrigation systems	Each	\$655.75	1	\$655.75
Data Logger with Telemetry System	1454	Data Logger W/Graphic Output for water management and telemetry - data communication device with power supply in a weather proof enclosure. Equipment only.	Each	\$1,679.44	1	\$1,679.44
Soil Moisture Meter	1455	Soil Moisture Sensor Reader. Equipment only.	Each	\$285.50	1	\$285.50
Soil Moisture Sensor	1456	Soil moisture resistance sensor W/10' cables. Equipment only.	Each	\$36.74	2	\$73.48
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	\$38.26	20	\$765.20
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance	Each	\$1,070.10	1	\$1,070.10
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: B000MRB2 - MRBI Bundle#2 - Non-Irrigated Cropland #1

Scenario #1 - MRBI Bundle#2 - Non-Irrigated Crop#1

Scenario Description:

Addresses soil erosion, soil quality degradation, and water quality degradation

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$942.00

Scenario Cost/Unit: \$9.42

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	5	\$176.80
Materials						
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	\$38.26	20	\$765.20

Practice: B000MRB3 - MRBI Bundle#3 - Non-Irrigated Cropland #2

Scenario #1 - MRBI Bundle#3 - Non-Irrigated Crop#2

Scenario Description:

Addresses soil erosion, soil quality degradation, and water quality degradation

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,266.81

Scenario Cost/Unit: \$12.67

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	1	\$35.36
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	5	\$466.25
Materials						
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	\$38.26	20	\$765.20

Practice: B000MRB4 - MRBI Bundle#4 - Cropland with Water Bodies, No till

Scenario #1 - MRBI Bundle#4 - Crop w/ Water Bodies, NT

Scenario Description:

Addresses soil erosion, soil quality degradation, and water quality degradation

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$2,911.61

Scenario Cost/Unit: \$29.12

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	10	\$353.60
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	1	\$35.36
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	6	\$559.50
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75
Materials						
Nitrogen-Urease inhibitor	260	Nitrogen-Urease inhibitor	Acre	\$8.55	100	\$855.00
Test, Soil Nitrogen Testing	311	Pre-Side Dress/Deep Soil Testing. Includes materials and shipping only.	Each	\$12.64	5	\$63.20
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	\$38.26	20	\$765.20

Practice: B000MRB5 - MRBI Bundle#5 - Cropland with Water Bodies, Reduced till

Scenario #1 - MRBI Bundle#5 - Crop w/ Water Bodies, RT

Scenario Description:

Addresses soil erosion, soil quality degradation, and water quality degradation

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$2,680.05

Scenario Cost/Unit: \$26.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	10	\$353.60
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	5	\$176.80
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75
Materials						
Nitrogen-Urease inhibitor	260	Nitrogen-Urease inhibitor	Acre	\$8.55	100	\$855.00
Test, Soil Nitrogen Testing	311	Pre-Side Dress/Deep Soil Testing. Includes materials and shipping only.	Each	\$12.64	5	\$63.20
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	\$38.26	20	\$765.20



Practice: B000MRB6 - MRBI Bundle#6 - Pastureland

Scenario #1 - MRBI Bundle#6 - Pastureland

Scenario Description:

Addresses soil quality degradation, water quality degradation, and fish/wildlife inadequate habitat plus an option on soil erosion

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 101.0

Scenario Total Cost: \$4,435.59

Scenario Cost/Unit: \$43.92

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	\$7.46	5	\$37.30
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	5	\$111.10
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	5	\$126.35
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	25	\$416.25
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	33	\$725.34
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	5	\$110.45
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Wire, Barbed, Galvanized, 12.5 Gauge, 1,320' roll	1	Galvanized 12.5 gauge, 1,320' roll. Includes materials and shipping only.	Each	\$71.19	4	\$284.76
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	\$6.26	20	\$125.20
Post, Wood, CCA treated, 6" x 8'	12	Wood Post, End 6" X 8', CCA Treated. Includes materials and shipping only.	Each	\$15.10	8	\$120.80
Post, Steel T, 1.33 lbs, 6'	15	Steel Post, Studded 6' - 1.33 lb. Includes materials and shipping only.	Each	\$6.68	90	\$601.20
Fence, Wire Assembly, Barbed Wire	30	Brace pins, battens, clips, staples. Includes materials and shipping only.	Foot	\$0.17	1320	\$224.40
Gate, Pipe, 12'	1057	6 rail tube gate, 16 gauge. Includes materials and shipping only.	Each	\$166.29	2	\$332.58
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2317	Cool season grass and legume mix. Includes material and shipping only.	Acre	\$48.34	20	\$966.80
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: B000MRB7 - MRBI Bundle#7 - Rangeland

Scenario #1 - MRBI Bundle#7 - Rangeland

Scenario Description:

Addresses soil erosion, water quality degradation, and fish/wildlife inadequate habitat

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1,001.0

Scenario Total Cost: \$5,149.04

Scenario Cost/Unit: \$5.14

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Equipment Installation						
Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	\$7.46	5	\$37.30
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	4	\$88.88
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	5	\$111.10
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	5	\$126.35
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	12	\$346.08
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	36	\$599.40
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	33	\$725.34
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	17	\$373.66
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	5	\$110.45
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Wire, Barbed, Galvanized, 12.5 Gauge, 1,320' roll	1	Galvanized 12.5 gauge, 1,320' roll. Includes materials and shipping only.	Each	\$71.19	4	\$284.76
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	\$47.61	1	\$47.61
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	\$6.26	20	\$125.20
Post, Wood, CCA treated, 6" x 8'	12	Wood Post, End 6" X 8', CCA Treated. Includes materials and shipping only.	Each	\$15.10	8	\$120.80
Post, Steel T, 1.33 lbs, 6'	15	Steel Post, Studded 6' - 1.33 lb. Includes materials and shipping only.	Each	\$6.68	90	\$601.20
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43
Fence, Wire Assembly, Barbed Wire	30	Brace pins, battens, clips, staples. Includes materials and shipping only.	Foot	\$0.17	1320	\$224.40
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	\$257.52	1	\$257.52

Gate, Pipe, 12'	1057	6 rail tube gate, 16 gauge. Includes materials and shipping only.	Each	\$166.29	2	\$332.58
<b>Mobilization</b>						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: B000OGL1 - Ogallala Bundle#1

Scenario #1 - Ogallala Bundle#1

**Scenario Description:**

Addresses insufficient water, water quality degradation, and inefficient energy use plus an option on soil quality degradation

**Before Situation:**

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$8,887.28

Scenario Cost/Unit: \$88.87

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	20	\$439.60
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	4	\$373.00
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	35	\$3,107.65
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	10	\$318.40
<b>Materials</b>						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will incl	Each	\$460.51	1	\$460.51
Switches and Controls, temp sensors	1192	Temperature and soil moisture sensors installed as part of an electronic monitoring (with or without wireless telecommunications) commonly used to control pumps and irrigation systems	Each	\$655.75	1	\$655.75
Data Logger with Telemetry System	1454	Data Logger W/Graphic Output for water management and telemetry - data communication device with power supply in a weather proof enclosure. Equipment only.	Each	\$1,679.44	1	\$1,679.44
Soil Moisture Meter	1455	Soil Moisture Sensor Reader. Equipment only.	Each	\$285.50	1	\$285.50
Soil Moisture Sensor	1456	Soil moisture resistance sensor W/10' cables. Equipment only.	Each	\$36.74	2	\$73.48
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance	Each	\$1,070.10	1	\$1,070.10
<b>Mobilization</b>						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: B000OGL2 - Ogallala Bundle#2

Scenario #1 - Ogallala Bundle#2

**Scenario Description:**

Addresses insufficient water, water quality degradation, and inefficient energy use plus an option on soil quality degradation

**Before Situation:**

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 80.0

Scenario Total Cost: \$8,887.28

Scenario Cost/Unit: \$111.09

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	20	\$439.60
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	4	\$373.00
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	35	\$3,107.65
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	10	\$318.40
<b>Materials</b>						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will incl	Each	\$460.51	1	\$460.51
Switches and Controls, temp sensors	1192	Temperature and soil moisture sensors installed as part of an electronic monitoring (with or without wireless telecommunications) commonly used to control pumps and irrigation systems	Each	\$655.75	1	\$655.75
Data Logger with Telemetry System	1454	Data Logger W/Graphic Output for water management and telemetry - data communication device with power supply in a weather proof enclosure. Equipment only.	Each	\$1,679.44	1	\$1,679.44
Soil Moisture Meter	1455	Soil Moisture Sensor Reader. Equipment only.	Each	\$285.50	1	\$285.50
Soil Moisture Sensor	1456	Soil moisture resistance sensor W/10' cables. Equipment only.	Each	\$36.74	2	\$73.48
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance	Each	\$1,070.10	1	\$1,070.10
<b>Mobilization</b>						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

**Practice:** B000PST1 - Pasture Bundle#1 - Organic

**Scenario #1** - Pasture Bundle#1 - Organic

**Scenario Description:**

Addresses water quality degradation, degraded plant condition, and fish/wildlife inadequate habitat

**Before Situation:**

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 111.0

**Scenario Total Cost:** \$9,665.37

**Scenario Cost/Unit:** \$87.08

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

**Equipment Installation**

Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	\$7.46	5	\$37.30
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	5	\$111.10
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	5	\$126.35

**Foregone Income**

FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	30	\$499.50
------------------	------	---------------------------------	-------------------	---------	----	----------

**Labor**

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	33	\$725.34
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	5	\$110.45
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	4	\$373.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	1	\$93.25

**Materials**

Wire, Barbed, Galvanized, 12.5 Gauge, 1,320' roll	1	Galvanized 12.5 gauge, 1,320' roll. Includes materials and shipping only.	Each	\$71.19	4	\$284.76
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	\$6.26	20	\$125.20
Post, Wood, CCA treated, 6" x 8'	12	Wood Post, End 6" X 8', CCA Treated. Includes materials and shipping only.	Each	\$15.10	8	\$120.80
Post, Steel T, 1.33 lbs, 6'	15	Steel Post, Studded 6' - 1.33 lb. Includes materials and shipping only.	Each	\$6.68	90	\$601.20
Fence, Wire Assembly, Barbed Wire	30	Brace pins, battens, clips, staples. Includes materials and shipping only.	Foot	\$0.17	1320	\$224.40
Test, Soil Test, Standard	299	Includes materials, shipping, labor, and equipment costs.	Each	\$10.04	1	\$10.04
Gate, Pipe, 12'	1057	6 rail tube gate, 16 gauge. Includes materials and shipping only.	Each	\$166.29	2	\$332.58
Three Species Mix, Native Forb	2333	Native forb mix. Includes material and shipping only.	Acre	\$571.46	10	\$5,714.60

**Mobilization**

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50
-------------------------------	------	--	------	----------	---	----------

Practice: B000PST2 - Pasture Bundle#2

Scenario #1 - Pasture Bundle#2

Scenario Description:

Addresses soil quality degradation, water quality degradation, and degraded plant condition plus an option on fish/wildlife inadequate habitat

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 210.0

Scenario Total Cost: \$3,392.72

Scenario Cost/Unit: \$16.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	2	\$132.38
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	6	\$173.04
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	0	\$0.00
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	10	\$166.50
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	\$47.61	1	\$47.61
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43
Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.43	2000	\$860.00
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	\$257.52	1	\$257.52
Test, Soil Test, Standard	299	Includes materials, shipping, labor, and equipment costs.	Each	\$10.04	3	\$30.12
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2317	Cool season grass and legume mix. Includes material and shipping only.	Acre	\$48.34	20	\$966.80

Practice: B000PST3 - Pasture Bundle#3 -- Soil Health

Scenario #1 - Pasture Bundle#3 -- Soil Health

Scenario Description:

Addresses soil quality degradation, water quality degradation, and degraded plant condition

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$2,966.29

Scenario Cost/Unit: \$29.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	0	\$0.00
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	25	\$416.25
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	32	\$1,131.52
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	8	\$310.24
Materials						
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2317	Cool season grass and legume mix. Includes material and shipping only.	Acre	\$48.34	20	\$966.80



Practice: B000PST4 - Pasture Bundle#4 - Monarch butterfly

Scenario #1 - Pasture Bundle#4 - Monarch butterfly

Scenario Description:

Addresses soil erosion, soil quality degradation, and fish/wildlife inadequate habitat

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 200.0

Scenario Total Cost: \$9,274.83

Scenario Cost/Unit: \$46.37

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	0	\$0.00
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	25	\$416.25
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	\$47.61	1	\$47.61
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43
Three plus Species Mix, Warm Season, Native Perennial	2327	Native, warm season perennial grass. Includes material and shipping only.	Acre	\$215.16	10	\$2,151.60
Three Species Mix, Native Forb	2333	Native forb mix. Includes material and shipping only.	Acre	\$571.46	10	\$5,714.60

Practice: B000RNG1 - Range Bundle#1 - Organic

Scenario #1 - Range Bundle#1 - Organic

Scenario Description:

Addresses degraded plant condition, fish/wildlife inadequate habitat and livestock production limitation

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1,000.0

Scenario Total Cost: \$914.70

Scenario Cost/Unit: \$0.91

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Equipment Installation						
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	\$126.50	4	\$506.00
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	1	\$28.84
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	4	\$113.20
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78
Materials						
Vinyl Undersill Strips	241	Marking material using the "undersill" strips of vinyl siding. Priced per foot of fence per each wire. Materials only.	Foot	\$0.06	2000	\$120.00

Practice: B000RNG2 - Range Bundle#2

Scenario #1 - Range Bundle#2

Scenario Description:

Addresses soil erosion, degraded plant condition, fish/wildlife inadequate habitat and livestock production limitation

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1,100.0

Scenario Total Cost: \$4,470.91

Scenario Cost/Unit: \$4.06

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	4	\$88.88
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	1	\$28.84
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	12	\$346.08
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	12	\$199.80
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	54	\$899.10
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	32	\$1,131.52
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	17	\$373.66
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	8	\$310.24
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	\$47.61	4	\$190.44
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43
Vinyl Undersill Strips	241	Marking material using the "undersill" strips of vinyl siding. Priced per foot of fence per each wire. Materials only.	Foot	\$0.06	2000	\$120.00
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	\$257.52	1	\$257.52

Practice: B000RNG3 - Range Bundle#3 - Soil Health

Scenario #1 - Range Bundle#3 - Soil Health

Scenario Description:

Addresses soil quality degradation, degraded plant condition, and livestock production limitation plus an option on fish/wildlife inadequate habitat

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1,000.0

Scenario Total Cost: \$1,788.56

Scenario Cost/Unit: \$1.79

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Equipment Installation						
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	8	\$230.72
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	4	\$155.12
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	12	\$1,119.00

Practice: B000WLW - Working Lands for Wildlife Bundle

Scenario #1 - Working Lands for Wildlife Bundle

Scenario Description:

Addresses degraded plant condition, fish/wildlife inadequate habitat, and livestock production limitation plus an option on soil quality degradation and water quality degradation.

Before Situation:

Resources are protected at the minimum level of the conservation practice standard(s) applied as part of the enhancement.

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level of the conservation practice standard(s) applied

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1,000.0

Scenario Total Cost: \$2,934.87

Scenario Cost/Unit: \$2.93

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	1	\$28.84
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	15	\$249.75
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	150	\$2,497.50
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78
Materials						
Vinyl Undersill Strips	241	Marking material using the "undersill" strips of vinyl siding. Priced per foot of fence per each wire. Materials only.	Foot	\$0.06	2000	\$120.00

Practice: E314133Z - Brush management for improved structure and composition

Scenario #1 - Brush mgmt, improved structure and comp

Scenario Description:

Brush management is employed to create a desired plant community, consistent with the related ecological site steady state, which will maintain or enhance the wildlife habitat desired for the identified wildlife species. It will be designed to provide plant structure, density and diversity needed to meet those habitat objectives. This enhancement does not apply to removal of woody vegetation by prescribed fire or removal of woody vegetation to facilitate a land use change.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 314 - Brush Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 314 - Brush Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,705.48

Scenario Cost/Unit: \$17.05

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	12	\$199.80
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	32	\$1,131.52
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	8	\$310.24

Practice: E314134Z - Brush management that maintains or enhances wildlife or fish habitat

Scenario #1 - Brush mgmt, enhance habitat

Scenario Description:

Brush management is employed to create a desired plant community, consistent with the related ecological site steady state, which will maintain or enhance the wildlife habitat desired for the identified wildlife species. It will be designed to provide plant structure, density and diversity needed to meet those habitat objectives. This enhancement does not apply to removal of woody vegetation by prescribed fire or removal of woody vegetation to facilitate a land use change.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 314 - Brush Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 314 - Brush Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,705.48

Scenario Cost/Unit: \$17.05

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	12	\$199.80
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	32	\$1,131.52
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	8	\$310.24

**Practice:** E315132Z - Herbaceous weed control for desired plant communities/habitats consistent with the ecological site

**Scenario #1** - Herbaceous weed control-habitats

**Scenario Description:**

Mechanical, chemical, or biological, herbaceous weed control will be employed to control targeted, herbaceous weeds so as to create, release, or restore desired plant communities that are consistent with achievable, ecological site, steady state descriptions.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 315 - Herbaceous Weed Control

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 315 - Herbaceous Weed Control

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 10.0

**Scenario Total Cost:** \$132.38

**Scenario Cost/Unit:** \$13.24

**Cost Details:**

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	2	\$132.38



Practice: E315133Z - Herbaceous weed control (inadequate structure and comp) for desired plant communities/habitats

Scenario #1 - Herbaceous weed control-communities

Scenario Description:

Mechanical, chemical, or biological, herbaceous weed control will be employed to control targeted, herbaceous weeds so as to create, release, or restore desired plant communities that are consistent with achievable, ecological site, steady state descriptions.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 315 - Herbaceous Weed Control

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 315 - Herbaceous Weed Control

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$132.38

Scenario Cost/Unit: \$13.24

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	2	\$132.38

Practice: E315134Z - Herbaceous weed control (plant pest pressures) for desired plant communities/habitats

Scenario #1 - Herbaceous weed control-pest pressures

Scenario Description:

Mechanical, chemical, or biological, herbaceous weed control will be employed to control targeted, herbaceous weeds so as to create, release, or restore desired plant communities that are consistent with achievable, ecological site, steady state descriptions.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 315 - Herbaceous Weed Control

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 315 - Herbaceous Weed Control

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$132.38

Scenario Cost/Unit: \$13.24

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	2	\$132.38

Practice: E327136Z1 - Conservation cover to provide food habitat for pollinators and beneficial insects

Scenario #1 - Conservation cover-pollinator food

Scenario Description:

Seed or plug nectar and pollen producing plants in non-cropped areas such as field borders, vegetative barriers, contour buffer strips, grassed waterways, shelterbelts, hedgerows, windbreaks, conservation cover, and riparian forest and herbaceous buffers.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 327 - Conservation Cover

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 327 - Conservation Cover

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$325.13

Scenario Cost/Unit: \$325.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
Materials						
Untreated Conventional Seed, Pollinator Mix, Native Perennial Grasses and Forbs	2346	Untreated conventional native perennial grass and legume pollinator mix. May contain seed that are not available as certified organic. Includes material and shipping only.	Acre	\$254.41	1	\$254.41

Practice: E327136Z2 - Establish Monarch butterfly habitat

Scenario #1 - Establish monarch butterfly habitat

Scenario Description:

Seed or plug milkweed (Asclepias spp.), the Monarch butterfly larval hostplant, and high-value monarch butterfly nectar plants in non-cropped areas such as field borders, contour buffer strips, and associated grasslands.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 327 - Conservation Cover

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 327 - Conservation Cover

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$2,363.34

Scenario Cost/Unit: \$2,363.34

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	1	\$52.94
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	2	\$132.38
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	\$7.85	1	\$7.85
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	1	\$93.25
Materials						
Highly Specialized native grass and forb mix	2618	A mix of native grass and forbs to be used for restoration of Monarch butterfly foraging and larva development habitat. Includes material and shipping only.	Acre	\$1,999.36	1	\$1,999.36

Practice: E327137Z - Conservation cover to provide cover and shelter habitat for pollinators and beneficial insects

Scenario #1 - Conservation cover-pollinator shelter

Scenario Description:

Seed or plug nectar and pollen producing plants in non-cropped areas such as field borders, vegetative barriers, contour buffer strips, grassed waterways, shelterbelts, hedgerows, windbreaks, conservation cover, and riparian forest and herbaceous buffers.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 327 - Conservation Cover

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 327 - Conservation Cover

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$325.13

Scenario Cost/Unit: \$325.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
Materials						
Untreated Conventional Seed, Pollinator Mix, Native Perennial Grasses and Forbs	2346	Untreated conventional native perennial grass and legume pollinator mix. May contain seed that are not available as certified organic. Includes material and shipping only.	Acre	\$254.41	1	\$254.41

Practice: E327139Z - Conservation cover to provide habitat continuity for pollinators and beneficial insects

Scenario #1 - Conservation cover-habitat continuity

Scenario Description:

Seed or plug nectar and pollen producing plants in non-cropped areas such as field borders, vegetative barriers, contour buffer strips, grassed waterways, shelterbelts, hedgerows, windbreaks, conservation cover, and riparian forest and herbaceous buffers.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 327 - Conservation Cover

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 327 - Conservation Cover

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$325.13

Scenario Cost/Unit: \$325.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
Materials						
Untreated Conventional Seed, Pollinator Mix, Native Perennial Grasses and Forbs	2346	Untreated conventional native perennial grass and legume pollinator mix. May contain seed that are not available as certified organic. Includes material and shipping only.	Acre	\$254.41	1	\$254.41

Practice: E328101I - Improved resource conserving crop rotation to reduce water erosion

Scenario #1 - IRCCR water erosion

Scenario Description:

Improve an existing Resource Conserving Crop Rotation. The crop rotation will reduce soil erosion (water and wind), improve soil health, improve soil moisture efficiency, and reduce plan pest pressures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$466.25

Scenario Cost/Unit: \$4.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	5	\$466.25

Practice: E328101R - Resource conserving crop rotation to reduce water erosion

Scenario #1 - RCCR water erosion

Scenario Description:

Establish a Resource Conserving Crop Rotation. Rotation must include AT LEAST one resource conserving crop as determined by the State Conservationist in a minimum three year crop rotation. The crop rotation will reduce soil erosion (water and wind), improve soil health, improve soil moisture efficiency, and reduce plan pest pressures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,305.50

Scenario Cost/Unit: \$13.06

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	14	\$1,305.50



Practice: E328101Z - Conservation crop rotation on recently converted CRP grass/legume cover for water erosion

Scenario #1 - CRP trans crop rotation-water erosion

Scenario Description:

Implement a crop rotation management system on crop land acres that have recently converted from CRP grass/legume conservation cover to annual planted crops. Crop rotation minimizes disturbance resulting in a Soil Tillage Intensity Rating (STIR) less than10 and reduces soil erosion from water to below soil tolerance (T) level. RUSLE2 must be used to document the rotation, soil erosion estimate, and STIR calculations. \*This enhancement is limited to acres where the conversion event took place not more than 2 years prior. Enhancement not applicable on hayland.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$279.75

Scenario Cost/Unit: \$2.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75

Practice: E328102I - Improved resource conserving crop rotation to reduce wind erosion

Scenario #1 - IRCCR wind erosion

Scenario Description:

Improve an existing Resource Conserving Crop Rotation. The crop rotation will reduce soil erosion (water and wind), improve soil health, improve soil moisture efficiency, and reduce plan pest pressures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$466.25

Scenario Cost/Unit: \$4.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	5	\$466.25

Practice: E328102R - Resource conserving crop rotation to reduce wind erosion

Scenario #1 - RCCR wind erosion

Scenario Description:

Establish a Resource Conserving Crop Rotation. Rotation must include AT LEAST one resource conserving crop as determined by the State Conservationist in a minimum three year crop rotation. The crop rotation will reduce soil erosion (water and wind), improve soil health, improve soil moisture efficiency, and reduce plan pest pressures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,305.50

Scenario Cost/Unit: \$13.06

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	14	\$1,305.50

Practice: E328102Z - Conservation crop rotation on recently converted CRP grass/legume cover for wind erosion

Scenario #1 - CRP trans crop rotation-wind erosion

Scenario Description:

Implement a crop rotation management system on crop land acres that have recently converted from CRP grass/legume conservation cover to annual planted crops. Crop rotation minimizes disturbance resulting in a Soil Tillage Intensity Rating (STIR) less than10 and reduces soil erosion from wind to below soil tolerance (T) level. WEPS must be used to document the rotation, soil erosion estimate, and STIR calculations. \*This enhancement is limited to acres where the conversion event took place not more than 2 years prior. Enhancement not applicable on hayland.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$279.75

Scenario Cost/Unit: \$2.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75

Practice: E328106l - Improved resource conserving crop rotation for soil organic matter improvement

Scenario #1 - IRCCR for SOM improvement

Scenario Description:

Improve an existing Resource Conserving Crop Rotation. The crop rotation will reduce soil erosion (water and wind), improve soil health, improve soil moisture efficiency, and reduce plan pest pressures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$466.25

Scenario Cost/Unit: \$4.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	5	\$466.25

Practice: E328106R - Resource conserving crop rotation for soil organic matter improvement

Scenario #1 - RCCR for SOM improvement

Scenario Description:

Establish a Resource Conserving Crop Rotation. Rotation must include AT LEAST one resource conserving crop as determined by the State Conservationist in a minimum three year crop rotation. The crop rotation will reduce soil erosion (water and wind), improve soil health, improve soil moisture efficiency, and reduce plan pest pressures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,305.50

Scenario Cost/Unit: \$13.06

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Labor

Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	14	\$1,305.50
------------------	-----	---	------	---------	----	------------

Practice: E328106Z1 - Soil health crop rotation

Scenario #1 - Soil health crop rotation

Scenario Description:

Implement a crop rotation which addresses all four principle components of soil health: increases diversity of the cropping system; maintains residue throughout the year; keeps a living root; and minimizes soil chemical, physical and biological disturbance. The rotation will include at least 4 different crop and/or cover crop types (crop types include cool season grass, warm season grass, cool season broadleaf, warm season broadleaf) grown in a sequence that will produce a positive trend in the Organic Matter (OM) subfactor value over the life of the rotation, as determined by the Soil Conditioning Index (SCI). RUSLE2 or WEPS must be used to document the rotation and SCI calculations.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$466.25

Scenario Cost/Unit: \$4.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	5	\$466.25

Practice: E328106Z2 - Modifications to improve soil health and increase soil organic matter

Scenario #1 - Mod to improve SH and SOM

Scenario Description:

Use of soil health assessment to evaluate impact of current conservation crop rotation in addressing soil organic matter depletion (primary assessment made in Year 1). Modifications to the crop rotation and/or crop management will be made as a result of the assessment results (adding a new crop and/or cover crop to the rotation; making changes to planting and/or tillage system, harvest timing of crops, or termination timing of cover crops). During Year 3 a follow up assessment will be completed to allow time for the modifications to show increased soil organic matter. Modified system must produce a positive trend in the Organic Matter (OM) subfactor value over the life of the rotation, as determined by the Soil Conditioning Index (SCI). RUSLE2 or WEPS must be used to document the rotation and SCI calculations.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$896.60

Scenario Cost/Unit: \$8.97

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	8	\$746.00
Materials						
Test, Soil Test, Standard	299	Includes materials, shipping, labor, and equipment costs.	Each	\$10.04	15	\$150.60



Practice: E328106Z3 - Conservation crop rotation on recently converted CRP grass/legume cover for SOM improvement

Scenario #1 - CRP trans crop rotation-SOM

Scenario Description:

Implement a crop rotation management system on crop land acres that have recently converted from CRP grass/legume conservation cover to annual planted crops. The crop rotation adds diversity to the system; keeps a living root growing; and is managed to minimize soil chemical, physical and biological disturbance and maintain residue cover on the surface. The rotation includes crops and/or cover crops representing 3 of the 4 crop types during the planned crop sequence: warm season grass (WSG), warm season broadleaf (WSB), cool season grass (CSG), or cool season broadleaf (CSB). The crop rotation will produce a positive trend in the Organic Matter (OM) subfactor value over the life of the rotation, as determined by the SCI. Crop rotation minimizes disturbance resulting in a Soil Tillage Intensity Rating (STIR) less than10 and reduces soil erosion from wind to below soil tolerance (T) level. RUSLE2 or WEPS must be used to document the rotation, STIR and SCI calculations. \*This enhancement is limited to acres where the conversion event took place not more than 2 years prior. Enhancement not applicable on hayland.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$466.25

Scenario Cost/Unit: \$4.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	5	\$466.25

Practice: E328107I - Improved resource conserving crop rotation to improve soil compaction

Scenario #1 - IRCCR to improve soil compaction

Scenario Description:

Improve an existing Resource Conserving Crop Rotation. The crop rotation will reduce soil erosion (water and wind), improve soil health, improve soil moisture efficiency, and reduce plan pest pressures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$466.25

Scenario Cost/Unit: \$4.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	5	\$466.25

Practice: E328107R - Resource conserving crop rotation to improve soil compaction

Scenario #1 - RCCR to improve soil compaction

Scenario Description:

Establish a Resource Conserving Crop Rotation. Rotation must include AT LEAST one resource conserving crop as determined by the State Conservationist in a minimum three year crop rotation. The crop rotation will reduce soil erosion (water and wind), improve soil health, improve soil moisture efficiency, and reduce plan pest pressures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,305.50

Scenario Cost/Unit: \$13.06

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	14	\$1,305.50

Practice: E328109Z - Conservation crop rotation to reduce the concentration of salts

Scenario #1 - Rotate to reduce salt concentration

Scenario Description:

Implement a crop rotation to reduce the concentration of salts and other chemicals from saline seeps. The rotation should include at least 3 crops and/or cover crops grown in a sequence in the recharge areas of saline seeps that have rooting depths and water requirements adequate to fully utilize all available soil water. Do not use summer fallow. Use an approved water balance procedure to determine crop selection and sequence. Select crops with a tolerance to salinity levels that match the salinity of the discharge area. <see state lists>

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$373.00

Scenario Cost/Unit: \$3.73

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	4	\$373.00

Practice: E328134I - Improved resource conserving crop rotation to relieve plant pest pressure

Scenario #1 - IRCCR to relieve plant pest pressure

Scenario Description:

Improve an existing Resource Conserving Crop Rotation. The crop rotation will reduce soil erosion (water and wind), improve soil health, improve soil moisture efficiency, and reduce plan pest pressures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$466.25

Scenario Cost/Unit: \$4.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	5	\$466.25

Practice: E328134R - Resource conserving crop rotation to relieve plant pest pressure

Scenario #1 - RCCR to relieve plant pest pressure

Scenario Description:

Establish a Resource Conserving Crop Rotation. Rotation must include AT LEAST one resource conserving crop as determined by the State Conservationist in a minimum three year crop rotation. The crop rotation will reduce soil erosion (water and wind), improve soil health, improve soil moisture efficiency, and reduce plan pest pressures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,305.50

Scenario Cost/Unit: \$13.06

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Labor

Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	14	\$1,305.50
------------------	-----	---	------	---------	----	------------

Practice: E328136Z - Leave standing grain crops unharvested to benefit wildlife food sources

Scenario #1 - Leave standing grain crops for food

Scenario Description:

Implement a crop rotation which allows a portion of grain crops to be left in fields un-harvested to provide food and cover for wildlife during winter months.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$495.20

Scenario Cost/Unit: \$4.95

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.51	\$211.76
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.45	\$186.75
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.29	\$57.91
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78

Practice: E328137Z - Leave standing grain crops unharvested to benefit wildlife cover and shelter

Scenario #1 - Leave standing grain crops for shelter

Scenario Description:

Implement a crop rotation which allows a portion of grain crops to be left in fields un-harvested to provide food and cover for wildlife during winter months.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 328 - Conservation Crop Rotation

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$495.20

Scenario Cost/Unit: \$4.95

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.51	\$211.76
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.45	\$186.75
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.29	\$57.91
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78



Practice: E329101Z - No till to reduce water erosion

Scenario #1 - No till to reduce water erosion

Scenario Description:

Establish no till system to reduce sheet and rill erosion soil loss. Field(s) must have a soil loss at or below the soil tolerance (T) level for water erosion for the crop rotation and a Soil Tillage Intensity Rating (STIR) of no greater than 10 for each crop in the planned rotation. RUSLE2 must be used to calculate soil loss and STIR.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$279.75

Scenario Cost/Unit: \$2.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75

Practice: E329102Z - No till system to reduce wind erosion

Scenario #1 - No till system to reduce wind erosion

Scenario Description:

Establish no till system to reduce wind erosion soil loss. Field(s) must have a soil loss at or below the soil tolerance (T) level for wind erosion for the crop rotation and a Soil Tillage Intensity Rating (STIR) of no greater than 10 for each crop in the planned rotation. WEPS must be used to calculate soil loss and STIR.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$279.75

Scenario Cost/Unit: \$2.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Labor

Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75
------------------	-----	---	------	---------	---	----------

Practice: E329106Z - No till system to increase soil health and soil organic matter content

Scenario #1 - No till system to increase SH and SOM

Scenario Description:

Establish a reduced till system to increase soil health and soil organic matter content. Each crop in the crop rotation shall have a Soil Tillage Intensity Rating (STIR) of no greater than 20. The crop rotation must achieve a soil conditioning index (SCI) of zero or higher and produce a positive trend in the Organic Matter (OM) subfactor over the life of the crop rotation. RUSLE2 or WEPS must be used to document STIR and SCI calculations. Residue shall not be burned, grazed, or harvested.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$373.00

Scenario Cost/Unit: \$3.73

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	4	\$373.00

Practice: E329114Z - No till to increase plant-available moisture: irrigation water

Scenario #1 - No till for IWM

Scenario Description:

Establish a no till system to increase plant-available moisture. Each crop in the crop rotation shall have a Soil Tillage Intensity Rating (STIR) of no greater than 20. RUSLE2 or WEPS must be used to document STIR calculations. Maintain a minimum 60 percent surface residue cover throughout the year to reduce evaporation from the soil surface.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$279.75

Scenario Cost/Unit: \$2.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75

Practice: E329115Z - No till to increase plant-available moisture: moisture management

Scenario #1 - No till for moisture mgmt

Scenario Description:

Establish a no till system to increase plant-available moisture. Each crop in the crop rotation shall have a Soil Tillage Intensity Rating (STIR) of no greater than 20. RUSLE2 or WEPS must be used to document STIR calculations. Maintain a minimum 60 percent surface residue cover throughout the year to reduce evaporation from the soil surface.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$279.75

Scenario Cost/Unit: \$2.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75

Practice: E329128Z - No till to reduce tillage induced particulate matter

Scenario #1 - No till to reduce PM

Scenario Description:

Establish no till system to reduce tillage induced particulate matter. Field(s) must have a soil loss at or below the soil tolerance (T) level for the crop rotation and a Soil Tillage Intensity Rating (STIR) of no greater than 10 for each crop in the planned rotation. RUSLE2 or WEPS must be used to document soil loss and STIR calculations.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$279.75

Scenario Cost/Unit: \$2.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75

Practice: E329144Z - No till to reduce energy

Scenario #1 - No till to reduce energy

Scenario Description:

Establish a no till system which reduces total energy consumption associated with field operations by at least 25% compared to current tillage system (benchmark). Each crop in the crop rotation shall have a Soil Tillage Intensity Rating (STIR) of no greater than 20. The current NRCS wind and water erosion prediction technologies must be used to document STIR calculations and energy consumption.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 329 - Residue and Tillage Management - No-Till/ Strip Till/ Direct Seed

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$373.00

Scenario Cost/Unit: \$3.73

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	4	\$373.00

**Practice:** E333118Z - Apply gypsum products to improve surface WQ quality by reducing dissolved P conc in surface runoff

**Scenario #1** - Apply gypsum to control P in runoff

**Scenario Description:**

Apply approved gypsum products to improve surface water quality by reducing dissolved phosphorus concentrations in surface runoff.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 333 - Amending Soil Properties with Gypsiferous Products

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 333 - Amending Soil Properties with Gypsiferous Products

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 100.0

**Scenario Total Cost:** \$353.60

**Scenario Cost/Unit:** \$3.54

**Cost Details:**

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Labor</b>						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	10	\$353.60



**Practice:** E333119Z - Apply gypsum products to improve surface WQ by reducing dissolved P conc in subsurface drainage

**Scenario #1** - Apply gypsum to control P in drainage

**Scenario Description:**

Apply approved gypsum products to improve surface water quality by reducing dissolved phosphorus concentrations in subsurface drainage.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 333 - Amending Soil Properties with Gypsiferous Products

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 333 - Amending Soil Properties with Gypsiferous Products

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 100.0

**Scenario Total Cost:** \$353.60

**Scenario Cost/Unit:** \$3.54

**Cost Details:**

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	10	\$353.60

Practice: E333122Z - Apply gypsum to improve WQ, contaminants transported from manure/biosolid application-surface water

Scenario #1 - Gypsum to control pathogens in runoff

Scenario Description:

Apply approved gypsum products to improve water quality by reducing the potential for pathogens and other contaminants transport from areas of manure and biosolids application.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 333 - Amending Soil Properties with Gypsiferous Products

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 333 - Amending Soil Properties with Gypsiferous Products

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$353.60

Scenario Cost/Unit: \$3.54

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	10	\$353.60

Practice: E333123Z - Apply gypsum to improve WQ, contaminants transported from manure/biosolid application-ground water

Scenario #1 - Gypsum to control pathogens in drainage

Scenario Description:

Apply approved gypsum products to improve water quality by reducing the potential for pathogens and other contaminants transport from areas of manure and biosolids application.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 333 - Amending Soil Properties with Gypsiferous Products

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 333 - Amending Soil Properties with Gypsiferous Products

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$353.60

Scenario Cost/Unit: \$3.54

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	10	\$353.60

Practice: E334107Z - Controlled traffic farming to reduce compaction

Scenario #1 - Controlled traffic for compaction

Scenario Description:

Establish a controlled traffic system where no more than 25% of the surface is tracked with heavy axel loads to minimize soil compaction. For row crops (e.g. corn in 30-inch rows) no tire should run on a row except for flotation tires on combines and/or fertilizer and lime spreading trucks. If wide flotation tires are used, they must be big enough that the inflation pressure will be below 18 psi to minimize compaction on trafficked rows.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 334 - Controlled Traffic Farming

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 334 - Controlled Traffic Farming

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$686.05

Scenario Cost/Unit: \$6.86

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	5	\$466.25

Practice: E338134Z - Strategic patch burning for grazing distribution/wildlife habitat (undesirable plant pressure)

Scenario #1 - Patch burning-plant pest pressure

Scenario Description:

Patch burn grazing is the application of prescribed fires on portions of an identified grazing unit at different times of the year. Patch burn grazing allows grazing animals to select where they want to graze creating a mosaic of vegetation structures and diversity that will maintain or enhance the wildlife habitat desired for the identified wildlife species and maintain livestock production.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 338 - Prescribed Burning

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 338 - Prescribed Burning

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$765.86

Scenario Cost/Unit: \$7.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Equipment Installation						
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	\$126.50	4	\$506.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	4	\$113.20
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78

Practice: E338135Z - Strategically planned, patch burning for grazing distribution and wildlife habitat (fuel loading)

Scenario #1 - Patch burning-fuel loading

Scenario Description:

Patch burn grazing is the application of prescribed fires on portions of an identified grazing unit at different times of the year. Patch burn grazing allows grazing animals to select where they want to graze creating a mosaic of vegetation structures and diversity that will maintain or enhance the wildlife habitat desired for the identified wildlife species and maintain livestock production.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 338 - Prescribed Burning

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 338 - Prescribed Burning

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$765.86

Scenario Cost/Unit: \$7.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Equipment Installation						
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	\$126.50	4	\$506.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	4	\$113.20
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78

Practice: E338137Z1 - Sequential patch burning

Scenario #1 - Sequential patch burning

Scenario Description:

Prescribed burning to promote and enhance conifer forests and maintain a healthy understory. This enhancement is to conduct prescribed burns in a conifer forest, burning only a portion of the area each year to create a mosaic of vegetation in several stages of development, to provide a more diverse wildlife habitat.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 338 - Prescribed Burning

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 338 - Prescribed Burning

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$1,617.55

Scenario Cost/Unit: \$161.76

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	2	\$57.68
Water tank, portable	1602	Portable water tank transported in a pick up truck. Typically with 200 gallon capacity includes tank with pump, hose and sprayer. Does not include the pickup truck. Equipment only.	Hour	\$2.47	2	\$4.94
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	16	\$565.76
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75
Materials						
Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	\$4.32	5	\$21.60
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: E338137Z2 - Short-interval burn

Scenario #1 - Short-interval burn

Scenario Description:

This enhancement is the controlled use of fire in a forest to restore native forest conditions with a focus on improving the condition of fire-adapted plants and wildlife habitat and reducing the risk of damage from intense, severe wildfires.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 338 - Prescribed Burning

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 338 - Prescribed Burning

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$2,468.43

Scenario Cost/Unit: \$49.37

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	8	\$177.76
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	8	\$230.72
Water tank, portable	1602	Portable water tank transported in a pick up truck. Typically with 200 gallon capacity includes tank with pump, hose and sprayer. Does not include the pickup truck. Equipment only.	Hour	\$2.47	8	\$19.76
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	48	\$1,697.28
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78
Materials						
Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	\$4.32	10	\$43.20
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93



Practice: E338140Z - Short-interval prescribed burning to promote a healthy herbaceous plant community

Scenario #1 - Short-interval prescribed burning

Scenario Description:

???Increase the frequency of prescribed burning to help restore ecological conditions in forests and woodlands, with a focus on improving the condition of fire-adapted plants and forage while improving wildlife habitat and reducing the risk of damage from intense, severe wildfires. Short return-interval burns can also be effective in regenerating desirable native tree and herbaceous vegetation, and limiting the encroachment of competing vegetation including non-native species.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 338 - Prescribed Burning

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 338 - Prescribed Burning

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: \$3,486.57

Scenario Cost/Unit: \$87.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$67.45	8	\$539.60
Truck, water	1448	Water tanker truck. Equipment only. Labor not included.	Hour	\$166.79	8	\$1,334.32
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	24	\$527.52
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	8	\$226.40
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	8	\$310.24
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	4	\$287.56
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: E340101Z - Cover crop to reduce water erosion

Scenario #1 - Cover crop to reduce water erosion

Scenario Description:

Cover crop added to current crop rotation to reduce soil erosion from water to below soil tolerance (T) level. Cover crops grown during critical erosion period(s). Species are selected that will have physical characteristics to provide adequate erosion protection.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 340 - Cover Crop

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 340 - Cover Crop

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$800.56

Scenario Cost/Unit: \$8.01

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	1	\$35.36
Materials						
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	\$38.26	20	\$765.20

Practice: E340102Z - Cover crop to reduce wind erosion

Scenario #1 - Cover crop to reduce wind erosion

Scenario Description:

Cover crop added to current crop rotation to reduce soil erosion from wind to below the soil tolerance (T) level. Cover crops grown during critical erosion period(s). Species are selected that will have physical characteristics to provide adequate erosion protection.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 340 - Cover Crop

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 340 - Cover Crop

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$800.56

Scenario Cost/Unit: \$8.01

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	1	\$35.36
Materials						
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	\$38.26	20	\$765.20

Practice: E340106Z1 - Intensive cover cropping to increase soil health and soil organic matter content

Scenario #1 - Cover cropping for SH and SOM

Scenario Description:

Use of cover crops in a cropping system to add diversity, keep the soil covered, and maintain a living root as long as possible. Cover crop will be used during ALL non-crop production periods in an annual crop rotation. Cover crop may be a single species or multi-species mix. Cover crop shall not be harvested or burned. Planned crop rotation including cover crops and associated management activities must achieve a soil conditioning index (SCI) of zero or higher and produce a positive trend in the Organic Matter (OM) subfactor over the life of the crop rotation. RUSLE2 or WEPS must be used to document SCI calculations. Cover crops may be grazed following a prescribed grazing plan that removes no more than 40% of the biomass produced.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 340 - Cover Crop

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 340 - Cover Crop

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,240.10

Scenario Cost/Unit: \$12.40

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50
Materials						
Two Species Mix, Cool Season Annual (1 grass and 1 legume)	2314	Cool season annual grass and legume mix. Includes material and shipping only.	Acre	\$52.68	20	\$1,053.60

Practice: E340106Z2 - Use of multi-species cover crops to improve soil health and increase soil organic matter

Scenario #1 - Multi-species cover crops

Scenario Description:

Implement a multi-species cover crop to add diversity and increase biomass production to improve soil health and increased soil organic matter. Cover crop mix must include a minimum of 4 different species. The cover crop mix will increase diversity of the crop rotation by including crop types currently missing, e.g. Cool Season Grass (CSG), Cool Season Broadleaves (CSB), Warm Season Grasses (WSG), Warm Season Broadleaves (WSB).

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 340 - Cover Crop

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 340 - Cover Crop

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,240.72

Scenario Cost/Unit: \$12.41

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
Materials						
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	\$58.50	20	\$1,170.00

Practice: E340106Z3 - Intensive cover cropping (orchard/vineyard floor) to increase soil health and SOM content

Scenario #1 - Cover cropping for orchards/vineyards

Scenario Description:

Implementation of cover crops to provide orchard or vineyard floor coverage throughout the year. Cover crop shall not be harvested, grazed, or burned. Planned cover crop management activities must achieve a soil conditioning index (SCI) of zero or higher and produce a positive trend in the Organic Matter (OM) subfactor over the life of the crop rotation. RUSLE2 or WEPS must be used to document SCI calculations.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 340 - Cover Crop

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 340 - Cover Crop

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,124.32

Scenario Cost/Unit: \$11.24

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
Materials						
Two Species Mix, Cool Season Annual (1 grass and 1 legume)	2314	Cool season annual grass and legume mix. Includes material and shipping only.	Acre	\$52.68	20	\$1,053.60

**Practice:** E340106Z4 - Use of SHA to assist with development of cover crop mix to improve soil health and increase SOM

**Scenario #1** - Soil health assessment

**Scenario Description:**

Use of a soil health assessment to evaluate impact of current conservation crop rotation in addressing soil organic matter depletion (primary assessment made in Year 1). Soil health assessment results will be utilized to determine the correct Carbon to Nitrogen ratio of a multi-species cover crop mix that will be added to the crop rotation. During Year 3 a follow up assessment will be completed to allow time for the addition of a cover crop to increased soil organic matter.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 340 - Cover Crop

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 340 - Cover Crop

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 100.0

**Scenario Total Cost:** \$1,469.81

**Scenario Cost/Unit:** \$14.70

**Cost Details:**

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Labor</b>						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	1	\$35.36
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	1	\$93.25
<b>Materials</b>						
Test, Soil Test, Standard	299	Includes materials, shipping, labor, and equipment costs.	Each	\$10.04	15	\$150.60
Three Species Mix, Warm Season, Annual Grasses and Legumes	2326	Warm season annual grass and legume mix. Includes material and shipping only.	Acre	\$59.53	20	\$1,190.60

Practice: E340107Z - Cover crop to minimize soil compaction

Scenario #1 - Cover crop to minimize soil compaction

Scenario Description:

Establish a cover crop mix that includes plants with both fibrous root and deep rooted systems. Fibrous to treat and prevent both near surface (0-4'') and deep (>4'') soil compaction and deep rooted to break up deep compacted soils. Cover crop shall not be harvested, grazed, or burned.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 340 - Cover Crop

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 340 - Cover Crop

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,088.96

Scenario Cost/Unit: \$10.89

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	1	\$35.36
Materials						
Two Species Mix, Cool Season Annual (1 grass and 1 legume)	2314	Cool season annual grass and legume mix. Includes material and shipping only.	Acre	\$52.68	20	\$1,053.60



**Practice:** E340118Z - Cover crop to reduce water quality degradation by utilizing excess soil nutrients-surface water

**Scenario #1** - Cover crop for WQ nutrients-runoff

**Scenario Description:**

Establish a cover crop mix to take up excess soil nutrients. Select cover crop species for their ability to effectively utilize nutrients. Terminate the cover crop as late as practical to maximize plant biomass production and nutrient uptake. Cover crop shall not be harvested, grazed, or burned.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 340 - Cover Crop

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 340 - Cover Crop

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 100.0

**Scenario Total Cost:** \$1,088.96

**Scenario Cost/Unit:** \$10.89

**Cost Details:**

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Labor</b>						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	1	\$35.36
<b>Materials</b>						
Two Species Mix, Cool Season Annual (1 grass and 1 legume)	2314	Cool season annual grass and legume mix. Includes material and shipping only.	Acre	\$52.68	20	\$1,053.60

Practice: E340119Z - Cover crop to reduce water quality degradation by utilizing excess soil nutrients-ground water

Scenario #1 - Cover crops for WQ nutrients-drainage

Scenario Description:

Establish a cover crop mix to take up excess soil nutrients. Select cover crop species for their ability to effectively utilize nutrients. Terminate the cover crop as late as practical to maximize plant biomass production and nutrient uptake. Cover crop shall not be harvested, grazed, or burned.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 340 - Cover Crop

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 340 - Cover Crop

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,088.96

Scenario Cost/Unit: \$10.89

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	1	\$35.36
Materials						
Two Species Mix, Cool Season Annual (1 grass and 1 legume)	2314	Cool season annual grass and legume mix. Includes material and shipping only.	Acre	\$52.68	20	\$1,053.60

Practice: E340134Z - Cover crop to suppress excessive weed pressures and break pest cycles

Scenario #1 - Cover crops for suppression

Scenario Description:

Establish a cover crop mix to suppress excessive weed pressures and break pest cycles. Select cover crop species for their life cycles, growth habits, and other biological, chemical and/or physical characteristics. Select cover crop species that do not harbor pests or diseases of subsequent crops in the rotation. Cover crop shall not be harvested, grazed, or burned.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 340 - Cover Crop

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 340 - Cover Crop

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,124.32

Scenario Cost/Unit: \$11.24

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
Materials						
Two Species Mix, Cool Season Annual (1 grass and 1 legume)	2314	Cool season annual grass and legume mix. Includes material and shipping only.	Acre	\$52.68	20	\$1,053.60

Practice: E345101Z - Reduced tillage to reduce water erosion

Scenario #1 - Reduced tillage to reduce water erosion

Scenario Description:

Establish a reduced tillage system to reduce sheet and rill erosion soil loss. Field(s) must have a soil loss at or below the soil tolerance (T) level for water erosion for the crop rotation and a Soil Tillage Intensity Rating (STIR) of no greater than 40 for each crop in the planned rotation. RUSLE2 must be used to calculate soil loss and STIR.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$373.00

Scenario Cost/Unit: \$3.73

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	4	\$373.00

Practice: E345102Z - Reduced tillage to reduce wind erosion

Scenario #1 - Reduced tillage to reduce wind erosion

Scenario Description:

Establish a reduced tillage system to reduce wind erosion soil loss. Field(s) must have a soil loss at or below the soil tolerance (T) level for wind erosion for the crop rotation and a Soil Tillage Intensity Rating (STIR) of no greater than 40 for each crop in the planned rotation. WEPS must be used to calculate soil loss and STIR.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$279.75

Scenario Cost/Unit: \$2.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75

**Practice:** E345106Z - Reduced tillage to increase soil health and soil organic matter content

**Scenario #1** - Reduced tillage for SH and SOM

**Scenario Description:**

Establish a reduced till system to increase soil health and soil organic matter content. Each crop in the crop rotation shall have a Soil Tillage Intensity Rating (STIR) of no greater than 80. The crop rotation must achieve a soil conditioning index (SCI) of zero or higher and produce a positive trend in the Organic Matter (OM) subfactor over the life of the crop rotation. RUSLE2 or WEPS must be used to document STIR and SCI calculations. Residue shall not be burned, grazed, or harvested.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 100.0

**Scenario Total Cost:** \$373.00

**Scenario Cost/Unit:** \$3.73

**Cost Details:**

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	4	\$373.00

Practice: E345114Z - Reduced tillage to increase plant-available moisture: irrigation water

Scenario #1 - Reduced tillage for IWM

Scenario Description:

Establish a reduced till system to increase plant-available moisture. Each crop in the crop rotation shall have a Soil Tillage Intensity Rating (STIR) of no greater than 80. RUSLE2 or WEPS must be used to document STIR calculations. Maintain a minimum 60 percent surface residue cover throughout the year to reduce evaporation from the soil surface.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$279.75

Scenario Cost/Unit: \$2.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75

Practice: E345115Z - Reduced tillage to increase plant-available moisture: moisture management

Scenario #1 - Reduced tillage for moisture mgmt

Scenario Description:

Establish a reduced till system to increase plant-available moisture. Each crop in the crop rotation shall have a Soil Tillage Intensity Rating (STIR) of no greater than 80. RUSLE2 or WEPS must be used to document STIR calculations. Maintain a minimum 60 percent surface residue cover throughout the year to reduce evaporation from the soil surface.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$279.75

Scenario Cost/Unit: \$2.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75



Practice: E345128Z - Reduced tillage to reduce tillage induced particulate matter

Scenario #1 - Reduced tillage to reduce PM

Scenario Description:

Establish a reduced tillage system to reduce tillage induced particulate matter. Field(s) must have a soil loss at or below the soil tolerance (T) level for the crop rotation and a Soil Tillage Intensity Rating (STIR) of no greater than 40 for each crop in the planned rotation. RUSLE2 or WEPS must be used to document soil loss and STIR calculations.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$279.75

Scenario Cost/Unit: \$2.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75

Practice: E345144Z - Reduced tillage to reduce energy use

Scenario #1 - Reduced tillage to reduce energy use

Scenario Description:

Establish a reduced tillage system which reduces total energy consumption associated with field operations by at least 25% compared to conventional tillage systems (benchmark). Each crop in the crop rotation shall have a Soil Tillage Intensity Rating (STIR) of no greater than 80. RUSLE2 must be used to document STIR calculations and energy consumption. <State lists will be prepared providing conventional system benchmark energy values and reduced tillage system values for those systems using at least 25% less energy>

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 345 - Residue and Tillage Management, Reduced Till

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$373.00

Scenario Cost/Unit: \$3.73

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	4	\$373.00

Practice: E374144Z1 - Install variable frequency drive(s) on pump(s)

Scenario #1 - Variable frequency drives

Scenario Description:

Install Variable Frequency Drive(s) (CPS 533 Pumping Plant) with the correct sensors, on all pumps indicated in the energy audit.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 374 - Farmstead Energy Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 374 - Farmstead Energy Improvement

Feature Measure: Each

Scenario Unit:: Brake Horse Power

Scenario Typical Size: 50.0

Scenario Total Cost: \$12,179.50

Scenario Cost/Unit: \$243.59

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Materials

Variable Speed Drive, 50 HP	1288	Variable speed drive for 50 Horsepower electric motor. Does not include motor. Materials only.	Horsepower	\$243.59	50	\$12,179.50
-----------------------------	------	--	------------	----------	----	-------------

Practice: E374144Z2 - Switch fuel source for pump motor(s)

Scenario #1 - Switch fuel source for pump motor(s)

Scenario Description:

Switch fuel source for the pump motor(s) indicated in the audit to a renewable source (wind, solar, geothermal, etc..). (CPS 533 Pumping Plant)

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 374 - Farmstead Energy Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 374 - Farmstead Energy Improvement

Feature Measure: Horsepower

Scenario Unit:: Horsepower

Scenario Typical Size: 5.0

Scenario Total Cost: \$38,589.17

Scenario Cost/Unit: \$7,717.83

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	1	\$22.22
---------------	-----	---	------	---------	---	---------

Labor

Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	12	\$424.32
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50

Materials

Pump, <= 5 HP, pump and motor, fixed cost portion	1009	Fixed cost portion of a pump less than or equal to 5 HP pump and motor. This portion is a base cost and is not dependant on horsepower. The total cost of any pump will include this fixed cost plus a variable cost portion. The completed pump and motor will	Each	\$549.88	1	\$549.88
Pump, <= 5 HP, pump and motor, variable cost portion	1010	Variable cost portion of a pump less than or equal to 5 HP pump and motor. This portion IS dependent on the total horsepower for the pump. The total cost of any pump will include this variable cost plus the fixed cost portion. The completed pump and moto	Horsepower	\$413.86	5	\$2,069.30
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will incl	Each	\$460.51	5	\$2,302.55
Solar Panels, variable cost portion	1135	Variable cost portion of the Solar Panels. This portion IS dependent on the total Kilowatt for the Solar Panels. The total cost of any Solar Panels will include this variable cost plus the fixed cost portion. The completed Solar Panels will include all ma	Kilowatt	\$8,258.60	4	\$33,034.40

Practice: E376128Z - Modify field operations to reduce particulate matter

Scenario #1 - Mod field ops to reduce PM

Scenario Description:

Modify tillage and/or harvest operations to reduce particulates by at least 20 percent below the required levels.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 376 - Field Operations Emissions Reduction

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 376 - Field Operations Emissions Reduction

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$279.75

Scenario Cost/Unit: \$2.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75

Practice: E381133Z - Silvopasture for wildlife habitat (structure and composition)

Scenario #1 - Silvopasture-structure and comp

Scenario Description:

Establishing a combination of trees or shrubs and compatible forages on the same acreage, providing forage for livestock and the production of wood products, and including a purpose of enhancing wildlife habitat.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 381 - Silvopasture

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 381 - Silvopasture

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$8,521.56

Scenario Cost/Unit: \$85.22

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	20	\$125.20
------------------------------	-----	---	------	--------	----	----------

Foregone Income

FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	200	\$3,330.00
------------------	------	---------------------------------	-------------------	---------	-----	------------

Labor

Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
-----------------------	-----	--	------	---------	---	---------

Materials

Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	20	\$349.60
Shrub, seedling or transplant, bare root, 36-60"	1508	Bare root shrubs 3 to 5 foot tall. Includes materials and shipping only.	Each	\$1.68	200	\$336.00
Three plus Species Mix, Warm Season, Native Perennial	2327	Native, warm season perennial grass. Includes material and shipping only.	Acre	\$215.16	20	\$4,303.20

Practice: E381137Z - Silvopasture for wildlife habitat (cover and shelter)

Scenario #1 - Silvopasture for wildlife habitat-food

Scenario Description:

Establishing a combination of trees or shrubs and compatible forages on the same acreage, providing forage for livestock and the production of wood products, and including a purpose of enhancing wildlife cover and shelter.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 381 - Silvopasture

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 381 - Silvopasture

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$8,915.24

Scenario Cost/Unit: \$89.15

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	20	\$125.20
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	200	\$3,330.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	20	\$349.60
Shrub, seedling or transplant, bare root, 36-60"	1508	Bare root shrubs 3 to 5 foot tall. Includes materials and shipping only.	Each	\$1.68	200	\$336.00
Tree, conifer, seedling, bare root, 3-0	1515	Bare root conifer trees, 3-0 (3 years old). Includes materials and shipping only.	Each	\$0.42	100	\$42.00
Three plus Species Mix, Warm Season, Native Perennial	2327	Native, warm season perennial grass. Includes material and shipping only.	Acre	\$215.16	20	\$4,303.20

Practice: E383135Z - Grazing-maintained fuel break to reduce the risk of fire

Scenario #1 - Grazed fuel break

Scenario Description:

The property has existing fuel breaks of 30 to 60 feet in width. Warm-season perennial vegetation will be established on the fuel breaks, and will be over-seeded with cool-season annual forages in the fall. Grazing will be managed on the fuel break to remove or modify the fine fuel vegetation, to reduce the risk of fire spread from ground fires, maintain adequate soil cover, control erosion, and facilitate prescribed burning.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 383 - Fuel Break

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 383 - Fuel Break

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$2,495.82

Scenario Cost/Unit: \$249.58

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.75	10	\$67.50
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	10	\$217.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	24	\$527.52
Materials						
Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.43	1000	\$430.00
Three Species Mix, Cool Season, Introduced Perennial Grass	2315	Cool season, introduced grass mix. Includes material and shipping only.	Acre	\$45.35	10	\$453.50
One Species, Warm Season, Introduced Perennial Grass (seed or sprigs)	2323	Introduced, warm season perennial grass seed or sprig. Includes material and shipping only.	Acre	\$62.40	10	\$624.00
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50



Practice: E384135Z - Biochar production from woody residue

Scenario #1 - Biochar production from woody residue

Scenario Description:

Utilizes woody debris remaining after fuel reduction harvests or wildfires to create biochar. Biochar stores carbon and is a useful soil amendment that improves SOM and water-holding capacity.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 384 - Woody Residue Treatment

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 384 - Woody Residue Treatment

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: \$9,165.25

Scenario Cost/Unit: \$4,582.63

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hydraulic Excavator, .5 CY	930	Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included.	Hour	\$63.99	40	\$2,559.60
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	40	\$178.00
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	15	\$333.30
Water tank, portable	1602	Portable water tank transported in a pick up truck. Typically with 200 gallon capacity includes tank with pump, hose and sprayer. Does not include the pickup truck. Equipment only.	Hour	\$2.47	80	\$197.60
Wood Processor	2680	Towable equipment used to cut and split wood, Daily rental rate. All materials and equipment included	Day	\$184.40	5	\$922.00
Biochar Kiln, open fire	2681	Open fire kiln or metal container used to produce biochar/charcoal production. Daily rental rate. Includes all material and equipment	Hour	\$1.44	320	\$460.80
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	120	\$2,637.60
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	40	\$883.60
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	5	\$466.25
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	3	\$526.50

Practice: E386101Z - Enhanced field borders to reduce water induced erosion along the edge(s) of a field

Scenario #1 - Field borders to reduce water erosion

Scenario Description:

Enhance existing field borders to a width of at least 30 feet and establish a single specie or mixture of species that provide a dense ground cover along the edge(s) of the field.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 386 - Field Border

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 386 - Field Border

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$732.25

Scenario Cost/Unit: \$732.25

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	1	\$11.37
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	\$7.85	1	\$7.85
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.41	\$170.24
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.36	\$149.40
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.23	\$45.93
Materials						
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	\$58.50	1	\$58.50
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: E386102Z - Enhanced field borders to reduce wind induced erosion along the windward side(s) of a field

Scenario #1 - Field borders to reduce wind erosion

Scenario Description:

Enhance existing field borders to a width of at least 30 feet and establish a single specie or mixture of species that provide a dense ground cover along the edge(s) of the field.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 386 - Field Border

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 386 - Field Border

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$732.25

Scenario Cost/Unit: \$732.25

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	1	\$11.37
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	\$7.85	1	\$7.85
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.41	\$170.24
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.36	\$149.40
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.23	\$45.93
Materials						
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	\$58.50	1	\$58.50
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: E386106Z - Enhanced field borders to increase carbon storage along the edge(s) of the field

Scenario #1 - Field borders to increase carbon storage

Scenario Description:

Enhance existing field borders to a width of at least 30 feet and establish a single specie or mixture of species that provide a dense ground cover and dense rooting system along the edge(s) of the field.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 386 - Field Border

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 386 - Field Border

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$732.25

Scenario Cost/Unit: \$732.25

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	1	\$11.37
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	\$7.85	1	\$7.85
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.41	\$170.24
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.36	\$149.40
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.23	\$45.93
Materials						
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	\$58.50	1	\$58.50
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: E386128Z - Enhanced field borders to decrease particulate emissions along the edge(s) of the field

Scenario #1 - Field borders to decrease particulates

Scenario Description:

Enhance existing field borders to a width of at least 40 feet and establish a mixture of species that decrease the particulate emissions along the edge(s) of the field.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 386 - Field Border

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 386 - Field Border

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$732.25

Scenario Cost/Unit: \$732.25

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	1	\$11.37
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	\$7.85	1	\$7.85
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.41	\$170.24
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.36	\$149.40
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.23	\$45.93
Materials						
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	\$58.50	1	\$58.50
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: E386136Z - Enhanced field border to provide wildlife food for pollinators along the edge(s) of a field

Scenario #1 - Field border to provide wildlife food

Scenario Description:

Enhance existing field borders to a width of at least 40 feet and establish a mixture of species that provide food for pollinators along the edge(s) of the field.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 386 - Field Border

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 386 - Field Border

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$732.25

Scenario Cost/Unit: \$732.25

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	1	\$11.37
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	\$7.85	1	\$7.85
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.41	\$170.24
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.36	\$149.40
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.23	\$45.93
Materials						
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	\$58.50	1	\$58.50
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: E386137Z - Enhanced field border to provide wildlife cover or shelter along the edge(s) of a field

Scenario #1 - Field border to provide wildlife cover

Scenario Description:

Enhance existing field borders to a width of at least 40 feet and establish a mixture of species that provide wildlife food and cover along the edge(s) of the field.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 386 - Field Border

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 386 - Field Border

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$732.25

Scenario Cost/Unit: \$732.25

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	1	\$11.37
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	\$7.85	1	\$7.85
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.41	\$170.24
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.36	\$149.40
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.23	\$45.93
Materials						
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	\$58.50	1	\$58.50
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

**Practice:** E386139Z - Enhanced field border to provide wildlife habitat continuity along the edge(s) of a field

**Scenario #1** - Field border to provide continuity

**Scenario Description:**

Enhance existing field borders to a width of at least 40 feet and establish a mixture of species that provide wildlife habitat continuity along the edge(s) of the field.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 386 - Field Border

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 386 - Field Border

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 1.0

**Scenario Total Cost:** \$732.25

**Scenario Cost/Unit:** \$732.25

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	1	\$11.37
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	\$7.85	1	\$7.85
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.41	\$170.24
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.36	\$149.40
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.23	\$45.93
Materials						
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	\$58.50	1	\$58.50
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93



Practice: E390118Z - Increase riparian herbaceous cover width for nutrient reduction

Scenario #1 - Riparian herbaceous cover-nut reduction

Scenario Description:

Where an existing herbaceous riparian buffer is located along a river, stream, pond, lake, or other waterbody, increase the width of the buffer in order to allow a greater percentage of nutrient removal from surface and subsurface flows. Saturated buffer or nutrient control wetland to capture subsurface drainage.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 390 - Riparian Herbaceous Cover

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 390 - Riparian Herbaceous Cover

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: \$1,175.57

Scenario Cost/Unit: \$587.78

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	2	\$12.52
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	2	\$43.56
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.82	\$340.47
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.72	\$298.80
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.46	\$91.86
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$37.13	2	\$74.26
One Species, Cool Season, Native Perennial Grass	2312	Native, cool season perennial grass. Includes material and shipping only.	Acre	\$157.05	2	\$314.10

Practice: E390126Z - Increase riparian herbaceous cover width to reduce sediment loading

Scenario #1 - Riparian herbaceous cover-sed loading

Scenario Description:

Where an existing herbaceous riparian buffer is located along a river, stream, pond, lake, or other waterbody, increase the width of the buffer in order to allow a greater percentage of nutrient removal from surface and subsurface flows.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 390 - Riparian Herbaceous Cover

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 390 - Riparian Herbaceous Cover

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: \$1,175.57

Scenario Cost/Unit: \$587.78

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	2	\$12.52
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	2	\$43.56
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.82	\$340.47
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.72	\$298.80
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.46	\$91.86
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$37.13	2	\$74.26
One Species, Cool Season, Native Perennial Grass	2312	Native, cool season perennial grass. Includes material and shipping only.	Acre	\$157.05	2	\$314.10

Practice: E390136Z - Increase riparian herbaceous cover width to enhance wildlife habitat

Scenario #1 - Riparian herbaceous cover-habitat

Scenario Description:

Where an existing herbaceous riparian buffer is located along a river, stream, pond, lake, or other waterbody, increase the diversity of native species, control invasive species, install fencing and relocate equipment operations, trails, and livestock, and increase the width of the buffer.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 390 - Riparian Herbaceous Cover

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 390 - Riparian Herbaceous Cover

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 4.0

Scenario Total Cost: \$3,136.61

Scenario Cost/Unit: \$784.15

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	4	\$25.04
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	2	\$43.56
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	1	\$415.21
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	1	\$415.00
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.46	\$91.86
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$37.13	4	\$148.52
Specialized native grass and forb mix	2619	A mix of native grass and forbs to be used for specialized purposes such as wildlife (including pollinators) or ecosystem restoration, requiring species not readily available and/or difficult to produce and harvest. Includes material and shipping only	Acre	\$998.71	2	\$1,997.42

Practice: E391118Z - Increase riparian forest buffer width for nutrient reduction

Scenario #1 - Riparian forest buffer-nut reduction

Scenario Description:

Where an existing forested riparian area is located along a river, stream, pond, lake, or other waterbody, increase the width of the buffer in order to allow a greater percentage of nutrient removal from surface and subsurface flows. Saturated buffer or nutrient control wetland to capture subsurface drainage.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 391 - Riparian Forest Buffer

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 391 - Riparian Forest Buffer

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: \$3,490.26

Scenario Cost/Unit: \$1,745.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	16	\$355.52
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	2	\$105.88
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	4	\$101.08
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	16	\$192.64
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.82	\$340.47
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.72	\$298.80
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.46	\$91.86
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	4	\$88.36
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	4	\$155.12
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	1	\$17.48
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$25.63	1	\$25.63
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shi	Acre	\$1.28	1	\$1.28

Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.59	872	\$514.48
Tree shelter, solid tube type, 4" x 48"	1566	4" x 48" tree tube for protection from animal damage. Materials only.	Each	\$4.14	100	\$414.00
Stakes, wood, 1" x 1" x 48"	1578	1" x 1" x 48" wood stakes to fasten items in place. Includes materials only.	Each	\$2.04	100	\$204.00
<b>Mobilization</b>						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: E391126Z - Increase riparian forest buffer width to reduce sediment loading

Scenario #1 - Riparian forest buffer-sed loading

Scenario Description:

Where an existing forested riparian area is located along a river, stream, pond, lake, or other waterbody, increase the width of the buffer in order to allow a greater percentage of nutrient removal from surface and subsurface flows.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 391 - Riparian Forest Buffer

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 391 - Riparian Forest Buffer

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: \$3,490.26

Scenario Cost/Unit: \$1,745.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	16	\$355.52
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	2	\$105.88
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	4	\$101.08
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	16	\$192.64
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.82	\$340.47
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.72	\$298.80
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.46	\$91.86
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	4	\$88.36
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	4	\$155.12
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	1	\$17.48
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$25.63	1	\$25.63
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shi	Acre	\$1.28	1	\$1.28

Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.59	872	\$514.48
Tree shelter, solid tube type, 4" x 48"	1566	4" x 48" tree tube for protection from animal damage. Materials only.	Each	\$4.14	100	\$414.00
Stakes, wood, 1" x 1" x 48"	1578	1" x 1" x 48" wood stakes to fasten items in place. Includes materials only.	Each	\$2.04	100	\$204.00
<b>Mobilization</b>						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: E391127Z - Increase stream shading for stream temperature reduction

Scenario #1 - Shade stream to reduce temp

Scenario Description:

Riparian area tree canopy cover density is increased and the extent of the forested riparian area is increased to provide greater stream shading.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 391 - Riparian Forest Buffer

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 391 - Riparian Forest Buffer

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: \$3,490.26

Scenario Cost/Unit: \$1,745.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	16	\$355.52
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	2	\$105.88
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	4	\$101.08
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	16	\$192.64
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.82	\$340.47
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.72	\$298.80
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.46	\$91.86
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	4	\$88.36
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	4	\$155.12
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	1	\$17.48
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$25.63	1	\$25.63
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shi	Acre	\$1.28	1	\$1.28



Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.59	872	\$514.48
Tree shelter, solid tube type, 4" x 48"	1566	4" x 48" tree tube for protection from animal damage. Materials only.	Each	\$4.14	100	\$414.00
Stakes, wood, 1" x 1" x 48"	1578	1" x 1" x 48" wood stakes to fasten items in place. Includes materials only.	Each	\$2.04	100	\$204.00
<b>Mobilization</b>						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: E391136Z - Increase riparian forest buffer width to enhance wildlife habitat

Scenario #1 - Riparian forest buffer-habitat

Scenario Description:

Where an existing forested riparian area is located along a river, stream, pond, lake, or other waterbody, increase the diversity of native species, control invasive species, install fencing and relocate equipment operations, trails, and livestock, and increase the width of the buffer.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 391 - Riparian Forest Buffer

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 391 - Riparian Forest Buffer

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: \$3,490.26

Scenario Cost/Unit: \$1,745.13

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	16	\$355.52
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	2	\$105.88
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	4	\$101.08
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	16	\$192.64
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.82	\$340.47
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.72	\$298.80
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.46	\$91.86
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	4	\$88.36
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	4	\$155.12
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	1	\$17.48
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$25.63	1	\$25.63
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shi	Acre	\$1.28	1	\$1.28

Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.59	872	\$514.48
Tree shelter, solid tube type, 4" x 48"	1566	4" x 48" tree tube for protection from animal damage. Materials only.	Each	\$4.14	100	\$414.00
Stakes, wood, 1" x 1" x 48"	1578	1" x 1" x 48" wood stakes to fasten items in place. Includes materials only.	Each	\$2.04	100	\$204.00
<b>Mobilization</b>						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: E393118Z - Extend existing filter strip to reduce excess nutrients in surface water

Scenario #1 - Extend filter strips- nut runoff

Scenario Description:

Extend existing filter strips for water quality protection (reduce excess nutrients in surface water). Extend the existing buffer for a total of 60 feet or more to enhance water quality functions. The extended buffers must be composed of at least 5 species of non-noxious, wildlife friendly grasses and/or perennial forbs best suited to site conditions. Include species that provide pollinator food and habitat where possible.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 393 - Filter Strip

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 393 - Filter Strip

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$918.75

Scenario Cost/Unit: \$918.75

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	1	\$11.37
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	\$7.85	1	\$7.85
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.41	\$170.24
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.36	\$149.40
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.23	\$45.93
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50
Materials						
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	\$58.50	1	\$58.50
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: E393122Z - Extend existing filter strip to reduce excess pathogens and chemicals in surface water

Scenario #1 - Extend filter strips-pathogen runoff

Scenario Description:

Extend existing filter strips for water quality protection (reduce excess pathogens and chemicals from manure, bio-solids or compost applications in surface waters ).  
Extend the existing buffer for a total of 60 feet or more to enhance water quality functions. The extended buffers must be composed of at least 5 species of non-noxious, wildlife friendly grasses and/or perennial forbs best suited to site conditions. Include species that provide pollinator food and habitat where possible.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 393 - Filter Strip

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 393 - Filter Strip

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$918.75

Scenario Cost/Unit: \$918.75

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	1	\$11.37
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	\$7.85	1	\$7.85
Foregone Income						
Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.41	\$170.24
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.36	\$149.40
Fl, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.23	\$45.93
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50
Materials						
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	\$58.50	1	\$58.50
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: E393126Z - Extend existing filter strip to reduce excess sediment in surface water

Scenario #1 - Extend filter strips-sediment

Scenario Description:

Extend existing filter strips for water quality protection (reduce excess sediment in surface waters ). Extend the existing buffer for a total of 60 feet or more to enhance water quality functions. The extended buffers must be composed of at least 5 species of non-noxious, wildlife friendly grasses and/or perennial forbs best suited to site conditions. Include species that provide pollinator food and habitat where possible.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 393 - Filter Strip

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 393 - Filter Strip

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$918.75

Scenario Cost/Unit: \$918.75

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$11.37	1	\$11.37
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Cultipacking	1100	Includes equipment, power unit and labor costs.	Acre	\$7.85	1	\$7.85
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.41	\$170.24
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.36	\$149.40
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.23	\$45.93
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50
Materials						
Five Species Mix, Cool Season, Annual Grasses and Legumes	2320	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	\$58.50	1	\$58.50
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: E395137X - Stream habitat improvement through placement of woody biomass

Scenario #1 - Stream habitat improvement with wood

Scenario Description:

Flexible placement of wood (unanchored/unpinned) in small, 1st and 2nd order streams to improve stream habitat conditions for aquatic species and natural stream processes.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 395 - Stream Habitat Improvement and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 395 - Stream Habitat Improvement and Management

Feature Measure: Bankfull width X Length

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$20,553.56

Scenario Cost/Unit: \$20,553.56

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$167.73	16	\$2,683.68
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	\$98.65	8	\$789.20
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$28.30	24	\$679.20
Materials						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic Yard	\$25.23	20	\$504.60
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	30	\$767.10
Compost	265	A mixture of decaying organic matter, as from leaves and manure, used to improve soil structure and provide nutrients.	Ton	\$43.27	1	\$43.27
Cuttings, woody, large size	1309	Woody pole cuttings or posts 2" to 6" in diameter and 6' long. Includes materials and shipping only.	Each	\$17.90	300	\$5,370.00
Boulder	1761	Rock boulders (approximately 5 ft dia. 6.67 Tons) Includes materials and delivery (up to 100 miles) only.	Ton	\$34.32	40	\$1,372.80
Steel, rebar	1832	Steel rebar, grade 60. Materials only.	Pound	\$0.52	50	\$26.00
Aggregate, river rock	1834	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	\$21.45	15	\$321.75
Log, un-anchored	2035	Price of log picked up at the Mill. Includes material only.	Ton	\$227.38	30	\$6,821.40
Root Wad	2045	Tree stump buried into the streambank with the roots left exposed. Includes material only.	Ton	\$8.91	20	\$178.20
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	2	\$996.36

Practice: E399137X - Fishpond management for native aquatic and terrestrial species

Scenario #1 - Fishpond mgmt

Scenario Description:

Pond rehabilitation (e.g., dredging), buffer, and watershed management actions are taken to improve habitat for native species of fish, amphibians, and shorebirds.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 399 - Fishpond Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 399 - Fishpond Management

Feature Measure: Pond area + buffer area

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: \$3,581.50

Scenario Cost/Unit: \$1,790.75

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	4	\$88.88
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	1	\$21.78
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	3	\$106.08
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	32	\$703.36
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$37.13	1	\$37.13
Herbicide, Diquat dibromide	1820	Aquatic herbicide and plant growth regulator. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Gallon	\$113.80	1	\$113.80
Native Aquatic Plants, Emergent or Submerged	2336	Native aquatic emergent or submerged. All required materials for establishing vegetation. Includes material and shipping.	Each	\$1.33	1000	\$1,330.00
Specialized native grass and forb mix	2619	A mix of native grass and forbs to be used for specialized purposes such as wildlife (including pollinators) or ecosystem restoration, requiring species not readily available and/or difficult to produce and harvest. Includes material and shipping only	Acre	\$998.71	1	\$998.71
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50



Practice: E449114Z1 - Advanced IWM--Soil moisture is monitored, recorded, and used in decision making

Scenario #1 - Advanced IWM-soil moisture

Scenario Description:

Advanced irrigation water management using soil moisture monitoring (one sensor per 40 acres or more) with data loggers. Record keeping is such that a daily water balance is calculated, and future irrigations forecast.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 449 - Irrigation Water Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 449 - Irrigation Water Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 80.0

Scenario Total Cost: \$4,322.65

Scenario Cost/Unit: \$54.03

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	40	\$1,414.40
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	6	\$559.50
Materials						
Switches and Controls, Wi-Fi system and software	1194	Software with built-in cellular or Wi-Fi communication commonly used to control pumps and irrigation systems	Each	\$449.51	1	\$449.51
Data Logger with Telemetry System	1454	Data Logger W/Graphic Output for water management and telemetry - data communication device with power supply in a weather proof enclosure. Equipment only.	Each	\$1,679.44	1	\$1,679.44

Practice: E449114Z2 - Advanced IWM--Weather is monitored, recorded and used in decision making

Scenario #1 - Advanced IWM-weather

Scenario Description:

Advanced irrigation water management using on-site weather measurements to calculate real-time evapotranspiration and forecast future water use by plants. Record keeping is such that a daily water balance is calculated and future irrigations forecast.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 449 - Irrigation Water Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 449 - Irrigation Water Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 80.0

Scenario Total Cost: \$5,109.43

Scenario Cost/Unit: \$63.87

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	20	\$439.60
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	4	\$373.00
Materials						
Solar Panels, fixed cost portion	1031	Fixed cost portion of the Solar Panels. This portion is a base cost for all Solar Panels and is not dependant on KiloWatt. The total cost of any Solar Panels will include this fixed cost plus a variable cost portion. The completed Solar Panels will incl	Each	\$460.51	1	\$460.51
Switches and Controls, temp sensors	1192	Temperature and soil moisture sensors installed as part of an electronic monitoring (with or without wireless telecommunications) commonly used to control pumps and irrigation systems	Each	\$655.75	1	\$655.75
Data Logger with Telemetry System	1454	Data Logger W/Graphic Output for water management and telemetry - data communication device with power supply in a weather proof enclosure. Equipment only.	Each	\$1,679.44	1	\$1,679.44
Soil Moisture Meter	1455	Soil Moisture Sensor Reader. Equipment only.	Each	\$285.50	1	\$285.50
Soil Moisture Sensor	1456	Soil moisture resistance sensor W/10' cables. Equipment only.	Each	\$36.74	2	\$73.48
Weather Station, Advanced	2550	Advance Weather Station which collects and records recording rainfall, humidity, barometric pressure, wind speed, temperature, and solar radiation from a solar powered self-standing tripod to an advance weather recording console. Used for both 449 advance	Each	\$1,070.10	1	\$1,070.10
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: E449114Z3 - Complete pumping plant eval for all pumps on a farm to determine the VFD potential

Scenario #1 - Pumping plant evaluation for VFD

Scenario Description:

On branching systems, or pumps that service multiple fields, or multiple pumps, install a Variable Frequency Drive motor controller(s) if recommended in the pump test and the simple payback in terms of energy savings is less than 10 years.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 449 - Irrigation Water Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 449 - Irrigation Water Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 640.0

Scenario Total Cost: \$3,498.10

Scenario Cost/Unit: \$5.47

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	35	\$3,107.65
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	10	\$318.40
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: E449114Z4 - Intermittent flooding of rice fields

Scenario #1 - Intermittent flooding of rice fields

Scenario Description:

Rice fields are drained and allowed to "dry down" to a saturated soil condition prior to re-flooding the field

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 449 - Irrigation Water Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 449 - Irrigation Water Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: \$2,965.76

Scenario Cost/Unit: \$74.14

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	40	\$879.20
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	6	\$232.68
Materials						
Flow Meter, with mechanical Index	1450	10 inch, Turbine Type Flow Meter with Mechanical Index, permanently installed. Includes material, labor and installation.	Each	\$1,853.88	1	\$1,853.88

Practice: E449144Z - Complete pumping plant evaluation for all pumps on a farm.

Scenario #1 - Pumping plant evaluation

Scenario Description:

Rehabilitate/replace/reconfigure all pumps that have the potential to perform 10% more efficiently as identified in the pump test.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 449 - Irrigation Water Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 449 - Irrigation Water Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 640.0

Scenario Total Cost: \$3,498.10

Scenario Cost/Unit: \$5.47

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, professional engineer	1297	Conservation Activity Plan labor to apply knowledge of engineering technology and biological science to agricultural problems concerned with power and machinery, electrification, structures, soil and water conservation, and processing of agricultural prod	Hour	\$88.79	35	\$3,107.65
CAP Labor, Skilled	1604	Conservation Activity Plan labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$31.84	10	\$318.40
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: E472118Z - Manage livestock access to streams/ditches/other waterbodies to reduce nutrients in surface water

Scenario #1 - Livestock access to waterbody-nutrients

Scenario Description:

Installation of structures and implementation of grazing management actions that restrict livestock access to streams, ditches, and other waterbodies in order to reduce nutrient loading to surface waters.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 472 - Access Control

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 472 - Access Control

Feature Measure: (Stream length protected \* 2) + ((C

Scenario Unit:: Foot

Scenario Typical Size: 1,320.0

Scenario Total Cost: \$2,974.98

Scenario Cost/Unit: \$2.25

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	\$7.46	5	\$37.30
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	5	\$111.10
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	5	\$126.35
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	33	\$725.34
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	5	\$110.45
Materials						
Wire, Barbed, Galvanized, 12.5 Gauge, 1,320' roll	1	Galvanized 12.5 gauge, 1,320' roll. Includes materials and shipping only.	Each	\$71.19	4	\$284.76
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	\$6.26	20	\$125.20
Post, Wood, CCA treated, 6" x 8'	12	Wood Post, End 6" X 8', CCA Treated. Includes materials and shipping only.	Each	\$15.10	8	\$120.80
Post, Steel T, 1.33 lbs, 6'	15	Steel Post, Studded 6' - 1.33 lb. Includes materials and shipping only.	Each	\$6.68	90	\$601.20
Fence, Wire Assembly, Barbed Wire	30	Brace pins, battens, clips, staples. Includes materials and shipping only.	Foot	\$0.17	1320	\$224.40
Gate, Pipe, 12'	1057	6 rail tube gate, 16 gauge. Includes materials and shipping only.	Each	\$166.29	2	\$332.58
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: E472122Z - Manage livestock access to streams/ditches/other waterbodies to reduce pathogens in surface water

Scenario #1 - Livestock access to waterbody-pathogens

Scenario Description:

Installation of structures and implementation of grazing management actions that restrict livestock access to streams, ditches, and other waterbodies in order to reduce the introduction of pathogens to surface waters.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 472 - Access Control

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 472 - Access Control

Feature Measure: (Stream length protected \* 2) + ((C

Scenario Unit:: Foot

Scenario Typical Size: 1,320.0

Scenario Total Cost: \$2,974.98

Scenario Cost/Unit: \$2.25

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	\$7.46	5	\$37.30
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	5	\$111.10
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	5	\$126.35
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	33	\$725.34
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	5	\$110.45
Materials						
Wire, Barbed, Galvanized, 12.5 Gauge, 1,320' roll	1	Galvanized 12.5 gauge, 1,320' roll. Includes materials and shipping only.	Each	\$71.19	4	\$284.76
Post, Wood, CCA treated, 3-4" x 7'	9	Wood Post, Line 3-4" X 7', CCA Treated. Includes materials and shipping only.	Each	\$6.26	20	\$125.20
Post, Wood, CCA treated, 6" x 8'	12	Wood Post, End 6" X 8', CCA Treated. Includes materials and shipping only.	Each	\$15.10	8	\$120.80
Post, Steel T, 1.33 lbs, 6'	15	Steel Post, Studded 6' - 1.33 lb. Includes materials and shipping only.	Each	\$6.68	90	\$601.20
Fence, Wire Assembly, Barbed Wire	30	Brace pins, battens, clips, staples. Includes materials and shipping only.	Foot	\$0.17	1320	\$224.40
Gate, Pipe, 12'	1057	6 rail tube gate, 16 gauge. Includes materials and shipping only.	Each	\$166.29	2	\$332.58
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: E484106Z - Mulching to improve soil health

Scenario #1 - Mulching to improve soil health

Scenario Description:

Implement a crop rotation which utilizes mulch and addresses all four principle components of soil health: increases diversity of the cropping system; maintains residue throughout the year; keeps a living root; and minimizes soil chemical, physical and biological disturbance. Plant-based mulching materials will be applied at least once during the rotation. The rotation will include at least 4 different crop and/or cover crop types (crop types include cool season grass, warm season grass, cool season broadleaf, warm season broadleaf) grown in a sequence that will produce a positive trend in the Organic Matter (OM) subfactor value over the life of the rotation, as determined by the Soil Conditioning Index (SCI). RUSLE2 or WEPS must be used to document the rotation and SCI calculations.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 484 - Mulching

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 484 - Mulching

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$186.50

Scenario Cost/Unit: \$1.87

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50



**Practice:** E511137Z1 - Harvest of crops (hay or small grains) using measures that allow desired species to flush or escape

**Scenario #1** - Harvest using wildlife friendly methods

**Scenario Description:**

Harvest of crops (hay or small grains) using conservation measures that allow desired species to flush or escape. <species list State Wildlife Action Plan> Conservation measures include timing of harvest, idling land during the nesting or fawning period, and applying harvest techniques that reduce mortality to wildlife.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 511 - Forage Harvest Management

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 511 - Forage Harvest Management

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 50.0

**Scenario Total Cost:** \$185.69

**Scenario Cost/Unit:** \$3.71

**Cost Details:**

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Foregone Income</b>						
Fl, Hay, General Grass	2122	General Grass Hay is Primary Land Use	Ton	\$42.52	1.67	\$71.01
<b>Labor</b>						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96

Practice: E511137Z2 - Forage harvest management that helps maintain or improve wildlife habitat (cover and shelter)

Scenario #1 - FHM for cover and shelter

Scenario Description:

The timely cutting and removal of forages from the field as hay, green-chop, or ensilage in such as way and time frames so as optimize both forage yield/quality and wildlife cover and shelter.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 511 - Forage Harvest Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 511 - Forage Harvest Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$455.03

Scenario Cost/Unit: \$4.55

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	25	\$416.25
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78

Practice: E511139Z1 - Enhanced wildlife habitat on expired grass/legume covered CRP acres

Scenario #1 - FHM on expired CRP acres

Scenario Description:

Implement a forage management plan focused on wildlife habitat for the benefit of selected wildlife species on expired CRP grass/legume covered acres that have CRP conservation cover. Identify the target wildlife species or suite of species described in need of action within the State Wildlife Action Plan.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 511 - Forage Harvest Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 511 - Forage Harvest Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$7,308.94

Scenario Cost/Unit: \$146.18

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Foregone Income						
Fl, Hay, General Grass	2122	General Grass Hay is Primary Land Use	Ton	\$42.52	166.5	\$7,079.58
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	4	\$141.44
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	4	\$87.92

Practice: E511139Z2 - Forage harvest management that helps maintain wildlife habitat continuity (space)

Scenario #1 - FHM for habitat space continuity

Scenario Description:

The timely cutting and removal of forages from the field as hay, green-chop, or ensilage in such as way and time frames so as optimize both forage yield/quality and wildlife cover and shelter for habitat and/or continuity between otherwise disconnected habitats.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 511 - Forage Harvest Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 511 - Forage Harvest Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$185.69

Scenario Cost/Unit: \$3.71

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Foregone Income						
Fl, Hay, General Grass	2122	General Grass Hay is Primary Land Use	Ton	\$42.52	1.67	\$71.01
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96

Practice: E512101Z1 - Cropland conversion to grass-based agriculture to reduce water erosion

Scenario #1 - Convert crop to grass for water erosion

Scenario Description:

Conversion of cropped land to grass-based agriculture. Mixtures of perennial grasses, forbs, and/or legume species are established on cropland where annually-seeded cash crops have been grown.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$494.56

Scenario Cost/Unit: \$4.95

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2319	Cool season, introduced grass and legume mix. Includes material and shipping only.	Acre	\$20.85	20	\$417.00

Practice: E512101Z2 - Forage and biomass planting for water erosion to improve soil health

Scenario #1 - Forage planting for SH

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of herbaceous species suitable for pasture, hay, or biomass production that can provide for reduced soil erosion, improving soil health.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,458.76

Scenario Cost/Unit: \$14.59

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
One Species, Warm Season, Native Perennial Grass	2322	Native, warm season perennial grass. Includes material and shipping only.	Acre	\$69.06	20	\$1,381.20

Practice: E512102Z - Cropland conversion to grass-based agriculture to reduce wind erosion

Scenario #1 - Convert crop to grass for wind erosion

Scenario Description:

Conversion of cropped land to grass-based agriculture. Mixtures of perennial grasses, forbs, and/or legume species are established on cropland where annually-seeded cash crops have been grown.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,114.58

Scenario Cost/Unit: \$11.15

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78
Materials						
Three plus Species Mix, Warm Season, Native Perennial	2327	Native, warm season perennial grass. Includes material and shipping only.	Acre	\$215.16	5	\$1,075.80

Practice: E512106Z1 - Cropland conversion to grass-based agriculture for soil organic matter improvement

Scenario #1 - Convert crop to grass for SOM

Scenario Description:

Conversion of cropped land to grass-based agriculture. Mixtures of perennial grasses, forbs, and/or legume species are established on cropland where annually-seeded cash crops have been grown.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,383.76

Scenario Cost/Unit: \$13.84

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	2	\$43.96
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	4	\$373.00
Materials						
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2317	Cool season grass and legume mix. Includes material and shipping only.	Acre	\$48.34	20	\$966.80



Practice: E512106Z2 - Forage plantings that can help increase organic matter in depleted soils

Scenario #1 - Forage planting for SOM

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of herbaceous species suitable for pasture, hay, or biomass production that can help improve soil quality of depleted sites through increase or conservation of the organic matter in the soil.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,460.61

Scenario Cost/Unit: \$14.61

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	25	\$416.25
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2317	Cool season grass and legume mix. Includes material and shipping only.	Acre	\$48.34	20	\$966.80

Practice: E512126Z - Cropland conversion to grass-based agriculture to reduce sediment loading

Scenario #1 - Convert crop to grass-reduce sed loading

Scenario Description:

Conversion of cropped land to grass-based agriculture. Mixtures of perennial grasses, forbs, and/or legume species are established on cropland where annually-seeded cash crops have been grown.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,229.38

Scenario Cost/Unit: \$12.29

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78
Materials						
Three Species Mix, Warm Season, Annual Grasses and Legumes	2326	Warm season annual grass and legume mix. Includes material and shipping only.	Acre	\$59.53	20	\$1,190.60

Practice: E512132Z1 - Forage and biomass planting that produces feedstock for biofuels or energy production

Scenario #1 - Forage planting for feedstocks

Scenario Description:

Conversion of cropped land to grass-based agriculture. Mixtures of perennial grasses, forbs, and/or legume species are established on cropland where annually-seeded cash crops have been grown.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$3,639.50

Scenario Cost/Unit: \$36.40

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50
Materials						
One Species, Warm Season, Native Perennial Grass	2322	Native, warm season perennial grass. Includes material and shipping only.	Acre	\$69.06	50	\$3,453.00

Practice: E512132Z2 - Native grasses or legumes in forage base to improve plant productivity and health

Scenario #1 - Native grasses/legumes-plant health

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of perennial, herbaceous species that can provide the structure and composition needed to enhance livestock and wildlife habitat, particularly when targeted forage supply and quality, cover, and shelter are not available in other pastures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$2,173.58

Scenario Cost/Unit: \$21.74

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	1	\$21.98
Materials						
Three plus Species Mix, Warm Season, Native Perennial	2327	Native, warm season perennial grass. Includes material and shipping only.	Acre	\$215.16	10	\$2,151.60

Practice: E512133Z1 - Native grasses or legumes in forage base to improve plant community structure and composition

Scenario #1 - Native grasses/legumes-structure/comp

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of perennial, herbaceous species that can provide the structure and composition needed to enhance livestock and wildlife habitat, particularly when targeted forage supply and quality, cover, and shelter are not available in other pastures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$5,565.50

Scenario Cost/Unit: \$55.66

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50
Materials						
Three plus Species Mix, Warm Season, Native Perennial	2327	Native, warm season perennial grass. Includes material and shipping only.	Acre	\$215.16	25	\$5,379.00

Practice: E512133Z2 - Forage plantings that enhance bird habitat (structure and composition)

Scenario #1 - Forage planting for structure/comp

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of herbaceous species suitable for pasture, hay, or biomass production that can provide cover and shelter components of bird habitat.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$7,511.82

Scenario Cost/Unit: \$75.12

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
Materials						
One Species, Warm Season, Native Perennial Grass	2322	Native, warm season perennial grass. Includes material and shipping only.	Acre	\$69.06	25	\$1,726.50
Three Species Mix, Native Forb	2333	Native forb mix. Includes material and shipping only.	Acre	\$571.46	10	\$5,714.60

Practice: E512136Z1 - Establish pollinator and/or beneficial insect food habitat

Scenario #1 - Establish pollinator habitat-food

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of herbaceous species that can provide nectar for pollinators and forage and other habitat values for wildlife and livestock, particularly at times when targeted nectar, forage supply and quality, cover, and shelter are not available in other pastures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$5,807.85

Scenario Cost/Unit: \$58.08

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	1	\$93.25
Materials						
Three Species Mix, Native Forb	2333	Native forb mix. Includes material and shipping only.	Acre	\$571.46	10	\$5,714.60

Practice: E512136Z2 - Native grass or legumes in forage base to provide wildlife food

Scenario #1 - Native grasses/legumes-wildlife food

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of perennial, herbaceous species that can provide the structure and composition needed to enhance livestock and wildlife habitat, particularly when targeted forage supply and quality, cover, and shelter are not available in other pastures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$5,807.85

Scenario Cost/Unit: \$58.08

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	1	\$93.25
Materials						
Three Species Mix, Native Forb	2333	Native forb mix. Includes material and shipping only.	Acre	\$571.46	10	\$5,714.60



Practice: E512137Z - Forage plantings that enhance bird habitat (cover and shelter)

Scenario #1 - Forage planting for cover and shelter

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of herbaceous species suitable for pasture, hay, or biomass production that can provide cover and shelter components of bird habitat.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$7,511.82

Scenario Cost/Unit: \$75.12

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	2	\$70.72
Materials						
One Species, Warm Season, Native Perennial Grass	2322	Native, warm season perennial grass. Includes material and shipping only.	Acre	\$69.06	25	\$1,726.50
Three Species Mix, Native Forb	2333	Native forb mix. Includes material and shipping only.	Acre	\$571.46	10	\$5,714.60

Practice: E512138Z - Establish wildlife corridors to enhance access to water

Scenario #1 - Corridors for water access

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of perennial, herbaceous species that can provide cover needed for wildlife species of concern to move from food/cover/water sources to other food/cover/water sources as needed for their life cycles, and/or to enhance the utility of underused wildlife habitat areas.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$2,645.41

Scenario Cost/Unit: \$26.45

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	25	\$416.25
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Three plus Species Mix, Warm Season, Native Perennial	2327	Native, warm season perennial grass. Includes material and shipping only.	Acre	\$215.16	10	\$2,151.60

Practice: E512139Z1 - Establish wildlife corridors to provide habitat continuity

Scenario #1 - Corridors for habitat continuity

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of perennial, herbaceous species that can provide cover needed for wildlife species of concern to move from food/cover/water sources to other food/cover/water sources as needed for their life cycles, and/or to enhance the utility of underused wildlife habitat areas.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$2,535.90

Scenario Cost/Unit: \$25.36

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	10	\$217.80
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	10	\$166.50
Materials						
Three plus Species Mix, Warm Season, Native Perennial	2327	Native, warm season perennial grass. Includes material and shipping only.	Acre	\$215.16	10	\$2,151.60

Practice: E512139Z2 - Establish pollinator and/or beneficial insect habitat continuity (space)

Scenario #1 - Establish pollinator habitat-space

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of herbaceous species that can provide nectar for pollinators and forage and other habitat values for wildlife and livestock, particularly at times when targeted nectar, forage supply and quality, cover, and shelter are not available in other pastures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$5,901.10

Scenario Cost/Unit: \$59.01

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50
Materials						
Three Species Mix, Native Forb	2333	Native forb mix. Includes material and shipping only.	Acre	\$571.46	10	\$5,714.60

Practice: E512139Z3 - Establish Monarch butterfly habitat in pastures

Scenario #1 - Establish Monarch Butterfly Habitat in pastures

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of herbaceous species that can provide nectar for Monarch butterflies and forage and other habitat values for wildlife and livestock, particularly at times when targeted nectar, forage supply and quality, cover, and shelter are not available in other pastures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$5,901.10

Scenario Cost/Unit: \$59.01

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50
Materials						
Three Species Mix, Native Forb	2333	Native forb mix. Includes material and shipping only.	Acre	\$571.46	10	\$5,714.60

Practice: E512140Z - Native grasses or legumes in forage base

Scenario #1 - Native grasses or legumes in forage base

Scenario Description:

Establishing adapted and/or compatible species, varieties, or cultivars of perennial, herbaceous species that can provide the structure and composition needed to enhance livestock and wildlife habitat, particularly when targeted forage supply and quality, cover, and shelter are not available in other pastures.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 512 - Forage and Biomass Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$5,456.56

Scenario Cost/Unit: \$54.57

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Three plus Species Mix, Warm Season, Native Perennial	2327	Native, warm season perennial grass. Includes material and shipping only.	Acre	\$215.16	25	\$5,379.00

**Practice:** E528101Z - Improved grazing management for water erosion through monitoring activities

**Scenario #1** - Grazing mgmt for water erosion

**Scenario Description:**

Three predominant key grazing areas are evaluated utilizing the Rangeland Health Assessment protocols to determine how well the ecological processes of the site(s) are functioning. Departure from reference categories will be determined, justified, and ratings described for soil and site stability, hydrologic function, and biotic integrity. Utilizing knowledge learned from this as a part of the ranch resource assessment, a Certified Range Management Consultant or Certified Professional in Range Management will provide recommendations or follow-up evaluations toward mitigating some of the degradation risks that are initially identified.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 1,000.0

**Scenario Total Cost:** \$1,788.56

**Scenario Cost/Unit:** \$1.79

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Acquisition of Technical Knowledge</b>						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
<b>Equipment Installation</b>						
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	8	\$230.72
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	4	\$155.12
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	12	\$1,119.00

Practice: E528104Z - Grazing management that protects sensitive areas from gully erosion

Scenario #1 - Grazing mgmt-sensitive areas-erosion

Scenario Description:

Grazing management employed will provide cover and density needed in the watershed in order to protect sensitive areas such as sinkholes, streams, highly erodible areas, or locations with plants that cannot tolerate defoliation.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1,000.0

Scenario Total Cost: \$1,577.12

Scenario Cost/Unit: \$1.58

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	4	\$88.88
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	12	\$346.08
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	17	\$373.66
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Wire, Polytape	7	Wire, Polytape for electric fence. Rolls of 655' to 825'. Includes materials and shipping only.	Each	\$50.07	1	\$50.07
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	\$257.52	1	\$257.52



Practice: E528105Z - Prescribed grazing that improves or maintains riparian and watershed function-erosion

Scenario #1 - Prescribed grazing-erosion

Scenario Description:

Grazing management employed will provide cover and density needed in the watershed in order to reduce runoff, improve infiltration, provide for above ground water filtration and sustain applicable fish and wildlife species habitat.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$894.82

Scenario Cost/Unit: \$8.95

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	10	\$166.50
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	\$47.61	1	\$47.61
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43

Practice: E528107Z1 - Improved grazing management for soil compaction through monitoring activities

Scenario #1 - Grazing mgmt to improve compaction

Scenario Description:

Managing the harvest of vegetation with grazing and/or browsing animals as adjusted when following recommendations of a Certified Forage and Grassland Professional, Certified Range Management Consultant, or Certified Professional in Range Management, generated through pasture condition scoring (PCS).

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$704.98

Scenario Cost/Unit: \$7.05

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Foregone Income

FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	10	\$166.50
------------------	------	---------------------------------	-------------------	---------	----	----------

Labor

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	4	\$87.92
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	4	\$373.00

**Practice:** E528107Z2 - Improved grazing management for soil compaction on rangeland through monitoring activities

**Scenario #1** - Grazing mgmt-compaction on rangeland

**Scenario Description:**

Three predominant key grazing areas are evaluated utilizing the Rangeland Health Assessment protocols to determine how well the ecological processes of the site(s) are functioning. Departure from reference categories will be determined, justified, and ratings described for soil and site stability, hydrologic function, and biotic integrity. Utilizing knowledge learned from this as a part of the ranch resource assessment, a Certified Range Management Consultant or Certified Professional in Range Management will provide recommendations or follow-up evaluations toward mitigating some of the degradation risks that are initially identified.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 1,000.0

**Scenario Total Cost:** \$1,788.56

**Scenario Cost/Unit:** \$1.79

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Acquisition of Technical Knowledge</b>						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
<b>Equipment Installation</b>						
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	8	\$230.72
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	4	\$155.12
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	12	\$1,119.00

Practice: E528118Z1 - Prescribed grazing that maintains/improves riparian/watershed function impairment from nutrients

Scenario #1 - Prescribed grazing-nut runoff

Scenario Description:

Grazing management employed will provide cover and density needed in the watershed in order to reduce runoff, improve infiltration, provide for above ground water filtration and sustain applicable fish and wildlife species habitat.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,468.69

Scenario Cost/Unit: \$14.69

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	6	\$173.04
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	10	\$166.50
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	\$47.61	4	\$190.44
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	\$257.52	1	\$257.52

Practice: E528118Z2 - Grazing management that protects sensitive areas-surface water from nutrients

Scenario #1 - Grazing mgmt-sensitive areas-nut runoff

Scenario Description:

Grazing management employed will provide cover and density needed in the watershed in order to protect sensitive areas such as sinkholes, streams, highly erodible areas, or locations with plants that cannot tolerate defoliation.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1,000.0

Scenario Total Cost: \$1,727.33

Scenario Cost/Unit: \$1.73

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	4	\$88.88
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	12	\$346.08
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	17	\$373.66
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Wire, Polytape	7	Wire, Polytape for electric fence. Rolls of 655' to 825'. Includes materials and shipping only.	Each	\$50.07	4	\$200.28
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	\$257.52	1	\$257.52

Practice: E528119Z - Grazing management that protects sensitive areas-ground water from nutrients

Scenario #1 - Grazing mgmt-sensitive area-nut sub water

Scenario Description:

Grazing management employed will provide cover and density needed in the watershed in order to protect sensitive areas such as sinkholes, streams, highly erodible areas, or locations with plants that cannot tolerate defoliation.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1,000.0

Scenario Total Cost: \$1,727.33

Scenario Cost/Unit: \$1.73

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	4	\$88.88
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	12	\$346.08
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	17	\$373.66
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Wire, Polytape	7	Wire, Polytape for electric fence. Rolls of 655' to 825'. Includes materials and shipping only.	Each	\$50.07	4	\$200.28
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	\$257.52	1	\$257.52

**Practice:** E528122Z - Prescribed grazing that maintains/improves riparian/watershed function-pathogens/chemicals

**Scenario #1** - Prescribed grazing-pathogens

**Scenario Description:**

Grazing management employed will provide cover and density needed in the watershed in order to reduce runoff, improve infiltration, provide for above ground water filtration and sustain applicable fish and wildlife species habitat.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 100.0

**Scenario Total Cost:** \$1,468.69

**Scenario Cost/Unit:** \$14.69

**Cost Details:**

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Acquisition of Technical Knowledge</b>						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
<b>Equipment Installation</b>						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	6	\$173.04
<b>Foregone Income</b>						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	10	\$166.50
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
<b>Materials</b>						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	\$47.61	4	\$190.44
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	\$257.52	1	\$257.52

**Practice:** E528126Z - Prescribed grazing that maintains/improves riparian/watershed function-min sediment in surface water

**Scenario #1** - Prescribed grazing-sediment

**Scenario Description:**

Grazing management employed will provide cover and density needed in the watershed in order to reduce runoff, improve infiltration, provide for above ground water filtration and sustain applicable fish and wildlife species habitat.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 100.0

**Scenario Total Cost:** \$1,302.19

**Scenario Cost/Unit:** \$13.02

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Acquisition of Technical Knowledge</b>						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
<b>Equipment Installation</b>						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	6	\$173.04
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
<b>Materials</b>						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	\$47.61	4	\$190.44
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	\$257.52	1	\$257.52



Practice: E528132Z1 - Improved grazing mgmt for plant productivity/health through monitoring

Scenario #1 - Grazing mgmt-plant health

Scenario Description:

Managing the harvest of vegetation with grazing and/or browsing animals as adjusted when following recommendations of a Certified Forage and Grassland Professional, Certified Range Management Consultant, or Certified Professional in Range Management, generated through pasture condition scoring (PCS).

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$882.54

Scenario Cost/Unit: \$8.83

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	30	\$499.50
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	4	\$373.00
Materials						
Test, Soil Test, Standard	299	Includes materials, shipping, labor, and equipment costs.	Each	\$10.04	1	\$10.04

Practice: E528132Z2 - Stockpiling cool season forage to improve plant productivity and health

Scenario #1 - Stockpile cool season forage-plant prod

Scenario Description:

Grazing management employed to stop grazing events of selected paddock(s) to allow pasture forages to grow to maximum vegetative biomass accumulation before the end of the growing season.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$2,215.98

Scenario Cost/Unit: \$22.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	6	\$173.04
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	10	\$166.50
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	\$47.61	1	\$47.61
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43
Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.43	2000	\$860.00
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	\$257.52	1	\$257.52
Test, Soil Test, Standard	299	Includes materials, shipping, labor, and equipment costs.	Each	\$10.04	3	\$30.12

**Practice:** E528132Z3 - Improved grazing management for plant productivity/health through monitoring

**Scenario #1** - Gazing mgmt-plant health

**Scenario Description:**

Three predominant key grazing areas are evaluated utilizing the Rangeland Health Assessment protocols to determine how well the ecological processes of the site(s) are functioning. Departure from reference categories will be determined, justified, and ratings described for soil and site stability, hydrologic function, and biotic integrity. Utilizing knowledge learned from this as a part of the ranch resource assessment, a Certified Range Management Consultant or Certified Professional in Range Management will provide recommendations or follow-up evaluations toward mitigating some of the degradation risks that are initially identified.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 1,000.0

**Scenario Total Cost:** \$1,788.56

**Scenario Cost/Unit:** \$1.79

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Acquisition of Technical Knowledge</b>						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
<b>Equipment Installation</b>						
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	8	\$230.72
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	4	\$155.12
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	12	\$1,119.00

Practice: E528133Z1 - Stockpiling cool season forage to improve structure and composition.

Scenario #1 - Stockpile cool season forage-structure

Scenario Description:

Grazing management employed will stop grazing events of selected paddock(s) to allow pasture forages to grow to maximum vegetative biomass accumulation before the end of the growing season.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$2,215.98

Scenario Cost/Unit: \$22.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	6	\$173.04
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	10	\$166.50
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	\$47.61	1	\$47.61
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43
Nitrogen (N), Urea	71	Price per pound of N supplied by Urea. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.43	2000	\$860.00
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	\$257.52	1	\$257.52
Test, Soil Test, Standard	299	Includes materials, shipping, labor, and equipment costs.	Each	\$10.04	3	\$30.12

Practice: E528133Z2 - Grazing management for improving quantity/quality of plant structure/composition for wildlife

Scenario #1 - Grazing mgmt-structure for wildlife

Scenario Description:

Managing the harvest of vegetation with grazing and/or browsing animals for the purpose of improving or maintaining the structure and composition of the plant community that is available for wildlife.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$288.53

Scenario Cost/Unit: \$2.89

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	15	\$249.75
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78

**Practice:** E528133Z3 - Improved grazing management for plant structure and composition through monitoring activities

**Scenario #1 - Grazing mgmt-structure**

**Scenario Description:**

Three predominant key grazing areas are evaluated utilizing the Rangeland Health Assessment protocols to determine how well the ecological processes of the site(s) are functioning. Departure from reference categories will be determined, justified, and ratings described for soil and site stability, hydrologic function, and biotic integrity. Utilizing knowledge learned from this as a part of the ranch resource assessment, a Certified Range Management Consultant or Certified Professional in Range Management will provide recommendations or follow-up evaluations toward mitigating some of the degradation risks that are initially identified.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 1,000.0

**Scenario Total Cost:** \$1,788.56

**Scenario Cost/Unit:** \$1.79

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Acquisition of Technical Knowledge</b>						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
<b>Equipment Installation</b>						
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	8	\$230.72
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	4	\$155.12
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	12	\$1,119.00

**Practice:** E528134Z - Improved grazing management that reduces undesirable plant pest pressure through monitoring

**Scenario #1 -** Grazing mgmt-pest pressure

**Scenario Description:**

Three predominant key grazing areas are evaluated utilizing the Rangeland Health Assessment protocols to determine how well the ecological processes of the site(s) are functioning. Departure from reference categories will be determined, justified, and ratings described for soil and site stability, hydrologic function, and biotic integrity. Utilizing knowledge learned from this as a part of the ranch resource assessment, a Certified Range Management Consultant or Certified Professional in Range Management will provide recommendations or follow-up evaluations toward mitigating some of the degradation risks that are initially identified.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 1,000.0

**Scenario Total Cost:** \$1,788.56

**Scenario Cost/Unit:** \$1.79

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Acquisition of Technical Knowledge</b>						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
<b>Equipment Installation</b>						
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	8	\$230.72
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	4	\$155.12
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	12	\$1,119.00

Practice: E528136Z1 - Grazing management for improving quantity and quality of food for wildlife

Scenario #1 - Grazing mgmt-food

Scenario Description:

Grazing management employed will provide plant structure, density and diversity needed for the desired wildlife species of concern.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1,000.0

Scenario Total Cost: \$451.72

Scenario Cost/Unit: \$0.45

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	10	\$387.80



Practice: E528136Z2 - Incorporating wildlife refuge areas in contingency plans for wildlife food

Scenario #1 - Add wildlife refuge area-food

Scenario Description:

A prescribed grazing plan that includes 18 month (or longer) deferment of a pasture that consists of native grasses and/or legumes and/or perennial forbs for the purpose of meeting the needs for drought/disaster contingency plans that will also provide wildlife habitat for a period of time.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,551.94

Scenario Cost/Unit: \$15.52

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	6	\$173.04
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	15	\$249.75
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	\$47.61	4	\$190.44
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	\$257.52	1	\$257.52

Practice: E528136Z3 - Grazing management that improves Monarch butterfly habitat

Scenario #1 - Grazing mgmt-Monarch

Scenario Description:

Implement a grazing management plan that will increase the abundance and diversity of monarch nectar-producing perennial forbs, including milkweed, while maintaining ecosystem benefits for other wildlife and livestock.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$852.78

Scenario Cost/Unit: \$8.53

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	2.5	\$41.63
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	1	\$21.98
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	\$47.61	1	\$47.61
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	2	\$638.86

Practice: E528137Z1 - Grazing management for improving quantity and quality of cover and shelter for wildlife

Scenario #1 - Grazing mgmt-shelter

Scenario Description:

Grazing management employed will provide plant structure, density and diversity needed for the desired wildlife species of concern.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1,000.0

Scenario Total Cost: \$451.72

Scenario Cost/Unit: \$0.45

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	10	\$387.80

Practice: E528137Z2 - Incorporating wildlife refuge areas in contingency plans for prescribed grazing-cover/shelter

Scenario #1 - Add wildlife refuge area-shelter

Scenario Description:

A prescribed grazing plan that includes 12 month (or longer) deferment of a pasture that consists of native grasses and/or legumes and/or perennial forbs for the purpose of meeting the needs for drought/disaster contingency plans that will also provide wildlife habitat for a period of time.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,551.94

Scenario Cost/Unit: \$15.52

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	6	\$173.04
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	15	\$249.75
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	\$47.61	4	\$190.44
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	\$257.52	1	\$257.52

**Practice:** E528138Z - Incorporating wildlife refuge areas in contingency plans for prescribed grazing-water access

**Scenario #1** - Add wildlife refuge area-water

**Scenario Description:**

A prescribed grazing plan that includes 12 month (or longer) deferment of a pasture that consists of native grasses and/or legumes and/or perennial forbs for the purpose of meeting the needs for drought/disaster contingency plans that will also provide wildlife habitat for a period of time.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 100.0

**Scenario Total Cost:** \$1,551.94

**Scenario Cost/Unit:** \$15.52

**Cost Details:**

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Acquisition of Technical Knowledge</b>						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
<b>Equipment Installation</b>						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	6	\$173.04
<b>Foregone Income</b>						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	15	\$249.75
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
<b>Materials</b>						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	\$47.61	4	\$190.44
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	\$257.52	1	\$257.52

Practice: E528140Z1 - Maintaining quantity and quality of forage for animal health and productivity

Scenario #1 - Maintain forage quantity and quality

Scenario Description:

Managing the harvest of vegetation with grazing and/or browsing animals for the purposes of maintaining desired pasture composition/plant vigor and improving/maintaining quantity and quality of forage for the animals' health and productivity..

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1,000.0

Scenario Total Cost: \$2,416.10

Scenario Cost/Unit: \$2.42

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	4	\$88.88
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	12	\$346.08
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	36	\$599.40
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	17	\$373.66
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	\$47.61	1	\$47.61
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	\$257.52	1	\$257.52
Nutritional Balance Analyzer, fecal sample analysis only	1127	NIRS fecal analysis, animal performance report. Includes materials and shipping only.	Each	\$40.34	6	\$242.04

Practice: E528140Z2 - Incorporating wildlife refuge areas in contingency plans for livestock feed and forage

Scenario #1 - Add wildlife refuge area-forage

Scenario Description:

A prescribed grazing plan that includes 18 month (or longer) deferment of a pasture that consists of native grasses and/or legumes and/or perennial forbs for the purpose of meeting the needs for drought/disaster contingency plans that will also provide wildlife habitat for a period of time.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 528 - Prescribed Grazing

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 528 - Prescribed Grazing

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1,000.0

Scenario Total Cost: \$2,616.59

Scenario Cost/Unit: \$2.62

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Acquisition of Technical Knowledge						
Training, Workshops	294	Educational seminar or series of meetings emphasizing interaction and exchange of information among a usually small number of participants.	Each	\$63.92	1	\$63.92
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	4	\$88.88
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	12	\$346.08
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	54	\$899.10
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	17	\$373.66
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Wire, Polywire	8	Wire, Polywire for electric fence - 1,300 roll. Includes materials and shipping only.	Each	\$47.61	4	\$190.44
Electric, Energizer, Solar	27	Electric, Energizer, Solar for electric fence. Includes materials and shipping only.	Each	\$319.43	1	\$319.43
Tank, Polyethylene, 300 gallon	291	Portable heavy duty rubber stock tank.	Each	\$257.52	1	\$257.52

Practice: E550106Z - Range planting for increasing/maintaining organic matter

Scenario #1 - Range planting for SOM

Scenario Description:

Establishment of adapted perennial or self-sustaining vegetation such as grasses, forbs, legumes, shrubs and trees for the purpose of increasing or maintaining organic matter levels in the soil.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 550 - Range Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 550 - Range Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$4,143.46

Scenario Cost/Unit: \$41.43

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Foregone Income						
FI, Grazing AUMs	2079	Grazing is the Primary Land Use	Animal Unit Month	\$16.65	15	\$249.75
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	2	\$77.56
Materials						
Native Grass and Forb Mix, for Wildlife (including pollinators) or Ecosystem Restoration	2335	Native grass and forb/legume mix, including specialized species. Includes material and shipping only.	Acre	\$254.41	15	\$3,816.15



Practice: E550136Z - Range planting for improving forage, browse, or cover for wildlife

Scenario #1 - Range planting for wildlife

Scenario Description:

Establishment of adapted perennial or self-sustaining vegetation such as grasses, forbs, legumes, shrubs and trees for the purpose of improving forage, browse, or cover for wildlife on areas that have been degraded beyond recovery via ecological principles, or old crop fields and pastures devoid of desirable, native rangeland species that range within an ecological site description steady state.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 550 - Range Planting

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 550 - Range Planting

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$9,793.10

Scenario Cost/Unit: \$97.93

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50
Materials						
Six Species Mix, Native Forb	2334	Native forb mix. Includes material and shipping only.	Acre	\$960.66	10	\$9,606.60

Practice: E554118Z1 - Installation of end of pipe or ditch treatment for phosphorus

Scenario #1 - Installation of treatment for P

Scenario Description:

Add end of pipe treatment. If dissolved Phosphorus is the pollutant of concern, add Interim standard 782, Phosphorus Treatment Structure for each pipe outlet in a field.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 554 - Drainage Water Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 554 - Drainage Water Management

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$7,262.59

Scenario Cost/Unit: \$7,262.59

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$427.11	6	\$2,562.66
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	40	\$86.00
Earthfill, Dumped and Spread	51	Earthfill, dumped and spread without compaction effort, includes equipment and labor	Cubic Yard	\$3.33	40	\$133.20
Hydraulic Excavator, .5 CY	930	Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included.	Hour	\$63.99	16	\$1,023.84
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	16	\$353.44
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	4	\$373.00
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$25.57	20	\$511.40
Pipe, PVC, 4", SDR 41	983	Materials: - 4" - PVC - SDR 41 100 psi - ASTM D2241	Foot	\$1.89	80	\$151.20
Tank, Poly enclosed Storage, 300-1000 gal	1074	Water storage tanks. Includes materials and shipping only.	Gallon	\$0.90	0	\$0.00
Aggregate, gravel, washed, pea gravel	1331	Washed and graded pea gravel river stone. Includes materials and local delivery within 20 miles of quarry.	Cubic Yard	\$28.19	20	\$563.80
Water Control Structure, Stoplog, Inline, fixed costs portion	2145	Fixed cost portion of Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Fixed cost portion. Materials only.	Each	\$312.56	1	\$312.56
Water Control Structure, Stoplog, Inline, variable cost portion	2146	Variable cost portion of a Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Calculate total variable costs by multiplying by the structure height x pipe diameter. Materials only.	Height x Diameter	\$12.08	36	\$434.88
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93
Aggregate, Shipping, Cubic Yard-mile	2360	Mobilization of aggregate material beyond 20 miles of local delivery from quarry to construction site. Cubic Yard-mile (Cubic Yard * miles of haul).	Cubic Yard Mile	\$0.36	400	\$144.00

Practice: E554118Z2 - Installation of a saturated buffer drain outlet

Scenario #1 - Installation of a vegetated outlet

Scenario Description:

Install Conservation Practice Standard 604, Saturated Buffer so all of the drain outlets on a field are routed through an appropriate buffer.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 554 - Drainage Water Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 554 - Drainage Water Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$3,538.69

Scenario Cost/Unit: \$3,538.69

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Trenching, Earth, 12" x 48"	53	Trenching, earth, 12" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$1.26	400	\$504.00
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.17	4	\$228.68
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	4	\$87.92
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	4	\$88.36
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	4	\$155.12
Materials						
Pipe, HDPE, 5", PCPT, Single Wall	1271	Pipe, Corrugated Plastic Tubing, Single Wall, Perforated, 5" diameter - ASTM F405. Material cost only.	Foot	\$0.70	400	\$280.00
Water Level Control Structure, Inline, 2 Baffle, 10" diameter	2021	Inline Inlet WCS 6' High x 10" Dia.connections , 2 baffle (3 compartments)	Each	\$1,933.68	1	\$1,933.68
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: E554118Z3 - Installation of end of pipe or ditch treatment for nitrogen

Scenario #1 - Installation of treatment for N

Scenario Description:

Add end of pipe/ditch treatment if Nitrogen is the pollutant of concern. Add CPS 605, Denitrifying Bioreactor for each drainage outlet in a field.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 554 - Drainage Water Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 554 - Drainage Water Management

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$18,386.80

Scenario Cost/Unit: \$18,386.80

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.39	800	\$1,912.00
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	333	\$715.95
Earthfill, Dumped and Spread	51	Earthfill, dumped and spread without compaction effort, includes equipment and labor	Cubic Yard	\$3.33	333	\$1,108.89
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$45.49	8	\$363.92
Aggregate, Wood Chips	1098	Includes materials, equipment and labor	Cubic Yard	\$21.43	366	\$7,843.38
Trenching, Earth, 24" x 60"	1460	Trenching, earth, 24" wide x 60" depth, includes equipment and labor for trenching and backfilling.	Foot	\$3.88	50	\$194.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	8	\$176.72
Materials						
Pipe, HDPE, 6", CPT, Single Wall	1242	Pipe, Corrugated Plastic Tubing, Single Wall, 6" diameter - ASTM F405. Material cost only.	Foot	\$1.13	90	\$101.70
Water Level Control Structure, Inline, 2 Baffle, 10" diameter	2021	Inline Inlet WCS 6' High x 10" Dia.connections , 2 baffle (3 compartments)	Each	\$1,933.68	1	\$1,933.68
Water Control Structure, Stoplog, Inline, fixed costs portion	2145	Fixed cost portion of Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Fixed cost portion. Materials only.	Each	\$312.56	1	\$312.56
Water Control Structure, Stoplog, Inline, variable cost portion	2146	Variable cost portion of a Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Calculate total variable costs by multiplying by the structure height x pipe diameter. Materials only.	Height x Diameter	\$12.08	60	\$724.80
Water Level Control Structure, Inline, 2 Baffle, 8" diameter	2187	Inline Inlet WCS 6' High x 8" Dia.connections , 2 baffle (3 compartments)	Each	\$1,730.56	1	\$1,730.56
Pipe, HDPE, CPT, Double Wall, Water Tight, 10"	2204	Pipe, Corrugated HDPE Double Wall 10" diameter with water tight joints meeting ASTM F477. Material cost only.	Foot	\$5.49	40	\$219.60
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: E554138X - Extend the periods of soil saturation or shallow ponding for wildlife

Scenario #1 - Extend saturation/ponding period

Scenario Description:

Extending the periods of wetness (soil saturation or shallow water), in excess of those required under National Conservation Practice Standard (NCP) Drainage Water Management (554), to meet the additional consideration of wildlife.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 554 - Drainage Water Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 554 - Drainage Water Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 25.0

Scenario Total Cost: \$206.36

Scenario Cost/Unit: \$8.25

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	2	\$57.68
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	5	\$109.90
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	1	\$38.78

**Practice:** E578139X - Stream crossing elimination

**Scenario #1** - Stream crossing elimination

**Scenario Description:**

Existing stream crossings on an operation are consolidated into fewer crossings in order to reduce impacts to stream habitat.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 578 - Stream Crossing

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 578 - Stream Crossing

**Feature Measure:** Typical feature is 0.09 acres

**Scenario Unit::** Each

**Scenario Typical Size:** 1.0

**Scenario Total Cost:** \$7,496.03

**Scenario Cost/Unit:** \$7,496.03

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$67.45	16	\$1,079.20
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.01	8	\$928.08
Seeding Operation, Broadcast, Ground	959	Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs.	Acre	\$12.85	0.1	\$1.29
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	\$98.65	16	\$1,578.40
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	32	\$703.36
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	32	\$706.88
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	16	\$620.48
<b>Materials</b>						
Erosion Control Blanket, biodegradable	1213	Biodegradable erosion control blanket, typically a composite of natural fibers with reinforcing polymer netting. Materials and shipping only.	Square Yard	\$1.30	300	\$390.00
Cuttings, woody, medium size	1308	Woody cuttings, live stakes or whips typically 1/4" to 1" diameter and 24" to 48" long. Includes materials and shipping only.	Each	\$0.48	300	\$144.00
Aggregate, river rock	1834	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	\$21.45	42	\$900.90
One Species, Cool Season, Annual Grass or Legume	2311	Cool season annual grass or legume. Includes material and shipping only.	Acre	\$38.26	0.1	\$3.83
One Species, Cool Season, Introduced Perennial Grass	2313	Introduced, cool season perennial grass. Includes material and shipping only.	Acre	\$31.86	0.1	\$3.19
<b>Mobilization</b>						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: E580105Z - Stream corridor bank stability improvement

Scenario #1 - Stream bank stability improvement

Scenario Description:

Stream corridor bank vegetation components are established to provide additional streambank stability.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 580 - Streambank and Shoreline Protection

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 580 - Streambank and Shoreline Protection

Feature Measure: Area planted

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: \$3,682.69

Scenario Cost/Unit: \$1,841.35

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	8	\$177.76
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	8	\$230.72
Trailer, enclosed, small	1503	Small enclosed trailer (typically less than 30' in length) pulled by a pickup to transport materials and equipment. Truck not included.	Hour	\$7.12	8	\$56.96
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	8	\$96.32
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	48	\$1,055.04
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	8	\$310.24
Materials						
Shrub, seedling or transplant, potted, 1/2 to 1 gal.	1526	Potted shrub, 1/2 to 1 gal. Includes materials and shipping only.	Each	\$4.52	65	\$293.80
Tree, hardwood, seedling or transplant, potted, 1/2 to 1 gal.	1531	Potted hardwood tree, 1/2 to 1 gal. Includes materials and shipping only.	Each	\$4.54	65	\$295.10
Tree, conifer, seedling or transplant, potted, 1/2 to 1 gal.	1536	Potted conifer, 1/2 to 1 gal. Includes materials and shipping only.	Each	\$4.41	65	\$286.65
Tree shelter, mesh tree tube, 48"	1556	48" tall vexar or other open weave tubular tree shelter to protect from animal damage. Materials only.	Each	\$1.09	65	\$70.85
Tree shelter, solid tube type, 4" x 24"	1563	4" x 24" tree tube for protection from animal damage. Materials only.	Each	\$2.19	65	\$142.35
Tree shelter, solid tube type, 4" x 48"	1566	4" x 48" tree tube for protection from animal damage. Materials only.	Each	\$4.14	65	\$269.10
Stakes, wood, 1" x 1" x 48"	1578	1" x 1" x 48" wood stakes to fasten items in place. Includes materials only.	Each	\$2.04	195	\$397.80

Practice: E580137Z - Stream corridor bank vegetation improvement

Scenario #1 - Stream corridor bank veg improvement

Scenario Description:

Stream corridor bank vegetation components are established to improve ecosystem functioning and stability.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 580 - Streambank and Shoreline Protection

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 580 - Streambank and Shoreline Protection

Feature Measure: Area planted

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: \$3,682.69

Scenario Cost/Unit: \$1,841.35

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	8	\$177.76
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	8	\$230.72
Trailer, enclosed, small	1503	Small enclosed trailer (typically less than 30' in length) pulled by a pickup to transport materials and equipment. Truck not included.	Hour	\$7.12	8	\$56.96
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	8	\$96.32
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	48	\$1,055.04
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.78	8	\$310.24
Materials						
Shrub, seedling or transplant, potted, 1/2 to 1 gal.	1526	Potted shrub, 1/2 to 1 gal. Includes materials and shipping only.	Each	\$4.52	65	\$293.80
Tree, hardwood, seedling or transplant, potted, 1/2 to 1 gal.	1531	Potted hardwood tree, 1/2 to 1 gal. Includes materials and shipping only.	Each	\$4.54	65	\$295.10
Tree, conifer, seedling or transplant, potted, 1/2 to 1 gal.	1536	Potted conifer, 1/2 to 1 gal. Includes materials and shipping only.	Each	\$4.41	65	\$286.65
Tree shelter, mesh tree tube, 48"	1556	48" tall vexar or other open weave tubular tree shelter to protect from animal damage. Materials only.	Each	\$1.09	65	\$70.85
Tree shelter, solid tube type, 4" x 24"	1563	4" x 24" tree tube for protection from animal damage. Materials only.	Each	\$2.19	65	\$142.35
Tree shelter, solid tube type, 4" x 48"	1566	4" x 48" tree tube for protection from animal damage. Materials only.	Each	\$4.14	65	\$269.10
Stakes, wood, 1" x 1" x 48"	1578	1" x 1" x 48" wood stakes to fasten items in place. Includes materials only.	Each	\$2.04	195	\$397.80



**Practice:** E590118X - Reduce risks of nutrient losses to surface water by utilizing precision ag technologies

**Scenario #1** - Precision ag for nut reduction

**Scenario Description:**

Utilize precision application technology and techniques to reduce risk of nutrients in surface water by reducing total amount of applied and reducing the potential for delivery of nutrients into water bodies. Precision agriculture technology is utilized to plan and apply nutrients to improve nutrient use efficiency and reduce risk of nutrient losses.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 590 - Nutrient Management

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 590 - Nutrient Management

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 100.0

**Scenario Total Cost:** \$1,532.25

**Scenario Cost/Unit:** \$15.32

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Fertilizer, precision application	952	Fertilizer application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	\$10.88	100	\$1,088.00
<b>Labor</b>						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50
<b>Materials</b>						
Test, Soil Test, Precision, Grid or Zone DELETION SCHEDULED for PS FY 2018 , USE CID 299	300	Includes materials, shipping, labor, and equipment costs. DELETION SCHEDULED for PS FY 2018 , USE CID 299	Each	\$10.31	25	\$257.75

Practice: E590118Z - Improving nutrient uptake efficiency and reducing risk of nutrient losses to surface water

Scenario #1 - Nut mgmt for surface water

Scenario Description:

Nutrient management encompasses managing the amount, source, placement, and timing of the application of plant nutrients and soil amendments. Nutrients are currently being applied on the farm based on the 4R nutrient stewardship principles. Enhanced nutrient use efficiency strategies or technologies are utilized to improve nutrient use efficiency and reduce risk of nutrient losses.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 590 - Nutrient Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 590 - Nutrient Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,104.70

Scenario Cost/Unit: \$11.05

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50
Materials						
Nitrogen-Urease inhibitor	260	Nitrogen-Urease inhibitor	Acre	\$8.55	100	\$855.00
Test, Soil Nitrogen Testing	311	Pre-Side Dress/Deep Soil Testing. Includes materials and shipping only.	Each	\$12.64	5	\$63.20

Practice: E590119Z - Improving nutrient uptake efficiency and reducing risk of nutrient losses to groundwater

Scenario #1 - Nut mgmt for groundwater

Scenario Description:

Nutrient management encompasses managing the amount, source, placement, and timing of the application of plant nutrients and soil amendments. Nutrients are currently being applied on the farm based on the 4R nutrient stewardship principles. Enhanced nutrient use efficiency strategies or technologies are utilized to improve nutrient use efficiency and reduce risk of nutrient losses.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 590 - Nutrient Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 590 - Nutrient Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,104.70

Scenario Cost/Unit: \$11.05

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50
Materials						
Nitrogen-Urease inhibitor	260	Nitrogen-Urease inhibitor	Acre	\$8.55	100	\$855.00
Test, Soil Nitrogen Testing	311	Pre-Side Dress/Deep Soil Testing. Includes materials and shipping only.	Each	\$12.64	5	\$63.20

**Practice:** E595116X - Reduce risk of pesticides in surface water by utilizing precision pesticide application techniques

**Scenario #1** - Pest mgmt for surface water

**Scenario Description:**

Utilize precision application techniques to reduce risk of pesticides in surface water by reducing total amount of chemical applied and reducing the potential for delivery of chemicals into water bodies.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 595 - Integrated Pest Management

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 595 - Integrated Pest Management

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 100.0

**Scenario Total Cost:** \$1,284.75

**Scenario Cost/Unit:** \$12.85

**Cost Details:**

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Chemical, precision application	949	Chemical application performed by light bar/GPS navigation system. Includes equipment, power unit and labor costs.	Acre	\$10.05	100	\$1,005.00
<b>Labor</b>						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75

Practice: E595116Z - Reduce risk of pesticides in surface water by utilizing IPM PAMS techniques

Scenario #1 - IPM PAMS techniques

Scenario Description:

Utilize integrated pest management (IPM) prevent, avoidance, monitoring, and suppression (PAMS) techniques to reduce risk of pesticides in surface water and reducing the potential for delivery of chemicals into water bodies.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 595 - Integrated Pest Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 595 - Integrated Pest Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$633.35

Scenario Cost/Unit: \$6.33

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	10	\$353.60
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75

**Practice:** E595129Z - Reduce ozone precursor emissions related to pesticides by utilizing IPM PAMS techniques

**Scenario #1** - IPM PAMS techniques for ozone reduction

**Scenario Description:**

Utilize integrated pest management (IPM) prevent, avoidance, monitoring, and suppression (PAMS) techniques to reduce ozone precursor emissions related to pesticides.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 595 - Integrated Pest Management

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 595 - Integrated Pest Management

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 100.0

**Scenario Total Cost:** \$633.35

**Scenario Cost/Unit:** \$6.33

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	10	\$353.60
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	3	\$279.75

Practice: E612101Z - Cropland conversion to trees or shrubs for long term water erosion control

Scenario #1 - Convert crop to trees-water erosion

Scenario Description:

Conversion of cropped land to trees for long term erosion control and improvement of water quality. Trees are established on cropland where annually-seeded cash crops have been grown.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$7,587.00

Scenario Cost/Unit: \$758.70

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	10	\$217.80
Ripper or subsoiler, 16 to 36 inch depth	1235	Deep ripper or subsoiler, (16-36 inches depth) includes tillage implement, power unit and labor.	Acre	\$20.33	10	\$203.30
Materials						
Tree or shrub seedling, Tropical, native or non-native, 1 gal	1543	tree or shrub topical seedling, native or non-native, 1 gallon pot. Includes materials and shipping only.	Each	\$13.85	500	\$6,925.00
Four Species Mix, Cool Season, Introduced Perennial Grass	2318	Introduced, cool season perennial grass. Includes material and shipping only.	Acre	\$24.09	10	\$240.90

Practice: E612102Z - Cropland conversion to trees or shrubs for long term wind erosion control

Scenario #1 - Convert crop to trees-wind erosion

Scenario Description:

Conversion of cropped land to trees for long term erosion control and improvement of water quality. Trees are established on cropland where annually-seeded cash crops have been grown.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$7,587.00

Scenario Cost/Unit: \$758.70

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	10	\$217.80
Ripper or subsoiler, 16 to 36 inch depth	1235	Deep ripper or subsoiler, (16-36 inches depth) includes tillage implement, power unit and labor.	Acre	\$20.33	10	\$203.30
Materials						
Tree or shrub seedling, Tropical, native or non-native, 1 gal	1543	tree or shrub topical seedling, native or non-native, 1 gallon pot. Includes materials and shipping only.	Each	\$13.85	500	\$6,925.00
Four Species Mix, Cool Season, Introduced Perennial Grass	2318	Introduced, cool season perennial grass. Includes material and shipping only.	Acre	\$24.09	10	\$240.90



Practice: E612126Z - Cropland conversion to trees or shrubs for long term improvement of water quality

Scenario #1 - Convert crop to trees-WQ

Scenario Description:

Conversion of cropped land to trees for long term erosion control and improvement of water quality. Trees are established on cropland where annually-seeded cash crops have been grown

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$7,587.00

Scenario Cost/Unit: \$758.70

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	10	\$217.80
Ripper or subsoiler, 16 to 36 inch depth	1235	Deep ripper or subsoiler, (16-36 inches depth) includes tillage implement, power unit and labor.	Acre	\$20.33	10	\$203.30
Materials						
Tree or shrub seedling, Tropical, native or non-native, 1 gal	1543	tree or shrub topical seedling, native or non-native, 1 gallon pot. Includes materials and shipping only.	Each	\$13.85	500	\$6,925.00
Four Species Mix, Cool Season, Introduced Perennial Grass	2318	Introduced, cool season perennial grass. Includes material and shipping only.	Acre	\$24.09	10	\$240.90

## Missouri

### Scenario #1 - Planting for high carbon sequestration

Plant tree species and use stocking levels for higher growth to increase the rate of carbon sequestration (capture). Use species with a longer life span as well as relatively fast growth, and species suitable for durable manufactured products. Increase stocking levels in forests that are not fully stocked. Implement afforestation on appropriate open lands.

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

Scenario Unit:: Acre

**Scenario Total Cost:** \$9,209.78

Cost Details:

## Mobilization

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50
-------------------------------	------	--	------	----------	---	----------

Practice: E612132Z - Establishing tree/shrub species to restore native plant communities

Scenario #1 - Tree/shrubs-restore native communities

Scenario Description:

Establish trees and/or shrubs to restore elements of plant diversity that have been lost through past diseases or improper management. For example, disease-resistant varieties of elm and chestnut can be established to restore the ecological functions of American elm and American chestnut. At the stand level, past forest management may have eliminated certain native tree species. Restoring stand-level diversity and function addresses a wide array of resource concerns and strengthens ongoing management activities. This enhancement improves a forest that is already in good condition by increasing plant diversity, and improving health and vigor through adding plants with resistance to disease, pests, or other local hazards. Additional benefits include contributing to carbon storage, and providing diversity in wildlife habitat and food sources.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 5.0

Scenario Total Cost: \$3,146.24

Scenario Cost/Unit: \$629.25

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	12	\$144.48
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	12	\$263.76
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	4	\$287.56
Materials						
Shrub, seedling or transplant, potted, 1/2 to 1 gal.	1526	Potted shrub, 1/2 to 1 gal. Includes materials and shipping only.	Each	\$4.52	50	\$226.00
Tree, hardwood, seedling or transplant, potted or B&B, 2-3 gal.	1532	Potted or balled and burlapped hardwood tree, 2-3 gal. Includes materials and shipping only.	Each	\$7.15	100	\$715.00
Tree, conifer, seedling or transplant, potted or B&B, 2-3 gal.	1537	Potted or balled and burlapped conifer tree, 2-3 gal. Includes materials and shipping only.	Each	\$6.97	100	\$697.00
Tree shelter, solid tube type, 4" x 60"	1567	4" x 60" tree tube for protection from animal damage. Materials only.	Each	\$5.12	150	\$768.00

Practice: E612133X1 - Adding food-producing trees and shrubs to existing plantings

Scenario #1 - Adding food-producing trees and shrubs

Scenario Description:

Plant food-producing trees and shrubs for wildlife or human consumption within windbreaks, alley cropping, multi-story cropping, or silvopasture systems, or riparian forest buffers.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,371.32

Scenario Cost/Unit: \$1,371.32

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	10	\$120.40
Foregone Income						
Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.41	\$170.24
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.36	\$149.40
Fl, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.23	\$45.93
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	1	\$17.48
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$25.63	1	\$25.63
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shi	Acre	\$1.28	1	\$1.28
Shrub, seedling or transplant, bare root, 18"-36"	1507	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.57	341	\$194.37
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.59	340	\$200.60
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: E612133X2 - Cultural plantings

Scenario #1 - Cultural plantings

Scenario Description:

Plant trees and shrubs that are of cultural significance, such as those species utilized by Tribes in traditional practices, medicinals, species used in basket-making, etc. (e.g., paper birch, slippery elm, witch hazel).

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,378.14

Scenario Cost/Unit: \$1,378.14

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	10	\$120.40
Foregone Income						
Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.41	\$170.24
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.36	\$149.40
Fl, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.23	\$45.93
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	1	\$17.48
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$25.63	1	\$25.63
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shi	Acre	\$1.28	1	\$1.28
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.59	681	\$401.79
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: E612133X3 - Sugarbush management

Scenario #1 - Sugarbush management

Scenario Description:

Maintain at least 20% of basal area in species other than sugar maple to provide species diversity. Half of the trees that are not sugar maples (10%) will be mast-producing species. Use maple tree tapping guidelines that minimize tree damage.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 20.0

Scenario Total Cost: \$651.95

Scenario Cost/Unit: \$32.60

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	2	\$8.90
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	1	\$66.19
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	2	\$24.08
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	10	\$219.80
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	0.5	\$8.74
Tree, hardwood, seedling or transplant, potted or B&B, 2-3 gal.	1532	Potted or balled and burlapped hardwood tree, 2-3 gal. Includes materials and shipping only.	Each	\$7.15	20	\$143.00
Tree shelter, solid tube type, 4" x 60"	1567	4" x 60" tree tube for protection from animal damage. Materials only.	Each	\$5.12	20	\$102.40
Cable ties, plastic	1575	Plastic cable ties (typ. 8-12") to assist in securing items. Materials only.	Each	\$0.05	60	\$3.00
Stakes, wood, 3/4" x 3/4" x 60"	1583	3/4" x 3/4" x 60" wood stakes to fasten items in place. Includes materials only.	Each	\$1.57	20	\$31.40

Practice: E612136Z - Tree/shrub planting for wildlife food

Scenario #1 - Tree/shrub planting for wildlife food

Scenario Description:

Tree or shrub planting to enhance habitat for native wildlife. A minimum of five tree or shrub species will be used; they will be species that provide food and/or cover for identified wildlife species.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,483.84

Scenario Cost/Unit: \$1,483.84

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	11	\$132.44

Foregone Income

Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.41	\$170.24
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.36	\$149.40
Fl, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.23	\$45.93

Labor

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	11	\$241.78
---------------	-----	--	------	---------	----	----------

Materials

Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	1	\$17.48
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$25.63	1	\$25.63
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shi	Acre	\$1.28	1	\$1.28
Shrub, seedling or transplant, bare root, 18"-36"	1507	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.57	605	\$344.85
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.59	218	\$128.62

Mobilization

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50
-------------------------------	------	--	------	----------	---	----------



Practice: E612137Z - Tree/shrub planting for wildlife cover

Scenario #1 - Tree/shrub planting for wildlife cover

Scenario Description:

Tree or shrub planting to enhance habitat for native wildlife. A minimum of five tree or shrub species will be used; they will be species that provide food and/or cover for identified wildlife species.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 612 - Tree/Shrub Establishment

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 1.0

Scenario Total Cost: \$1,483.84

Scenario Cost/Unit: \$1,483.84

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	1	\$6.26
Hand tools, tree planting	1590	Various hand tools for digging holes and planting trees such as augers, dibble bars, planting shovel, hoe-dad. Equipment only. Labor not included.	Hour	\$12.04	11	\$132.44
Foregone Income						
Fl, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.41	\$170.24
Fl, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.36	\$149.40
Fl, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.23	\$45.93
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	11	\$241.78
Materials						
Herbicide, Glyphosate	334	A broad-spectrum, non-selective systemic herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$17.48	1	\$17.48
Herbicide, Sulfometuron & metsulfuron	344	A residual sulfonylurea herbicide that kills broadleaf weeds and some annual grasses. It is a systemic compound with foliar and soil activity. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$25.63	1	\$25.63
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shi	Acre	\$1.28	1	\$1.28
Shrub, seedling or transplant, bare root, 18"-36"	1507	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.57	605	\$344.85
Tree, hardwood, seedling or transplant, bare root, 16-36"	1510	Bare root hardwood trees 18-36" tall. Includes materials and shipping only.	Each	\$0.59	218	\$128.62
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: E643132X - Restoration of sensitive coastal vegetative communities

Scenario #1 - Restore sensitive coastal veg community

Scenario Description:

Enhance the level of restoration in unique and diminishing coastal ecosystems by establishing native herbaceous and woody plants. Protect established vegetation, and manage to maintain floristic quality and the provision of environmental services.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 643 - Restoration and Management of Rare and Declining Habitats

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 643 - Restoration and Management of Rare and Declining Habitats

Feature Measure: Each

Scenario Unit:: Each

Scenario Typical Size: 25.0

Scenario Total Cost: \$1,936.55

Scenario Cost/Unit: \$77.46

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	16	\$353.44
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	4	\$287.56
Materials						
Post, Steel T, 1.33 lbs, 6'	15	Steel Post, Studded 6' - 1.33 lb. Includes materials and shipping only.	Each	\$6.68	50	\$334.00
Cattle Panel	1409	Welded wire cattle panel typically 1/4" galvanized steel rods, 50" high x 16' long. Materials only.	Each	\$20.89	25	\$522.25
Tree, hardwood, seedling or transplant, potted or B&B, 5 gal.	1533	Potted or balled and burlapped hardwood tree, 5 gal. Includes materials and shipping only.	Each	\$14.69	25	\$367.25
Mobilization						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$72.05	1	\$72.05

Practice: E643139X - Creating native plant refugia

Scenario #1 - Creating native plant refugia

Scenario Description:

Provide protection from adverse environmental conditions to create refugia for documented occurrences of sensitive plant communities.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 643 - Restoration and Management of Rare and Declining Habitats

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 643 - Restoration and Management of Rare and Declining Habitats

Feature Measure: Feet of Fence

Scenario Unit:: Foot

Scenario Typical Size: 440.0

Scenario Total Cost: \$3,358.78

Scenario Cost/Unit: \$7.63

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Auger, Post driver attachment	934	Auger or post driver attachment to a tractor or skidsteer. Does not include power unit. Labor not included.	Hour	\$7.46	8	\$59.68
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	2	\$8.90
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	8	\$177.76
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$25.27	8	\$202.16
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	2	\$186.50
Materials						
Wire, Woven, Galvanized, 12.5 Gauge, 48"	4	Galvanized 12.5 gauge, 48" - 330' roll. Includes materials and shipping only.	Each	\$257.12	3	\$771.36
Post, Wood, CCA treated, 6" x 12-14'	13	Wood Post, Line/End 6" X 12-14', CCA Treated. Includes materials and shipping only.	Each	\$26.98	38	\$1,025.24
Fence, Wire Assembly, Woven Wire	35	Brace pins, twist sticks, staples. Includes materials and shipping only.	Foot	\$0.12	1648	\$197.76
Gate, Game, 8' High X 4'	1082	4' Wide Game Gate (8' Tall). Includes materials and shipping only.	Each	\$202.24	1	\$202.24
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: E645137Z - Reduction of attractants to human-subsidized predators in sensitive wildlife species habitat

Scenario #1 - Reduce human-subsidized predators

Scenario Description:

Reduction of artificial perching sites, nest sites, food, and water available to subsidized predators in areas where human-subsidized predators are a threat to sensitive wildlife species. Human-subsidized predators may include ravens, crows, magpies, coyotes, foxes, skunks, raccoons, and other species. Activities under this enhancement may include removal of non- native or invasive trees; removal of unused power poles, corrals, windmills, buildings, and other vertical structures; and/or removal or management of watering facilities, dead livestock, road kill, garbage, animal feed, dumps, and other non-natural food sources.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 645 - Upland Wildlife Habitat Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 645 - Upland Wildlife Habitat Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 40.0

Scenario Total Cost: \$3,343.02

Scenario Cost/Unit: \$83.58

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	72	\$1,599.84
Trailer, enclosed, small	1503	Small enclosed trailer (typically less than 30' in length) pulled by a pickup to transport materials and equipment. Truck not included.	Hour	\$7.12	72	\$512.64
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	48	\$1,055.04
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

**Practice:** E646136Z1 - Close structures to capture/retain rainfall to improve food for waterfowl/wading birds during winter

**Scenario #1** - Close structures to improve food

**Scenario Description:**

When flooded to shallow depths during fall and winter, agricultural fields provide ideal foraging habitat for myriad species of waterfowl and wading birds . In addition, flooded conditions promote establishment of aquatic invertebrate populations, thus providing protein-rich food sources for shorebirds as well as waterfowl and wading birds.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

**Feature Measure:** acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 50.0

**Scenario Total Cost:** \$1,282.14

**Scenario Cost/Unit:** \$25.64

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	9	\$199.98
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	2.5	\$132.35
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	22	\$483.56
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	5	\$466.25

Practice: E646136Z2 - Extend retention of rainfall to provide food for late winter habitat

Scenario #1 - Extend retention - food

Scenario Description:

When flooded to shallow depths during fall and retention of the captured rainfall is extended into late winter, agricultural fields provide maximum foraging habitat for myriad species of waterfowl and wading birds. Agriculture fields are typically drained in preparation of spring planting, but retention of water into late winter will provide high quality food for wildlife during a time when it may otherwise be in low abundance.???

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$1,507.75

Scenario Cost/Unit: \$30.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	11	\$244.42
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	2.5	\$132.35
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	26	\$571.48
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	6	\$559.50

**Practice:** E646136Z3 - Shorebird habitat, late season shallow water with manipulation to improve food sources

**Scenario #1** - Late season shallow water - food

**Scenario Description:**

Suitable shorebird habitat is limited during the summer and fall as birds migrate south post-breeding and providing shallow water and mud flat habitat will benefit a variety of shorebird species. Optimal conditions are created when water levels are slowly reduced through evaporation, which allows for propagation of invertebrates (typically insect larvae) used as food by shorebirds. Manipulation of vegetation, preferably through rolling, creates open conditions required by this suite of birds as a means to detect and avoid predators, and provides nutrient inputs for invertebrate production.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

**Feature Measure:** acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 50.0

**Scenario Total Cost:** \$2,586.02

**Scenario Cost/Unit:** \$51.72

**Cost Details:**

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	9	\$199.98
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	4.5	\$238.23
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	\$16.94	50	\$847.00
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	22	\$483.56
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	5	\$466.25
<b>Mobilization</b>						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00

Practice: E646136Z4 - Shorebird habitat, extended late season shallow water with manipulation to improve food sources

Scenario #1 - Extended late season shallow water-food

Scenario Description:

When flooded to shallow depths during fall and retention of the captured rainfall is extended into late winter, the shallow water and mud flat habitat will benefit a variety of shorebird species. Optimal conditions are created when water levels are slowly reduced through evaporation, which allows for propagation of invertebrates (typically insect larvae) used as food by shorebirds. Agriculture fields are typically drained in preparation of spring planting, but retention of water into late winter will provide high quality food for wildlife during a time when it may otherwise be in low abundance. Manipulation of vegetation, preferably through rolling, creates open conditions required by this suite of birds as a means to detect and avoid predators, and provides nutrient inputs for invertebrate production.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$2,864.57

Scenario Cost/Unit: \$57.29

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	11	\$244.42
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	5.5	\$291.17
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	\$16.94	50	\$847.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	26	\$571.48
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	6	\$559.50
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00



Practice: E646137X - Renovate small, shallow pothole and playa sites which may seasonally hold water

Scenario #1 - Shallow water development and management

Scenario Description:

Renovate small, shallow pothole and playa sites which may seasonally hold water.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 4.0

Scenario Total Cost: \$6,718.33

Scenario Cost/Unit: \$1,679.58

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	1613	\$3,467.95
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	4	\$25.04
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$21.78	3	\$65.34
Foregone Income						
FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$415.21	0.41	\$170.24
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$415.00	0.23	\$95.45
FI, Wheat Dryland	1963	Dryland Wheat is Primary Crop	Acre	\$199.69	0.36	\$71.89
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$37.13	4	\$148.52
Six Species Mix, Native Forb	2334	Native forb mix. Includes material and shipping only.	Acre	\$960.66	2	\$1,921.32
Native Grass and Forb Mix, for Wildlife (including pollinators) or Ecosystem Restoration	2335	Native grass and forb/legume mix, including specialized species. Includes material and shipping only.	Acre	\$254.41	1	\$254.41
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	1	\$498.18

**Practice:** E646137Z1 - Close structures to capture and retain rainfall to improve cover and shelter for birds during winter

**Scenario #1** - Close structures during winter.

**Scenario Description:**

When flooded to shallow depths during fall and winter, agricultural fields provide ideal cover and shelter for myriad species of waterfowl and wading birds.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

**Feature Measure:** acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 50.0

**Scenario Total Cost:** \$1,282.14

**Scenario Cost/Unit:** \$25.64

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	9	\$199.98
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	2.5	\$132.35
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	22	\$483.56
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	5	\$466.25

Practice: E646137Z2 - Extend retention of captured rainfall to provide enhanced cover and shelter for late winter habitat

Scenario #1 - Extend retention-cover and shelter

Scenario Description:

When flooded to shallow depths during the fall and retained into late winter, agricultural fields provide maximum shelter and cover for myriad species of waterfowl and wading birds. Agriculture fields are typically drained in preparation of spring planting, but retention of water into late winter will provide shelter and cover for waterfowl and shorebirds during a time when it may otherwise be in low abundance.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$1,507.75

Scenario Cost/Unit: \$30.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	11	\$244.42
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	2.5	\$132.35
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	26	\$571.48
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	6	\$559.50

Practice: E646137Z3 - Shorebird habitat, late season shallow water with manipulation to improve cover and shelter

Scenario #1 - Late season shallow water - cover

Scenario Description:

Suitable shorebird habitat is limited during the summer and fall as birds migrate south post-breeding. Providing shallow water and mud flat habitat will benefit a variety of shorebird species. Improved conditions are created when water levels are slowly reduced through evaporation, which allows for propagation of invertebrates (typically insect larvae) used as food by shorebirds. Manipulation of vegetation, preferably through rolling, creates open conditions required by this suite of birds as a means to detect and avoid predators, and provides nutrient inputs for invertebrate production.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$2,586.02

Scenario Cost/Unit: \$51.72

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	9	\$199.98
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	4.5	\$238.23
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	\$16.94	50	\$847.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	22	\$483.56
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	5	\$466.25
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00

Practice: E646137Z4 - Extended late season shallow water with manipulation to improve cover and shelter

Scenario #1 - Extended late season shallow water-cover

Scenario Description:

Suitable shorebird habitat is limited during the summer and fall as birds migrate south post-breeding. Agriculture fields are typically drained in preparation of spring planting, but retention of water into late winter will provide shelter and cover for waterfowl and shorebirds during a time when it may otherwise be in low abundance. Optimal conditions are created when water levels are slowly reduced and manipulation of vegetation, preferably through rolling, creates open conditions required by this suite of birds as a means to detect and avoid predators, and provides nutrient inputs for invertebrate production.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$2,864.57

Scenario Cost/Unit: \$57.29

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	11	\$244.42
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	5.5	\$291.17
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	\$16.94	50	\$847.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	26	\$571.48
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	6	\$559.50
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00

Practice: E646138Z1 - Close structures to capture and retain rainfall to provide water for birds during winter

Scenario #1 - Close structures to provide water

Scenario Description:

When flooded to shallow depths during fall and winter, agricultural fields provide water essential for myriad species of waterfowl and wading birds.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$1,282.14

Scenario Cost/Unit: \$25.64

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	9	\$199.98
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	2.5	\$132.35
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	22	\$483.56
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	5	\$466.25

Practice: E646138Z2 - Extend retention of captured rainfall to provide late winter water habitat

Scenario #1 - Extend winter water habitat

Scenario Description:

When flooded to shallow depths during fall and winter, agricultural fields provide water essential for myriad species of waterfowl and wading birds. Agriculture fields are typically drained in preparation of spring planting, but retention of water into late winter will provide water for shorebirds and waterfowl during a time when it may otherwise be in low abundance.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$1,507.75

Scenario Cost/Unit: \$30.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	11	\$244.42
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	2.5	\$132.35
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	26	\$571.48
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	6	\$559.50

Practice: E646138Z3 - Shorebird habitat, late season shallow water with manipulation

Scenario #1 - Late season shallow water

Scenario Description:

Suitable water is limited during the summer and fall as birds migrate south post-breeding. Providing shallow water and mud flat habitat will benefit a variety of shorebird species. Improved conditions are created when water levels are slowly reduced through evaporation. Manipulation of vegetation, preferably through rolling, creates open water conditions required by this suite of birds as a means to detect and avoid predators, and provides nutrient inputs for invertebrate production.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$2,586.02

Scenario Cost/Unit: \$51.72

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	9	\$199.98
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	4.5	\$238.23
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	\$16.94	50	\$847.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	22	\$483.56
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	5	\$466.25
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00



Practice: E646138Z4 - Shorebird habitat, extended late season shallow water with manipulation

Scenario #1 - Extended late season shallow water

Scenario Description:

Suitable water is limited during the summer and fall as birds migrate south post-breeding. Agriculture fields are typically drained in preparation of spring planting, but retention of water into late winter will provide habitat during a time when it may otherwise be in low abundance. Optimal conditions are created when water levels are slowly reduced and manipulation of vegetation, preferably through rolling, creates open water conditions required by this suite of birds as a means to detect and avoid predators, and provides nutrient inputs for invertebrate production.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$2,864.57

Scenario Cost/Unit: \$57.29

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	11	\$244.42
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	5.5	\$291.17
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	\$16.94	50	\$847.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	26	\$571.48
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	6	\$559.50
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00

Practice: E646139Z1 - Close structures to capture and retain rainfall for birds to improve habitat continuity

Scenario #1 - Close structures - habitat continuity

Scenario Description:

When flooded to shallow depths during fall and winter, agricultural fields provide habitat for myriad species of migratory birds. Those flooded conditions promote a network or continuity of habitat that is available to migratory waterfowl, shorebirds, and wading birds.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$1,282.14

Scenario Cost/Unit: \$25.64

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	9	\$199.98
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	2.5	\$132.35
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	22	\$483.56
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	5	\$466.25

Practice: E646139Z2 - Extend retention of captured rainfall to provide habitat continuity during late winter

Scenario #1 - Extend retention - habitat continuity

Scenario Description:

When flooded to shallow depths during the fall and retained into late winter, agricultural fields provide habitat for myriad species of migratory birds. Agriculture fields are typically drained in preparation of spring planting, but retention of water into late winter will provide a network or continuity of habitat for waterfowl, wading birds, and shorebirds during a time when it may otherwise be in low abundance.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$1,507.75

Scenario Cost/Unit: \$30.16

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	11	\$244.42
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	2.5	\$132.35
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	26	\$571.48
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	6	\$559.50

Practice: E646139Z3 - Shorebird habitat, late season shallow water with manipulation to enhance habitat continuity

Scenario #1 - Late season shallow water-continuity

Scenario Description:

Suitable water is limited during the summer and fall as birds migrate south post-breeding. Providing shallow water and mud flat habitat will benefit a variety of shorebird species. Improved conditions are created when water levels are slowly reduced through evaporation. Manipulation of vegetation, preferably through rolling, creates open water conditions required by this suite of birds as a means to detect and avoid predators, and provides nutrient inputs for invertebrate production.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$2,586.02

Scenario Cost/Unit: \$51.72

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	9	\$199.98
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	4.5	\$238.23
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	\$16.94	50	\$847.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	22	\$483.56
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	5	\$466.25
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00

Practice: E646139Z4 - Shorebird habitat, extended late season shallow water with manipulation - habitat continuity

Scenario #1 - Extended late season water-continuity

Scenario Description:

Suitable water is limited during the summer and fall as birds migrate south post-breeding. Providing shallow water with manipulation of vegetation creates a network or continuity of habitat required by this suite of migratory birds during a time when it may otherwise be in low abundance.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 646 - Shallow Water Development and Management

Feature Measure: acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$2,864.57

Scenario Cost/Unit: \$57.29

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	11	\$244.42
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	5.5	\$291.17
Tillage, Primary	946	Includes heavy disking (offset) or chisel plow. Includes equipment, power unit and labor costs.	Acre	\$16.94	50	\$847.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	26	\$571.48
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	6	\$559.50
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00

Practice: E647136Z1 - Manipulate vegetation on fields where rainfall is to be captured and retained-food

Scenario #1 - Manipulate veg for food

Scenario Description:

Harvested and idled agricultural lands, notably those occurring within rice rotations, contain high densities of residual (i.e., waste) grain and natural seeds following harvest. Seed densities in harvested rice fields may rival those documented in intensively managed moist-soil units. When flooded to shallow depths during fall and winter, these agricultural fields provide ideal foraging habitat for myriad species of waterfowl and wading birds. In addition, flooded conditions promote establishment of aquatic invertebrate populations, thus providing protein-rich food sources for shorebirds as well as waterfowl and wading birds. In many cases, light manipulation of dense vegetation is needed to improve the accessibility of food resources to waterfowl, wading birds, and shorebirds.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$1,169.38

Scenario Cost/Unit: \$23.39

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	\$58.85	8	\$470.80
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	8	\$176.72
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: E647136Z2 - Provide early successional habitat between first rice crop and ratoon crop-food

Scenario #1 - Ratoon crop food sources

Scenario Description:

This enhancement is to encourage the establishment of early successional, naturally occurring vegetation in ditches, side slope and bank borders to provide cover, critical nesting and brood rearing habitat as well as filtering overland flow and improving water quality. Ditches perform the critical function of removing water from agricultural lands. Allowing naturally occurring vegetation to develop along ditches, including side slopes, banks and borders, will help provide food and cover for wildlife while enhancing aquatic habitat and improving water quality. Ditches and ditch borders provide a foundation that supports a diverse wildlife community including Northern Bobwhite (*Colinus virginianus*) and other birds preferring early successional cover. Rabbits, furbearers, amphibians and many other species that inhabit agriculture areas will use this vegetative cover. These areas can also provide critical nesting habitat for the Mottled Duck (*Anas fulvigula*).

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$1,169.38

Scenario Cost/Unit: \$23.39

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	\$58.85	8	\$470.80
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	8	\$176.72
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: E647136Z3 - Establish and maintenance of moist soil vegetation on cropland edges to increase wildlife food

Scenario #1 - Moist soil vegetation-food

Scenario Description:

The wetter or more water saturated portions of cropland fields such as areas adjacent to field drains, have the potential to produce a significant amount of moist soil plants which are a tremendously valuable source of forage and cover for many waterfowl, shorebird and wading bird species, especially during a period of time when such plants may be limited. Under normal cropland production, the native vegetation is restricted on these sites through mechanical and/or chemical control. These maintained moist soil plants also will provide filtering and improve water quality.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$576.09

Scenario Cost/Unit: \$11.52

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	3	\$158.82
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	3	\$66.27
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00



Practice: E647137Z1 - Manipulate vegetation on fields where rainfall is to be captured and retained-cover/shelter

Scenario #1 - Manipulate veg for cover/shelter

Scenario Description:

This enhancement is to provide cover and shelter for wildlife by retaining some standing rice stubble and by encouraging the establishment of early successional, naturally occurring vegetation in fields post harvest. Allowing some standing rice stubble and naturally occurring vegetation to develop will help provide food and cover for wildlife while enhancing aquatic habitat and improving water quality.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$1,169.38

Scenario Cost/Unit: \$23.39

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	\$58.85	8	\$470.80
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	8	\$176.72
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: E647137Z2 - Establish and maintenance of moist soil vegetation on cropland edges to increase cover/shelter

Scenario #1 - Moist soil vegetation-cover/shelter

Scenario Description:

The wetter or more water saturated portions of cropland fields such as areas adjacent to field drains, have the potential to produce a significant amount of moist soil plants which are a tremendously valuable source of forage and cover for many waterfowl, shorebird and wading bird species, especially during a period of time when such plants may be limited. Under normal cropland production, the native vegetation is restricted on these sites through mechanical and/or chemical control. These maintained moist soil plants also will provide filtering and improve water quality.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$576.09

Scenario Cost/Unit: \$11.52

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	3	\$158.82
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	3	\$66.27
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00

Practice: E647139Z1 - Establish/maintain habitat continuity, naturally occurring vegetation in ditches/ditch bank borders

Scenario #1 - Naturally occurring veg in ditches

Scenario Description:

This enhancement is to encourage the establishment of early successional, naturally occurring vegetation in ditches, side slope and bank borders to provide cover, critical nesting and brood rearing habitat as well as filtering overland flow and improving water quality. Ditches perform the critical function of removing water from agricultural lands. Allowing naturally occurring vegetation to develop along ditches, including side slopes, banks and borders, will help provide food and cover for wildlife while enhancing aquatic habitat and improving water quality. Ditches and ditch borders provide a foundation that supports a diverse wildlife community including Northern Bobwhite (*Colinus virginianus*) and other birds preferring early successional cover. Rabbits, furbearers, amphibians and many other species that inhabit agriculture areas will use this vegetative cover. These areas can also provide critical nesting habitat for the Mottled Duck (*Anas fulvigula*).

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$576.09

Scenario Cost/Unit: \$11.52

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$52.94	3	\$158.82
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	3	\$66.27
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00

Practice: E647139Z2 - Provide early successional habitat between first rice crop and ratoon crop-continuity

Scenario #1 - Ratoon crop-continuity

Scenario Description:

Many declining suites of wildlife species rely on early successional habitats for at least part of their life cycle needs. Migratory shorebird species in particular rely on open, moist soil or shallowly flooded conditions for foraging and security. Rice farms support many migratory and resident water bird species. The first rice crop harvest often coincides with the arrival of early migrating shorebirds. This time of year is also the highest rainfall months. If standing rice stubble from the first crop is rolled to push above-ground stalks level with the soil surface, the first component of this type of habitat is met. When moisture is added to this situation, short-term habitat is available until the ratoon crop initiates growth to a height beyond that which would provide benefit to the early successional species.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 647 - Early Successional Habitat Development and Management

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$1,169.38

Scenario Cost/Unit: \$23.39

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	\$58.85	8	\$470.80
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	8	\$176.72
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	2	\$521.86

Practice: E666106Z1 - Implementing sustainable practices for pine straw raking

Scenario #1 - Sustainable pine straw raking

Scenario Description:

Adopts guidelines for sustaining soil quality and wildlife habitat on sites where pine straw raking is currently practiced. Raking and removal of pine needles ("pine straw") provides valuable landscaping material but at a high cost to soil fertility, soil organic matter, wildlife habitat, and in some cases, soil compaction, soil erosion and water quality degradation. Straw removal also makes prescribed burning less feasible by removal of the fine fuels needed to carry frequent surface fires that maintain longleaf pine and its characteristic understory. This enhancement is most applicable to longleaf pine forestland because: (1) longleaf-dominated ecosystems with their characteristic suite of flora and fauna historically predominated in most places where pines are currently grown in the Southeast, and (2) longleaf is the favored species for pine straw operations.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$1,236.00

Scenario Cost/Unit: \$24.72

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	4	\$115.36
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	10	\$932.50
Materials						
Test, Soil Test, Standard	299	Includes materials, shipping, labor, and equipment costs.	Each	\$10.04	10	\$100.40
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	\$6.96	5	\$34.80
One Species, Cool Season, Native Perennial Grass Sprig, Plug or Culm	2696	Native perennial grass sprig, plug or culms used to stabilize areas, such as sand dunes and riparian areas. Includes materials and shipping.	Each	\$0.17	50	\$8.50

Practice: E666106Z2 - Maintaining and improving forest soil quality

Scenario #1 - Maintain/improve forest SQ

Scenario Description:

Adopts guidelines for maintaining and improving soil quality on sites where forest management activities are practiced. These guidelines will increase soil organic matter content, improve nutrient cycling, and increase infiltration and retention of precipitation. Avoiding soil compaction will allow for greater root development and tree growth, limit windthrow, and reduce drought stress. Increasing carbon storage on site will maintain the soil microbial community and provide wildlife benefits.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$2,239.32

Scenario Cost/Unit: \$44.79

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	4	\$17.80
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	4	\$115.36
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	10	\$932.50
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	8	\$575.12
Materials						
Test, Soil Test, Standard	299	Includes materials, shipping, labor, and equipment costs.	Each	\$10.04	10	\$100.40
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	\$6.96	5	\$34.80
Certified Organic, Three plus Species Mix, Cool Season, Annual Grasses and Legumes	2343	Certified organic cool season annual grass and legume mix. Includes material and shipping only.	Acre	\$81.02	3	\$243.06

Practice: E666107Z - Maintaining and improving forest soil quality by limiting compaction

Scenario #1 - Maintain/improve forest compaction

Scenario Description:

Adopts guidelines for maintaining and improving soil quality on sites where forest management activities are practiced. These guidelines will increase soil organic matter content, improve nutrient cycling, and increase infiltration and retention of precipitation. Avoiding soil compaction will allow for greater root development and tree growth, limit windthrow, and reduce drought stress. Increasing carbon storage on site will maintain the soil microbial community and provide wildlife benefits.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$2,239.32

Scenario Cost/Unit: \$44.79

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	4	\$17.80
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	4	\$115.36
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	10	\$932.50
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	8	\$575.12
Materials						
Test, Soil Test, Standard	299	Includes materials, shipping, labor, and equipment costs.	Each	\$10.04	10	\$100.40
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	\$6.96	5	\$34.80
Certified Organic, Three plus Species Mix, Cool Season, Annual Grasses and Legumes	2343	Certified organic cool season annual grass and legume mix. Includes material and shipping only.	Acre	\$81.02	3	\$243.06

Practice: E666115Z1 - Converting loblolly and slash pine plantations to longleaf pine to retain soil moisture

Scenario #1 - Convert to longleaf pine-soil moisture

Scenario Description:

Longleaf pine has greater wildlife habitat value, is more resistant to insects and disease, and is better able to withstand hurricane-force winds than other southern pines, particularly loblolly and slash pines. Because of rapid early growth, loblolly and slash pines have often been planted on soils and sites better suited to longleaf. Loblolly has a higher rate of evapotranspiration than longleaf and can deplete soil moisture. Loblolly and slash pine plantations can be converted to longleaf by clearcutting and planting seedlings but mature tree cover is then lost for 20 or more years. This enhancement will gradually convert an existing loblolly or slash pine plantation to longleaf while at the same time maintaining mature tree cover with the associated benefits of wildlife habitat and visual quality, and moderating effects on soil temperature, soil moisture and understory plants.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$5,962.11

Scenario Cost/Unit: \$119.24

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	14	\$311.08
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	10	\$62.60
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	2	\$57.68
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	16	\$565.76
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	48	\$1,055.04
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	18	\$1,678.50
Materials						
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	\$6.96	10	\$69.60
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$37.13	10	\$371.30
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shi	Acre	\$1.28	10	\$12.80
Tree, conifer, seedling, containerized, 4 cu. in.	1516	Containerized conifer stock, 4 cubic inches (e.g., "4a" plug), 1.1" x 5.2". Includes materials and shipping only.	Each	\$0.25	6050	\$1,512.50
Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	\$4.32	1	\$4.32
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93



Practice: E666115Z2 - Enhance development of the forest understory to improve site moisture

Scenario #1 - Forest understory to improve moisture

Scenario Description:

Forest stand improvement to manage the structure and composition of overstory and understory vegetation so that additional moisture is captured and filtered through the vegetation and soil. Managing the understory vegetation will increase available water to the plants, minimize run-off and erosion, and improve water quality.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: \$4,538.72

Scenario Cost/Unit: \$226.94

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	\$84.38	16	\$1,350.08
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	16	\$1,059.04
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	16	\$353.44
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	8	\$746.00
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	4	\$287.56
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$37.13	20	\$742.60

Practice: E666118Z - Enhance development of the forest understory to capture nutrients in surface water

Scenario #1 - Understory-nutrients in surface water

Scenario Description:

Forest stand improvement to manage the structure and composition of overstory and understory vegetation so that additional moisture is captured and filtered through the vegetation and soil, thus minimizing nutrient movement in surface water. Managing the understory vegetation will increase available water to the plants, minimize run-off and erosion, and improve water quality.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: \$4,538.72

Scenario Cost/Unit: \$226.94

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	\$84.38	16	\$1,350.08
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	16	\$1,059.04
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	16	\$353.44
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	8	\$746.00
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	4	\$287.56
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$37.13	20	\$742.60

Practice: E666119Z - Enhance development of the forest understory to capture nutrients -ground water

Scenario #1 - Understory-nutrients in ground water

Scenario Description:

Forest stand improvement to manage the structure and composition of overstory and understory vegetation so that additional moisture is captured and filtered through the vegetation and soil, thus minimizing nutrient loss through ground water. Managing the understory vegetation will increase available water to the plants, minimize run-off and erosion, and improve water quality.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: \$4,538.72

Scenario Cost/Unit: \$226.94

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	\$84.38	16	\$1,350.08
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	16	\$1,059.04
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	16	\$353.44
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	8	\$746.00
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	4	\$287.56
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$37.13	20	\$742.60

Practice: E666130Z - Increase on-site carbon storage

Scenario #1 - Increase on-site carbon storage

Scenario Description:

Utilize forest management techniques to increase on-site carbon storage, including uneven-aged management, longer rotations, leave-tree retention, snags and down woody debris, and soil organic ma

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 100.0

Scenario Total Cost: \$1,222.13

Scenario Cost/Unit: \$12.22

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Labor						
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	17	\$1,222.13

Practice: E666132Z1 - Crop tree management for mast production

Scenario #1 - Crop tree management for mast production

Scenario Description:  
Forest stand improvement using crop tree management techniques to increase mast production

Before Situation:  
Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:  
The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$3,433.72

Scenario Cost/Unit: \$343.37

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	25	\$111.25
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	6	\$133.32
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	25	\$1,654.75
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	25	\$549.50
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	8	\$746.00
Materials						
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	\$6.96	10	\$69.60
Herbicide, Picloram	337	Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$16.93	10	\$169.30

Practice: E666132Z2 - Reduce forest stand density to improve a degraded plant community

Scenario #1 - Forest density-degraded plant community

Scenario Description:

Open pine or conifer management reduces the number of trees per acre while still maintaining the stand as forest land. It restores elements of stand structure that were formerly created by fire on sites where it is not currently feasible to conduct prescribed burning at the intensity needed to open the canopy. The open stand condition allows a significant amount of sunlight to reach the forest floor and stimulate understory vegetation. The initial treatment creates a stand structure that allows prescribed burning to be applied to limit redevelopment of the woody component of the understory and maintain open conditions. The vegetation management, and wide spacing between trees or clumps of trees, provides visual appeal, reduces the risk of wildfire, and provides wildlife habitat for many at-risk and listed wildlife species.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: \$5,404.86

Scenario Cost/Unit: \$270.24

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	\$84.38	20	\$1,687.60
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	20	\$1,323.80
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	20	\$441.80
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	8	\$746.00
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	4	\$287.56
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$37.13	20	\$742.60
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: E666133X - Forest Stand Improvement to rehabilitate degraded hardwood stands

Scenario #1 - FSI-structure/composition in hardwoods

Scenario Description:

Mixed species hardwood stands have been subjected to poor logging practices (???high-grading???) for decades. Without professional forestry assistance the best species and individual trees are removed, often before maturity (???diameter-limit cutting???), leaving the poorest species and individual trees to regenerate the stand. Reversing this process requires cutting or killing poor quality trees while retaining any desirable species that might still be present. A combination of 3 silvicultural methods are applied: crop tree release, group selection (all trees removed from an area 0.25 to 1.0 acre in size) and small clear-cuts (all trees removed from an area 1-3 acres in size). A professional forester is needed to recognize and mark crop trees to be retained and delineate areas without crop trees to be clearcut. Thinning and forest stand improvement will include cutting with hand tools (chainsaws) and injection. Costs involved in any commercial harvesting including marking, access, and transportation are not included in this scenario. However the costs involved in marking trees to be treated or left and supervising the TSI work is included.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acres treated

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$5,159.46

Scenario Cost/Unit: \$515.95

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	16	\$71.20
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	40	\$2,647.60
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	16	\$461.44
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	16	\$351.68
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	8	\$746.00
Materials						
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	\$6.96	10	\$69.60
Herbicide, Triazine	1321	Broad spectrum herbicide. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$41.65	10	\$416.50
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	2	\$351.00

Practice: E666133Z1 - Creating structural diversity with patch openings

Scenario #1 - Structural diversity with patch openings

Scenario Description:

Forest stand improvement that creates patch openings. Size and shape of patches will be based on characteristic natural wind disturbances, which will vary geographically and by forest type.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 15.0

Scenario Total Cost: \$7,095.30

Scenario Cost/Unit: \$473.02

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	150	\$667.50
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	15	\$333.30
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	150	\$3,297.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	30	\$2,797.50



**Practice:** E666133Z2 - Converting loblolly and slash pine plantations to longleaf pine with FSI and prescribed burning

**Scenario #1** - Convert to longleaf pine-FSI and burning

**Scenario Description:**

Longleaf pine has greater wildlife habitat value, is more resistant to insects and disease, and is better able to withstand hurricane-force winds than other southern pines, particularly loblolly and slash pines. Because of rapid early growth, loblolly and slash pines have often been planted on soils and sites better suited to longleaf. Loblolly and slash pine plantations can be converted to longleaf by clearcutting and planting seedlings but mature tree cover is then lost for 20 or more years. This enhancement will gradually convert an existing loblolly or slash pine plantation to longleaf while at the same time maintaining mature tree cover with the associated benefits of wildlife habitat and visual quality, and moderating effects on soil temperature, soil moisture and understory plants.

**Before Situation:**

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

**After Situation:**

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 50.0

**Scenario Total Cost:** \$5,962.11

**Scenario Cost/Unit:** \$119.24

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	14	\$311.08
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	10	\$62.60
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	2	\$57.68
<b>Labor</b>						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	16	\$565.76
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	48	\$1,055.04
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	18	\$1,678.50
<b>Materials</b>						
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	\$6.96	10	\$69.60
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$37.13	10	\$371.30
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shi	Acre	\$1.28	10	\$12.80
Tree, conifer, seedling, containerized, 4 cu. in.	1516	Containerized conifer stock, 4 cubic inches (e.g., "4a" plug), 1.1" x 5.2". Includes materials and shipping only.	Each	\$0.25	6050	\$1,512.50
Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	\$4.32	1	\$4.32
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: E666134Z - Enhance development of the forest understory to create conditions resistant to pests

Scenario #1 - Forest understory-resistant to pests

Scenario Description:

Forest stand improvement that manages the structure and composition of overstory and understory vegetation to reduce vulnerability to damage by insects and diseases of forest trees. Managing the understory vegetation will also reduce the risk of wildfire, and promote development of herbaceous plants that benefit wildlife.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: \$4,538.72

Scenario Cost/Unit: \$226.94

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	\$84.38	16	\$1,350.08
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	16	\$1,059.04
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	16	\$353.44
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	8	\$746.00
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	4	\$287.56
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$37.13	20	\$742.60

Practice: E666135Z1 - Reduce height of the forest understory to limit wildfire risk

Scenario #1 - Forest understory-limit wildfire risk

Scenario Description:

Forest stand improvement that manages forest structure to reduce the risk of wildfire, and creates conditions that facilitate prescribed burning. The fire risk reduction is accomplished by reducing the height of the woody understory and midstory, creating space between the ground cover and the tree canopy.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: \$4,538.72

Scenario Cost/Unit: \$226.94

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	\$84.38	16	\$1,350.08
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	16	\$1,059.04
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	16	\$353.44
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	8	\$746.00
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	4	\$287.56
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$37.13	20	\$742.60

Practice: E666135Z2 - Reduce forest density and manage understory along roads to limit wildfire risk

Scenario #1 - Manage understory-limit wildfire risk

Scenario Description:

Opening the tree canopy along roads ("daylighting"), and providing space between ground vegetation and tree crowns, minimizes the spread of wildfires that often start along roads. Additionally, opening the canopy will allow more sunlight to reach the forest floor and promote flowering plants, and will reduce maintenance needs by allowing moisture to evaporate from roads.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$2,710.02

Scenario Cost/Unit: \$271.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	8	\$35.60
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	\$84.38	8	\$675.04
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	8	\$529.52
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	8	\$176.72
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	8	\$746.00
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$37.13	10	\$371.30

Practice: E666136Z1 - Reduce forest density and manage understory along roads to improve wildlife food sources

Scenario #1 - Manage understory-wildlife food sources

Scenario Description:

Opening the tree canopy along roads ("daylighting") allows more sunlight to reach the forest floor and promotes the growth of herbaceous plants. The resulting condition is more visually appealing for users of the roadway, and improves wildlife habitat and food sources for many wildlife species.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$2,710.02

Scenario Cost/Unit: \$271.00

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	8	\$35.60
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	\$84.38	8	\$675.04
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	8	\$529.52
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	8	\$175.84
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	8	\$176.72
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	8	\$746.00
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$37.13	10	\$371.30

Practice: E666136Z2 - Reduce forest stand density to improve wildlife food sources

Scenario #1 - Stand density-wildlife food sources

Scenario Description:

Open pine or conifer management reduces the number of trees per acre while still maintaining the stand as forest land. It restores elements of wildlife habitat that formerly resulted from fire, on sites where it is not currently feasible to conduct prescribed burning. The open stand condition allows a significant amount of sunlight to reach the forest floor and stimulate understory vegetation. The initial treatment creates a stand structure that allows prescribed burning to be applied, where feasible, to limit redevelopment of the woody component of the understory and maintain open conditions. The vegetation management, and wide spacing between trees or clumps of trees, provides visual appeal, reduces the risk of wildfire, and provides wildlife habitat for many at-risk and listed wildlife species.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: \$5,404.86

Scenario Cost/Unit: \$270.24

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	\$84.38	20	\$1,687.60
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	20	\$1,323.80
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	20	\$441.80
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	8	\$746.00
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	4	\$287.56
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$37.13	20	\$742.60
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50

Practice: E666136Z3 - Create patch openings to enhance wildlife food sources and availability

Scenario #1 - Patch openings-food and availability

Scenario Description:

Forest stand improvement that creates patch openings. Size, shape, and arrangement of patches will be based on natural features, and emulate patches that would result from natural disturbance regimes of wind or fire, varying geographically and by forest type. The treatment will create diversity in stand composition and structure, and enhance wildlife food availability.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 15.0

Scenario Total Cost: \$7,382.86

Scenario Cost/Unit: \$492.19

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	150	\$667.50
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	15	\$333.30
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	150	\$3,297.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	30	\$2,797.50
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	4	\$287.56

Practice: E666137Z1 - Snags, den trees, and coarse woody debris for wildlife habitat

Scenario #1 - Snags and den trees for wildlife

Scenario Description:

Create and retain snags, den trees, forest stand structural diversity, and coarse woody debris on the forest floor to provide cover/shelter for native wildlife species.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$516.39

Scenario Cost/Unit: \$51.64

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	7	\$31.15
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	1	\$22.22
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	3	\$198.57
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	7	\$247.52
Materials						
Herbicide, Picloram	337	Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$16.93	1	\$16.93



Practice: E666137Z2 - Summer roosting habitat for native forest-dwelling bat species

Scenario #1 - Summer roosting habitat for bats

Scenario Description:

Creates new potential roost trees within upland and riparian forests to achieve desired summer habitat for forest dwelling bat species.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 10.0

Scenario Total Cost: \$1,949.28

Scenario Cost/Unit: \$194.93

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	13	\$57.85
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	6	\$133.32
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	13	\$860.47
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	13	\$285.74
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	4	\$373.00
Materials						
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	\$6.96	10	\$69.60
Herbicide, Picloram	337	Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$16.93	10	\$169.30

Practice: E666137Z3 - Increase diversity in pine plantation monocultures

Scenario #1 - Improve pine plantation diversity

Scenario Description:

Creates small openings to provide diversity in pine plantations, which are typically monocultures and inhospitable to wildlife. Small openings are one-half (0.5) to three (3) acres in size. The cleared area will have the vegetation removed through harvesting, mulching, or other means compatible with the site.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 2.0

Scenario Total Cost: \$946.04

Scenario Cost/Unit: \$473.02

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	20	\$89.00
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	20	\$439.60
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	4	\$373.00

**Practice:** E666137Z4 - Converting loblolly and slash pine plantations to longleaf pine to enhance wildlife habitat

**Scenario #1** - Convert to longleaf pine-habitat

#### Scenario Description:

Longleaf pine has greater wildlife habitat value, is more resistant to insects and disease, and is better able to withstand hurricane-force winds than other southern pines, particularly loblolly and slash pines. Because of rapid early growth, loblolly and slash pines have often been planted on soils and sites better suited to longleaf. Loblolly and slash pine plantations can be converted to longleaf by clearcutting and planting seedlings but mature tree cover is then lost for 20 or more years. This enhancement will gradually convert an existing loblolly or slash pine plantation to longleaf while at the same time maintaining mature tree cover with the associated benefits of wildlife habitat and visual quality, and moderating effects on soil temperature, soil moisture and understory plants.

#### Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

#### After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

**Feature Measure:** Acre

**Scenario Unit::** Acre

**Scenario Typical Size:** 50.0

**Scenario Total Cost:** \$5,962.11

**Scenario Cost/Unit:** \$119.24

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	14	\$311.08
Chemical, ground application	948	Chemical application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.26	10	\$62.60
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	2	\$57.68
<b>Labor</b>						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$35.36	16	\$565.76
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	48	\$1,055.04
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	18	\$1,678.50
<b>Materials</b>						
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	\$6.96	10	\$69.60
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$37.13	10	\$371.30
Herbicide, Surfactant	1095	Surfactants reduce the surface tension of water to produce more uniform coverage and penetration of herbicides, and weed killers. Paraffin Based Petroleum Surfactant. Refer to WIN-PST for product names and active ingredients. Includes materials and shi	Acre	\$1.28	10	\$12.80
Tree, conifer, seedling, containerized, 4 cu. in.	1516	Containerized conifer stock, 4 cubic inches (e.g., "4a" plug), 1.1" x 5.2". Includes materials and shipping only.	Each	\$0.25	6050	\$1,512.50
Fuel, ignition fuel mixture	1596	Mixture of gasoline and diesel for ignition of prescribed burns. Materials only.	Gallon	\$4.32	1	\$4.32
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.93	1	\$260.93

Practice: E666137Z5 - Implementing sustainable practices for pine straw raking to enhance wildlife habitat

Scenario #1 - Sustainable pine straw raking-habitat

Scenario Description:

Adopts guidelines for sustaining soil quality and wildlife habitat on sites where pine straw raking is currently practiced. Raking and removal of pine needles ("pine straw") provides valuable landscaping material but at a high cost to soil fertility, soil organic matter, wildlife habitat, and in some cases, soil compaction, soil erosion and water quality degradation. Straw removal also makes prescribed burning less feasible by removal of the fine fuels needed to carry frequent surface fires that maintain longleaf pine and its characteristic understory. This enhancement is most applicable to longleaf pine forestland because: (1) longleaf-dominated ecosystems with their characteristic suite of flora and fauna historically predominated in most places where pines are currently grown in the Southeast, and (2) longleaf is the favored species for pine straw operations.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 50.0

Scenario Total Cost: \$1,236.00

Scenario Cost/Unit: \$24.72

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	2	\$44.44
All terrain vehicles, ATV	965	Includes equipment, power unit and labor costs.	Hour	\$28.84	4	\$115.36
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	10	\$932.50
Materials						
Test, Soil Test, Standard	299	Includes materials, shipping, labor, and equipment costs.	Each	\$10.04	10	\$100.40
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	\$6.96	5	\$34.80
One Species, Cool Season, Native Perennial Grass Sprig, Plug or Culm	2696	Native perennial grass sprig, plug or culms used to stabilize areas, such as sand dunes and riparian areas. Includes materials and shipping.	Each	\$0.17	50	\$8.50

Practice: E666137Z6 - Create patch openings to enhance wildlife cover and shelter

Scenario #1 - Patch openings-cover and shelter

Scenario Description:

Forest stand improvement that creates patch openings. Size, shape, and arrangement of patches will be based on natural features, and emulate patches that would result from natural disturbance regimes of wind or fire, varying geographically and by forest type. The treatment will create diversity in stand composition and structure, and enhance the availability of wildlife food and cover.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 15.0

Scenario Total Cost: \$7,382.86

Scenario Cost/Unit: \$492.19

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.45	150	\$667.50
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$22.22	15	\$333.30
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$21.98	150	\$3,297.00
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	30	\$2,797.50
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	4	\$287.56

Practice: E66613727 - Enhance development of the forest understory to provide wildlife cover and shelter

Scenario #1 - Understory to provide cover/shelter

Scenario Description:

Forest stand improvement that manages the structure and composition of overstory and understory vegetation to improve the quantity and quality of wildlife cover and shelter. Reducing the number of trees per acre provides canopy openings that allow sunlight to reach the forest floor and promote the growth of herbaceous plants, improving wildlife shelter and cover in the forest understory. The treatment also creates conditions that facilitate the use of prescribed burning as a follow-up practice to maintain wildlife shelter and cover.

Before Situation:

Resources are protected at the minimum level of the Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

After Situation:

The adoption of this enhancement will provide resource protection above the minimum level as described in Conservation Practice Standard (CPS) 666 - Forest Stand Improvement

Feature Measure: Acre

Scenario Unit:: Acre

Scenario Typical Size: 20.0

Scenario Total Cost: \$4,714.22

Scenario Cost/Unit: \$235.71

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Mechanical cutter, chopper	943	Forestry mulcher, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	\$84.38	16	\$1,350.08
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$66.19	16	\$1,059.04
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.09	16	\$353.44
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$93.25	8	\$746.00
CAP Labor, forester	1302	Conservation Activity Plan labor to manage nonindustrial private forest lands for conservation, economic, and recreational purposes. Will inventory the type, amount, and location of standing timber and appraise the timber's condition. Will determine how t	Hour	\$71.89	4	\$287.56
Materials						
Herbicide, Imazapyr	336	Pre and post-emergent, non-selective herbicide for control of undesirable vegetation in non-crop areas. Refer to WIN-PST for product names and active ingredients. Includes materials and shipping only.	Acre	\$37.13	20	\$742.60
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$175.50	1	\$175.50